

Wausau Rehabilitation and Preservation Project
 1166-09-62, 1170-01-66, and 1170-01-67
 USH 51/STH 29 Wausau
 Marathon County

Inquiry No.	Project Inquiry	WisDOT Response
1	Do you have quantities and locations on Joint repair and slab replacement?	<p>The following items will be included in the RFP</p> <ul style="list-style-type: none"> • An exhibit showing locations, station and length. • A table with locations of approach slab replacement. <p>The Design-Builder will be responsible for developing quantities.</p>
2	Do you have quantities and locations on Asphalt Shoulder mill and overlay?	<p>Tables will be included in the RFP to specify mill and overlay locations.</p> <p>The Design-Builder will be responsible for developing quantities.</p>
3	Do you have quantities and locations on Guardrail replacement and embankment improvements?	<p>Guardrail replacement will be required at all existing guardrail locations within the project limits.</p> <p>The Design-Builder will be responsible for designing embankment improvements at guardrail locations to comply with Midwest Guardrail System (MGS) requirements. The Design-Builder will be responsible for developing quantities.</p>
4	The bridges are listed for polymer overlays, do any of these bridges need deck repairs or have an existing polymer overlay that would need to be removed?	<p>Existing overlays are present on bridges and are expected to be removed. It is anticipated that both Type 1 and Type 2 deck preparation will be required. Estimated quantities and unit prices will be provided in the RFP for items associated with this work. The design-builder will be required to include these costs in their price proposal. WisDOT will issue a change order to adjust the quantity to reflect the measured field quantities.</p>
5	Please provide a list of all conflicted parties for review and record.	<p>Mead & Hunt, Garver, Ayres Associates, and ECMS are not eligible to participate on a design-build team for this project.</p>