

## August 2024 Solicitation Questions and Responses

Solicitation	Project	Question	Response
NC-02	6999-19-00	Please clarify the limits of the project.	<ul style="list-style-type: none"> <li>•6999-19-70 <ul style="list-style-type: none"> <li>o S 3rd Ave and S 1st Ave from W Thomas Street to Stewart Ave</li> <li>o W Thomas from S 3rd to the river</li> <li>o E Thomas from the river to Bus 51</li> <li>o Bus 51 from Kent Street to E Thomas</li> </ul> </li> <li>•6999-19-71 <ul style="list-style-type: none"> <li>o Bridge Street from NB ramps of US 51 to N 6th Street</li> <li>o N 5th and N 6th from Bridge Street to E Wausau Ave</li> <li>o E Wausau Ave from N 5th Street to N 6th Street</li> </ul> </li> <li>•6999-19-72 <ul style="list-style-type: none"> <li>o S 1st Ave and S 3rd Ave from Stewart Ave T to Bridge Street</li> <li>o N 1st Ave and N 3rd Ave from Bridge Street to W Union Ave</li> <li>o Bus 51 (Merrill Ave) From W Union Ave to College Drive</li> </ul> </li> </ul>
NC-03	0154-86-62	Is an archeologist anticipated for this project?	This project is not on the screening list and needs to go through the Sec106/DT1030 process, but not anticipated to require an archeologist
NW-02	1180-00-10	Will any pedestrian accommodations be required for the trail over the structure?	No pedestrian accommodations were identified in project scoping.
NW-02	1180-00-10	The Branch of Denomie Creek crosses USH 2 in a number of locations. Can WisDOT provide a specific location or coordinates of the culvert to be replaced?	The culvert is located in T47N, R2W, Section 23. At approximately 46.5361N, -90.5716W. 1.3 miles NW of the intersection of US 2 and Res Hwy 7/Birch Hill Rd.
NW-02	1180-00-10	What is the size of the existing & proposed culvert? What R/W services will the consultant perform?	The project anticipates replacing a 36" culvert with a 72" culvert. The project will include obtaining title searches and preparation of a ROW plat.
NW-03	0208-55-38	Is Section 4(f) coordination anticipated for work around the Red Cedar State Trail trailhead?	Not at this time.
NW-03	0208-55-38	Is the deck of structure B-17-0075 proposed to be replaced half at a time with temporary traffic signals?	Yes.
NW-04	8010-00-07	The NOI mentions other railroad work, what is the extent and who will be completing the railroad work?	The railroad is planning to complete crossing surface work during this project. Coordination will be required.
SW-02	1110-06-00	Will the Department make the ongoing SWR/Jacobs US 151 Corridor Study ID 1110-00-00 draft findings available to teams that are pursuing this project?	See the link on the solicitation page.
SW-03	1071-01-02	Please provide clarification on the project schedule.	The roadway design portion of this project, which will be designed by the department, has a DSR date of 2/1/25 and a PS&E of 8/1/26. The department would like preliminary structure plans submitted by 2/1/25 and final structure plans submitted by 6/1/26.
SW-03	1071-01-02	Will WisDOT be completing the project management and other design components (roadway approaches, traffic control, design reports...)?	Solicitation is for structure design only. WisDOT will be completing project management and design of the other components, including the TMP.