

December 2024 Solicitation Questions and Responses

Solicitation	Project	Question	Response
NC-03	0171-30-28	Are the retaining walls mentioned in this NOI proprietary walls or non-proprietary walls? Will a structural engineer be required on this project for these walls?	Proprietary wall - the need for a structural engineer depends on the scope of the work for the retaining wall, but it is anticipated the work will be minimal (cap block repairs) so a detail with manufacturer's instructions should be sufficient
NC-04	1053-02-36	Can the locations where real estate is anticipated be provided?	There is the potential for TLE (less than 10 parcels) related to culverts and/or right-of-way fence
NC-04	1053-02-36	Can the intersection/crossovers requiring queue length evaluation be provided?	Queue length evaluation is required of the STH 29 EB left turn lane for the median crossover to the landfill (Marathon County Solid Waste)
SE-02	1009-21-02	Are the preliminary designs available?	The selected firm will be given preliminary plans during the negotiation process.
SE-02	1009-21-02	Who completed the ecological work?	A consultant.
SW-03	1161-00-04	Are the published deliverable dates Survey and SSR correct?	Updated dates below: Survey: 10/1/2025 Structure Survey Report: 12/1/2025
SW-03	1161-00-04	Is guardrail on IH 39 being replaced?	No
SW-03	1161-00-04	Is chain link fence on structure being replaced?	Yes
SW-03	1161-00-04	Will the new approach joints be part of the roadway approach work, or part of the structure work?	Part of the roadway approach work (CTH O roadway approaches will receive an asphaltic surface butt joint; Concrete Pavement Approach Slabs are anticipated with added curb and gutter and drainage features for the bridge)
SW-04	1161-00-39	Will analysis of the existing beam guard and design of new beam guard be included for the project?	Yes