

January 2025 Solicitation Questions and Responses

Solicitation	Project	Question	Response
BOS-01		Please verify that the anticipated project completion date is 6/30/2025.	The 6/30/2025 completion date is correct for this group of master contracts. The completion date is the end date for writing new work orders under the master contracts. The completion dates for work orders may go beyond that date.
BTS-01		Should resumes be uploaded?	No
NE-01	6505-04-00	Will an environmental document be required for this project?	An environmental document is not anticipated.
NE-01	6505-04-00	Is a new building structure anticipated at either location?	Not at this time. This could change once the preliminary scope is completed.
NE-04	4110-35-00	Please describe the rehabilitation work planned for structure B-20-52.	The primary work concept for B-20-0052 will be a concrete deck overlay. Secondary work concepts may include concrete surface repair for parapets with delamination, concrete surface repair on sidewalk, polymer overlay for sidewalk that has debonded, sealing of approach joints, polyjacking approach slabs and approach curb. Additional secondary items would include Type 1 & 2 repairs.
SW-04	1400-00-06	Please describe the rehabilitation work planned for structures B-14-59 and B-14-60.	Rehabilitation work planned for structures: B-14-0059: MMA Flood seal, concrete surface repairs at abutments, wing strap on NW wing, re-grade/re-oil slopes, new HMA approaches B-14-0060: Thin polymer overlay, concrete surface repair abutments
SW-05	6040-04-03		Project cancelled