



WIS 64 Resurfacing WIS 13 to Lincoln County Line Taylor County


Fall 2025





Agenda

- Project Team
- Project Location
- Project Needs
- Project Improvements
- Traffic Impacts
- Real Estate
- Project Schedule
- Public Comments























Project Team

- Maxwell Sebesta, P.E.
 - WisDOT Consultant Project Manager
 - (608) 667-4377, (715) 529-8897 or maxwell.sebesta@wsp.com
- James Rinzel
 - WisDOT Project Design Leader
 - (715) 836-2800 or james.rinzel@dot.wi.gov
- Nicholas Pitsch, P.E.
 - WisDOT Project Development Supervisor
 - (715) 225-1271 or nicholas.pitsch@dot.wi.gov















Project Location



















Project Location























- Roadway and shoulders
 - Last resurfacing: 2009
 - Distressed asphalt driving and shoulder surface























- Bridge B-60-0020
 - Concrete spalling on concrete beams
 - Water infiltration through joints
 - Abutment settlement



















- Culvert C-60-1112
 - Northwest wing wall tipping
- Culvert C-60-1099
 - Concrete spalling at southeast wing wall
- Culvert C-60-1100
 - Concrete spalling and large cracks on wing walls



















- Guardrail
 - Service life exceeded
 - Current requirements not met
- Culvert pipes
 - Pipe failing, pipes and ditches blocked by debris
- Curb Ramps
 - Current requirements not met























Project Improvements

- Resurface WIS 64 driving lanes and paved shoulders
- Complete work on bridge B-60-0020: Make concrete surface repairs, fiber wrap beams, void fill abutment settlement, install underdrain, seal abutment joints and repair deck drains
- Remove and replace northwest wing wall on culvert C-60-1112
- Complete concrete surface repairs on culvert C-60-1099
- Extend culvert ends on culvert C-60-1100



















Project Improvements

- Remove and replace culvert pipe east of Lemke Drive
- Regrade ditches and clean culvert pipes
- Remove and replace sidewalk curb ramps
- Install centerline rumble strips
- Clear roadside
- Replace guardrail


















- During construction, motorists will encounter:
 - Single-lane closures controlled by flagging for most work
 - Single-lane closures controlled by temporary traffic signals for work at culvert C-60-1100
 - Shoulder closures for guardrail replacement, curb ramp improvements and, as needed, work at bridge B-60-0020
 - Short-term detours (approximately five days/each) for excavation work at bridge B-60-0020 and a culvert pipe replacement east of Lemke Drive







- For work at bridge B-60-0020:
 - Eastbound WIS 64 traffic will be detoured via WIS 13 south to WIS 29 east to WIS 97 north.
 - Westbound WIS 64 traffic will follow the eastbound detour in reverse.
 - Access will be maintained on both sides of the bridge.






















- For culvert pipe replacement:
 - Eastbound WIS 64 traffic will be detoured via WIS 97 south to WIS 29 east to WIS 107 north.
 - Westbound WIS 64 traffic will follow the eastbound detour in reverse.
 - Access will be maintained on both sides of the culvert pipe.




















- During closure of the crosswalk at One Weather Shield Plaza:
 - Temporary accommodations will be made to maintain pedestrian access to One Weather Shield Plaza.



















Real Estate

- FEE
 - Permanent land purchase of a portion of a property by WisDOT for highway needs
- TLE (Temporary Limited Easement)
 - Temporary land purchase of a portion of a property by WisDOT for construction needs; disturbed areas restored during construction
- Project Needs
 - Five FEE purchases (Three for culvert C-60-1100 extension and two for guardrail replacement at property entrances next to existing box culverts)
 - Anticipated acreage per property 0.01 acre (approximately 875 square feet)
 - One TLE purchase (for guardrail replacement grading)
 - Anticipated acreage 0.04 acre (approximately 1,750 square feet)
- Access
 - No changes to existing access





















Project Schedule

- Local Officials Meeting #1
- Public Input Solicitation
- Recorded Plat
- Real Estate Acquisition
- Utility Coordination
- Agency Coordination
- Final Plans Due
- Construction Information Meeting
- Construction

Oct. 28, 2025 Dec. 12, 2025 July 2026 Summer 2026 – fall 2027 **April 2027** Ongoing to October 2027 November 2027 Prior to construction start Spring to late fall 2028



















Public Comments Questions? Comments?

- Comments are being accepted through Dec. 12, 2025, by:
 - Email: james.rinzel@dot.wi.gov
 - Phone: (715) 836-2800
 - Mail: Wisconsin Department of Transportation 718 W. Clairemont Ave. Eau Claire, WI 54701
 - Attn.: James Rinzel







