# ST CLOUD ST - LIVINGSTON ST: ALTERNATIVE 1

RECOMMENDED ALTERNATIVE

ALTERNATIVE 1 TYPICAL SECTION
CAUSEWAY BLVD TO CLINTON ST

ALTERNATIVE 1 TYPICAL SECTION
CLINTON ST TO LIVINGSTON ST




Scale: 1 IN:50 FT

ST CLOUD ST
ST JAMES ST
WALL ST
WINDSOR ST
CLINTON ST
ST PAUL ST
GOLD ST
LOGAN ST
SILL ST
GILLETTE ST
RUBLE ST
RIVERVIEW CT
GOHRES ST
LIVINGSTON ST

LA CROSSE CORRIDOR STUDIES

Project ID 1630-09-01
US 53 & US 14/61 Corridor Study
Green Bay St to Livingston St
La Crosse County

PRELIMINARY 6/6/2025

Note: Aerial imagery may be out of date and shall be used for informational purposes only; may vary from present-day conditions.

Note: In addition to the spot improvements planned in the Clinton St to Livingston St section, other work includes pavement overlay and curb ramp improvements as needed to comply with current ADA standards.

## LEGEND

- Pavement
- Structure - Concrete Overlay
- Curb & Gutter/Median/Sidewalk
- Shared Use Path
- Sidewalk-Level Bike Lane
- Steet-Level Bike Lane or Cycle-Track
- Bike Crossing
- Pedestrian Crossing
- Terrace/Grass Median
- Paved Terrace
- Raised Median
- Existing Right of Way
- Proposed Right of Way
- Bus Stop
- Signalized Intersection

1. Signal Infrastructure Improvements
2. Signal Operation Improvements
3. Rectangular Rapid Flashing Beacon
4. Pedestrian Refuge
5. Speed Feedback Signs
6. New Driveway Access
7. Driveway Right In/Out Only
   *Full Access from Other Driveways
   **No other Full Access Driveway
   XXX Driveway Closure
   Note: Existing driveways to remain unless otherwise noted.
8. Public Road Access Changes Due to Geometric Improvements