

Wisconsin Department of Transportation

February 26, 2015

Proposal #26:

Division of Transportation Systems Development

(608) 266-1631

Bureau of Project Development 4802 Sheboygan Avenue, Rm 601

Facsimile (FAX): (608) 266-8459

P O Box 7916

Telephone:

Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

1517-75-78, WISC 2015 138 1517-75-81, WISC 2015 139

USH 10 – USH 10/STH 441 USH 10 – USH 10/STH 441 County CB – Oneida St County CB – Oneida St

USH 10 USH 10

Winnebago County Calumet County
Appleton Road (STH 47) Intcha Vermillion Street

Appleton Road (STH 47) Intchg

Letting of March 10, 2015

This is Addendum No. 3, which provides for the following:

Special Provisions

| Revised Special Provisions | | | | | | |
|----------------------------|--|--|--|--|--|--|
| Article | Article No. Description | | | | | |
| No. | | | | | | |
| 2.2 | Prosecution and Progress, Paragraph 13 | | | | | |
| 2.2 | Prosecution and Progress US 10/STH 441 Mainline, Stage 4, second paragraph | | | | | |
| 2.2 | Prosecution and Progress US 10/STH 441 Mainline, Stage 4, last paragraph | | | | | |
| 20.7 | 20.7 Temporary Crosswalk Access, Item SPV.0045.016, E. Payment | | | | | |
| 20.8 | 20.8 Temporary Sidewalk or Walkway, Item SPV.0165.017, B. Materials | | | | | |

Schedule of Items

| Added Bid Item Quantities | | | | | | | | |
|---------------------------|---------------------|------|-----------------|---------------------|-------------------|--|--|--|
| Bid Item | Item Description | Unit | Old Quantity | Revised Quantity | Proposal Total | | | |
| 642.5201 | Field Office Type C | Each | 0 | 1 | 1 | | | |

Plan Sheets

| | Revised Plan Sheets | | | | | | | |
|--|--|--|--|--|--|--|--|--|
| Plan Sheet Title (brief description of changes to sheet) | | | | | | | | |
| 315 | Miscellaneous Quantities (Added Field Office Type C to quantity table) | | | | | | | |

Other

Revise the contract time for completion from July 20, 2015 to August 14, 2015.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 1

1517-75-78

February 26, 2015

Special Provisions

2.2. Prosecution and Progress

Delete the thirteenth paragraph that starts with "Comply with all local ordinances..." and replace with:

The contractor may not work on the South East Ramp or perform pile driving work from 10:00 PM to 7:00 AM.

US 10/ STH 441 Mainline Stage 4

Replace with the following:

Restore traffic onto existing two concrete travel lanes. The temporary asphaltic median-side travel lanes will be barricaded with temporary concrete barrier and will be used for future contract staging.

Contractor is expected to demo existing bridge deck prior to Appleton Road interim completion. Any repairs required will be incidental.

Complete all of the work in USH 10/STH 441 Mainline Stages 1-4 prior to 12:01 AM August 15, 2015.

20.7 Temporary Crosswalk Access, Item SPV.0045.016

E. Payment

Replace the last paragraph with the following:

Payment is full compensation for furnishing all labor, tools, equipment, materials, fencing, and incidentals necessary to complete the contract work.

20.8 Temporary Sidewalk or Walkway, Item SPV.0165.017

B. Materials

Replace with the following:

Furnish a hard temporary surface material consisting of asphaltic surface temporary in accordance to standard spec 465.2, concrete conforming to section 602.2 of the standard specifications, or pressure treated wood with skid resistant. Furnish base aggregate dense 1 ½" in accordance to standard spec 305. The surface course for the sidewalk shall be a minimum of one and one-half inches (1-1/2") thick.

Schedule of Items

Attached, dated February 26, 2015, are the revised Schedule of Items Page 38.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 315

END OF ADDENDUM

FENCE WOVEN WIRE

| 616.0100 | FENCE WOVEN | WI RE | 4 | 08 | 425 | 96 | 0/ |
|----------|-------------|-------|-------------|--------------------|-------------------|------------|-------------------|
| | | | LOCATI ON | ANE RAMP | ASE RAMP | ASW RAMP | ASW RAMP |
| | | | OFFSET | 105' LT | 65' RT | 70' RT | 80' RT |
| | | | STATI ON | 1293ANE+04 105' LT | 1303ASE+23 65' RT | 1278ASW+99 | 1283ASW+34 80' RT |
| | | | 10 | 1 | ı | ı | |
| | | | STATI ON TO | 1292ANE+35 | 1298ASE+98 | 1278ASW+18 | 1282ASW+73 |
| | | | CATEGORY | 1000 | | | |

MOBILI ZATI ON

WATER

MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 1517-75-78

618. 0100 EACH

LOCATI ON

CATEGORY STATION TO STATION

| | REMARKS | DUST CONTROL | COMPACTI ON | |
|--------------------|--------------------|--------------|-------------|-------|
| 624. 0100 WATER | MGAL | 131 | 328 | 460 |
| | LOCATI ON | PROJECT | PROJECT | TOTAL |
| | OFFSET | R/L | R/L | |
| | STATION TO STATION | 133ANB+95 | 133ANB+95 | |
| | 2 | ı | 1 | |
| | STATI ON | 101ANB+07 | 101ANB+07 | |
| | CATEGORY | 1000 | | |
| | | | | |
| | | | | |

CONCRETE MEDIAN SLOPED NOSE

| 620. 0300 CONCRETE | MEDI AN | SF SF | 68 | 68 | 44 | 09 | 20 | 31 | 09 | 69 | 69 | 141 |
|-----------------------|---------|-----------|-----------|-----------|-----------|-----------|-----------|------------|-----------|------------|------------|-------|
| | | LOCATI ON | STH 47 | MI DWAY RD | STH 47 | ANE RAMP | ASW RAMP | TOTAL |
| | | OFFSET | MED | MED | MED | RT | MED | LT | LT | MED | MED | |
| | | STATI ON | 105ANB+38 | 109ANB+51 | 110ANB+40 | 114ANB+82 | 131ANB+19 | 104ASB+72 | 125ASB+48 | 1291ANE+72 | 1286ASW+46 | |
| | | CATEGORY | 1000 | | | | | | | | | |

| -75-78 | | REMARKS | | |
|--|-----------|-----------|---------|-------|
| FIELD OFFICE TYPE C (PROJECT) 1517-75-78 | 642. 5201 | EACH | 1 | 1 |
| OFFI CE TYPE | | LOCATI ON | PROJECT | TOTAL |
| FIELD | | CATEGORY | 1000 | |

MISCELLANEOUS QUANTITIES COUNTY: WINNEBAGO HWY: STH 441/USH 10 PROJECT NO: 1517-75-78 FILE NAME:

Ш

SHEET: 315

Addendum No. 3 IDs 1517-75-78 Revised Sheet 315 February 26, 2015

က

Wisconsin Department of Transportation PAGE: 38 DATE: 02/26/15

SCHEDULE OF ITEMS REVISED:

ONTRACT: 20150310026 CONTRACT:

PROJECT(S): FEDERAL ID(S): 1517-75-78 WISC 2015138 1517-75-81 WISC 2015139

| LINE NO | I | APPROX. | UNIT PRICE | BID AMOUNT | | |
|------------|---|-------------------------|----------------|----------------|--|--|
| NO | DESCRIPTION | AND UNITS | ! | DOLLARS CT | | |
| | SPV.0180 Special 011. Colored Concrete 9-Inch | 249.000 SY | | | | |
| | SPV.0180 Special 014. Geogrid Reinforcement 1517-75-78 | 16,525.000 SY | | | | |
| | SPV.0180 Special 015. Geogrid Reinforcement | 2,416.000 SY | | | | |
| 3860 | SPV.0180 Special 503. Mulch, Mississippi River Gravel 1 1/2- Inch | 7.000 | | | | |
| | 108.4400 CPM Progress Schedule | 4.000 EACH | | | | |
| 3880 | 642.5201 Field Office Type C | 1.000 EACH | | | | |
| | SECTION 0001 TOTAL | | | | | |
| | TOTAL BID | | | | | |