



Wisconsin Department of Transportation

December 11, 2016

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #15: 3180-07-60
Illinois – Lake Geneva
Illinois State Line to Willow Road
STH 120
Walworth County

Letting of December 13, 2016

This is Addendum No. 01, which provides for the following:

Special Provisions

Revised Special Provisions	
Article No.	Description
4	Lane Rental Fee Assessment
31	Concrete Masonry Deck Patching, Item SPV.0035.02

Special Provisions

4. Lane Rental Fee Assessment.

Replace the 2nd paragraph under B Lane Rental Fee Assessment with the following:

\$5,000 per lane, per direction of travel, per hour broken into 15 minute increments

31. Concrete Masonry Deck Patching, Item SPV.0035.02

Replace the 5th paragraph under C Construction with the following:

Cure the concrete masonry deck patching according to the requirements of standard spec 502.2.6.1. Before cleaning the deck surface or applying the sheet membrane waterproofing (if applicable), ensure that the deck patching concrete has a minimum compressive strength of 3,000 psi.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

