



Wisconsin Department of Transportation

December 9, 2016

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #26: 4630-05-71, WISC 2016 487
Calumet Drive, City of Sheboygan
Main Avenue – 26th Street
STH 42
Sheboygan County

4630-30-60
Sheboygan – Howard Grove
Mueller Rd – IH 43
STH 42
Sheboygan County

4630-05-72
Calumet Drive, City of Sheboygan
Main Avenue – 26th Street
STH 42
Sheboygan County

Letting of December 13, 2016

This is Addendum No. 02, which provides for the following:

Special Provisions

Revised Special Provisions	
Article No.	Description
47	Lateral Connection Sealing, Item SPV.0060.28
54	Sanitary Sewer Cured-In-Place Liner, SPV.0090.12
56	Televising sanitary Sewer, Item SPV.0090.17

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
79	Revised diagonal pavement marking

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02
4630-05-71/4630-05-72/4630-30-60
December 7, 2016

Special Provisions

47. Lateral Connection Sealing, Item SPV.0060.28

Replace the first sentence under C.2 Televising with the following:

Television inspection is required prior to sealing and is limited to a "Quick Pull".

54. Sanitary Sewer Cured-In-Place Liner, Item SPV.0090.12

Revise the first sentence under B.1.6 (8) with the following:

Contractor must submit design data and cured-in-place pipe liner thickness for each run of pipe from manhole to manhole to the engineer prior to installation.

Delete the second sentence under B.1.6 (8).

Revise the title of B2.3 Post Lining Submittals to the following:

Pre and Post Lining Submittals

Revise subsection (2) of B2.3 to the following:

Pre lining CCTV tapes and reports per section C.5.5.

Replace first sentence under C.1 Examination with the following:

Televising the existing pipes and review tapes prior to starting lining operations. Previous televising records of the existing pipes can be obtained by contacting Paul Brauer at the NE Region office, telephone = 920-366-1097.

Replace the subsection (1) of C5.5 CCTV Examination with the following:

Televising interior of pipes prior to start of work and provide tape to City of Sheboygan; Ryan Sazama, Telephone = 920-459-3485.

Remove the last sentence under E Payment.

56 Televising Sanitary Sewer, Item SPV.0090.17

Replace the first sentence under C.1 Procedures with the following:

The intent of closed circuit televising inspection (CCTI) is to observe and record the condition of the sanitary sewer sections being either lined or installed after the lining and installation is completed.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 79

END OF ADDENDUM

