



Wisconsin Department of Transportation

March 21, 2017

**Division of Transportation Systems
Development**

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #10: 5145-00-60
Mazomanie - Sun Prairie
STH 78 to USH 12
STH 19
Dane County**

Letting of April 11, 2017

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
18	Salvaged Asphaltic Shoulder Material, Item SPV.0195.01.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5145-00-60

March 21, 2017

Special Provisions

18. Salvaged Asphaltic Shoulder Material, Item SPV.0195.01.

Replace entire article language with the following:

A Description

This special provision describes constructing a dense graded aggregate base recovered under Removing Asphaltic Surface Milling, Item 204.0120, or Removing Distressed Pavement Milling, Item SPV.0180.01 from existing asphaltic pavement within the project limits.

B Materials

Furnish material with 100 percent passing a 1 1/4-inch sieve. For shouldering applications, provide reprocessed material or blended material.

C Construction

Under the Salvaged Shoulder Material bid item, process stockpiled material as necessary to conform to standard spec 305.2 and place material as the plans specify. Construct the base conforming to standard spec 305.3.

Excess material recovered from within the project limits under Removing Asphaltic Surface Milling, Item 204.0120, and Removing Distressed Pavement Milling, Item SPV.0180.01 becomes the contractor's property.

D Measurement

The department will determine weight or volume, adjust for moisture, and convert between weight and volume as specified in standard spec 301.4. The department may deduct for contaminated aggregate or unrecovered aggregate deposited outside the outer shoulder limits.

The department will measure the Salvaged Asphaltic Shoulder Material by the ton acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0195.01	Salvaged Asphaltic Shoulder Material	TON

Payment for Salvaged Asphaltic Shoulder Material is full compensation for processing to size; for preparing the foundation; and for placing, compacting, shaping, and maintaining the base. The department will pay for EBS in areas of placed base, and compaction water as specified in standard spec 301.5.

END OF ADDENDUM