



Wisconsin Department of Transportation

November 5, 2018

Division of Transportation Systems Development
Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #06: 3300-01-73, WISC 2018 137
C. Lake Mills, Main Street
Topel Street to Madison St
STH 89
Jefferson County

3300-01-74
C. Lake Mills, Main Street
Topel Street to Madison St
STH 89
Jefferson County

Letting of November 13, 2018

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0090.36	Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 35 12-Inch	LF	4,409	-1,057	3,352
SPV.0090.37	Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 26 12-Inch	LF	1,264	1,057	2,321

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
209	Miscellaneous Quantities

Schedule of Items

Attached, dated November 5, 2018, are the revised Schedule of Items Page 14.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 209

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 3300-01-74
Revised Sheet 209
November 5, 2018

SANITARY SEWER PIPES											
SPV.0090.34	SPV.0090.35	SPV.0090.36	SPV.0090.38	SPV.0090.37	SPV.0035.26	SPV.0060.41					
SANITARY SEWER (UPSTREAM)		SANITARY SEWER (DOWNSTREAM)		POLYVINYL CHLORIDE (PVC)		IRREGULAR BACKFILL, SANITARY SEWER		CONNECT TO EXISTING SANITARY SEWER MAIN OR MANHOLE			
LOCATION (DOWNSTREAM)	LOCATION (UPSTREAM)	IE (DOWNSTREAM)	IE (UPSTREAM)	SLOPE (%)	8-INCH LF	10-INCH LF	12-INCH LF	15-INCH LF	12-INCH LF	12-INCH LF	
CATEGORY											
0020	2	850.01	850.01	0.49%	123					62	
	3	849.35	849.68	0.25%			131			66	
	4	848.80	849.25	0.25%			179			90	
	5	847.86	848.70	0.25%			338			169	
	6	847.18	847.76	0.25%			232			116	
	7	846.10	847.08	0.25%			392			196	
	8	845.21	846.00	0.22%				313		157	
	9	844.18	845.12	0.25%				375		188	
	10	843.15	844.08	0.25%				371		186	
	11	842.06	843.05	0.25%				396		198	
	12	840.97	841.96	0.25%			395			198	
	13	840.34	840.87	0.25%			213			107	
	14	839.40	840.24	0.25%						169	
	15	838.33	839.30	0.25%						194	
	16	834.00	838.23	1.13%			375			188	
	17	831.50	833.90	0.67%			360			180	
	18	827.77	831.45	1.05%			349			175	
	19	826.05	827.72	0.92%			181			91	
	20	821.80	826.00	2.98%					141	71	
EX MH SAN-1	20	819.64	821.55	1.77%				108		54	
EX MH SAN-6941	21	820.55	821.70	0.40%						144	
	12	846.99	848.86	3.33%						28	
CONNECT TO EXISTING	10	846.79	850.11	2.86%						23	
CONNECT TO EXISTING	10	849.10	849.68	0.74%						39	
CONNECT TO EXISTING	11	847.84	849.58	3.48%						25	
CONNECT TO EXISTING	14	846.15	846.35	0.40%						25	
CONNECT TO EXISTING	19	826.40	826.56	0.26%						30	
CONNECT TO EXISTING	2	849.78	850.29	0.25%			207			104	
	4	849.47	850.26	1.00%						40	
	5	850.70	851.25	1.27%						22	
	7	848.98	849.25	0.45%						30	
CONNECT TO EXISTING	7	851.48	851.64	0.40%						20	
	6	849.58	850.89	8.65%						8	
TOTALS					972	15	3,352	108	2,321	3,384	13

ADJUST EXISTING MANHOLE CASTING			
ADJUST EXISTING MANHOLE CASTING	REFERENCE ALIGNMENT	STATION	LOCATION (OFFSET)
EA	89 PROP	89+65.11	8.9' LT
EA	89 PROP	89+99.7	8.9' LT
EA	89 PROP	93+97.8	7.9' LT
UNDISTRIBUTED			3
TOTAL			6



Proposal Schedule of Items

Proposal ID: 20181113006 Project(s): 3300-01-73, 3300-01-74

Federal ID(s): WISC 2018137, N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0396	SPV.0090 Special 32. Sanitary Lateral, 4-Inch	5,095.000 LF	_____.	_____.
0398	SPV.0090 Special 33. Sanitary Lateral, 6-Inch	200.000 LF	_____.	_____.
0400	SPV.0090 Special 34. Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 35, 8-Inch	972.000 LF	_____.	_____.
0402	SPV.0090 Special 35. Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 35, 10-Inch	15.000 LF	_____.	_____.
0404	SPV.0090 Special 36. Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 35, 12-Inch	3,352.000 LF	_____.	_____.
0406	SPV.0090 Special 37. Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 26, 12-Inch	2,321.000 LF	_____.	_____.
0408	SPV.0090 Special 38. Sanitary Sewer, Polyvinyl Chloride (PVC), SDR 35, 15-Inch	108.000 LF	_____.	_____.
0410	SPV.0090 Special 39. Water Main Insulation	550.000 LF	_____.	_____.
0412	SPV.0090 Special 40. Special Bedding	500.000 LF	_____.	_____.
0414	SPV.0105 Special 26. Temporary Water Main and Service Connections	LS	LUMP SUM	_____.
0416	SPV.0105 Special 27. Remove Existing Water Main	LS	LUMP SUM	_____.
0418	SPV.0105 Special 28. Abandon Existing Water Main	LS	LUMP SUM	_____.
0420	SPV.0105 Special 29. Abandon Existing Sanitary Sewer	LS	LUMP SUM	_____.
0422	SPV.0195 Special 01. Excavation, Hauling, and Disposal of Contaminated Soil	3,591.000 TON	_____.	_____.

