



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

July 3, 2019

### NOTICE TO ALL CONTRACTORS:

**Proposal #2: 1007-12-74, WISC 2019 497**  
**Illinois State Line - Madison**  
**CTH AB to USH 12/18 INCTHG -**  
**TEMP**  
**IH 39**  
**Dane County**

**1007-12-75, WISC 2019 498**  
**Illinois State Line - Madison**  
**CTH AB to USH 12/18 INCTHG -**  
**RECSTE**  
**IH 39**  
**Dane County**

### Letting of July 9, 2019

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
68	Department Owned Field Office Equipment and Maintenance, Item SPV.0060.005

Added Special Provisions	
Article No.	Description
108	Portable Speed Trailer, Item SPV.0045.001

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0045.001	Portable Speed Trailer	DAY	0	410	410

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**  
**1007-12-74 & 1007-12-75**  
**July 3, 2019**

**Special Provisions**

**68. Department Owned Field Office Equipment and Maintenance, Item SPV.0060.005.**

*Replace paragraph one under section titled **B Materials** with the following:*

Provide and maintain field office services beginning September 1, 2019.

**108. Portable Speed Trailer, Item SPV.0045.001.**

**A Description**

This special provision describes furnishing, hauling, placing, erecting, re-erecting, operating, maintaining, moving and removal of portable speed trailers during the construction of this project.

**B Materials**

Furnish portable speed trailer conforming to the appropriate requirements of standard spec 643 and the Manual on Uniform Traffic Control Devices (MUTCD), latest edition, for portable changeable message signs (PCMS).

In rural areas with no view obstructions, the contractor may reduce the minimum mounting height to 5 feet.

Provide a battery powered device with a regulatory speed limit sign and a radar speed sign displaying speed in mph. The flash rate should be between 50 and 60 cycles per minute. Place the sign so that in the operating mode the bottom of the message panel is 5 feet or higher above the top of curb or near edge of pavement. Orient the message panel so the message is legible from 850 feet under both day and night conditions.

**C Construction**

Furnish, haul, place, erect, re-erect, operate, maintain, move, and remove devices at locations as the plans show and as directed by the engineer.

Coordinate the placement and duration of these devices with the engineer/CMT traffic at least 24 hours before its intended use and accommodate within the project. Provide an area to park the devices that is still visible to traffic.

Space five traffic control drums at ten-foot intervals as needed in front of the portable speed trailer.

Move devices not performing as intended to the satisfaction of the engineer within 24 hours of notification.

**D Measurement**

The department will measure Portable Speed Trailer by the day, acceptably completed. For this special provision, the number of days measured is defined as the number of calendar days that the portable speed trailer is used in moving operations or short-term stationary work. A calendar day begins with each deployment within a defined time-frame and exceeding two hours.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0045.001	Portable Speed Trailer	DAY

Payment is full compensation for furnishing, hauling, placing, erecting, re-erecting, operating, maintaining, moving and removal of portable speed trailers during the construction of this project. Drums are paid separately under traffic control items.

**Schedule of Items**

Attached, dated July 3, 2019, are the revised Schedule of Items Page 22.

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20190709002 Project(s): 1007-12-74, 1007-12-75

Federal ID(s): WISC 2019497, WISC 2019498

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0634	SPV.0090 Special 207. Concrete Barrier Temporary Precast Delivered - Department Owned	10,050.000 LF	_____.	_____.
0636	SPV.0090 Special 208. Removing Department-Owned Concrete Barrier Precast	7,876.000 LF	_____.	_____.
0638	SPV.0045 Special 001. Portable Speed Trailer	410.000 DAY	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.