



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

January 8, 2020

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #20: 9465-00-71, WISC 2019 808
Lincoln County Line – USH 51
S Leisure Dr to S Garth Lake Rd
CTH Y
Oneida County

Letting of January 14, 2020

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
4	Traffic
12	Clearing and Grubbing
15	Temporary Diversion Channel, Item SPV.0105.01

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
208.0100	Borrow	CY	7,221	-950	6,271
305.0120	Base Aggregate Dense 1 ¼-Inch	Ton	7,590	3,250	10,840
624.0100	Water	MGAL	100	31	131

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
630.0160	Seed Mix No. 60	LB	0	34	34

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
28	Miscellaneous Quantities (Revised mainline unexpanded fill area and borrow quantity.)
29	Miscellaneous Quantities (Revised mainline base aggregate dense 1 ¼-inch and water quantities.)
30	Miscellaneous Quantities (Added Seed Mix No.60 quantity to Landscaping Items.)
31	Miscellaneous Quantities (Revised "For Information Only" Temporary Diversion Channel quantities of geotextile fabric and sand bags.)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

9465-00-71

January 8, 2020

Special Provisions

3. Prosecution and Progress

Replace paragraph one under section titled Fish Spawning with the following:

There shall be no instream disturbance of McCormick Creek as a result of construction activity under or for this contract, between March 1 and June 15, in order to avoid adverse impacts upon the spawning of fish.

4. Traffic

Replace entire article language with the following:

CTH Y will be closed to through traffic and remain open to local traffic only, except when cross culverts are being installed, all traffic is to be detoured. The detour signing will be installed by the contractor. Access will be maintained to side roads and business entrances within the construction limits. Additional intermediate construction staging or staging gaps, not shown on the plans may be necessary to maintain continuous access to all properties. The contractor shall provide, install, and maintain all construction staging items as part of this contract.

12. Clearing and Grubbing

Replace entire article language with the following:

Clear and grub all areas according to standard spec 201 and as hereinafter provided.

Property owners to retain ownership of all hardwood trees being removed in easement or new right-of-way areas. Remove and dispose of all trees, shrubs, brush, or branches not wanted by the property owner according to standard spec 201. Cut all hardwood to 8 foot or shorter lengths, and coordinate with the property owner for location and placement of hardwood.

15. Temporary Diversion Channel, Item SPV.0105.01

Replace paragraph eight under section titled C Construction with the following:

Upon completion of the culvert installation, remove all diversion devices from the waterway. Remove and dispose of the geotextile fabric above the stone bottom. Backfill the diversion channel with an engineer approved material. The material used, and the construction methods shall conform to the appropriate specifications in standard spec 205 and 208. All disturbed wetland areas must be filled with native organic fill material and seeded with No. 60 seed mix per standard specifications.

Schedule of Items

Attached, dated January 8, 2020, are the revised Schedule of Items Pages 1 – 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 28, 29, 30 and 31.

END OF ADDENDUM

CLEARING AND GRUBBING ITEMS

STATION	LOCATION	201.0105 CLEARING (STA)	201.0205 GRUBBING (STA)
24+00	RT	1	1
28+00	LT	1	1
30+00	RT	2	2
35+00	LT & RT	11	11
48+00	RT	2	2
50+00	LT & RT	14	14
68+00	RT	2	2
99+00	RT	4	4
TOTALS		37	37

REMOVING SMALL PIPE CULVERTS

STATION	LOCATION	203.0100 EACH	COMMENTS
31+11	CL	1	15' CMP
71+24	CL	1	57" X 38" CMP
TOTALS		2	

REMOVING ASPHALTIC SURFACE BUTT JOINTS

STATION	LOCATION	204.0115 SY	COMMENTS
800	ML	428	S LESURE DR
12+97	LT	284	S LESURE DR
22+05	LT	21	DRIVEWAY
23+06	LT	21	DRIVEWAY
23+68	LT	21	DRIVEWAY
26+01	LT	21	DRIVEWAY
26+87	LT	21	DRIVEWAY
27+29	LT	21	DRIVEWAY
85+62	LT	21	DRIVEWAY
95+42	LT	21	DRIVEWAY
101+10	RT	21	DRIVEWAY
101+43	RT	21	DRIVEWAY
110+50	RT	428	DRIVEWAY
TOTAL		1,351	

REMOVING DELINEATORS AND MARKERS

STATION	LOCATION	204.0180 EACH
13+40	LT	1
22+40	LT	1
26+70	LT	1
27+50	LT	1
TOTALS		4

From/To Station	Location	Common Excavation (1)		EBS Excavation (Item # 205.0100)	Salvaged/Unusable Pavement Material (4)	Available Material (5)	Unexpanded Fill (CY)	Expanded Fill Factor (13)	Mass Ordinate +/- (14)	Waste (CY)	Borrow (Item # 208.0100) (CY)
		Cut (2) (CY)	Excavation (CY)								
8+00 to 110+50	Mainline N Leisure Dr	1244	0	0	0	1244	6012	7515	-6271	0	6271
		86	0	0	0	86	0	0	86	86	0
Grand Total		1331	0	0	0	1331	6012	7515	-6184	86	6271
Total Common Exc											1331

1) Common Excavation is the sum of the Cut and EBS Excavation columns. Item number 205.0100

2) Salvaged/Unusable Pavement Material is included in Cut.

4) Salvaged/Unusable Pavement Material

5) Available Material = Cut - Salvaged/Unusable Pavement Material

13) Expanded Fill Factor = 1.25

Depending on selections:

Or

Or

Or

14) The Mass Ordinate +/- Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.

Addendum No. 01
ID 9465-00-71
Revised Sheet 28
January 8, 2020

PROJECT NO: 9465-00-71

HWY: CTH Y

COUNTY: ONEIDA


MISCELLANEOUS QUANTITIES

SHEET NO: 28

E

AGGREGATE ITEMS

STATION - CATEGORY CODE	STATION - LOCATION	305.0110 BASE AGGREGATE DENSE 3/4-INCH	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	624.0100 WATER MGAL
8+00 - 110+50	MANLINE BASE DRIVEWAYS	2,650	10,400	126
8+00 - 110+50	CULVERT PPS	--	440	5
			--	--
TOTALS	30	2,650	10,840	131



PULVERIZE AND RELAY

STATION - CATEGORY CODE	STATION - LOCATION	325.0100 CMP	374.1020.S COMPACTION
8+00 - 110+50	MANLINE	41,100	41,100
TOTALS	41,100	41,100	

CULVERT PIPE ITEMS

STATION - CATEGORY CODE	LOCATION	CPRC Class IV 15-INCH	AW FOR RCCP 15-INCH	CPRCHE CLASS HE-III 38X60-INCH	AW FOR CPRCHE 38X60-INCH	MARKER POSTS CULVERT END FLEXIBLE	CULVERT PIPE CHECKS EACH	CONSTRUCTION STAKING
15+14	LT	--	--	--	--	--	1	--
15+59	LT	--	--	--	--	--	1	--
31+11	CL	74	2	--	--	2	2	1
71+24	CL	--	--	46	2	2	6	1
TOTALS		74	2	46	2	4	10	2

ASPHALTIC ITEMS

STATION - CATEGORY CODE	STATION - LOCATION	455.0605 TACK COAT	460.6223 HMA Pavement 3 MT 58-28 S	460.6244 HMA Pavement 4 MT 58-34 S	465.0120 ASPHALTIC SURFACE DRIVEWAYS	465.0315 ASPHALTIC FLUMES
8+00 - 110+50	MANLINE	1,410	3,800	2,950	--	47
	SIDEROADS DRIVEWAYS	270	730	200	--	--
		--	--	--	38	--
TOTALS	1,680	4,530	3,150	38	47	

CONCRETE CURB AND GUTTER ITEMS

STATION - CATEGORY CODE	STATION - LOCATION	601.0657 CONCRETE CURB & GUTTER 6-INCH SLOPED 36-INCH TYPED	660.5500 CONSTRUCTION STAKING CURB & GUTTER
50+00 - 54+78	LT	478	478
58+13 - 66+70	LT	857	857
61+81 - 64+25	RT	244	244
TOTALS		1,579	1,579

Addendum No. 01
ID 9465-00-71
Revised Sheet 29
January 8, 2020



Proposal Schedule of Items

Proposal ID: 20200114020 Project(s): 9465-00-71

Federal ID(s): WISC 2019808

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	37.000 STA	_____	_____
0004	201.0205 Grubbing	37.000 STA	_____	_____
0006	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____	_____
0008	204.0115 Removing Asphaltic Surface Butt Joints	1,351.000 SY	_____	_____
0010	204.0180 Removing Delineators and Markers	4.000 EACH	_____	_____
0012	205.0100 Excavation Common	1,331.000 CY	_____	_____
0014	208.0100 Borrow	6,271.000 CY	_____	_____
0016	209.2100 Backfill Granular Grade 2	30.000 CY	_____	_____
0018	213.0100 Finishing Roadway (project) 01. 9465-00-71	1.000 EACH	_____	_____
0020	305.0110 Base Aggregate Dense 3/4-Inch	2,650.000 TON	_____	_____
0022	305.0120 Base Aggregate Dense 1 1/4-Inch	10,840.000 TON	_____	_____
0024	325.0100 Pulverize and Relay	41,100.000 SY	_____	_____
0026	374.1020.S QMP Pulverize and Relay Compaction	41,100.000 SY	_____	_____
0028	455.0605 Tack Coat	1,680.000 GAL	_____	_____
0030	460.2000 Incentive Density HMA Pavement	4,920.000 DOL	1.00000	4,920.00
0032	460.6223 HMA Pavement 3 MT 58-28 S	4,530.000 TON	_____	_____



Proposal Schedule of Items

Proposal ID: 20200114020 Project(s): 9465-00-71

Federal ID(s): WISC 2019808

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	460.6244 HMA Pavement 4 MT 58-34 S	3,150.000 TON	_____.	_____.
0036	465.0120 Asphaltic Surface Driveways and Field Entrances	38.000 TON	_____.	_____.
0038	465.0315 Asphaltic Flumes	47.000 SY	_____.	_____.
0040	522.0415 Culvert Pipe Reinforced Concrete Class IV 15-Inch	74.000 LF	_____.	_____.
0042	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	2.000 EACH	_____.	_____.
0044	522.2338 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 38x60-Inch	46.000 LF	_____.	_____.
0046	522.2638 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 38x60-Inch	2.000 EACH	_____.	_____.
0048	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	1,579.000 LF	_____.	_____.
0050	618.0100 Maintenance And Repair of Haul Roads (project) 01. 9465-00-71	1.000 EACH	_____.	_____.
0052	619.1000 Mobilization	1.000 EACH	_____.	_____.
0054	624.0100 Water	131.000 MGAL	_____.	_____.
0056	625.0100 Topsoil	17,100.000 SY	_____.	_____.
0058	627.0200 Mulching	8,550.000 SY	_____.	_____.
0060	628.1104 Erosion Bales	13.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200114020 Project(s): 9465-00-71

Federal ID(s): WISC 2019808

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	628.1504 Silt Fence	6,380.000 LF	_____.	_____.
0064	628.1520 Silt Fence Maintenance	6,380.000 LF	_____.	_____.
0066	628.2004 Erosion Mat Class I Type B	8,550.000 SY	_____.	_____.
0068	628.7504 Temporary Ditch Checks	950.000 LF	_____.	_____.
0070	628.7555 Culvert Pipe Checks	10.000 EACH	_____.	_____.
0072	629.0210 Fertilizer Type B	13.000 CWT	_____.	_____.
0074	630.0120 Seeding Mixture No. 20	462.000 LB	_____.	_____.
0076	630.0200 Seeding Temporary	462.000 LB	_____.	_____.
0078	630.0500 Seed Water	385.000 MGAL	_____.	_____.
0080	633.5200 Markers Culvert End	4.000 EACH	_____.	_____.
0082	634.0614 Posts Wood 4x6-Inch X 14-FT	22.000 EACH	_____.	_____.
0084	634.0616 Posts Wood 4x6-Inch X 16-FT	9.000 EACH	_____.	_____.
0086	637.2210 Signs Type II Reflective H	255.360 SF	_____.	_____.
0088	638.2102 Moving Signs Type II	1.000 EACH	_____.	_____.
0090	638.2602 Removing Signs Type II	40.000 EACH	_____.	_____.
0092	638.3000 Removing Small Sign Supports	31.000 EACH	_____.	_____.
0094	642.5001 Field Office Type B	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200114020 Project(s): 9465-00-71
 Federal ID(s): WISC 2019808

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	643.0420 Traffic Control Barricades Type III	700.000 DAY	_____.	_____.
0098	643.0705 Traffic Control Warning Lights Type A	700.000 DAY	_____.	_____.
0100	643.0900 Traffic Control Signs	4,550.000 DAY	_____.	_____.
0102	643.0920 Traffic Control Covering Signs Type II	9.000 EACH	_____.	_____.
0104	643.1050 Traffic Control Signs PCMS	35.000 DAY	_____.	_____.
0106	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0108	646.1020 Marking Line Epoxy 4-Inch	41,000.000 LF	_____.	_____.
0110	650.4500 Construction Staking Subgrade	130.000 LF	_____.	_____.
0112	650.5000 Construction Staking Base	10,450.000 LF	_____.	_____.
0114	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,579.000 LF	_____.	_____.
0116	650.6000 Construction Staking Pipe Culverts	2.000 EACH	_____.	_____.
0118	650.8000 Construction Staking Resurfacing Reference	10,450.000 LF	_____.	_____.
0120	650.9910 Construction Staking Supplemental Control (project) 01. 9465-00-71	LS	LUMP SUM	_____.
0122	690.0150 Sawing Asphalt	160.000 LF	_____.	_____.
0124	740.0440 Incentive IRI Ride	7,770.000 DOL	1.00000	7,770.00
0126	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	300.000 HRS	5.00000	1,500.00



Proposal Schedule of Items

Proposal ID: 20200114020 Project(s): 9465-00-71

Federal ID(s): WISC 2019808

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0130	SPV.0105 Special 01. Temporary Diversion Channel	LS	LUMP SUM	_____.
0132	SPV.0170 Special 01. Proof Rolling	103.000 STA	_____.	_____.
0134	630.0160 Seeding Mixture No. 60	34.000 LB	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

