



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

April 9, 2020

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #01: 1011-01-63, WISC 2020 124**  
**Madison - Portage**  
**Patton Road Bridge B-11-0018**  
**IH 39**  
**Columbia County**

### Letting of April 14, 2020

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
4	Traffic
5	Holiday Work Restrictions

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0420	Barricades Type III	Days	548	130	678
643.0705	Warning Lights Type A	Days	664	156	820
643.0900	Traffic Control Signs	Days	1,508	234	1,742

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
11	Miscellaneous Quantities (Revised Traffic Control Quantities)

**Other**

Revise the contract time for completion from a completion date of July 21, 2020 to a completion date of September 11, 2020.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**1011-01-63**

**April 9, 2020**

**Special Provisions**

**3. Prosecution and Progress.**

*Replace first 3 paragraphs with the following:*

Do not begin work prior to noon on July 6, 2020.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

**4. Traffic.**

*Replace entire article language with the following:*

Submit to the engineer for approval a detailed traffic control plan for any changes to the proposed traffic control as shown in the plans. The contractor must submit the plan to the engineer at least 14 days prior to anticipated use. Modifications to the traffic control plan may be required by the engineer at any time for traffic safety and mobility.

Maintain access at all times to the intersection of Patton Road and Meek Road. There will be no signed detour route for Patton Road.

Notify appropriate local emergency services at least 24 hours prior to any of the following:

1. Roadway closure of Patton Road
2. Opening of Patton Road
3. Temporary lane closures on IH 39

Keep all lanes of IH 39 open to traffic at all times except for lane closures in accordance with the following schedule:

<b>IH 39 – Single Lane Closure Only</b>		
<b>Month</b>	<b>Northbound</b>	<b>Southbound</b>
July	Sunday 9:00 PM through Wednesday 3:00 PM Wednesday 6:00 PM through Thursday 12:00 PM Thursday 6:00 PM through Friday 8:00 AM Friday 9:00 PM through Saturday 6:00 AM	Sunday 9:00 PM through Friday 12:00 PM Friday 9:00 PM through Saturday 6:00 AM
August	Sunday 9:00 PM through Thursday 11:00 AM Thursday 6:00 PM through Friday 9:00 AM Friday 9:00 PM through	Sunday 9:00 PM through Friday 11:00 AM Friday 9:00 PM through Saturday 6:00 AM

	Saturday 6:00 AM	
September	Sunday 9:00 PM through Thursday 4:00 PM Thursday 6:00 PM through Friday 11:00 AM Friday 9:00 PM through Saturday 6:00 AM	Sunday 9:00 PM through Saturday 6:00 AM

Traffic control shall conform to SDD 15D12-02 "Traffic Control, Lane Closure, Speeds Greater Than 40 MPH". Open lanes shall maintain a minimum clear width of 12 feet at all times.

Provide the engineer with a schedule of lane and shoulder closures a minimum of two weeks prior to the start of construction for incorporation into the Wisconsin Lane Closure System.

Shoulder closures are allowed at any time, however, only one shoulder in each direction will be allowed at any one time. Traffic control shall conform to SDD 15D27-01 "Traffic Control, Shoulder Closure on Divided Highway, Speeds Greater Than 40 MPH".

Submit any traffic control change request to the engineer at least 72 hours prior to an actual traffic control change. A request does not constitute approval.

#### Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

**TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION**

<b>Closure type with height, weight, or width restrictions (available width, all lanes in one direction &lt; 16')</b>	<b>MINIMUM NOTIFICATION</b>
Lane and shoulder closures	7 calendar days
Full roadway closures	7 calendar days
Ramp closures	7 calendar days
Detours	7 calendar days
<b>Closure type without height, weight, or width restrictions (available width, all lanes in one direction ≥ 16')</b>	<b>MINIMUM NOTIFICATION</b>
Lane and shoulder closures	3 business days
Ramp closures	3 business days
Modifying all closure types	3 business days

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

#### 5. Holiday Work Restrictions.

*Replace entire article language with the following:*

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying IH 39 traffic, and entirely clear the traveled way and shoulders of such portions of the

highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Thursday, July 2, 2020 to 6:00 AM Monday, July 6, 2020 for Independence Day;
  - From noon Friday, September 4, 2020 to 6:00 AM Tuesday, September 8, 2020 for Labor Day.
- stp-107-005 (20181119)

**Schedule of Items**

Attached, dated April 9, 2020, are the revised Schedule of Items Page 4.

**Plan Sheets**

The following 8 ½ x 11-inch plan sheets are attached and made part of the plans for this proposal:

Revised: 11

END OF ADDENDUM

Addendum No. 01  
ID 1011-01-63  
Revised Sheet 11  
April 9, 2020

REMOVING SIGNS AND SMALL SIGN SUPPORTS

REMOVING SMALL SIGN SIGNS TYPE II SUPPORTS (63.8.2602) (638.3000) (EACH)		SIGN MESSAGE (EACH)	
STATION	LOCATION	RT	STOP
14+50	RT	STOP AHD/ FARM MACHINERY	2
22+05	RT	STOP	1
TOTALS		3	2

FIELD OFFICE TYPE B

LOCATION	(EACH)
PROJECT	1
TOTALS	1

TRAFFIC CONTROL ITEMS

LOCATION	SERVICE PERIOD (DAYS)	NO. IN (643.0300)	DRUMS TYPE III	BARRICADES TYPE III	WARNING LIGHTS TYPE A	WARNING LIGHTS TYPE C	ARROW BOARDS	TRAFFIC CONTROL	DAYS		PAY	
									NO. IN (643.0420)	NO. IN (643.0715)	NO. IN (643.0800)	NO. IN (643.0900)
PATTON ROAD	67	---	10	670	12	---	---	---	18	1206	---	---
IH-39 (SHOULDER CLOSURE)	30	30	---	---	---	10	300	2	60	480	---	---
IH-39 (LANE CLOSURE)	4	80	2	8	4	34	136	4	16	56	---	---
PROJECT	---	---	---	---	---	---	---	---	---	---	---	---
TOTALS	---	---	---	678	820	436	76	---	---	1742	---	1

PORTABLE CHANGEABLE MESSAGE SIGN

LOCATION	SERVICE PERIOD (DAYS)	NO. IN (EACH)	NO. IN (DAYS)
PATTON ROAD	7	2	14
TOTALS	---	---	14

CONSTRUCTION STAKING

STATION TO STATION	LOCATION	RESURFACING REFERENCE LINE (650.8000) (LF)	SUPPLEMENTAL CONTROL (650.9910) (LS)
17+84 - 19+28	PATTON RD	144	---
21+32 - 22+18	PATTON RD	86	---
PROJECT	---	---	1
TOTALS	---	230	1

SAWING ASPHALT

STATION	LOCATION	(LF)
17+84	PATTON ROAD	22
22+18	PATTON ROAD	95
TOTALS	---	117

PROJECT NO: 1011-01-63

HWY: IH 39

COUNTY: COLUMBIA

MISCELLANEOUS QUANTITIES

SHEET: 11

E

FILE NAME: \_\_\_\_\_ PLOT DATE: \_\_\_\_\_ PLOT NAME: \_\_\_\_\_ ORG DATE: \_\_\_\_\_ ORIGINATOR: \_\_\_\_\_ PLOT SCALE: 1:1



Proposal Schedule of Items

Proposal ID: 20200414001 Project(s): 1011-01-63

Federal ID(s): WISC 2020124

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	2.000 STA	_____.	_____.
0004	201.0205 Grubbing	2.000 STA	_____.	_____.
0006	204.0115 Removing Asphaltic Surface Butt Joints	200.000 SY	_____.	_____.
0008	204.0120 Removing Asphaltic Surface Milling	480.000 SY	_____.	_____.
0010	204.0165 Removing Guardrail	246.000 LF	_____.	_____.
0012	204.0170 Removing Fence	20.000 LF	_____.	_____.
0014	213.0100 Finishing Roadway (project) 01. 1011-01-63	1.000 EACH	_____.	_____.
0016	305.0110 Base Aggregate Dense 3/4-Inch	40.000 TON	_____.	_____.
0018	455.0605 Tack Coat	53.000 GAL	_____.	_____.
0020	465.0105 Asphaltic Surface	106.000 TON	_____.	_____.
0022	465.0315 Asphaltic Flumes	8.000 SY	_____.	_____.
0024	502.2000 Compression Joint Sealer Preformed Elastomeric (width) 01. 2 1/4-Inch	106.000 LF	_____.	_____.
0026	502.3101 Expansion Device 01. B-11-0018	24.000 LF	_____.	_____.
0028	502.3200 Protective Surface Treatment	830.000 SY	_____.	_____.
0030	505.0600 Bar Steel Reinforcement HS Coated Structures	1,195.000 LB	_____.	_____.
0032	506.5000 Bearing Assemblies Fixed (structure) 01. B-11-0018	18.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200414001 Project(s): 1011-01-63

Federal ID(s): WISC 2020124

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	506.7050.S Removing Bearings (structure) 01. B-11-0018	18.000 EACH	_____.	_____.
0036	509.0301 Preparation Decks Type 1	20.000 SY	_____.	_____.
0038	509.0302 Preparation Decks Type 2	10.000 SY	_____.	_____.
0040	509.0500 Cleaning Decks	551.000 SY	_____.	_____.
0042	509.1000 Joint Repair	28.000 SY	_____.	_____.
0044	509.1200 Curb Repair	150.000 LF	_____.	_____.
0046	509.1500 Concrete Surface Repair	100.000 SF	_____.	_____.
0048	509.2000 Full-Depth Deck Repair	1.000 SY	_____.	_____.
0050	509.2500 Concrete Masonry Overlay Decks	42.000 CY	_____.	_____.
0052	603.8000 Concrete Barrier Temporary Precast Delivered	1,400.000 LF	_____.	_____.
0054	603.8125 Concrete Barrier Temporary Precast Installed	1,400.000 LF	_____.	_____.
0056	604.9015.S Reseal Crushed Aggregate Slope Paving	280.000 SY	_____.	_____.
0058	614.0905 Crash Cushions Temporary	4.000 EACH	_____.	_____.
0060	616.0100 Fence Woven Wire (height) 01. 54-Inch	20.000 LF	_____.	_____.
0062	618.0100 Maintenance And Repair of Haul Roads (project) 01. 1011-01-63	1.000 EACH	_____.	_____.
0064	619.1000 Mobilization	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200414001 Project(s): 1011-01-63

Federal ID(s): WISC 2020124

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	624.0100 Water	2.000 MGAL	_____.	_____.
0068	625.0500 Salvaged Topsoil	200.000 SY	_____.	_____.
0070	627.0200 Mulching	200.000 SY	_____.	_____.
0072	628.1504 Silt Fence	360.000 LF	_____.	_____.
0074	628.1520 Silt Fence Maintenance	360.000 LF	_____.	_____.
0076	628.1905 Mobilizations Erosion Control	2.000 EACH	_____.	_____.
0078	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0080	628.2004 Erosion Mat Class I Type B	100.000 SY	_____.	_____.
0082	629.0210 Fertilizer Type B	0.130 CWT	_____.	_____.
0084	630.0120 Seeding Mixture No. 20	6.000 LB	_____.	_____.
0086	630.0200 Seeding Temporary	6.000 LB	_____.	_____.
0088	630.0500 Seed Water	5.000 MGAL	_____.	_____.
0090	634.0612 Posts Wood 4x6-Inch X 12-FT	6.000 EACH	_____.	_____.
0092	634.0614 Posts Wood 4x6-Inch X 14-FT	1.000 EACH	_____.	_____.
0094	634.0616 Posts Wood 4x6-Inch X 16-FT	1.000 EACH	_____.	_____.
0096	637.2210 Signs Type II Reflective H	5.180 SF	_____.	_____.
0098	637.2230 Signs Type II Reflective F	41.500 SF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200414001 Project(s): 1011-01-63

Federal ID(s): WISC 2020124

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	638.2602 Removing Signs Type II	3.000 EACH	_____.	_____.
0102	638.3000 Removing Small Sign Supports	2.000 EACH	_____.	_____.
0104	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0106	643.0300 Traffic Control Drums	1,220.000 DAY	_____.	_____.
0108	643.0420 Traffic Control Barricades Type III	678.000 DAY	_____.	_____.
0110	643.0705 Traffic Control Warning Lights Type A	820.000 DAY	_____.	_____.
0112	643.0715 Traffic Control Warning Lights Type C	436.000 DAY	_____.	_____.
0114	643.0800 Traffic Control Arrow Boards	76.000 DAY	_____.	_____.
0116	643.0900 Traffic Control Signs	1,742.000 DAY	_____.	_____.
0118	643.1050 Traffic Control Signs PCMS	14.000 DAY	_____.	_____.
0120	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0122	650.8000 Construction Staking Resurfacing Reference	230.000 LF	_____.	_____.
0124	650.9910 Construction Staking Supplemental Control (project) 01. 1011-01-63	LS	LUMP SUM	_____.
0126	690.0150 Sawing Asphalt	117.000 LF	_____.	_____.
0128	SPV.0060 Special 01. Cleaning And Painting Bearings	18.000 EACH	_____.	_____.
Section: 0001			Total:	_____.

Total Bid: \_\_\_\_\_.

