



Wisconsin Department of Transportation

May 05, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #08: 1030-22-84
Oakwood Noise Barrier
500'S to 1500'N of Oakwood Rd
IH 41
Milwaukee County

Letting of May 12, 2020

This is Addendum No. 01 which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
20	Noise Barriers Double-Sided Sound Absorptive N-40-93, Item 531.0200.S.0001

Other

Revise the contract time for completion from a completion date of October 16, 2020 to a completion date of November 20, 2020.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1030-22-84

May 5, 2020

Special Provisions

3. Prosecution and Progress

Replace entire section titled Interim Liquidated Damages with the following:

Interim Liquidated Damages

IH 41 Northbound/ IH 94 Westbound Long-Term Outside Lane Closure and Ramp EA Long-Term Closure

The outside lane of IH 41 Northbound / IH 94 Westbound and Ramp EA can be closed for a maximum of 60 consecutive calendar days between August 24, 2020 and November 20, 2020. Complete all work on IH 41 Northbound / IH 94 Westbound necessary to open all lanes of IH 41 Northbound / IH 94 Westbound and Ramp EA, including noise barrier construction, concrete barrier, pavement marking, guardrail, and all other incidentals necessary to fully reopen the roadways.

If the contractor fails to complete the work necessary to reopen IH 41 Northbound/ IH 94 Westbound to traffic in four 12' lanes and to reopen Ramp EA to traffic within a maximum of 60 calendar days between August 24, 2020 and November 20, 2020, the department will assess the contractor \$4,000 in interim liquidated damages for each calendar day that the contract work remains incomplete beyond 60 calendar days, or the number of calendar days approved by the engineer. An entire calendar day will be charged for any period of time within each calendar day that the outside lane of IH 41 Northbound/ IH 94 Westbound remains closed and/or Ramp EA remains closed beyond 12:01 AM. If the outside lane of IH 41 Northbound/ IH 94 Westbound remains closed and/or Ramp EA remains closed beyond the overall contract completion date, only the liquidated damages provided in standard spec 108.11 will be assessed by the department.

20. Noise Barriers Double-Sided Sound Absorptive N-40-93, Item 531.0200.S.0001.

Replace paragraph two under section titled B.2.1 Structural and Foundation Design with the following:

The minimum design wind pressure shall be 35 psf (Strength III) for ground mounted noise barriers and 40 psf (Strength III) for structure mounted noise barriers. For ground and structure mounted noise barriers, the minimum Service I design wind pressure shall be 15 psf. All wind loads shall be applied perpendicular to the barrier, alternately in each direction.

END OF ADDENDUM