

GRE

WITH:

PROJECT ID:

4987-11-71


COUNTY:

BROWN

JANUARY 2022
ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 62



DESIGN DESIGNATION

A.A.D.T.	2022	=	5,735
A.A.D.T.	2042	=	6,337
D.H.V.		=	-
D.D.		=	60/40
T.		=	5.0%
DESIGN SPEED		=	25 mph
ESALS		=	1,200,000

CONVENTIONAL SYMBOLS

PLAN		PROFILE	
CORPORATE LIMITS		GRADE LINE	
PROPERTY LINE		ORIGINAL GROUND	
LOT LINE		MARSH OR ROCK PROFILE (To be noted as such)	
LIMITED HIGHWAY EASEMENT		SPECIAL DITCH	
EXISTING RIGHT OF WAY		GRADE ELEVATION	
PROPOSED OR NEW R/W LINE		CULVERT (Profile View)	
SLOPE INTERCEPT		UTILITIES	
REFERENCE LINE		ELECTRIC	
EXISTING CULVERT		FIBER OPTIC	
PROPOSED CULVERT (Box or Pipe)		GAS	
COMBUSTIBLE FLUIDS		SANITARY SEWER	
MARSH AREA		STORM SEWER	
WOODED OR SHRUB AREA		TELEPHONE	
		WATER	
		UTILITY PEDESTAL	
		POWER POLE	
		TELEPHONE POLE	

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT


C GREEN BAY, TAYLOR STREET

BEAVER DAM CREEK BRIDGE

LOC STR

BROWN COUNTY

STATE PROJECT NUMBER
4987-11-71



LAYOUT
SCALE 0 1000 FT
TOTAL NET LENGTH OF CENTERLINE = 0.019 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), BROWN COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12B.

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
4987-11-71		

ACCEPTED FOR
CITY OF GREEN BAY

07/12/21
DATE
DIRECTOR PUBLIC WORKS

ORIGINAL PLANS PREPARED BY
AYRES

WISCONSIN
RYAN D. SCHAITEL
44367
GREEN BAY, WI
PROFESSIONAL ENGINEER
7-8-21
(Date)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY
Surveyor AYRES
Designer AYRES
Project Manager TIMOTHY VERHAGEN, PE
Regional Examiner
Regional Supervisor BRIAN EDWARDS, PE

APPROVED FOR THE DEPARTMENT
DATE: 7/20/2021
Y. Verhagen
(Signature)

E

GENERAL NOTES

THE LOCATION OF EXISTING UTILITY FACILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY FACILITIES WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

FILL EXPANSION FACTOR IS 30%.

PROPERTY LINES AS SHOWN ARE APPROXIMATE.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT APPROVAL OF THE ENGINEER.

BEARINGS SHOWN ON THIS PLAN ARE TRUE BEARINGS TO THE NEAREST SECOND.

ALL TIES ON THIS PLAN ARE HORIZONTAL UNLESS DESCRIBED OTHERWISE.

PRIOR TO ORDERING DRAINAGE PIPES AND STRUCTURES, VERIFY RELATED DRAINAGE INFORMATION IN THE PLAN AND PROVIDE DOCUMENTATION TO THE ENGINEER.

INLET AND DISCHARGE ELEVATIONS FOR DRAINAGE STRUCTURES SHOWN ON THE PLAN ARE APPROXIMATE AND SHALL BE VERIFIED IN THE FIELD, ELEVATIONS MAY BE ADJUSTED BY THE ENGINEER TO FIT FIELD CONDITIONS.

EROSION CONTROL LOCATIONS AS SHOWN ON THE EROSION CONTROL PLAN ARE APPROXIMATE. THE EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.

DISTURBED AREAS WITHIN THE RIGHT OF WAY, EXCEPT THE AREAS WITHIN THE FINISHED SUBGRADE SHOULDER POINTS ARE TO BE SEEDED AND EROSION MAT AS DIRECTED BY THE ENGINEER.

SAW CUT LOCATIONS SHOWN ON THE PLAN ARE SUBJECT TO ADJUSTMENT BY THE ENGINEER IN THE FIELD. THE LINE OF SUCH SAW CUTS WILL BE NEATLY DELINEATED THROUGH THE ASPHALT WITHOUT ANY DAMAGE TO THE REMAINING PORTION OF THE EXISTING PAVEMENT.

RUNOFF COEFFICIENT TABLE

	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER									
ROW CROPS	.08 .22	.16 .30	.22 .38	.12 .26	.20 .34	.27 .44	.15 .30	.24 .37	.33 .50	.19 .34	.28 .41	.38 .56
MEDIAN STRIP-TURF	.19 .24	.20 .26	.24 .30	.19 .25	.22 .28	.26 .33	.20 .26	.23 .30	.30 .37	.20 .27	.25 .32	.30 .40
SIDE SLOPE-TURF			.25 .32			.27 .34			.28 .36			.30 .38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											

TOTAL PROJECT AREA= 0.184 ACRES
 TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.166 ACRES
 SOIL GROUP C/D

UTILITIES

*** AT&T DISTRIBUTION**

205 S. JEFFERSON ST.
 GREEN BAY, WI 54301
 ATTENTION: VICTORIA KASSAB
 E-MAIL: vk352k@att.com

TELEPHONE 920-401-7512

*** LUMEN**

3235 INTERTECH DR.
 SUITE 600
 BROOKFIELD, WI 53045
 ATTENTION: BRAHIM GADDOUR
 E-MAIL: brahim.gaddour@lumen.com

TELEPHONE 414-908-1027

CELL 414-704-1026

*** CHARTER COMMUNICATIONS**

3520 E. DESTINATION DR.
 APPLETON, WI 54915
 ATTENTION: VINCE ALBIN
 E-MAIL: Vince.albin@charter.com

TELEPHONE 920-831-9249

CELL 920-378-0444

*** WISCONSIN PUBLIC SERVICE - ELECTRIC**

PO BOX 19001
 700 N. ADAMS STREET
 GREEN BAY, WI 54307-9001
 ATTENTION: ROBERT SMITH
 E-MAIL: robert.smith@wisconsinpublicservice.com

TELEPHONE 920-617-5284

CELL 715-622-0037

*** CITY OF GREEN BAY - SEWER**

110 N. JEFFERSON ST.
 GREEN BAY, WI 54301
 ATTENTION: MATT HECKENLAIBLE
 E-MAIL: matthe@greenbaywi.gov

TELEPHONE 920-448-3100

AFTER HOURS EMERGENCY 920-448-3735

*** WPS - GAS**

2850 S. ASHLAND AVENUE
 GREEN BAY, WI 54304
 ATTENTION: JIM EIDEN
 E-MAIL: james.eiden@wisconsinpublicservice.com

TELEPHONE 920-617-5231

CELL 920-676-8068

*** GREEN BAY WATER UTILITY**

631 S. ADAMS ST.
 GREEN BAY, WISCONSIN 53205-1210
 ATTENTION: KRISTIN ROMANOWICZ
 E-MAIL: kristin.romanowicz@greenbaywi.gov

TELEPHONE 920-448-3480

AFTER HOURS EMERGENCY 920-448-3483

*-MEMBER OF DIGGERS HOTLINE

STANDARD ABBREVIATIONS


ADT	AVERAGE DAILY TRAFFIC	NC	NORMAL CROWN
AC	ASPHALT CEMENT	PT	POINT OF TANGENCY
AGG	AGGREGATE	PC	POINT OF CURVATURE
ASPH	ASPHALT	PI	POINT OF INTERSECTION
BM	BENCH MARK	PE	PRIVATE ENTRANCE
C/L	CENTERLINE	R	RADIUS
CONC	CONCRETE	REM	REMOVE
CMP	CORRUGATED METAL PIPE	R/L OR RL	REFERENCE LINE
CR.	CREEK	RCCP	REINFORCED CONCRETE CULVERT PIPE
D	DEGREE OF CURVE	RCPSS	REINFORCED CONCRETE PIPE STORM SEWER
DHV	DESIGN HOUR VOLUME	R.O.	RUNOUT
ESALS	EQUIVALENT SINGLE AXIS LOADS	R/W	RIGHT-OF-WAY
EXIST	EXISTING	STA	STATION
FE	FIELD ENTRANCE	SE	SUPER ELEVATION
HYD	HYDRANT	SS	STORM SEWER
IP	IRON PIPE OR PIN	T	TANGENT
L	LENGTH OF CURVE	TEL	TELEPHONE
LC	LONG CHORD OF CURVE	TLE	TEMPORARY LIMITED EASEMENT
LR	LENGTH OF RUNOFF	T	TRUCKS
MH	MANHOLE	VC	VERTICAL CURVE
		W	WELL

DEPARTMENT OF NATURAL RESOURCES

WDNR
 2984 SHAWANO AVE.
 GREEN BAY, WISCONSIN 54313
 ATTENTION: JAMES DOPERALSKI
 E-MAIL: JAMES.DOPERALSKI@WISCONSIN.GOV
 TELEPHONE 920-412-0165




Dial 811 or (800)242-8511
 www.DiggersHotline.com




EXISTING TYPICAL SECTION FOR TAYLOR STREET

STA. 9+50 - STA. 10+50




FINISHED TYPICAL SECTION FOR TAYLOR STREET

STA. 9+50 - STA. 10+50



NORMAL




AT DRIVEWAY OPENING AND CURB RAMPS

NOTES:

- CONTRACTION JOINTS SHALL BE SAWED EVERY 15 FEET MAXIMUM OR AS DESIGNATED BY ENGINEER IN FIELD.
- 6"x6" EXPANSION JOINTS (3/4") SHALL BE PLACED AT CURB HEAD AT END OF RADII.
- ① 1-1/2" AT DRIVEWAY OPENINGS, 1/2" AT CURB RAMPS.
- ② 1-1/4"x18" SMOOTH EPOXY COATED DOWEL BARS NECESSARY AT CONTRACTION JOINTS (TYPICAL ACROSS PAVEMENT SECTION)

INTEGRAL CURB AND GUTTER DETAILS

INLET WITH INTEGRAL CURB





NOTES:

- ① IN CASES WHERE THERE IS NO CONTRACTION JOINT, REPLACE WITH #4 REBAR.
- ② #4 REBAR TO BE PLACED AT A MINIMUM DEPTH OF 4 INCHES (OR HALF THE DEPTH OF THE PAVEMENT).
- ③ AN 18" MINIMUM CLEARANCE BETWEEN THE EXTERIOR LIMIT OF THE STRUCTURE TO THE DIAMOND BOXOUT.

CONCRETE PAVEMENT INLET AND MANHOLE


MANHOLE IN CONCRETE PAVEMENT OFF C





GENERAL NOTE:
STEPS ARE PROHIBITED IN ALL MANHOLE SECTIONS.

MANHOLE INFORMATION KEY						
A	B	C	D	E	F	G
48"	5"	8"	68"	12"	0.12	8"
60"	6"	10"	80"	15"	0.17	10"
72"	7"	10"	96"	16"	0.18	10"
84"	8"	11"	120"	16"	0.20	11"
96"	9"	12"	126"	17"	0.24	12"




MANHOLE GB

NOTE:

TYPE A INLET PROTECTION IS REQUIRED FOR ALL INLETS AFTER INSTALLATION AND BEFORE CURB PLACEMENT. AFTER CURB PLACEMENT INSTALL TYPE B, C, OR D INLET PROTECTION. (SEE MISCELLANEOUS QUANTITIES)

LEGEND

-  EROSION MAT URBAN CLASS I, TYPE B URBAN
-  SILT FENCE
-  SLOPE INTERCEPT
-  TURBIDITY BARRIER
-  SURFACE WATER FLOW
-  INLET PROTECTION



Estimate Of Quantities

4987-11-71

Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	2.000	2.000
0004	201.0205	Grubbing	STA	2.000	2.000
0006	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. P-5-721	EACH	1.000	1.000
0008	204.0100	Removing Concrete Pavement	SY	330.000	330.000
0010	204.0245	Removing Storm Sewer (size) 01. 24-Inch	LF	26.000	26.000
0012	205.0100	Excavation Common	CY	191.000	191.000
0014	206.1000	Excavation for Structures Bridges (structure) 01. B-5-469	LS	1.000	1.000
0016	210.1500	Backfill Structure Type A	TON	390.000	390.000
0018	213.0100	Finishing Roadway (project) 01. 4987-11-71	EACH	1.000	1.000
0020	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	198.000	198.000
0022	415.0080	Concrete Pavement 8-Inch	SY	211.000	211.000
0024	415.0410	Concrete Pavement Approach Slab	SY	80.000	80.000
0026	416.0620	Drilled Dowel Bars	EACH	56.000	56.000
0028	502.0100	Concrete Masonry Bridges	CY	239.000	239.000
0030	502.3200	Protective Surface Treatment	SY	210.000	210.000
0032	502.3210	Pigmented Surface Sealer	SY	48.000	48.000
0034	505.0400	Bar Steel Reinforcement HS Structures	LB	6,580.000	6,580.000
0036	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	26,460.000	26,460.000
0038	513.7011	Railing Steel Type C2	LF	114.700	114.700
0040	516.0500	Rubberized Membrane Waterproofing	SY	30.000	30.000
0042	522.1024	Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	EACH	1.000	1.000
0044	550.0010	Pre-Boring Unconsolidated Materials	LF	30.000	30.000
0046	550.0500	Pile Points	EACH	16.000	16.000
0048	550.1100	Piling Steel HP 10-Inch X 42 Lb	LF	1,120.000	1,120.000
0050	601.0452	Concrete Curb & Gutter Integral 30-Inch Type D	LF	132.000	132.000
0052	606.0300	Riprap Heavy	CY	130.000	130.000
0054	608.0324	Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	LF	39.000	39.000
0056	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	210.000	210.000
0058	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0060	619.1000	Mobilization	EACH	1.000	1.000
0062	624.0100	Water	MGAL	2.000	2.000
0064	625.0100	Topsoil	SY	200.000	200.000
0066	628.1504	Silt Fence	LF	200.000	200.000
0068	628.1520	Silt Fence Maintenance	LF	400.000	400.000
0070	628.1905	Mobilizations Erosion Control	EACH	5.000	5.000
0072	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0074	628.2008	Erosion Mat Urban Class I Type B	SY	200.000	200.000
0076	628.6005	Turbidity Barriers	SY	146.000	146.000
0078	628.7005	Inlet Protection Type A	EACH	2.000	2.000
0080	628.7015	Inlet Protection Type C	EACH	3.000	3.000
0082	629.0210	Fertilizer Type B	CWT	0.150	0.150
0084	630.0140	Seeding Mixture No. 40	LB	5.000	5.000
0086	630.0200	Seeding Temporary	LB	5.000	5.000
0088	630.0500	Seed Water	MGAL	5.000	5.000
0090	642.5001	Field Office Type B	EACH	1.000	1.000
0092	643.0420	Traffic Control Barricades Type III	DAY	1,088.000	1,088.000
0094	643.0705	Traffic Control Warning Lights Type A	DAY	1,792.000	1,792.000
0096	643.0900	Traffic Control Signs	DAY	768.000	768.000
0098	643.5000	Traffic Control	EACH	1.000	1.000

Estimate Of Quantities

4987-11-71

Line	Item	Item Description	Unit	Total	Qty
0100	645.0111	Geotextile Type DF Schedule A	SY	150.000	150.000
0102	645.0120	Geotextile Type HR	SY	260.000	260.000
0104	646.1020	Marking Line Epoxy 4-Inch	LF	200.000	200.000
0106	650.4000	Construction Staking Storm Sewer	EACH	3.000	3.000
0108	650.4500	Construction Staking Subgrade	LF	100.000	100.000
0110	650.6500	Construction Staking Structure Layout (structure) 01. B-5-469	LS	1.000	1.000
0112	650.7000	Construction Staking Concrete Pavement	LF	100.000	100.000
0114	650.9910	Construction Staking Supplemental Control (project) 01. 4987-11-71	LS	1.000	1.000
0116	650.9920	Construction Staking Slope Stakes	LF	100.000	100.000
0118	690.0250	Sawing Concrete	LF	90.000	90.000
0120	715.0502	Incentive Strength Concrete Structures	DOL	1,434.000	1,434.000
0122	715.0720	Incentive Compressive Strength Concrete Pavement	DOL	500.000	500.000
0124	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. Station	EACH	1.000	1.000
0126	SPV.0060	Special 01. Manhole Covers Type GB-J	EACH	2.000	2.000
0128	SPV.0060	Special 02. Manholes GB 4-FT	EACH	2.000	2.000
0130	SPV.0195	Special 01. Select Crushed Material for Travel Corridor	TON	5.000	5.000

3

CLEARING AND GRUBBING

STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA
9+00	-	11+00	TAYLOR ST	2	2
TOTALS				2	2

REMOVING CONCRETE PAVEMENT

STATION	TO	STATION	LOCATION	204.0100 SY
9+50	-	9+86	TAYLOR ST, RT	180
10+20	-	10+50	TAYLOR ST, RT	150
TOTAL				330

3

REMOVING STORM SEWER

STATION	TO	STATION	LOCATION	204.0245 REMOVING STORM SEWER 24 - INCH LF	REMARKS
9+64.0	-	9+89.7	TAYLOR ST, RT	26	24" RCP
TOTAL				26	

EARTHWORK SUMMARY

Division	From/To Station	Location	Common Excavation (item #205.0100)	Unexpanded Fill	Expanded Fill (13)	Mass Ordinate +/- (14)	Waste	Comment:
			Cut (1)		Factor 1.30			
1	9+50 - 10+50	TAYLOR ST	191	6	8	183	183	
Division 1 Totals			191	6	8	183	183	

- 1) Common Excavation includes existing concrete pavement.
- 13) Expanded Fill. Factor = 1.3 Expanded Fill = Unexpanded Fill * Fill Factor
- 14) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED

BASE AGGREGATE DENSE & WATER

STATION	TO	STATION	LOCATION	305.0120 BASE AGGREGATE DENSE 1 1/4 - INCH TON	624.0100 WATER MGAL
9+50	-	9+85.75	TAYLOR ST	108	1
10+20.25	-	10+50	TAYLOR ST	90	1
TOTALS				198	2

CONCRETE PAVEMENT

STATION	TO	STATION	LOCATION	415.0080 CONCRETE PAVEMENT 8-INCH SY	415.0410 CONCRETE PAVEMENT APPROACH SLAB SY
9+50	-	9+85.75	TAYLOR ST.	119	40
10+20.25	-	10+50	TAYLOR ST.	92	40
TOTALS				211	80

CONCRETE CURB & GUTTER

STATION	TO	STATION	LOCATION	601.0452 CONCRETE CURB & GUTTER INTEGRAL 30-INCH TYPE D LF
9+50	-	9+86	TAYLOR ST, RT	36
9+50	-	9+86	TAYLOR ST, LT	36
10+20	-	10+50	TAYLOR ST, RT	30
10+20	-	10+50	TAYLOR ST, LT	30
TOTAL				132

STORM SEWER STRUCTURES AND COVERS

STRUCTURE NO.	STATION	OFFSET	LOCATION	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH EACH	SPV.0060.01 MANHOLE COVERS TYPE GB-J EACH	SPV.0060.02 MANHOLES GB 4-FT EACH	RIM ELEV.	OUTLET INVERT ELEV.	STRUCTURE DEPTH FT.
1	9+63.8	10.4' RT	TAYLOR ST	-	1	1	641.33	634.82	5.26
2	9+72.3	31.7' RT	TAYLOR ST	-	1	1	641.03	634.70	5.08
3	9+93.7	37.8' RT	TAYLOR ST	1	-	-	-	634.60	-
TOTALS				1	2	2			

NOTES:

- OFFSET DISTANCE TO CENTER FOR MANHOLES OR END OF ENDWALL.
- GRATE ELEVATION IS FIGURED TO CENTER OF MANHOLE COVER OR ENDWALL INVERT.
- FINAL LOCATION TO BE DETERMINED BY THE ENGINEER.
- STRUCTURE DEPTHS COMPUTED WITH A MINIMUM OF 6-INCHES ADJUSTMENT TO COVERS

STORM SEWER PIPE

FROM	TO	LOCATION	608.0324 REINFORCED CONCRETE CLASS III 24-INCH LF	INLET ELEVATION	DISCHARGE ELEVATION	SLOPE FT/FT
1	2	TAYLOR ST, RT	23	634.82	634.70	0.0040
2	3	TAYLOR ST, RT	16	634.70	634.60	0.0045
TOTALS			39			

DRILLED DOWEL BARS

STATION	LOCATION	416.0620 EACH	REMARKS
9+50	TAYLOR ST	28	SOUTH MATCHPOINT
10+50	TAYLOR ST	28	NORTH MATCHPOINT
TOTAL		56	

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED

TOPSOIL, FERTILIZER, AND SEED

STATION	TO	STATION	LOCATION	625.0100 TOPSOIL SY	629.0210 FERTILIZER TYPE B CWT	630.0140 SEEDING MIXTURE NO. 40 LB	630.0200 SEEDING TEMPORARY LB	630.0500 SEED WATER MGAL
9+50	-	9+96	TAYLOR ST, LT	45	0.03	1	1	1
9+50	-	9+96	TAYLOR ST, RT	45	0.03	1	1	1
10+09	-	10+50	TAYLOR ST, LT	30	0.03	1	1	1
10+09	-	10+50	TAYLOR ST, RT	40	0.03	1	1	1
UNDISTRIBUTED				40	0.03	1	1	1
TOTALS				200	0.15	5	5	5

EROSION MAT

STATION	TO	STATION	LOCATION	628.2008 EROSION MAT URBAN CLASS I TYPE B SY
9+50	-	9+85.75	TAYLOR ST, RT	45
9+50	-	9+85.75	TAYLOR ST, LT	45
10+20.25	-	10+50	TAYLOR ST, RT	30
10+20.25	-	10+50	TAYLOR ST, LT	40
UNDISTRIBUTED				40
TOTAL				200

MOBILIZATIONS EROSION CONTROL

LOCATION	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL EACH
TAYLOR ST	5	3
TOTALS	5	3

TURBIDITY BARRIERS

STATION	LOCATION	628.6005 SY
SOUTH ABUTMENT	TAYLOR ST	69
NORTH ABUTMENT	TAYLOR ST	77
TOTAL		146

INLET PROTECTION

STATION	LOCATION	TYPE A 628.7005 EACH	TYPE C 628.7015 EACH
8+75	TAYLOR ST, LT	-	2
8+75	TAYLOR ST, RT	-	1
9+64	TAYLOR ST, RT	1	-
9+72	TAYLOR ST, RT	1	-
TOTALS		2	3

SILT FENCE

STATION	TO	STATION	LOCATION	628.1504 SILT FENCE LF	628.1520 MAINTENANCE LF
9+50	-	9+92	TAYLOR ST, LT	43	86
9+50	-	9+92	TAYLOR ST, RT	44	88
10+16	-	10+50	TAYLOR ST, LT	36	72
10+16	-	10+50	TAYLOR ST, RT	38	76
UNDISTRIBUTED				39	78
TOTALS				200	400

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED

TRAFFIC CONTROL SUMMARY

LOCATION	APPROXIMATE SERVICE DAYS	643.0420 BARRICADES TYPE III		643.0705 WARNING LIGHTS TYPE A		643.0900 SIGNS		REMARKS
		NO. IN SERVICE	DAYS	NO. IN SERVICE	DAYS	NO. IN SERVICE	DAYS	
TAYLOR ST / MASON ST	64	1	64	2	128	1	64	BRIDGE OUT .20 MILES AHEAD
TAYLOR ST / 7TH ST	64	4	256	8	512	5	320	SEE BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL C
NORTH WORK ZONE LIMITS	64	4	256	5	320	1	64	SEE BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL D
SOUTH WORK ZONE LIMITS	64	4	256	5	320	1	64	SEE BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL D
TAYLOR ST / 9TH ST	64	4	256	8	512	4	256	SEE BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL C
TOTALS			1,088		1,792		768	

MARKING LINE EPOXY

STATION TO STATION	LOCATION	646.1020 MARKING LINE EPOXY 4-INCH YELLOW LF	REMARKS
9+50 - 10+50	TAYLOR ST, CL	200	DOUBLE SOLID YELLOW
TOTAL		200	

SAWING CONCRETE

STATION	LOCATION	690.0250 LF	REMARKS
9+75	TAYLOR ST	45	PROJECT LIMITS
10+25	TAYLOR ST	45	PROJECT LIMITS
TOTAL		90	



CONSTRUCTION STAKING

CATEGORY	STATION	TO STATION	LOCATION	650.4000	650.4500	650.6500	650.7000	650.9910	650.9920	
				STORM SEWER EACH	SUBGRADE LF	STRUCTURE LAYOUT LS	CONCRETE PAVEMENT LF	SUPPLEMENTAL CONTROL 4987-11-71 LS	SLOPE STAKES LF	
0010	9+50	-	10+03	TAYLOR ST	3	53	-	53	1	53
0010	10+03	-	10+50	TAYLOR ST	-	47	-	47	-	47
0010	SUBTOTALS				3	100	0	100	1	100
0020	10+03		B-05-469		-	-	1	-	-	-
0020	SUBTOTALS				0	0	1	0	0	0
TOTALS					3	100	1	100	1	100


ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED

LEGEND

- XXXX SAW CUTS
- X TREE TO BE REMOVED
- DONNY G. AND ALICE H. WILEGUS FAMILY TRUST



NO.	STATION	DESCRIPTION	ELEV.
101	7+02	NE COR. BACKSTOOP OF BLDG - 111' RT	644.11
100	10+12	TOP OF NW WING WALL - 28' LT	642.03
2796	11+97	BURY TAG BOLT ON HYDRANT, 27' RT	645.52
2887	12+55	SE COR. TOP STEP BLDG, 90' LT.	646.30




7+00	7+50	8+00	8+50	9+00	9+50	10+00	10+50	11+00	11+50	12+00	12+50	13+00
------	------	------	------	------	------	-------	-------	-------	-------	-------	-------	-------


PROJECT NO: 4987-11-71 HWY: TAYLOR STREET COUNTY: BROWN PLAN AND PROFILE SHEET E

Standard Detail Drawing List


08D01-22A	CONCRETE CURB & GUTTER
08D01-22B	CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS
08E09-06	SILT FENCE
08E10-02	INLET PROTECTION TYPE A, B, C AND D
08E11-02	TURBIDITY BARRIER
08F01-11	APRON ENDWALLS FOR CULVERT PIPE
08F04-07	JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL
12A03-10	NAME PLATE (STRUCTURES)
13B02-09A	CONCRETE PAVEMENT APPROACH SLAB
13C01-19	CONCRETE PAVEMENT LONGITUDINAL JOINTS AND TIES
13C13-09	URBAN DOWELED CONCRETE PAVEMENT
13C18-07A	CONCRETE PAVEMENT JOINTING
13C18-07B	CONCRETE PAVEMENT STEEL REINFORCEMENT
13C18-07C	CONCRETE PAVEMENT JOINT TYPES
15C02-08A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-08B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C06-09	SIGNING & MARKING FOR TWO LANE BRIDGES
15C08-20A	LONGITUDINAL MARKING (MAINLINE)
15C11-09B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS




TYPES A¹ & D




6" SLOPED CURB TYPES G¹ & J



4" SLOPED CURB TYPES G¹ & J




TYPES K¹ & L
(OPTIONAL CURB SHAPE)




TYPES K¹ & L

CONCRETE CURB AND GUTTER 30"




TYPES A¹ & D

CONCRETE CURB AND GUTTER 18"




6" SLOPED CURB TYPES A¹ & D




4" SLOPED CURB TYPES A¹ & D

CONCRETE CURB AND GUTTER 36"



4" SLOPED CURB TYPES R¹ & T

TBT & TBTT	X
30"	22"
36"	28"




TYPES TBT & TBTT¹

CONCRETE CURB AND GUTTER


PAVEMENT THICKNESS AND MAXIMUM CONCRETE PANEL WIDTH TABLE

PAVEMENT THICKNESS	MAXIMUM PANEL WIDTH
LESS THAN 10"	12'
10" & ABOVE	15'



PARTIAL SECTION OF PAVEMENT *
WITH INTEGRAL CURB AND GUTTER

* BIKE LANE IS NOT SHOWN



REVERSE SLOPE GUTTER⁶
(TYPICAL FOR ALL CURB & GUTTER TYPES)

GENERAL NOTES


DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.


INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ CONCRETE CURB AND GUTTER 4-INCH SLOPED 30-INCH TYPE "R" AND "T" = 17 INCHES
CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE "R" AND "T" = 23 INCHES



END SECTION CURB AND GUTTER



DETAIL OF CURB AND GUTTER AT INLETS
(TYPICAL H INLET COVER SHOWN)


GENERAL NOTES

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.


PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2'-0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑨ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.



TYPICAL TIE BAR LOCATION^①




TYPES A^① & D




TYPES G^① & J

CONCRETE CURB




PLAN VIEW



SECTION A - A

TIE BARS DRILLED INTO EXISTING PAVEMENT




DRIVEWAY ENTRANCE CURB^⑨
(WHEN DIRECTED BY THE ENGINEER)

CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2021 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.


- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL



SILT FENCE



JOINING TWO LENGTHS OF SILT FENCE ⑤





SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
4-29-05 /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



INLET PROTECTION, TYPE A


GENERAL NOTES

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED.


WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- ① FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- ② FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- ③ FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.



**INLET PROTECTION, TYPE B
(WITHOUT CURB BOX)**

(CAN BE INSTALLED IN ANY INLET WITHOUT A CURB BOX)



INLET PROTECTION, TYPE C (WITH CURB BOX)

INSTALLATION NOTES

TYPE B & C

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D

DO NOT INSTALL INLET PROTECTION TYPE D IN INLETS SHALLOWER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3" CLEARANCE. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.



INLET PROTECTION, TYPE D


(CAN BE INSTALLED IN ANY INLET TYPE WITH OR WITHOUT A CURB BOX AS PER NOTE ②)

INLET PROTECTION TYPE A, B, C, AND D	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 10/16/02 DATE	/s/ Beth Conestra CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA	




SECTION B - B

**TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6**




PLAN VIEW



SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION



PLAN VIEW


TURBIDITY BARRIER PLACEMENT DETAILS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW



SECTION C - C

**TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES**

TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/4/02 DATE /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT
ENGINEER


FHWA

METAL APRON ENDWALLS											
PIPE DIA. (IN.)	MIN. THICK. (Inches)		DIMENSIONS (Inches)							APPROX. SLOPE	BODY
	STEEL	ALUM.	A (±1")	B (MAX.)	H (±1")	L (±1 1/2")	L1	L2	W (±2")		
12	.064	.060	6	6	6	21	12	17 1/2	24	2 1/2 to 1	1 Pc.
15	.064	.060	7	8	6	26	14	21 3/4	30	2 1/2 to 1	1 Pc.
18	.064	.060	8	10	6	31	15	28 1/4	36	2 1/2 to 1	1 Pc.
21	.064	.060	9	12	6	36	18	29 5/8	42	2 1/2 to 1	1 Pc.
24	.064	.075	10	13	6	41	18	37 1/4	48	2 1/2 to 1	1 Pc.
30	.079	.075	12	16	8	51	18	52 1/4	60	2 1/2 to 1	1 Pc.
36	.079	.105	14	19	9	60	24	59 3/4	72	2 1/2 to 1	2 Pc.
42	.109	.105	16	22	11	69	24	75 5/8	84	2 1/2 to 1	2 Pc.
48	.109	.105	18	27	12	78	24	81	90	2 1/4 to 1	3 Pc.
54	.109	.105	18	30	12	84	30	85 1/2	102	2 1/4 to 1	3 Pc.
60	.109x	.105x	18	33	12	87	—	—	114	2 to 1	3 Pc.
66	.109x	.105x	18	36	12	87	—	—	120	2 to 1	3 Pc.
72	.109x	.105x	18	39	12	87	—	—	126	2 to 1	3 Pc.
78	.109x	.105x	18	42	12	87	—	—	132	1 1/2 to 1	3 Pc.
84	.109x	.105x	18	45	12	87	—	—	138	1 1/2 to 1	3 Pc.
90	.109x	.105x	18	37	12	87	—	—	144	1 1/2 to 1	3 Pc.
96	.109x	.105x	18	35	12	87	—	—	150	1 1/2 to 1	3 Pc.


* EXCEPT CENTER PANEL SEE GENERAL NOTES

REINFORCED CONCRETE APRON ENDWALLS									
PIPE DIA. (IN.)	DIMENSIONS (Inches)							APPROX. SLOPE	
	T	A	B	C	D	E	G		
12	2	4	24	48 1/8	72 1/8	24	2	3 to 1	
15	2 1/4	6	27	46	73	30	2 1/4	3 to 1	
18	2 1/2	9	27	46	73	36	2 1/2	3 to 1	
21	2 3/4	9	36	37 1/2	73 1/2	42	2 3/4	3 to 1	
24	3	9 1/2	43 1/2	30	73 1/2	48	3	3 to 1	
27	3 1/4	10 1/2	49 1/2	24	73 1/2	54	3 1/4	3 to 1	
30	3 1/2	12	54	19 3/4	73 1/2	60	3 1/2	3 to 1	
36	4	15	63	34 3/4	97 3/4	72	4	3 to 1	
42	4 1/2	21	63	35	98	78	4 1/2	3 to 1	
48	5	24	72	26	98	84	5	3 to 1	
54	5 1/2	27	65	33 1/4-35	98 1/4-100	90	5 1/2	2 1/2 to 1	
60	6	30-35	60	39	99	96	5	2 to 1	
66	6 1/2	30-35	72-78	21-27	99	102	5 1/2	2 to 1	
72	7	30-35	78	21	99	108	6	2 to 1	
78	7 1/2	30-35	78	21	99	114	6 1/2	2 to 1	
84	8	36	90 1/2	21	111 1/2	120	6 1/2	1 1/2 to 1	
90	8 1/2	41	87 1/2	24	111 1/2	132	6 1/2	1 1/2 to 1	


* MINIMUM
** MAXIMUM




END CORNER PLATES MAY BE FASTENED TO APRON PROPER BY BOLTS, RIVETS, OR RESISTANCE SPOT WELDS WHICH WILL HOLD THE SURFACES TIGHTLY TOGETHER




SIDE ELEVATION
METAL ENDWALLS



PLAN




END VIEW




LONGITUDINAL SECTION
CONCRETE ENDWALLS


1" WIDE, 12 GA. (0.109" THICK) GALVANIZED STRAP WITH STANDARD 6" X 1/2" BAND BOLT AND NUT




ALTERNATE FOR TYPE 1 CONNECTION
END SECTION CONNECTOR STRAP




TYPE 1
FOR 12" THRU 24" CORR. PIPE



TYPE 2
FOR 30" THRU 96" CORR. PIPE



TYPE 3
FOR 42" THRU 96" CORR. PIPE



TYPE 5
ALTERNATE FOR:
ALL SIZES CORRUGATED CIRCULAR PIPE


NOTE: DIMPLED BAND FITS OVER OUTSIDE OF ENDWALL, AND CORRUGATED BAND FITS INSIDE ENDWALL. DIMPLED BAND MAY BE USED WITH HELICALLY CORRUGATED PIPE.

FOR CIRCUMFERENTIALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2, 3 OR 5 AS APPLICABLE.

FOR HELICALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2 OR 5.

FOR HELICALLY CORRUGATED PIPES WITH TWO CIRCUMFERENTIAL CORRUGATIONS AT EACH END USE ENDWALL CONNECTION DETAILS 1, 2 OR 3.

CONNECTION DETAILS



SECTION A-A

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT ENDWALLS MAY NOT BE USED WITH GALVANIZED STEEL OR ALUMINUM CULVERT PIPE OR VICE VERSA. GALVANIZED STEEL OR ALUMINUM ENDWALLS SHALL NORMALLY BE INSTALLED ON CULVERT PIPE OF THE SAME METAL.

ALL THREE PIECE STEEL APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.109" SIDES AND 0.138" CENTER PANELS. ALL THREE PIECE ALUMINUM APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.105" SIDES AND 0.134" CENTER PANELS. THE WIDTH OF CENTER PANELS SHALL BE GREATER THAN 20 PERCENT OF THE PIPE PERIMETER.

LAP SEAMS SHALL BE TIGHTLY JOINED BY GALVANIZED RIVETS OR BOLTS FOR STEEL UNITS AND ALUMINUM RIVETS AND BOLTS FOR ALUMINUM UNITS. FOR THE 60" THROUGH 96" DIAMETER APRON ENDWALL SIZES, THE REINFORCED EDGES AND CENTER PANEL SEAMS SHALL BE FURTHER REINFORCED WITH GALVANIZED STEEL OR ALUMINUM STIFFENER ANGLES. THE ANGLES SHALL BE ATTACHED BY GALVANIZED NUTS AND BOLTS FOR STEEL UNITS AND ALUMINUM NUTS AND BOLTS FOR ALUMINUM UNITS.


WHERE TWO OR MORE PIPES WITH APRON ENDWALLS ARE LAID ADJACENT TO EACH OTHER, THEY SHALL BE SEPARATED BY A DISTANCE SUFFICIENT TO PROVIDE A MINIMUM CLEARANCE OF 6 INCHES BETWEEN APRON ENDWALLS.

① FOR PIPE SIZES UP TO 60" DIAMETER, A 180° ROLLED EDGE MAY BE USED INSTEAD OF STEEL ROD REINFORCEMENT. SEE SECTION A-A.

APRON ENDWALLS FOR
CULVERT PIPE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
11/30/94 /S/ Rory L. Rhinesmith
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



EYE BOLTS AND TIE ROD

EYE BOLT AND TIE ROD ASSEMBLY (ALTERNATE NO. 1)



(CAST-IN-PLACE THREADED INSERT)
LONGITUDINAL SECTIONS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT AND STORM SEWER PIPE SHALL BE TIED TOGETHER IN THE MANNER ILLUSTRATED BY THIS DETAIL AT LOCATIONS DESIGNATED IN THE STANDARD SPECIFICATIONS AND THE PLAN. THE CONTRACTOR MAY USE EITHER ALTERNATE 1, 2 OR 3 FOR DRAINAGE STRUCTURES. ONLY ALTERNATE 1 AND 3 MAY BE USED FOR CATTLE PASSES, UNLESS OTHERWISE STATED IN THE CONTRACT. THE MATERIALS, FABRICATION AND WORK NECESSARY TO TIE THE PIPE BY THIS DETAIL WILL BE CONSIDERED INCIDENTAL TO THE PIPE AND APRON ENDWALLS IF REQUIRED.


DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR JOINT TIES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.

JOINT TIES TO BE HOT-DIP GALVANIZED PER ASTM A 153.

- ① ϕ OF TONGUE AND GROOVE OR BELL AND SPIGOT JOINTS.
- ② THE INSIDE OF THE THREADED INSERTS SHALL BE CLEAN TO ALLOW THE INSERTION OF THREADED EYE BOLTS.
- ③ HOLES SHALL BE CAST-IN-PLACE OR DRILLED 12 INCHES FROM ϕ OF TONGUE AND GROOVE.
- ④ BOLT PROJECTION INSIDE OF PIPE SHALL NOT EXCEED 2 INCHES.
- ⑤ OPENING TO BE ROD DIAMETER PLUS 1 INCH.
- ⑥ LENGTH ADEQUATE TO EXTEND TO WITHIN $\frac{1}{2}$ INCH OF THE INNER SURFACE OF THE PIPE.



(TONGUE & GROOVE PIPE)



(MODIFIED BELL PIPE)
LONGITUDINAL SECTION


EYE BOLT DIMENSION TABLE

PIPE SIZE	L = LENGTH	
	TONGUE & GROOVE PIPE	MODIFIED BELL PIPE
18" TO 24"	4 1/2"	6 1/4"
30"	5"	7"
36"	5 1/2"	7"
42"	6"	
48"	6 1/2"	
60"	7 1/2"	
66"	8"	


ADJUSTABLE TIE ROD TABLE

PIPE DIAMETER	TIE ROD DIAMETER	D	L ₁	N
12-60	5/8	5/8	5	1/2
66-84	3/4	3/4	5	1/2
90-108	1	1	7	1 1/6


DIMENSIONS SHOWN ARE IN INCHES



TAPERED PLAIN
RIGHT AND LEFT THREADS
SLEEVE NUTS




(JOINT TIES FOR 12" TO 108" DIA. CONCRETE PIPE)
LONGITUDINAL SECTION
ADJUSTABLE TIE ROD (ALTERNATE NO. 3)



PLACEMENT OF (2) CAST-IN-PLACE
INSERTS OR HOLES DURING FABRICATION
FOR PIPE SECTIONS REQUIRING TIE RODS

TRANSVERSE SECTION




SECTION A-A
CONCRETE COLLAR DETAIL

JOINT TIES FOR CONCRETE
PIPE AND CONCRETE
COLLAR DETAIL

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/5/2012 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA

(JOINT TIES FOR 18" TO 66" DIA. CONCRETE PIPE)
EYE BOLT AND TIE ROD ASSEMBLY (ALTERNATE NO. 2)




EYE BOLT AND TIE ROD

EYE BOLT

NOTE: TWO EYE BOLTS MAY BE USED WITH
A 30" LONG THREADED ROD IN LIEU
OF THE 90° BENT TIE ROD.

EYE BOLT AND TIE ROD ASSEMBLY (ALTERNATE NO. 2)




TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.



SECTION A-A




ALTERNATE LUG

6

6


FOR MULTI-UNIT STRUCTURES
LINE 3 ABOVE SHALL READ

- B = BRIDGE
- C = CULVERT
- R = RETAINING WALL
- UNIT NO. FOR MULTIPLE UNIT BRIDGE



**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)


S.D.D. 12 A 3-10

S.D.D. 12 A 3-10


NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE 3/26/10	/S/ Scot Becker CHIEF STRUCTURAL DEVELOPMENT ENGINEER
FHWA	



**SKewed Approach
(Pavement more than two lanes)**




**Skews > 20°
(Pavement width ≤ 30')**




**Skews ≤ 20°
(Pavement width ≤ 30')**
Approach Slab and Adjacent Pavement


- * (RS) = REINFORCED CONCRETE SLAB
- * (PS) = PAVED CONCRETE SHOULDER OR CONCRETE DRAINAGE SLAB
- * (NRS) = NON - REINFORCED CONCRETE SLAB
- *** STANDARD DOWEL BAR DIAMETER (SEE SDD 13C11 AND SDD 13C13)



**SECTION A - A
REINFORCEMENT POSITIONING DETAIL**



**SECTION B - B
BEND DETAIL
BOTTOM REINFORCEMENT**




**SECTION C - C
TRANSITION DETAIL
Approach Slab to Adjacent Pavement**

GENERAL NOTES


THE CONTRACTOR MAY SPLICE NO. 6 BARS IN THE APPROACH SLAB FOR SKEWED STRUCTURES ONLY. STAGGER SPLICES WITH A MAXIMUM OF ONE SPLICE PER BAR. THE LENGTH OF LAP IS 20 INCHES.

TACK WELD DOWEL BARS TO THE BASKETS ON ALTERNATE ENDS.

- ① THE CONTRACTOR MAY USE NO. 4 BARS SPACED AT 2' - 0" C - C IN BOTH THE LONGITUDINAL AND TRANSVERSE DIRECTIONS FOR TOP REINFORCEMENT AS AN ALTERNATIVE TO THE WELDED WIRE FABRIC.
- ② THE CONTRACTOR MAY OMIT THE BARS BETWEEN REINFORCED SLABS WHERE SLAB REINFORCEMENT BARS EXTEND ACROSS THE CENTERLINE OR REFERENCE LINE.
- ③ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING AN HMA PAVEMENT.
- ④ USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ⑤ PLACE EXPANSION CAP ON THE END OF THE DOWEL THAT IS NOT TACK WELDED TO THE BASKET. DO NOT FORCE DOWEL BAR PAST THE DOWEL STOP.
- ⑥ EXTEND EXPANSION JOINT THROUGH ANY ADJACENT TIED CONCRETE.
- (A) STANDARD CONTRACTION JOINT NORMAL TO \bar{C} OR \bar{R} .
- (B) STANDARD LONGITUDINAL JOINT WITH TIE BARS.
- (C) 1 1/2" EXPANSION JOINT WITH DOWEL BARS NORMAL TO \bar{C} OR \bar{R} .



**SECTION D - D
CONTRACTION JOINT**




EXPANSION JOINT DETAIL

**CONCRETE PAVEMENT
APPROACH SLAB**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Peter Kemp, P.E.
DATE DATE PAVEMENT SUPERVISOR

FHWA



CONSTRUCTION JOINT




SAWED JOINT

GENERAL NOTES

CREATE A LONGITUDINAL JOINT FOR PAVEMENT WIDTHS GREATER THAN 15 FEET.


CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.

- ① ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.
- ② PAVEMENT THAT WAS IN PLACE PRIOR TO THE CONTRACT.




PLAN VIEW


NO. 6 TIE BARS SPACED 30" C-C, INSTALLED PERPENDICULAR TO THE LONGITUDINAL JOINT. ①




**SECTION A-A
LONGITUDINAL CONSTRUCTION JOINT
TIE BARS ANCHORED
INTO EXISTING PAVEMENT**



DETAIL "A"



DETAIL "B"




DETAIL "C"

TIE BAR TABLE

PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4 *	30"	24" **

* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)

** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.




**PLAN VIEW
SHOWING LOCATION OF TIE BARS**


**CONCRETE PAVEMENT
LONGITUDINAL JOINTS AND TIES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR
FHWA



PLAN VIEW



SIDE VIEW

CONTRACTION JOINT DOWEL ASSEMBLY ①

PAVEMENT DEPTH, DOWEL BAR SIZE AND JOINT SPACING TABLE

PAVEMENT DEPTH (D)	DOWEL BAR DIAMETER	CONTRACTION JOINT SPACING
5 1/2", 6", 6 1/2"	NONE	12'
7", 7 1/2"	1"	14'
8", 8 1/2"	1 1/4"	15'
9", 9 1/2"	1 1/4"	15'
10" & ABOVE	1 1/2"	15'

GENERAL NOTES

CONTRACTION JOINTS

CONSTRUCT TRANSVERSE CONTRACTION JOINTS NORMAL TO THE CENTERLINE. SHOW THE LOCATION OF CONTRACTION JOINTS THROUGH INTERSECTIONS ON THE PLANS OR AS DIRECTED BY THE ENGINEER.


INSTALL DOWEL BARS PARALLEL TO THE PAVEMENT CENTERLINE AND PAVEMENT SURFACE.

FOR PAVEMENT SLABS OF VARYING WIDTHS, LOCATE THE OUTER MOST DOWEL BAR SO THAT THE CENTER OF THE BAR IS A MINIMUM OF 6 INCHES AND A MAXIMUM OF 18 INCHES FROM THE LONGITUDINAL JOINT AND THE FREE EDGE OF PAVEMENT.


CONSTRUCTION JOINTS

LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO CONTRACTION JOINTS.


- ① OBTAIN THE ENGINEER'S APPROVAL FOR THE USE OF ALTERNATIVE DESIGNS OF THE DOWEL ASSEMBLY. USE MECHANICAL DOWEL BAR INSERTERS OR DOWEL ASSEMBLIES WHEN CONSTRUCTING CONTRACTION JOINTS.
- ② SECURE BASKETS WITH ANCHORS TO HOLD DOWEL BARS IN THE CORRECT POSITION AND ALIGNMENT. TYPE, LOCATION, NUMBER AND LENGTH OF ANCHORS ARE DEPENDENT UPON FIELD CONDITIONS.
- ③ FORM OR SAW CONSTRUCTION JOINTS. PROVIDE A 1/4-INCH RADIUS AT FORMED JOINTS.
- ④ PROVIDE A SMOOTH VERTICAL FACE FOR THE ENTIRE DEPTH OF THE PAVEMENT WHEN FORMING CONSTRUCTION JOINTS.
- ⑤ INSTALL DOWEL BARS AT CONSTRUCTION JOINTS BY FORMING OR DRILLING. INSTALL FORMED DOWEL BARS 12 INCHES C-C AND 12 INCHES FROM PAVEMENT EDGE. REMOVE EXCESS CONCRETE FROM THE FREE END OF THE DOWEL BAR IF DOWEL BARS ARE FORMED THROUGH A HEADER BOARD. INSTALL DRILLED DOWEL BARS ACCORDING TO DRILLED DOWEL BAR CONSTRUCTION JOINT DETAIL.
- ⑥ APPLY A THIN UNIFORM COATING OF SURFACE TREATMENT TO THE FREE END OF DOWEL BARS TO PREVENT BONDING.
- ⑦ ANCHOR DOWEL BARS INTO DRILLED HOLES WITH AN EPOXY. MAXIMUM DRILLED HOLE SIZE IS 1/8-INCH GREATER THAN DOWEL BAR DIAMETER, 9 INCHES IN LENGTH.




DRILLED DOWEL BAR CONSTRUCTION JOINT ⑦




TRANSVERSE CONSTRUCTION JOINT



JOINT DETAIL



DOWELED CONTRACTION JOINT




CONTRACTION JOINT LOCATIONS


URBAN DOWELED
CONCRETE PAVEMENT

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
March 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR
FHWA




DETAIL "A"



DETAIL "B"



DETAIL "C"




DETAIL "D"

GENERAL NOTES

- THE PRIMARY ROADWAY CONTROLS THE TRANSVERSE JOINT PATTERN.
- ALIGN NEW JOINTS WITH EXISTING JOINTS OR CRACKS.
- CONSTRUCT TRANSVERSE JOINTS PERPENDICULAR TO THE ROADWAY.
- ADJUST TRANSVERSE JOINTS TO ALIGN WITH UTILITY FIXTURES (E.G MANHOLES AND INLETS) IN THE PAVEMENT STRUCTURE WHEN POSSIBLE. WATER VALVES DO NOT REQUIRE JOINT ADJUSTMENT.
- AVOID SLABS LESS THAN 2 FEET WIDE OR GREATER THAN 15 FEET WIDE.
- SEE TABLE FOR TRANSVERSE JOINT SPACING. JOINT SPACING SPECIFIED IS MAXIMUM AND ACTUAL SPACING CAN BE ADJUSTED TO ACCOMMODATE INTERSECTIONS.
- AVOID ANGLES LESS THAN 60° BY DOGLEGGING JOINTS THROUGH CURVE RADIUS POINTS. USE 90° ANGLES WHEN POSSIBLE.
- CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.


- ① PROVIDE TRANSVERSE JOINTS AT ALL PAVEMENT WIDTH CHANGES.
- ② CONSTRUCT DOWELED EXPANSION JOINT ON THE SIDE ROAD OF AN INTERSECTION IF THE SIDE ROAD IS CONCRETE PAVEMENT AND GREATER THAN 300 FEET IN LENGTH. ALIGN EXPANSION JOINT WITH EDGE OF RADIUS.
- ③ THE ENGINEER MAY APPROVE SLIGHT VARIATIONS FROM THESE JOINTING DETAILS.




STANDARD INTERSECTION

PAVEMENT DEPTH AND JOINT SPACING TABLE


PAVEMENT DEPTH (D)	CONTRACTION JOINT SPACING
6", 6 1/2"	12'
7", 7 1/2"	14'
8" & ABOVE	15'



SKEWED INTERSECTION



APPROACH TO MEDIAN



LARGE RIGHT TURN

CONCRETE PAVEMENT JOINTING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


LEGEND

- - - - - POTENTIAL DOWELED EXPANSION JOINT
- - - - - DOWELED JOINT
- TIED JOINT

GENERAL NOTES


USE AN EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF STANDARD SPECIFICATION 415.

6



STANDARD INTERSECTION


6




SKEWED INTERSECTION

**CONCRETE PAVEMENT
STEEL REINFORCEMENT**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



DOWELED TRANSVERSE ①



UNTIED - LONGITUDINAL

EXPANSION JOINTS

TIE BAR TABLE


PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4*	30"	24" **

* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)


** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.

GENERAL NOTES


- ① USE DOWELED EXPANSION JOINTS ON SIDE ROADS AT INTERSECTIONS (TO ISOLATE THE SIDE ROAD FROM THE THROUGH STREET) IF THE SIDE ROAD IS CONCRETE PAVEMENT AND GREATER THAN 300 FEET IN LENGTH.
- ② SPACE CONTRACTION JOINTS IN ACCORDANCE WITH SDD 13C4, 13C11 OR 13C13.
- ③ LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO CONTRACTION JOINTS.
- ④ CONSTRUCTION JOINTS CAN BE FORMED OR SAWED.
- ⑤ IF JOINT IS FORMED, PROVIDE A 1/4" RADIUS.
- ⑥ ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.




UNDOWELED TRANSVERSE




TIED LONGITUDINAL




DOWELED TRANSVERSE ③




TIED LONGITUDINAL



DOWELED TRANSVERSE



TIED TRANSVERSE ③
(FOR USE ON NON-DOWELED PAVEMENTS ONLY)




TIED LONGITUDINAL TO EXISTING

CONTRACTION JOINTS ②

CONSTRUCTION JOINTS ④

CONCRETE PAVEMENT JOINT TYPES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

**DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR**


WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750

- M4 - 8
- M3 - X
- M1 - 4 OR M1 - 6 OR M1 - 5A
- M05 - 1 OR M06 - 1




**DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR**

SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦


**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE DATE WORK ZONE ENGINEER
FHWA



**DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW**



**DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW**

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:

- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

**BARRICADES AND SIGNS
FOR
VARIOUS CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

GENERAL NOTES


DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W5-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.


① OMIT ON ONE-WAY TRAVELLED WAYS.

➡ DIRECTION OF TRAFFIC



SITUATION 1

WARRANTING CRITERIA:
BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.



SITUATION 2

WARRANTING CRITERIA:
1. BRIDGE WIDTH IS AT LEAST 24 FEET AND
2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET.


DISTANCE TABLE

POSTED OR 85th PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	750'


SIGNING & MARKING FOR TWO LANE BRIDGES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2017 /S/ Matthew R. Rauch
DATE STATE SIGNING AND MARKING ENGINEER
FHWA




TWO WAY TRAFFIC




ONE WAY TRAFFIC

PERMANENT PAVEMENT MARKING



TWO WAY TRAFFIC



ONE WAY TRAFFIC

TEMPORARY PAVEMENT MARKING


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.

LEGEND


- "T" MARKING
- SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC




**LONGITUDINAL MARKING
(MAINLINE)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Matthew Rauch
DATE STATEWIDE SIGNING AND MARKING
ENGINEER




DRUM



42" CONE

DO NOT USE IN TAPERS
 1/2 SPACING OF DRUMS




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.


**CHANNELIZING DEVICES
 DRUMS, CONES, BARRICADES
 AND VERTICAL PANELS**

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION


APPROVED
 May 2021 /S/ Andrew Heidtke
 DATE WORK ZONE ENGINEER

URBAN AREA


RURAL AREA (See Note 2)




White Edgeline Location



Outside Edge of Gravel



White Edgeline Location



Outside Edge of Gravel

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

GENERAL NOTES

1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.
The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).
3. For expressways and freeways, mounting height is 7'- 3" (±) or 6'-3" (±) depending upon existence of a sub-sign.
4. Minimum mounting height for signs mounted on traffic signal poles is 5'- 3" (±).
5. Offset distance shall be consistent with existing signs or consistent throughout length of project.
6. The (±) tolerance for mounting height is 3 inches.
7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the Engineer.

* * The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.


* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

TYPICAL INSTALLATION OF PERMANENT TYPE II SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 5/13/2020 PLATE NO. A4-3.22



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :



- Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

- STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)
- MACHINE BOLTS - $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts
- WOOD POSTS (4" x 6")
- LAG SCREWS - $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)
 - $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)
- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 - $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)
- RIVETS - $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL
- O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH
- WASHERS (ALL POSTS) -
- 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL
 - 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON

* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.

ATTACHMENT OF SIGNS TO POSTS	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R Rauch</i> For State Traffic Engineer
DATE 4/1/2020	PLATE NO. A4-8.9



GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1½" diameter holes drilled perpendicular to the roadway centerline.


7

7

4 X 6 WOOD POST MODIFICATIONS	
<i>WISCONSIN DEPT OF TRANSPORTATION</i>	
APPROVED	<i>Chester J Spang</i> for State Traffic Engineer
DATE <u>3/27/97</u>	PLATE NO. <u>A4-11.2</u>

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
 - Background - White
 - Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R11-2B

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
2M	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
3	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
4	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
5	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0

STANDARD SIGN
R11-2B

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 4/1/11 PLATE NO. R11-2B.2

PROJECT NO: _____ SHEET NO: _____ E


NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Substitute appropriate numerals to nearest quarter mile and optically adjust spacing to achieve proper balance.



R11-3C

** See Note 5



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	15	1 3/8	1/2	5/8	4	3	2 1/2	13 1/4	2 1/4	3	8	8	1 1/2	2	10 3/4		7 1/8									3.75
2S	60	24	1 3/8	1/2	5/8	6	5	4	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8		11 7/8									10.0
2M	60	24	1 3/8	1/2	5/8	6	5	4	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8		11 7/8									10.0
3																											
4																											
5																											

STANDARD SIGN
R11-3C

WISCONSIN DEPT OF TRANSPORTATION


APPROVED
Matthew R. Rauch
For State Traffic Engineer

DATE 7/28/16 PLATE NO. R11-3C.3


PROJECT NO:

SHEET NO:


E




W20-3A



W20-3D



W20-3C



W20-3B



W20-3G



W20-3F

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - see note 5
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Lines 1 and 2 are Series D.
Line 3 is Series D for AHEAD and Series C for all other distances.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	5	3 3/8	3 1/2	1 1/8	4	8 3/8	8 7/8	12 1/2	11	9	6	10 1/8	2 1/2	1 7/8	5 5/8	8	1 3/8	4 1/2	3 1/2	10 3/4	1 3/4	9.0
2S	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
2M	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
3	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
4	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
5	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0

STANDARD SIGN
W20-3A, B, C, D, F & G

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 3/18/11 PLATE NO. W20-3.7

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: _____ E

DESIGN DATA

LIVE LOAD:

DESIGN LOADING: HL-93
 INVENTORY RATING FACTOR: 1.16
 OPERATING RATING FACTOR: 1.50
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV) = 250 KIPS

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 "/S.F.

MATERIAL PROPERTIES:

CONCRETE MASONRY (SUPERSTRUCTURE) $f'c = 4,000$ p.s.i.
 (ALL OTHER) $f'c = 3,500$ p.s.i.
 HIGH STRENGTH BAR STEEL REINFORCEMENT (GRADE 60) $f_y = 60,000$ p.s.i.

HYDRAULIC DATA:

100 YEAR FREQUENCY

$Q_{100} = 840$ c.f.s.
 VEL. = 6.3 f.p.s.
 HW₁₀₀ = EL. 641.17
 WATERWAY AREA = 133 sq. ft.
 DRAINAGE AREA = 1.2 sq. mi.
 ROADWAY OVERTOPPING = N/A
 SCOUR CRITICAL CODE = 8
 DATUM = NAVD88

2 YEAR FREQUENCY

$Q_2 = 390$ c.f.s.
 VEL. = 3.6 f.p.s.
 HW₂ = EL. 639.4

FOUNDATION DATA:

SOUTH ABUTMENT TO BE SUPPORTED ON HP 10x42 STEEL PILING (WITH PILE POINTS) DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 140 TONS * PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA. ESTIMATED LENGTH 70'-0".


NORTH ABUTMENT TO BE SUPPORTED ON HP 10x42 STEEL PILING (WITH PILE POINTS) DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 140 TONS * PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA. ESTIMATED LENGTH 70'-0". PRE-BORE THE TWO PILES ADJACENT THE SANITARY LINE 15'-0".

* THE FACTORED AXIAL RESISTANCE OF PILES IN COMPRESSION USED FOR DESIGN IS THE REQUIRED DRIVING RESISTANCE MULTIPLIED BY A RESISTANCE FACTOR OF 0.5 USING MODIFIED GATES TO DETERMINE DRIVEN PILE CAPACITY.

TRAFFIC DATA:

A.A.D.T. = 5,735 (2022)
 A.A.D.T. = 6,350 (2042)
 R.D.S. = 25 M.P.H.


- * ATTACHMENT FOR THRIE BEAM TYPE GUARDRAIL.
- DENOTES WING NUMBER.
- ⊕ ECO-PASSAGE. SEE DETAIL ON SHEET 2.




PLAN
 SINGLE SPAN CONCRETE FLAT SLAB BRIDGE

/// COST OF EXCAVATION IN THE HATCHED AREAS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR "EXCAVATION FOR STRUCTURES BRIDGES B-5-469".

REMOVE EXISTING SUBSTRUCTURE AS NEEDED. COST CONSIDERED INCIDENTAL TO "REMOVING STRUCTURE" ITEM. TYPICAL AT ALL SUBSTRUCTURES.



ELEVATION



PROFILE GRADE LINE
 (TAYLOR STREET)

BENCH MARK:
 TOP SW WINGWALL
 STA. 10+14, 28' LT.
 EL. 642.03

LIST OF DRAWINGS

1. GENERAL PLAN
2. QUANTITIES AND NOTES
3. SUBSURFACE EXPLORATION
4. SOUTH ABUTMENT
5. SOUTH ABUTMENT PILE LAYOUT
6. SOUTH ABUTMENT WING 1 DETAILS
7. SOUTH ABUTMENT WING 2 DETAILS
8. SOUTH ABUTMENT DETAILS & BILL OF BARS
9. NORTH ABUTMENT
10. NORTH ABUTMENT PILE LAYOUT
11. NORTH ABUTMENT WING 3 DETAILS
12. NORTH ABUTMENT WING 4 DETAILS
13. NORTH ABUTMENT DETAILS & BILL OF BARS
14. ALTERNATE CONSTRUCTION JOINT
15. SUPERSTRUCTURE
16. SUPERSTRUCTURE PLAN
17. SUPERSTRUCTURE DETAILS AND BILL OF BARS
18. COMBINATION RAIL TYPE "C2"
19. COMBINATION RAIL TYPE "C2" DETAILS



07/30/2021

BRIDGE OFFICE CONTACT:
 AARON BONK
 (608)-261-0261
 CONSULTANT CONTACT:
 ARLEN BEAUDETTE
 (715)-834-3161

FOR TYPICAL SECTION SEE SHEET 2

NO.	DATE	REVISION	BY
ORIGINAL PLANS PREPARED BY			
AYRES 3433 Oakwood Hills Parkway Eau Claire, WI 54701 www.AyresAssociates.com			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
ACCEPTED	SDR		08/25/21
CHIEF STRUCTURES DESIGN ENGINEER		DATE	
STRUCTURE B-5-469			
TAYLOR STREET OVER BEAVER DAM CREEK			
COUNTY	BROWN	TOWN/CITY/VILLAGE	GREEN BAY
DESIGN SPEC. AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS			
DESIGNED BY	JLB	DESIGN CKD.	CJM
DRAWN BY	CJM	PLANS CKD.	AEB
GENERAL PLAN			SHEET 1 OF 19

5/13/2021
 PENTABLE:BRoadu_shd_util.tbl

CHECKED BY:
 BACK CHECKED BY:
 CORRECTED BY:

8

8

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	S. ABUT.	N. ABUT.	SUPER.	TOTAL
203.0260	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS P-5-721	EACH	-----	-----	-----	1
206.1000	EXCAVATION FOR STRUCTURES BRIDGES B-5-469	LS	-----	-----	-----	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	195	195	-----	390
502.0100	CONCRETE MASONRY BRIDGES	CY	49	49	141	239
502.3200	PROTECTIVE SURFACE TREATMENT	SY	-----	-----	210	210
502.3210	PIGMENTED SURFACE SEALER	SY	10	10	28	48
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	3,290	3,290	-----	6,580
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	1,660	1,660	23,140	26,460
513.7011	RAILING STEEL TYPE C2	LF	-----	-----	114.7	114.7
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	15	15	-----	30
550.0010	PRE-BORING UNCONSOLIDATED MATERIALS	LF	-----	30	-----	30
550.0500	PILE POINTS	EACH	8	8	-----	16
550.1100	PILING STEEL HP 10-INCH X 42-LB	LF	560	560	-----	1,120
606.0300	RIPRAP HEAVY	CY	65	65	-----	130
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	105	105	-----	210
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	2	2	-----	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	75	75	-----	150
645.0120	GEOTEXTILE TYPE HR	SY	130	130	-----	260
SPV.0195.01	SELECT CRUSHED MATERIAL FOR TRAVEL CORRIDOR	TON	-----	5	-----	5
NON-BID ITEMS						
	FILLER	SIZE	-----	-----	-----	1/2" & 3/4"

GENERAL NOTES


DRAWINGS SHALL NOT BE SCALED.
 BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS SHOWN OR NOTED OTHERWISE.
 THE FIRST DIGIT OF A THREE DIGIT BAR NO. AND THE FIRST TWO DIGITS OF A FOUR DIGIT BAR NO. SIGNIFIES THE BAR SIZE. JOINT FILLER SHALL CONFORM TO THE REQUIREMENTS OF A.A.S.H.T.O. DESIGNATION M 153, TYPE I, II OR III OR A.A.S.H.T.O. DESIGNATION M 213.
 THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH RIPRAP HEAVY AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON THE GENERAL PLAN SHEET AND IN THE ABUTMENT DETAILS.
 SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATIVE METHOD IS APPROVED BY THE ENGINEER.
 THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES BRIDGES B-5-469" SHALL BE THE EXISTING GROUNDLINE.
 THE EXISTING STRUCTURE, P-5-721, TO BE REMOVED, IS A SINGLE SPAN PRESTRESSED CONCRETE CHANNEL BRIDGE ON STEEL PILE BENT VERTICAL ABUTMENTS WITH CONCRETE BACKING, 23.3 FT. LONG WITH A 43.7 FT. CLEAR ROADWAY WIDTH WITH 6.3-FT. WIDE CLEAR WIDTH SIDEWALKS ON EACH SIDE.
 AT THE BACK FACE OF ABUTMENTS, ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH BACKFILL STRUCTURE TYPE A.
 PROTECTIVE SURFACE TREATMENT AND PIGMENTED SURFACE SEALER IS TO BE APPLIED AS SHOWN IN DETAIL ON THIS SHEET.
 BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS NOTED OTHERWISE.
 EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.

THE BACKFILL QUANTITIES ARE BASED ON THE PAY LIMITS SHOWN ON THE PLANS AND MAY NOT REFLECT ACTUAL PLACED QUANTITIES. "BACKFILL STRUCTURE TYPE A" REQUIRED DIRECTLY BEHIND ABUTMENTS AND ABUTMENT WINGS FOR 3 FEET. BACKFILL PLACED BEYOND PAY LIMITS OR EXCEEDING PLAN QUANTITIES SHALL BE INCIDENTAL TO EXCAVATIONS FOR STRUCTURES.

EXTENT OF BELOW GRADE SUBSTRUCTURES ARE NOT KNOWN. REMOVE EXISTING SUBSTRUCTURES AS NEEDED TO BUILD NEW SUBSTRUCTURES. COST OF SUBSTRUCTURE REMOVAL IS CONSIDERED INCIDENTAL TO THE "REMOVING STRUCTURE" BID ITEM.


AT ABUTMENTS, CONCRETE POURED UNDERWATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS.

REMOVAL OF EXISTING CONCRETE CAISSONS AND RAILINGS AT ALL FOUR WINGS WILL BE INCIDENTAL TO "REMOVING STRUCTURE" BID ITEM




TYPICAL SECTION THRU BRIDGE

▲ ± 0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.




ECO-PASSAGE DETAIL

● ECO-PASSAGE. FILL VOIDS IN RIPRAP HEAVY WITH TRAFFIC BOND LIMESTONE SCREENINGS 3/8-INCH TO FULLY FILL ALL VOIDS AND LEAVE, ON AVERAGE, TWO INCHES ABOVE THE LOWEST ROCK POINTS WHERE THEY ABUT EACH OTHER. PROVIDE LEVEL SURFACE OF THE ECO-PASSAGE. THE TRANSITIONS OF THE AT-GRADE ECO PASSAGE TO THE EDGES OF THE RIPRAP HEAVY SHALL BE GRADUAL WITH NO MORE THAN 2:1 SLOPE. TRAFFIC BOND LIMESTONE SHALL BE COMPACTED ONCE IN PLACE. "SELECT CRUSHED MATERIAL FOR TRAVEL CORRIDOR".




BACKFILL STRUCTURE LIMITS

- BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- ⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8.



PROTECTIVE SURFACE TREATMENT AND PIGMENTED SURFACE SEALER DETAIL



HP 10 x 42 SPLICE DETAIL

HP WELD DETAIL
FLANGE SHOWN, WEB SIMILAR

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
 Eau Claire, WI 54701
 www.AyresAssociates.com

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CJM		PLANS CK'D. AEB	
QUANTITIES AND NOTES			SHEET 2 OF 19



7/30/2021 PENTABLE:BRearu_shd_util.tbi

8

8

BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	12/27/2019	569560.3125	82717.5000
2	12/27/2019	569598.6979	82720.0208

BORINGS COMPLETED BY: ECS MIDWEST, LLC
 REPORT COMPLETED BY: ECS MIDWEST, LLC
 ALL COORDINATES REFERENCED TO WCCS BROWN COUNTY



STATE PROJECT NUMBER
4987-11-87

MATERIAL SYMBOLS

ASPHALT	TOPSOIL	PEAT
CONCRETE	FILL	GRAVEL
SAND	CLAY	SILT
BOULDERS OR COBBLES	LIMESTONE	BEDROCK (UNKNOWN)
SHALE	SANDSTONE	IGNEOUS/META

LEGEND OF BORING

⁽¹⁾ UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)
⁽²⁾ UNLESS OTHERWISE SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

- ▽ AT TIME OF DRILLING
- ▽ END OF DRILLING
- ▽ AFTER DRILLING

ABBREVIATIONS

F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.


5/4/2021
PENTABLE:BRedu_shd_util.tbl

8


8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CJM	PLANS CKD. AEB
SUBSURFACE EXPLORATION			SHEET 3 OF 19

NOTE:
SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF
1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT
SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE).




ELEVATION
(LOOKING SOUTH)
FOR SECTION A SEE SHEET 8.



SECTION F

- ① KEYED CONST. JOINT - FORMED BY A BEVELED 2" x 6".
 - ② PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".
 - ⊞ VERTICAL 18" RUBBERIZED MEMBRANE WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WINGWALL.
 - ⊞ VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING
- B.F. DENOTES BACK FACE



PLAN


5/4/2021 PENTABLE:BRRedu_shd_util.tbl

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CLP		PLANS CK'D. AEB	
SOUTH ABUTMENT			SHEET 4 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



PILE LAYOUT

VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14.
 SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING

FOR PILE SPLICE DETAIL SEE SHEET 2.

5/4/2021 PENTABLE:BRedu_shd_util.tbl

8


8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY	CLP	PLANS CK'D.	AEB
SOUTH ABUTMENT PILE LAYOUT			SHEET 5 OF 19


ORIGINAL PLANS PREPARED BY

AYRES

3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



FOR CLARITY PARAPET NOT SHOWN.
FOR DETAILS SEE SHEET 18



5/4/2021
PENTABLE:BRRedu_shd_util.tbl


8

8

- ⊕ 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
 - OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
 - ⊞ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.
- F.F. DENOTES FRONT FACE.
E.F. DENOTES EACH FACE.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
SOUTH ABUTMENT WING 1 DETAILS			SHEET 6 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com



ELEVATION - WING 2

FOR CLARITY PARAPET NOT SHOWN.
FOR DETAILS SEE SHEET 18



SECTION B

- 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
 - OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
 - ▣ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.
- F.F. DENOTES FRONT FACE.
E.F. DENOTES EACH FACE.

5/4/2021
PENTABLE:BRedu_shd_util.tbl

8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
SOUTH ABUTMENT WING 2 DETAILS			SHEET 7 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com

BILL OF BARS


BAR NO.	COATED BAR	NO. REOD.	LENGTH	BENT BAR	BUNDLED	BAR SERIES	1,660* COATED
							3,290* UNCOATED
							LOCATION
A401		8	28-0	X			BODY @ PILES
A402		16	2-3				BODY @ PILES
A503		72	14-2	X			BODY VERT.
A604		11	28-11				BODY HORIZ.
A605		11	31-10				BODY HORIZ.
A806		14	12-11	X			BODY HORIZ. B.F. @ WINGS
A607		7	19-10				BODY HORIZ. B.F. BTWN WINGS
A608		7	22-9				BODY HORIZ. B.F. BTWN WINGS
A409		3	7-11				BODY HORIZ.
A410		3	10-0				BODY HORIZ.
A511		16	5-1	X			BODY VERT.
A512	X	56	2-0				BODY DOWELS
A513	X	12	15-8	X			WING 1 VERT.
A514	X	6	14-2				WING 1 HORIZ. F.F.
A615	X	8	13-11				WING 1 HORIZ. B.F. & TOP
A516	X	17	9-2	X			WING 1 VERT.
A417	X	7	11-8				WING 1 HORIZ. E.F.
A418	X	17	5-1	X			WING 1 VERT. TOP
A619	X	2	11-8				WING 1 HORIZ. TOP E.F.
A420	X	3	4-7				BODY VERT. @ END @ WING 1
A521	X	12	15-8	X			WING 2 VERT.
A522	X	6	14-2				WING 2 HORIZ. F.F.
A623	X	8	13-11				WING 2 HORIZ. B.F. & TOP
A524	X	17	9-2	X			WING 2 VERT.
A425	X	7	11-8				WING 2 HORIZ. E.F.
A426	X	17	5-1	X			WING 2 VERT. TOP
A627	X	2	11-8				WING 2 HORIZ. TOP E.F.
A428	X	3	4-7				BODY VERT. @ END @ WING 2

BENDING DIMENSIONS ARE OUT TO OUT OF BARS.



SECTION A

◆ ABUTMENT TO BE SUPPORTED ON HP 10 x 42 STEEL PILING (WITH PILE POINTS) DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 140 TONS PER PILE. ESTIMATED LENGTH 70'-0".



SECTION G-G

* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".




THE RODENT SHIELD SHALL BE PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 x 1-INCH SHEET METAL SCREWS.

RODENT SHIELD DETAIL

A512 BARS MAY BE PLACED AFTER ABUT. IS POURED BUT BEFORE CONC. HAS SET. EMBED BARS 1'-0".

ALL HORIZONTAL BARS IN BODY ARE A604, A605 BARS UNLESS SHOWN OTHERWISE.

EXCAVATE OR FILL TO BOTTOM OF ABUTMENT BEFORE DRIVING PILES.



FOR LOCATION OF SECTION A SEE SHEET 4

- ⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON THIS SHEET. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".
- ⊙ KEYED CONST. JOINT - FORMED BY A BEVELED 2" x 6".


FOR PILE SPLICE DETAIL SEE SHEET 2.

F.F. DENOTES FRONT FACE
B.F. DENOTES BACK FACE
E.F. DENOTES EACH FACE

5/4/2021 PENTABLE:BRReou_shd_util.tb1


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CLP		PLANS CK'D. AEB	
SOUTH ABUTMENT DETAILS & BILL OF BARS			SHEET 8 OF 19

NOTE:
SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF
1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT
SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE).




ELEVATION
(LOOKING NORTH)

FOR SECTION A SEE SHEET 13



SECTION F

- ① KEYED CONST. JOINT - FORMED BY A BEVELED 2" x 6".
 - ② PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".
 - ③ VERTICAL 18" RUBBERIZED MEMBRANE WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WINGWALL.
 - ④ VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING
- B.F. DENOTES BACK FACE




PLAN

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT			SHEET 9 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com

5/4/2021 PENTABLE:BRRedu_shd_util.tbl



PILE LAYOUT

VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING

FOR PILE SPLICE DETAIL SEE SHEET 2.

5/4/2021 PENTABLE:BRedu_shd_utl1.tbl



8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY	CLP	PLANS CK'D.	AEB
NORTH ABUTMENT PILE LAYOUT			SHEET 10 OF 19

ORIGINAL PLANS PREPARED BY

AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



- ⊕ 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
 - OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
 - ⊞ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.
- F.F. DENOTES FRONT FACE.
E.F. DENOTES EACH FACE.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT WING 3 DETAILS			SHEET 11 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com


5/4/2021 PENTABLE:BRedu_shd_util.tbl

8

8



ELEVATION - WING 4



SECTION B

- ⊕ 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
 - OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
 - ⊞ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.
- F.F. DENOTES FRONT FACE.
E.F. DENOTES EACH FACE.

5/4/2021
PENTABLE:BRedu_shd_util.tbl

8

8





NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT WING 4 DETAILS			SHEET 12 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com

BILL OF BARS

BAR NO.	COATED BAR	NO. REQ'D.	LENGTH	BENT BAR	BUNDLED	BAR SERIES	1,660' COATED	3,290' UNCOATED
LOCATION								
B401		8	28-0	X			BODY @ PILES	
B402		16	2-3				BODY @ PILES	
B503		72	14-2	X			BODY VERT.	
B604		11	31-10				BODY HORIZ.	
B605		11	28-11				BODY HORIZ.	
B806		14	12-11	X			BODY HORIZ. B.F. @ WINGS	
B607		7	22-9				BODY HORIZ. B.F. BTWN WINGS	
B608		7	19-10				BODY HORIZ. B.F. BTWN WINGS	
B409		3	10-0				BODY HORIZ.	
B410		3	7-11				BODY HORIZ.	
B511		16	5-1	X			BODY VERT.	
B512	X	56	2-0				BODY DOWELS	
B513	X	12	15-8	X			WING 3 VERT.	
B514	X	6	14-2				WING 3 HORIZ. F.F.	
B615	X	8	13-11				WING 3 HORIZ. B.F. & TOP	
B516	X	17	9-2	X			WING 3 VERT.	
B417	X	7	11-8				WING 3 HORIZ. E.F.	
B418	X	17	5-1	X			WING 3 VERT. TOP	
B619	X	2	11-8				WING 3 HORIZ. TOP E.F.	
B420	X	3	4-7				BODY VERT. @ END @ WING 3	
B521	X	12	15-8	X			WING 4 VERT.	
B522	X	6	14-2				WING 4 HORIZ. F.F.	
B623	X	8	13-11				WING 4 HORIZ. B.F. & TOP	
B524	X	17	9-2	X			WING 4 VERT.	
B425	X	7	11-8				WING 4 HORIZ. E.F.	
B426	X	17	5-1	X			WING 4 VERT. TOP	
B627	X	2	11-8				WING 4 HORIZ. TOP E.F.	
B428	X	3	4-7				BODY VERT. @ END @ WING 4	

BENDING DIMENSIONS ARE OUT TO OUT OF BARS.




FOR LOCATION OF SECTION A SEE SHEET 9

- PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".
- KEYED CONST. JOINT - FORMED BY A BEVELED 2" x 6".

FOR PILE SPLICE DETAIL SEE SHEET 2.

F.F. DENOTES FRONT FACE
 B.F. DENOTES BACK FACE
 E.F. DENOTES EACH FACE

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CLP		PLANS CK'D. AEB	
NORTH ABUTMENT DETAILS & BILL OF BARS			SHEET 13 OF 19



ALTERNATE CONSTRUCTION JOINT AT ABUTMENT

NOTES

PARTIAL ZINC OR PLASTIC BULKHEAD MAY BE USED AS ALTERNATE CONSTRUCTION JOINT, WITH THE PERMISSION OF THE ENGINEER, AT THE CONTRACTOR'S EXPENSE.

VERTICAL CONSTRUCTION JOINT KEYWAY IS NOT REQUIRED WHEN USING ALTERNATE CONSTRUCTION JOINT.

CARE IS TO BE USED IN CASTING CONCRETE AROUND BULKHEAD TO PREVENT DISLOCATION OR MISALIGNMENT OF THE BULKHEAD.

① USE A JOINT TOOL TO CONSTRUCT A CONTRACTION JOINT APPROXIMATELY 1/2" DEEP.

F.F. DENOTES FRONT FACE

B.F. DENOTES BACK FACE

NO.	DATE	REVISION	BY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

STRUCTURE B-5-469

DRAWN BY	CLP	PLANS CK'D.	AEB
----------	-----	-------------	-----

ALTERNATE CONSTRUCTION JOINT


SHEET 14 OF 19

ORIGINAL PLANS PREPARED BY

AYRES

3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com

5/4/2021
PENTABLE:BRedu_shd_ufil.tbl




TYPICAL SECTION THRU BRIDGE


± 0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.

CONST. JOINT - STRIKE OFF AS SHOWN AND LEAVE ROUGH. FOR DECK POUR, MATCH BRIDGE X-SLOPE.

3/4" V-GROOVE. EXTEND V-GROOVE TO 6" FROM FRONT FACE OF ABUTMENTS - TYP.



TYPICAL SECTION THRU SIDEWALK



PART LONGITUDINAL SECTION


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
SUPERSTRUCTURE			SHEET 15 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equi Claire, WI 54701
www.AyresAssociates.com

5/4/2021 PENTABLE:BRedu_shd_ufile.tbl

8

8



PLAN

5/4/2021 PENTABLE:BRedu_shd_util.tbl

8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
SUPERSTRUCTURE PLAN			SHEET 16 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
 Eau Claire, WI 54701
 www.AyresAssociates.com

BILL OF BARS

BAR NO.	COATED BAR	NO. REOD.	LENGTH	BENT BAR	BUNDLED	BAR SERIES	23,140# COATED
							LOCATION
S501	X	118	6-2	X			SLAB @ ABUT.
S502	X	118	3-4	X			SLAB @ ABUT.
S903	X	117	29-6				SLAB LONG. BOT.
S504	X	47	57-10				SLAB TRANS. BOT.
S505	X	35	57-10				SLAB TRANS. TOP
S406	X	59	32-10				SLAB LONG. TOP
S407	X	140	3-4	X			SLAB @ SDWK. @ EDGE OF SLAB
S408	X	140	3-1	X			SLAB @ SDWK. @ CURB
S409	X	20	32-10				SDWK. LONG. TOP
S510	X	208	7-3	X			SDWK. TRANS. TOP
S511	X	86	4-4	X			SLAB @ PARAPET VERT.
S512	X	86	4-9	X			SLAB @ PARAPET VERT.
S513	X	16	34-2				PARAPET HORIZ.

BENDING DIMENSIONS ARE OUT TO OUT OF BARS.



CAMBER DIAGRAM

CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION & FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT.

TOP OF DECK ELEVATIONS



LOCATION	℄ OF S. ABUT.	0.1 PT	0.2 PT	0.3 PT	0.4 PT	0.5 PT	0.6 PT	0.7 PT	0.8 PT	0.9 PT	℄ OF N. ABUT.
W. EDGE OF SLAB	641.19	641.22	641.25	641.28	641.31	641.34	641.37	641.40	641.43	641.46	641.49
E. EDGE OF SIDEWALK	641.33	641.36	641.39	641.42	641.45	641.48	641.51	641.54	641.57	641.60	641.63
℄ OF TAYLOR STREET	641.77	641.80	641.83	641.86	641.89	641.92	641.95	641.98	642.01	642.04	642.07
W. EDGE OF SIDEWALK	641.33	641.36	641.39	641.42	641.45	641.48	641.51	641.54	641.57	641.60	641.63
E. EDGE OF SLAB	641.19	641.22	641.25	641.28	641.31	641.34	641.37	641.40	641.43	641.46	641.49

ELEVATIONS SHOWN ARE FINISHED DECK AND DO NOT INCLUDE ALLOWANCES OF DEAD LOAD DEFLECTION AND FUTURE CREEP.

SURVEY TOP OF SLAB ELEVATIONS

LOCATION	℄ OF S. ABUT.	5/10 PTS.	℄ OF N. ABUT.
W. GUTTER			
℄ OF STRUCTURE			
E. GUTTER			

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF DECK ELEVATIONS AT THE ℄ OF ABUTMENTS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR ℄. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.




DETAIL OF ANCHOR ASSEMBLY

NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.


ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
 Eau Claire, WI 54701
 www.AyresAssociates.com

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CLP		PLANS CK'D. AEB	
SUPERSTRUCTURE DETAILS AND BILL OF BARS			SHEET 17 OF 19




PLAN OF PARAPET




AT ABUTMENTS

INSIDE ELEVATION OF PARAPET




SECTION A-A



OUTSIDE FACE OF PARAPET

BILL OF BARS

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
R501	X	80		X		PARAPET VERT.
R502	X	80	4'-9"	X		PARAPET VERT.
R503	X	32				PARAPET HORIZ.




R501


R502

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY CLP		PLANS CK'D. AEB	
COMBINATION RAIL TYPE "C2"			SHEET 18 OF 19


ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com




TYPICAL RAIL POST BASE PLATE




ANCHOR PLATE



END RAIL BASE PLATE




END RAIL BASE PLATE



ANCHORAGE FOR RAIL POSTS


NOTE: ANCHOR PLATE NOT REQUIRED WHEN ADHESIVE ANCHORS ARE USED.




ANCHORAGE FOR END RAIL

NOTE: ANCHOR PLATES NOT REQ'D. WHEN ADHESIVE ANCHORS ARE USED.

WHEN ADHESIVE ANCHORS ARE USED, FIELD BEND AND/OR DISPLACE TO AVOID HITTING LONGITUDINAL BAR WHEN DRILLING FOR ADHESIVE ANCHORS.




END RAIL ANCHOR PLATE




RAIL POST SHIM DETAIL

(2 SETS PER POST)




SHOP RAIL SPLICE DETAIL

(LOCATION MUST BE SHOWN ON SHOP DRAWINGS)



FIELD ERECTION JOINT DETAIL

MIN. 5/8" FLAT SURFACE DIA. PUNCHINGS OR STUDS MAY BE USED AS AN ALTERNATE.



END RAIL SHIM DETAIL

(2 SETS PER POST)

LEGEND

- 1A PLATE 5/8" X 6" X 8" WITH 3/4" X 1/2" SLOTTED HOLES.
- 1C PLATE 5/8" X 8" X 1'-1" WITH 3/4" X 1/2" SLOTTED HOLES.
- 1D PLATE 5/8" X 8" X 1'-6" WITH 3/4" X 1/2" SLOTTED HOLES.
- 2A 1/4" X 5" X 7" ANCHOR PLATE WITH 1/16" DIA. HOLES FOR THR'D. RODS NO. 3.
- 2C 1/4" X 2 1/2" X 7 1/4" ANCHOR PLATE WITH 1/16" DIA. HOLES FOR THR'D. RODS NO. 3.
- 3 5/8" DIA. X 9" LONG, TYPE 316 STAINLESS STEEL THREADED RODS (MIN. TENSILE STRENGTH = 70 KSI) WITH NUT AND WASHERS OF SAME ALLOY GROUP. ALTERNATIVE ANCHORAGE: CONCRETE ADHESIVE ANCHORS 3/8"-INCH. EMBED 7" IN CONCRETE FOR RAIL POSTS. EMBED 5" IN CONCRETE FOR END RAILS. ADHESIVE ANCHORS SHALL CONFORM TO SECTION 502.2.12 OF THE STANDARD SPECIFICATIONS.
- 4A STRUCTURAL TUBING 3" X 1/2" X 3/16". PLACE VERTICAL. WELD TO NO. 1 & 5.
- 5A STRUCTURAL TUBING 3" X 1/2" X 3/16" RAILS. WELD TO NO. 1 & NO. 4. INSIDE OF TUBE TO BE PAINTED AT ALL FIELD ERECTION & EXPANSION JOINTS.
- 5C STRUCTURAL TUBING 2 1/2" DIA. (STANDARD SIZE) (2.875" O.D.). WELD TO NO. 1 & NO. 4. INSIDE OF TUBE TO BE PAINTED AT ALL FIELD ERECTION & EXPANSION JOINTS.
- 6A BAR 1" X 1" PICKETS. WELD TO NO. 5. PLACE VERTICAL.
- 9A RECTANGULAR SLEEVE FABRICATED FROM 3/16" PLATES. PROVIDE "SLIDING FIT".
- 9B CIRCULAR SLEEVE FABRICATED FROM STRUCTURAL TUBING 2" DIA. (STANDARD SIZE) (2.375" O.D.).
- 10A RECTANGULAR SLEEVE FABRICATED FROM 3/16" PLATES. (1'-4" @ FIELD ERECTION JTS.) (1'-4" @ STRIP SEAL JTS.)
- 10B CIRCULAR SLEEVE FABRICATED FROM STRUCTURAL TUBING 2" DIA. (STANDARD SIZE) (2.375" O.D.). (1'-4" @ FIELD ERECTION JTS.) (1'-4" @ STRIP SEAL EXP. JTS.)

RAILING NOTES

- BID ITEM SHALL BE "RAILING STEEL TYPE C2", WHICH SHALL INCLUDE ALL STEEL ITEMS SHOWN.
- POST BASE PLATES SHALL BE FLAT WITH ALL SURFACES SMOOTH AND FREE FROM WARP AND ALL EDGES SMOOTH, STRAIGHT AND VERTICAL. ALL PLATE CUTS SHALL BE MACHINE OR MACHINE FLAME CUTS.
- ALL PLATES, BARS, AND RECTANGULAR SLEEVES SHALL CONFORM TO ASTM A709 GRADE 36. ALL STRUCTURAL TUBING SHALL CONFORM TO ASTM A500 GRADE B.
- ANCHORAGES SHALL BE ACCURATELY PLACED TO PROVIDE CORRECT ALIGNMENT OF RAILING. SET NORMAL TO GRADE.
- CUT BOTTOM OF POST TO MAKE POST VERTICAL IN BOTH TRANSVERSE AND LONGITUDINAL DIRECTION.
- STEEL SHIMS SHALL BE PROVIDED & USED UNDER BASE PLATES WHERE REQUIRED FOR ALIGNMENT, AND SHALL BE GALVANIZED.
- CAULK AROUND PERIMETER OF BASE PLATES, NO. 1, AND FILL BOLT SLOT OPENINGS IN SHIMS AND BASE PLATES WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER.
- ALL JOINTS AND RECESSES IN CONCRETE PARAPET ARE TO BE VERTICAL.
- ALL MATERIAL (EXCEPT NO. 3 & 12) SHALL BE GALVANIZED AFTER FABRICATION. PRIOR TO GALVANIZING, THE STEEL RAILING SHALL BE GIVEN A NO. 6 BLAST CLEANING PER SSPC SPECIFICATIONS, PAINT OVER GALVANIZING WITH AN APPROVED TIE COAT AND TOP COAT AS SPECIFIED IN THE CONTRACT DOCUMENTS. THE RAILING SHALL BE PAINTED AMS STD. COLOR NO. [] , []
- VENT HOLES SHALL BE DRILLED IN POST AND RAIL MEMBERS AS REQUIRED TO FACILITATE GALVANIZING AND DRAINAGE.
- RAILING SHALL BE FABRICATED IN LENGTHS THAT INCLUDE 3 OR 4 POSTS.
- TOUCH-UP PAINTING TO BE DONE AT COMPLETION OF STEEL RAILING INSTALLATION TO THE SATISFACTION OF THE ENGINEER AT NO EXTRA COST.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-469			
DRAWN BY		CLP	PLANS CK'D. AEB
COMBINATION RAIL TYPE "C2" DETAILS			SHEET 19 OF 19


ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com

EARTHWORK - TAYLOR STREET


STATION	AREA (SF)			Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		Mass Ordinate
	Cut	Unusable Pavement Material	Fill	Cut	Unusable Pavement Material	Fill	Cut 1.00	Expanded Fill 1.30	
09+50	75.33	29.00	4.39	0	0	0	0	0	0
09+75	77.72	29.00	2.25	71	27	3	71	4	40
9+86.42	77.72	29.00	2.25	33	12	1	104	4	61
B-59-198									61
10+19.58	77.39	29.00	1.93	0	0	0	104	4	61
10+35	77.39	29.00	1.93	44	17	1	44	1	87
10+50	76.26	29.00	1.89	43	16	1	87	3	112

191 72 6

Notes:	
1 - Cut	Cut includes Salvaged/Unusable Pavement material
2 - Salvaged/Unusable Pavement Material	This does not show up in cross sections
3 - Fill	Does not include Unusable Pavement Exc volume
4 - Mass Ordinate	Cut - Unusable Pavement Material- (Fill * Fill Factor)



PROJECT NO: 4987-11-71	HWY: TAYLOR STREET	COUNTY: BROWN	CROSS SECTIONS: TAYLOR STREET	SHEET	E
------------------------	--------------------	---------------	-------------------------------	-------	---




9

9

PROJECT NO: 4987-11-71	HWY: TAYLOR STREET	COUNTY: BROWN	CROSS SECTIONS: TAYLOR STREET	SHEET E
------------------------	--------------------	---------------	-------------------------------	---------

FILE NAME : V:\TRANS-GB\450485 TAYLOR\C3D\SHEETSPLAN\090201 XS.DWG PLOT DATE : 7/8/2021 12:20 PM PLOT BY : SOUFAL, KEVIN PLOT NAME : PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 090202 xs



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>