



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

March 2, 2022

NOTICE TO ALL CONTRACTORS:

Proposal #34: 9050-03-71
Rhineland - Woodruff
Kildeer Road to Vilas County Line
STH 47
Oneida County

Letting of March 8, 2022

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
4	Traffic

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
465.0110	Asphaltic Surface Patching	TON	1774	-103	1671

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
109	Miscellaneous Quantities (Revised Asphaltic Surface Patching quantity)
115	Miscellaneous Quantities (Changed station range header)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

9050-03-71

March 2, 2022

Special Provisions

3. Prosecution and Progress.

Replace paragraph five with the following:

Traffic will be allowed to operate on a milled surface for up to 96 hours. A milled surface is prohibited during the time periods specified in this section and in the Holidays and Special Events article.

4. Traffic.

Replace paragraph one with the following:

When lane closures are necessary, maintain traffic through the area through the use of flagging operations. A second lane closure may occur if it is located more than one mile from the first operation. Maintain a minimum roadway width of 16 ft., with the exception of a 12 ft. roadway width during construction of culvert 43-047-520.

The contractor shall cease or alter their work operations if traffic delays become longer than 15 minutes. If the contractor fails to comply with this special provision within a timely manner the project engineer shall suspend work operations in accordance with Subsection 108.5 (Limiting Operations) until the contractor complies with the 15-minute delay period. If the contractor continues operations, Subsection 105.3.2.3 (Unauthorized Work) may be enforced for any work completed during that time, and no additional compensation or additional time will be allowed due to such suspension of operations.

Schedule of Items

Attached, dated March 2, 2022, are the revised Schedule of Items Page 2.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 109 and 115.

END OF ADDENDUM

Addendum No. 01
ID 9050-03-71
Revised Sheet 109
March 2, 2022

ASPHALTIC CENTER LINE RUMBLE STRIP

STA	STA	FT
646+11	807+00	12,100
908+00	1210+89	23,100
PROJECT 9050-03-71 TOTAL		35,200

ASPHALTIC FLUMES

STA	LOCATION	SY
840+60	STH 47/BLUEBIRD	6
1216+40	STH 47/CTH J	6
PROJECT 9050-03-71 TOTAL		12

STATION	LOCATION	LF	CONCRETE	MASONRY	CURB
9050-03-71 CATEGORY 0010					
1252+30 - 1252+60	STH 47	25	2		
PROJECT 9050-03-71 TOTALS		25	2	2	2

ASPHALTIC SURFACE PATCHING

LOCATION	TON
PROJECT 9050-03-71 CATEGORY 0010	
CURB REPLACEMENT/CURB RAMPS	872
SIGNAL LOOP PATCHES	199
SUBSURFACE REPAIR AREAS (UNDISTRIBUTED)	600
PROJECT 9050-03-71 TOTAL	1,671

ASPHALTIC SURFACE

STA	LOCATION	TON
PROJECT 9050-03-71 CATEGORY 0010		
953+08 - 954+18	CULVERT 47-043-460 STH 47	138
1147+73 - 1148+83	CULVERT 47-043-460 STH 47	127
	LAKE TOMAHAWK STORMSEWER (6" DEPTH)	123
	STA 971+45 RT MULTITUDE TRAIL APPROACH	6
	STA 1000+25 RT MULTITUDE TRAIL APPROACH	6
	STA 1021+20 RT MULTITUDE TRAIL APPROACH	6
	STA 1055+50 RT MULTITUDE TRAIL APPROACH	6
PROJECT 9050-03-71 CATEGORY 0010 TOTAL		412
PROJECT 9050-03-71 CATEGORY 0020		
	ASPHALT WALK BALSAM-OAK	71
	ASPHALT WALK VETERANS-BALSAM	23
PROJECT 9050-03-71 CATEGORY 0020 TOTAL		94

ASPHALTIC SURFACE DRIVEWAYS

LOCATION	TON	
PROJECT 9050-03-71 CATEGORY 0010		
PARKING LOTS	---	
3" DEPTH	10	
AR BUTLUS SW	2	
RAINBOW SE	6	
RAINBOW NW	4	
CHOATE SW	2	
CHOATE N	3	
CEDAR SE	3	
PROJECT 9050-03-71 CATEGORY 0010 TOTAL		27
PROJECT 9050-03-71 CATEGORY 0020		

DRIVEWAYS	15	
3" DEPTH	12	
STA 1254+00 RT	4	
STA 1256+53 RT	4	
STA 1257+83 RT	4	
PROJECT 9050-03-71 CATEGORY 0020 TOTAL		31

Addendum No. 01
ID 9050-03-71
Revised Sheet 115
March 2, 2022

PAVEMENT MARKING (LONGITUDINAL)

STATION	646.1040 MARKING LINE	646.3040 GROOVED WET REFLECTIVE EPOXY (WHITE)	646.1020 MARKING LINE EPOXY (WHITE)	649.0105 TEMPORARY MARKING PAVEMENT (YELLOW)	649.0120 TEMPORARY MARKING LINE EPOXY (YELLOW)
LOCATION	LF	LF	LF	LF	LF
STA 646+11 - STA 807+00	30,323	---	6,720	6,720	6,720
STA 807+00 - STA 824+35	---	6,894	6,900	6,900	---
STA 824+35 - STA 908+00	8,428	---	7,355	7,355	---
STA 908+00 - STA 1141+00	43,274	---	8,075	8,075	8,075
STA 1141+00 - STA 1210+89	13,526	---	4,045	4,045	4,045
STA 1210+89 - STA 1243+12	5,653	---	5,210	5,210	---
STA 1243+12 - STA 1287+12	---	2,051	6,710	6,710	---
CTH D (S)	---	---	72	---	---
CTH D (N)	---	---	70	---	---
CTH J (W)	---	60	150	---	---
CTH J (E)	---	85	170	---	---
VETS PKWY	---	---	54	---	---
PROJECT 9050-03-71 TOTALS	101,203	746	45,531	45,015	18,840
			9,012		54,543

STA 807+00 - STA 824+35

PAVEMENT MARKING (TRANSVERSE)

LOCATION	646.5020 MARKING ARROW EPOXY	646.5120 MARKING WORD EPOXY	646.7120 MARKING DIAGONAL EPOXY	646.8120 MARKING CURB EPOXY	646.8220 MARKING ISLAND NOSE EPOXY	646.6020 MARKING STOP LINE EPOXY	646.6120 MARKING STOP LINE EPOXY	646.7420 MARKING CROSSWALK EPOXY	646.8320 MARKING PARKING STALL EPOXY
	EACH	EACH	LF	LF	EACH	LF	LF	LF	LF
CTH D EAST	---	---	---	---	---	---	---	---	---
ARBUTUS	---	---	---	---	---	---	---	160	---
VIOLET	---	---	---	---	---	---	---	160	---
RAINBOW	---	---	---	---	---	---	---	224	---
CHOATE	---	---	---	---	---	---	---	140	---
PARKING STALLS - LAKE TOMAHAWK	---	---	---	---	---	---	---	---	402
CTH J (SOUTH LEG)	2	---	67	33	2	---	24	---	---
CTH J (NORTH LEG)	3	1	176	33	2	---	24	---	---
CTH J (WEST LEG)	2	---	---	---	---	---	33	---	---
CTH J (EAST LEG)	2	---	---	---	---	---	35	---	---
VETERANS PKWY	---	---	---	---	---	---	35	---	---
BALSAM	---	---	---	---	---	---	40	---	---
BIRCH	---	---	---	---	---	---	21	---	---
CEDAR	---	---	---	---	---	---	16	---	---
MARLE	---	---	---	---	---	---	12	---	---
PINE	---	---	---	---	---	---	12	---	---
POPLAR	---	---	---	---	---	---	12	---	---
SPRUCE	---	---	---	---	---	---	12	---	---
PARKING STALLS - WOODRUFF	---	---	---	---	---	---	---	---	114
PROJECT 9050-03-71 TOTALS	9	1	243	66	4	160	144	1,206	516



Proposal Schedule of Items

Proposal ID: 20220308034 Project(s): 9050-03-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	213.0100 Finishing Roadway (project) 01. 9050-03-71	1.000 EACH	_____.	_____.
0034	305.0110 Base Aggregate Dense 3/4-Inch	12,101.000 TON	_____.	_____.
0036	305.0120 Base Aggregate Dense 1 1/4-Inch	1,322.000 TON	_____.	_____.
0038	416.0610 Drilled Tie Bars	320.000 EACH	_____.	_____.
0040	455.0605 Tack Coat	15,661.000 GAL	_____.	_____.
0042	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0044	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	1.000 EACH	_____.	_____.
0046	460.5224 HMA Pavement 4 LT 58-28 S	27,700.000 TON	_____.	_____.
0048	465.0105 Asphaltic Surface	506.000 TON	_____.	_____.
0050	465.0110 Asphaltic Surface Patching	1,671.000 TON	_____.	_____.
0052	465.0120 Asphaltic Surface Driveways and Field Entrances	58.000 TON	_____.	_____.
0054	465.0315 Asphaltic Flumes	12.000 SY	_____.	_____.
0056	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	35,200.000 LF	_____.	_____.
0058	513.2001 Railing Pipe	25.000 LF	_____.	_____.
0060	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	2.000 EACH	_____.	_____.

