EAU DECEMBER 2022 FEDERAL PROJECT STATE PROJECT STATE OF WISCONSIN PROJECT CONTRACT ORDER OF SHEETS PROJECT ID: WITH: N/A 7849-03-73 WISC 2023121 1 **DEPARTMENT OF TRANSPORTATION** Typical Sections and Details Estimate of Quantities Miscellaneous Quantities PLAN OF PROPOSED IMPROVEMENT Plan and Profile Standard Detail Drawings **USH 10 - STH 98** 849-03-73 USH 10 TO CTH H **CTHY** TOTAL SHEETS = **CLARK COUNTY** STATE PROJECT NUMBER PROJECT LOCATION 7849-03-73 ACCEPTED FOR COUNTY R 1 E ORIGINAL PLANS PREPARED BY **END PROJECT** STA 217+25 RD CRK PANTHER DESIGN DESIGNATION A.A.D.T. SCONSIA 2042 = 1190 D.H.V. = 150 = 60/40 ROSS T. = 37.5 DESIGN SPEED = 55 MPH NET EXCEPTION TO CL LENGTH JOHNSON = 690,000 RD STA 178+14.08 - STA 178+96.59 TIMBER LN CONVENTIONAL SYMBOLS RD PINE CRK PROFILE GRADE LINE CORPORATE LIMITS /////// ORIGINAL GROUND PROPERTY LINE MARSH OR ROCK PROFILE 36 LOT LINE (Professional Engineer Signature) (To be noted as such) LIMITED HIGHWAY EASEMENT SPECIAL DITCH EXISTING RIGHT OF WAY STATE OF WISCONSIN T 25 N GRADE ELEVATION PROPOSED OR NEW R/W LINE RD DEPARTMENT OF TRANSPORTATION T 24 N CULVERT (Profile View) SLOPE INTERCEPT REPARED BY **BEGIN PROJECT** UTILITIES REFERENCE LINE CBS SQUARED, INC STA 10+00 ELECTRIC Designer EXISTING CULVERT - - ------Y=364235.65 FIBER OPTIC PROPOSED CULVERT X=747736.56 (Box or Pipe) Regional Examiner SANITARY SEWER TYLER RONGSTAD, PE COMBUSTIBLE FLUIDS LAYOUT STORM SEWER 2 MILES TELEPHONE SCALE PPROVED FOR THE DEPARTMENT HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN WATER MARSH AREA COORDINATE REFERENCE SYSTEM (WISCRS), CLARK COUNTY, NAD83 (2011), 7/18/2022 UTILITY PEDESTAL Д IN U.S. SURVEY FEET, POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES, GRID DISTANCES ARE THE SAME AS TOTAL NET LENGTH OF CENTERLINE = 3.910 MILES POWER POLE ₫ GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). Ø WOODED OR SHRUB AREA TELEPHONE POLE Ε GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A. FILE NAME : P:\CLARK\20001 CTH Y STP RURAL\CAD\C3D\SHEETSPLAN\010101 TI.DWG 7/13/2022 2:17 PM

#### GENERAL NOTES

WHEN THE QUANTITY OF BASE AGGREGATE IS MEASURED BY THE TON OR CUBIC YARD, THE DEPTH OR THICKNESS OF THE LAYER SHOWN ON THE PLANS IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE FNGINFFR.

DISTURBED AREAS OUTSIDE THE FINISHED SHOULDER POINTS SHALL BE SEEDED AND COVERED WITH EROSION MAT AS DIRECTED BY THE ENGINEER.

THE EXACT LOCATION OF THE UNDISTRIBUTED EROSION CONTROL DEVICES SHALL BE DETERMINED IN THE FIELD.

A SAWED JOINT WILL BE REQUIRED WHERE NEW PAVEMENT IS TO MEET AN EXISTING PAVED SURFACE.

THE CONTRACTOR'S HMA PAVING OPERATION SHALL BE CONSISTENT WITH THE TYPICAL SECTIONS AND CONSTRUCTED TO PREVENT LONGITUDINAL JOINTS FROM BEING LOCATED WITHIN THE DRIVING, TURNING, PASSING OR PARKING I ANF

4.25-INCH HMA PAVEMENT SHALL BE CONSTRUCTED WITH AN 2-INCH UPPER LAYER AND 2.25-INCH LOWER LAYER.

THE LOCATIONS OF THE EXISTING UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN

TEMPORARY STORAGE OF MATERIAL SHALL NOT BE PERMITTED IN WETLANDS.

THE PROPOSED SHOULDER WIDTHS SHOWN IN THE TYPICAL SECTIONS ARE MINIMUM WIDTHS. PERPETUATE EXISTING SHOULDER WIDTHS THAT ARE WIDER THAN WHAT IS SHOWN IN THE TYPICAL SECTIONS.

CONTROL POINT TABLE							
POINT NO.	<u>STA</u>	Y	Х	ELEVATION			
1	214+14	384646.2	747409.5	1220.891			
2	187+89	382021.6	747437.2	1216.518			
3	160+27	379259.1	747487.1	1213.658			
4	127+98	376031.3	747567.1	1235.594			
5	102+47	373481.4	747601.7	1229.393			
6	81+43	371377.6	747604.5	1231.564			
7	57+18	368951.7	747609.5	1235.975			
8	33+18	366553.0	747684.9	1196.231			
9	11+59	364294.2	747705.4	1208.642			
	CONTRO	OL POINTS ARE 3/4	" REBAR				

#### RUNOFF COEFFICIENT TABLE

	HY	DROLOG	C SOIL GROUP									
A	E	3	С								D	
	SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)				
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIP-	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
TURF	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPE:			.25			.27			.28			.30
TURF			.32			.34			.36			.38
PAVEMENT:												
ASPHALT						.7095						
CONCRETE						.8095						
BRICK	BRICK .7080											
DRIVES, WALKS						.7585						
ROOFS	ROOFS .7595											
GRAVEL ROADS, SHO	ULDERS					.4060						

TOTAL PROJECT AREA = 16.08 ACRES	
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIV	ITIES = <u>0.00</u> ACRES

BORING LOG						
NO.	STA (APPROX)	ASPH. THICKNESS (INCHES)	BASE (INCHES)			
1	12+00	5	9			
2	31+00	5	9			
3	72+50	5	9			
4	118+10	5	12			
5	142+50	5	12			
6	166+50	5	10			
7	192+50	5	7			
8	216+50	5	6			

WISCONSIN DNR

BRAD BETTHAUSER DNR LIAISON 473 GRIFFITH DRIVE WISCONSIN RAPIDS, WI 54494 (715) 421-7851 BRADLEY.BETTHAUSER@WISCONSIN.GOV

CLARK COUNTY
BRIAN DUELL
HIGHWAY COMMISSIONER
801 CLAY STREET
NEILLSVILLE, WI 54456
(715) 743-3680
BRIAN.DUELL@CO.CLARK.WI.US

TOWN OF FREMONT EDWARD SCHULTZ CHAIRMAN N 5671 OAK ST CHILI, WI 54420 (715) 683-2678 FREMONTCLERK@GMAIL.COM

DESIGN CONSULTANT
ROSS JOHNSON, P.E.
CBS SQUARED, INC.
770 TECHNOLOGY WAY
CHIPPEWA FALLS, WI 54729
(715) 579-4175
RJOHNSON@CBSSQUAREDINC.COM

WISDOT CONTACT
MATTHEW THORNSEN, P.E.
LOCAL PROGRAM PROJECT MANAGER
718 W. CLAIREMONT AVE
EAU CLAIRE, WI 54701
(715) 225-4159
MATTHEW.THORNSEN@DOT.WI.GOV

UTILITY CONTACTS

AT&T 304 S. DEWEY STREET EAU CLAIRE, WI 54701 RICK PODOLAK (715) 410-0656 RP4514@ATT.COM

TOWN OF FREMONT SANITATION COMMITTEE N 5671 OAK ST CHILI, WI 54420 TONY MAYER (715) 683-2823 FREMONTCLERK@GMAIL.COM

CLARK ELECTRIC COOPERATIVE 1209 W. DALL-BERG STREET GREENWOOD, WI 54437 JOSH BURNS (715) 456-3364 JBURNS@CECOOP.COM

FLINT HILLS RESOURCES 2267 COUNTY ROAD HH JUNCTION CITY, WI 54443 STEVE DOUCETTE (651) 244-9950 STEVE.DOUCETTE@FHR.COM

TDS TELECOM
410 4TH STREET
MOSINEE, WI 54455
MICHAEL FONDOW
(715) 360-4901
MICHAEL-FONDOW@TDSTELECOM.COM

VIKING GAS TRANSMISSION 2077 70TH AVE OSCEOLA, WI 54020 STEVE KEILEN (715) 294-2155 (OFFICE) (715) 417-0735 (CELL) STEVE.KEILEN@ONEOK.COM

WE ENERGIES
1921 8TH STREET SOUTH
WISCONSIN RAPIDS, WI 54494
TRAVIS KAHL
(715) 421-7256 (OFFICE)
(715) 498-6180 (CELL)
TRAVIS.KAHL@WE-ENERGIES.COM

XCEL ENERGY DISTRIBUTION 500 N 5TH STREET ABBOTSFORD, WI 54405 PAMELA DENZINE (715) 737-7174 (OFFICE) (715)218-6637 (CELL) PAMELA.DENZINE@XCELENERGY.COM

XCEL ENERGY TRANSMISSION
414 NICOLETT MALL 5TH FLOOR
MINNEAPOLIS, MN 54020
MITCHELL DIENGER
(612) 321-3109 (OFFICE)
MITCHELL.A.DIENGER@XCELENERGY.COM

DATUM


HORIZ: NAD 83 (2011), WISCRS CLARK CO.

VERT: NAVD 88 (2012), GEOID WI-12A

NORTHING = Y EASTING = X



PROJECT NO: 7849-03-73 HWY: CTH Y COUNTY: CLARK GENERAL NOTES SHEET **E** 



LAYOUT NAME - Project Overview


PLOT BY: CODY FELDMANN


PLOT NAME :


PLOT SCALE :

WISDOT/CADDS SHEET 44











HWY: CTH Y



#### TYPICAL EXISTING SECTION

PINE CREEK RD (EAST) TIMBER LANE RD PANTHER CREEK RD



#### TYPICAL EXISTING SECTION PINE CREEK RD (WEST)

FILE NAME : P:\CLARK\20001 CTH Y STP RURAL\CAD\C3D\SHEETSPLAN\020301\_TS.DWG

7849-03-73

PROJECT NO:

4/25/2022 11:26 AM

COUNTY: CLARK

PLOT BY:


PLOT NAME :

PLOT SCALE : 1 IN:10 FT SHEET


Ε


TYPICAL SECTIONS

WISDOT/CADDS SHEET 42



PLOT DATE : 7/9/2022 9:03 PM 1 IN:10 FT WISDOT/CADDS SHEET 42





P:\CLARK\20001 CTH Y STP RURAL\CAD\C3D\SHEETSPLAN\021002-CD.DWG LAYOUT NAME - Bridge Detail -40\_Scale PLOT DATE : 7/13/2022 10:47 AM PLOT BY: ED OCHS PLOT NAME : PLOT SCALE : ########## WISDOT/CADDS SHEET 44


EXISTING JOINT -




75' MAINLINE MIN. 100' MAINLINE MAX. —4.25" MIN SAW AND REMOVE AT TERMINI -HMA PAVEMENT -←4.25" MIN. REMOVING ASPHALTIC SURFACE BUTT JOINTS PULVERIZED MATERIAL EXISTING PAVEMENT

#### REMOVING ASPHALTIC SURFACE, BUTT JOINT


REMOVING ASPHALTIC SURFACE BUTT JOINTS STA 10+00 - STA 10+75, CTH Y STA 106+25 - STA 107+00, CTH Y STA 120+15 - STA 120+90, CTH Y STA 176+05 - STA 177+05, CTH Y STA 180+06 - STA 181+06, CTH Y STA 216+50 - STA 217+25, CTH Y







Ε PROJECT NO: 7849-03-73 HWY: CTH Y COUNTY: CLARK **CONSTRUCTION DETAILS** SHEET

P:\CLARK\20001 CTH Y STP RURAL\CAD\C3D\SHEETSPLAN\021003-CD.DWG PLOT DATE : 7/13/2022 10:48 AM PLOT BY: ED OCHS PLOT NAME : PLOT SCALE : 1 IN:10 FT FILE NAME : WISDOT/CADDS SHEET 42 LAYOUT NAME - BUTT JOINT DETAIL







LAYOUT NAME - Intersection Detail

MARANDA WENDT

1 IN:30 FT

7849-	$\sim$	70
7849-	11.5	- / .5

Line         Item         Item Description         Unit         Total         Qty           002         204.0110         Removing Asphaltic Surface Butt Joints         SY         5,000         50,000           006         204.0120         Removing Asphaltic Surface Buttl Joints         SY         1,508,000         1,508,000           006         204.0120         Removing Asphaltic Surface Milling         SY         4,310,000         1,000           008         211.0101         Prepare Foundation for Asphaltic Paving (project) 01.7849-03-73         EACH         1,000         1,000           010         213.0101         Finishing Roadway (project) 01.7849-03-73         EACH         1,000         1,000           0101         213.0101         Finishing Roadway (project) 01.7849-03-73         EACH         1,000         3,373,000           0101         23.710.002         Base Aggregate Dense 3/4-Inch         SY         51,766,000         51,766,000           0101         374.102.05         MP Ulverize and Relay         SY         50,960,000         51,766,000           0101         374.102.05         ABC         DAV         59,960,000         2,996,000           0104         455.0605         Tack Coat         GAL         2,996,000         2,996,000
004         204.0115         Removing Asphaltic Surface Butt Joints         SY         1,508.000         1,508.000           008         211.0101         Perpeare Foundation for Asphaltic Paving (project) 01.7849-03-73         EACH         1.000         1.000           010         213.0100         Finishing Roadway (project) 01.7849-03-73         EACH         1.000         1.000           012         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         51,766.000           014         325.0100         Pulverize and Relay         SY         51,766.000         51,766.000           016         374.1020.5         QMP Pulverize and Relay Compaction         SY         50,960.000         59,960.000           018         455.065         Tack Coat         GAL         2,886.000         2,896.000           019         460.2001         Incentive Density HMA Pavement         DOL         8,220.000         8,220.000           010         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           010         460.6223         HMA Pavement 4 MT 58-34 S         TON         6,537.000         6,537.000           02         460.6223         HMA Pavement 4 MT 58-34 S         TON         6,238.000
004         204.0115         Removing Asphaltic Surface Butt Joints         SY         1,508.000         1,508.000           008         211.0101         Perpeare Foundation for Asphaltic Paving (project) 01.7849-03-73         EACH         1.000         1.000           010         213.0100         Finishing Roadway (project) 01.7849-03-73         EACH         1.000         1.000           012         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         51,766.000           014         325.0100         Pulverize and Relay         SY         51,766.000         59,960.000           016         374.1020.5         GMP Pulverize and Relay Compaction         SY         50,960.000         59,960.000           018         455.065         Tack Coat         GAL         2,880.000         2,896.000           019         460.2001         Incentive Density HMA Pavement         DOL         8,220.000         8,220.000           010         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           010         465.0120         Asphaltic Intersection Rumble Strips         SY         142.000         12.000           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.
006         204.0120         Removing Asphaltic Surface Milling         SY         4,310.000         4,310.000           008         211.0101         Prepare Foundation for Asphaltic Paving (project) 01.7849-03-73         EACH         1.000         1.000           010         213.0100         Finishing Roadway (project) 01.7849-03-73         EACH         1.000         1.000           012         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         3,373.000           014         325.0100         Pulverize and Relay Compaction         SY         51,766.000         51,766.000           016         374.1020.S         QMP Pulverize and Relay Compaction         SY         50,960.000         2,986.000           018         455.0605         Tack Coat         GAL         2,896.000         2,896.000           020         460.2000         Incentive Density HMA Pavement         DOL         8,220.000           024         460.6224         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           024         460.6224         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           024         465.0120         Asphaltic Intersection Rumble Strips         SY         142.000         12.000
008         211.0101         Prepare Foundation for Asphaltic Paving (project) 01. 7849-03-73         EACH         1.000         1.000           010         213.0100         Finishing Roadway (project) 01. 7849-03-73         EACH         1.000         1.000           012         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         50,000.000         50,000.000         50,000.000         50,000.000         50,000.000         50,000.000         50,000.000         50,000.000         50,000.000         60,000 <td< td=""></td<>
01010         213.0100         Finishing Roadway (project) 01. 7849-03-73         EACH         1.000         1.000           0112         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         3,373.000           014         325.0110         Pulverize and Relay         SY         51,766.000         51,766.000           016         374.1020.S         QMP Pulverize and Relay Compaction         SY         50,960.000         2,986.000           018         455.0605         Tack Coat         GAL         2,896.000         2,896.000           024         460.0201         Incentive Density HMA Pavement         DOL         8,220.000         6,537.000           024         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           024         460.6224         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         6,296.000         12,100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000
0112         305.0110         Base Aggregate Dense 3/4-Inch         TON         3,373.000         3,373.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         50,806.000         50,806.000         50,806.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         51,766.000         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         3,200.000         8,220.000         8,220.000         8,220.000         8,220.000         8,200.000         6,537.00         6,537.00         6,537.000         6,537.000         6,537.00         6,537.00         6,537.00         6,537.00         6,537.00         6,537.00         6,537.00         6,537.00         6,296.000         12.100
014         325.0100         Pulverize and Relay         SY         51,766.000         51,766.000           016         374.1020.S         CMP Pulverize and Relay Compaction         SY         50,960.000         50,960.000           018         455.0605         Tack Coat         GAL         2,986.000         2,986.000         22,986.000         20         460.2000         Incentive Density HMA Pavement         DOL         8,220.000         8,220.000         6,537.000         1,200         1,200         1,200         1,200         1,200         1,200         1,200         1,200         1,200         1,200         1,200         1,200
016         374.1020.S         QMP Pulverize and Relay Compaction         SY         50,960.000         50,960.000           018         455.0605         Tack Coat         GAL         2,896.000         2,896.000           020         460.2000         Incentive Density HMA Pavement         DOL         8,220.000         8,220.000           022         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           024         460.6244         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         12.100         12.100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         611.8120.5         Cover Plates Temporary         EACH         1.000         1.000           034         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           035         624.0100         Water         MGAL         208.000         208.000
018         455.0605         Tack Coat         GAL         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         2,896.000         8,222.000         8,222.000         8,222.000         8,222.000         6,537.000         6,508.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,537.000         6,200.000         6,537.000         6,200.000         6,537.000         6,537.000         12,100         12,100         12,100         12,100         12,100         12,100         12,100         12,100         12,100         12,100         10,000         10,000         10,000         10,000         10,000         10,000         10,000         10,000 </td
020         460.2000         Incentive Density HMA Pavement         DOL         8,220.000         8,220.000           022         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           024         460.6224         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         12.100         12.100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           034         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046
0022         460.6223         HMA Pavement 3 MT 58-28 S         TON         6,537.000         6,537.000           024         460.6224         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         12.100         12.100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8120         Cover Plates Temporary         EACH         1.000         1.000           034         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence Maintenance         LF         50.000         50.000           042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           045         628
024         460.6244         HMA Pavement 4 MT 58-34 S         TON         6,296.000         6,296.000           026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         12.100         12.100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silf Fence Maintenance         LF         50.000         50.000           042         628.1520         Silf Fence Maintenance         LF         50.000         50.000           044         628.1910         Mobilizations Erosion Control         EACH         1.000         1.000           048         628.1927         Erosion Mat Class II Type C         SY         100.00         2.000           050         642.5001
026         465.0120         Asphaltic Surface Driveways and Field Entrances         TON         12.100         12.100           028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         611.8120. S. Cover Plates Temporary         EACH         1.000         1.000           034         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         MGAL         208.000         208.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1520         Silt Fence         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           044         628.1910         Mobilizations Ernergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.00         100.00           049         628.1901
028         465.0450         Asphaltic Intersection Rumble Strips         SY         142.000         142.000           030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         611.8120.S         Cover Plates Temporary         EACH         1.000         1.000           034         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence         LF         50.000         50.000           042         628.1502         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         10.000           044         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class Il Type C         SY         10.000         10.000           050         630.0110         Seeding M
030         611.8110         Adjusting Manhole Covers         EACH         1.000         1.000           032         611.8120.S         Cover Plates Temporary         EACH         1.000         1.000           034         618.0100         Maintenance And Repair of Haul Roads (project) 01.7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence         LF         50.000         50.000           044         628.1920         Mobilizations Erosion Control         EACH         1.000         1.000           044         628.1910         Mobilizations Emergency Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.00         2.000           052         642.5001         Field Offi
0032         611.8120.S         Cover Plates Temporary         EACH         1.000         1.000           0034         618.0100         Maintenance And Repair of Haul Roads (project) 01. 7849-03-73         EACH         1.000         1.000           0036         619.1000         Mobilization         EACH         1.000         1.000           0038         624.0100         Water         MGAL         208.000         208.000           0040         628.1504         Silt Fence         LF         50.000         50.000           0042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           0044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           0046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           0048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           0050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           0052         642.5001         Field Office Type B         EACH         1.000         1.000           0054         643.0900         Traffic Control Si
034         618.0100         Maintenance And Repair of Haul Roads (project) 01. 7849-03-73         EACH         1.000         1.000           036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence         LF         50.000         50.000           042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.000         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control
036         619.1000         Mobilization         EACH         1.000         1.000           038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence         LF         50.000         50.000           044         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.00
038         624.0100         Water         MGAL         208.000         208.000           040         628.1504         Silt Fence         LF         50.000         50.000           042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         396           060         648.0100         Locating No-Passing Zones         MI
0404         628.1504         Silt Fence         LF         50.000         50.000           042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Ref
042         628.1520         Silt Fence Maintenance         LF         50.000         50.000           044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1.772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         <
0044         628.1905         Mobilizations Erosion Control         EACH         1.000         1.000           0046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           0048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           0050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           0052         642.5001         Field Office Type B         EACH         1.000         1.000           0054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           0056         643.5000         Traffic Control         EACH         1.000         1.000           0058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           0060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           0062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           0064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000
046         628.1910         Mobilizations Emergency Erosion Control         EACH         2.000         2.000           048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068
048         628.2027         Erosion Mat Class II Type C         SY         100.000         100.000           050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.
050         630.0110         Seeding Mixture No. 10         LB         2.000         2.000           052         642.5001         Field Office Type B         EACH         1.000         1.000           054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
0052         642.5001         Field Office Type B         EACH         1.000         1.000           0054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           0056         643.5000         Traffic Control         EACH         1.000         1.000           0058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           0600         648.0100         Locating No-Passing Zones         MI         3.960         3.960           0622         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
054         643.0900         Traffic Control Signs         DAY         1,772.000         1,772.000           056         643.5000         Traffic Control         EACH         1.000         1.000           058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
0056         643.5000         Traffic Control         EACH         1.000         1.000           0058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           0060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           0062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           0064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           0066         690.0150         Sawing Asphalt         LF         202.000         202.000           0068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           0070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
058         646.1020         Marking Line Epoxy 4-Inch         LF         54,200.000         54,200.000           060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
060         648.0100         Locating No-Passing Zones         MI         3.960         3.960           062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
062         650.8000         Construction Staking Resurfacing Reference         LF         20,725.000         20,725.000           064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
064         650.9911         Construction Staking Supplemental Control (project) 01. 7849-03-73         EACH         1.000         1.000           066         690.0150         Sawing Asphalt         LF         202.000         202.000           068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
066         690.0150         Sawing Asphalt         LF         202.000         202.000           1068         740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           1070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
740.0440         Incentive IRI Ride         DOL         15,680.000         15,680.000           070         ASP.1T0A         On-the-Job Training Apprentice at \$5.00/HR         HRS         300.000         300.000
070 ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR HRS 300.000 300.000
0 11

					204.0115	204.0120	
					REMOVING	REMOVING	
					ASPHALTIC	ASPHALTIC	
					SURFACE BUTT	SURFACE	
					JOINTS	MILLING	
CATEGORY	STATION	TO	STATION	LOCATION	SY	SY	REMARKS
0010	107+00	-	120+15	CTH Y	_	4,310	
0010	10+00	-	10+75	CTH Y	200	_	
0010	106+25	-	107+00	CTH Y	200	_	
0010	120+15	-	120+90	CTH Y	200	_	
0010	216+50	-	217+25	CTH Y	200	_	
0010	176+05	-	177+05	CTH Y	354	_	
0010	180+06	-	181+06	CTH Y	354	_	
				TOTAL 0010	1,508	4,310	

#### 204.0110 - REM ASPH SURFACE

		204.0110	
		REMOVING	
		ASPHALTIC	
		SURFACE	
CATEGORY	LOCATION	SY	REMARKS
0010	STA 40+49 LT	25	DRIVEWAY APRON
0010	STA 103+92 LT+49 LT	25	DRIVEWAY APRON
	TOTAL 0010	50	

#### 305.0110 - BASE AGGREGATE DENSE

305.0110 BASE AGGREGATE DENSE 3/4-INCH CATEGORY STATION STATION LOCATION TON REMARKS 10+00 93+50 CTH Y 1,364 0010 0010 120+15 177+05 CTH Y 929 217+25 CTH Y 607 0010 18+06 107+00 CTH Y 179 93+50 0010 TOTAL 0010 3,079

ORIGINATOR : DIST \_

\*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

PROJECT NO: 7849-03-73 HWY: CTH Y COUNTY: CLARK MISCELLANEOUS QUANTITIES SHEET E

ORG DATE : \_\_

FILE NAME :

PLOT DATE : \_\_\_\_\_

PLOT BY : \_\_\_\_\_

PLOT NAME : \_

PLOT SCALE : 1:1

## 3

#### 305.0110 & 465.0120 - DRIVEWAYS

\* 305.0110

465.0120

ASPHALTIC SURFACE

BASE DRIVEWAYS AND AGGREGATE FIELD

			AGGREGATE DENSE 3/4-INCH	FIELD ENTRANCES	
CATEGORY	STATION	LOCATION	TON	TON	REMARKS
0010	10+00	RT	5.0		
0010	24+65		7.0		
		RT		_	
0010	28+63	LT	6.2	_	
0010	38+55	LT	6.0	_	
0010	40+49	LT	_	6.2	
0010	43+19	RT	5.0	_	
0010	44+01	RT	4.3	_	
0010	45+24	LT	4.2	_	
0010	49+77	RT	9.5	_	
0010	50+48	RT	4.8	_	
0010	68+48	LT	7.1	_	
0010	69+18	RT	4.9	_	
0010	76+24	RT	6.8	_	
0010	77+30	RT	4.9	_	
0010	89+31	RT	4.5	_	
0010	90+82	RT	4.5	_	
0010	93+83	LT	13.6	_	
0010	94+32	RT	17.9	_	
0010	96+63	LT	9.2	_	
0010	97+03	RT	6.3	_	
0010	97+10	LT	6.7	_	
0010	98+31	RT	5.3	_	
0010	99+33	LT	4.7	_	
0010	99+76	RT	5.1	_	
0010	100+36	LT	4.7	_	
0010	101+02	LT	4.7	_	
0010	103+59	RT	4.6	_	
0010	103+92	LT	_	5.9	
0010	122+41	RT	3.4	_	
0010	122+48	LT	9.3	_	
0010	122+89	RT	4.5	_	
0010	123+30	LT	10.5	_	
0010	127+45	RT	4.4	_	
0010	128+52	RT	5.9	_	
0010	129+35	RT	4.6	_	
0010	130+25	RT	4.6	_	
0010	131+44	RT	4.6	_	
0010	132+68	RT	5.2	_	
0010	133+37	RT	5.9	_	
0010	133+72	LT	10.1	_	
0010	141+53	LT	10.2	_	
0010	143+46	LT	10.2	_	
0010	149+24	RT	6.7	_	
0010	188+55	RT	7.4	_	
0010	198+90	LT	11.7	_	
0010	216+13	RT	7.5	_	
0010	210+13	TOTAL 0010	294.0	12.1	

\*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

PROJECT NO: 7849-03-73 HWY: CTH Y COUNTY: CLARK MISCELLANEOUS QUANTITIES SHEET E

FILE NAME : PLOT DATE : \_\_\_\_\_ PLOT BY : \_\_\_\_ PLOT NAME : \_\_\_\_ ORG DATE : \_\_\_\_ ORIGINATOR : DIST PLOT SCALE : 1:1

	_
	l
	l
13	l
5	l
	l
$\vdash$	J

#### 325 - PULVERIZE AND RELAY

					325.0100 PULVERIZE AND RELAY	374.1020.S QMP PULVERIZE AND RELAY COMPACTION	624.0100 WATER	
CATEGORY	STATION	TO	STATION	LOCATION	SY	SY	MGAL	REMARKS
0010	10+75	-	106+25		25,884	25,467	104	
0010	120+90	-	216+50		25,882	25,493	104	
				TOTAL 0010	51,766	50,960	208	

#### 460 - ASPHALTIC PAVEMENT ITEMS

					455.0605	460.6223	460.6244	465.0450	
					TACK COAT	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-34 S	ASPHALTIC INTERSECTION RUMBLE STRIPS	
CATEGORY	STATION	TO	STATION	LOCATION	GAL	TON	TON	SY	REMARKS
0010	10+00	-	20+00		_	_	_	71	SOUTHBOUND APPROACH TO USH 10
0010	10+00	-	107+00		1,311	3,306	2,939	_	
0010	107+00	-	120+15		302	_	483	_	
0010	120+15	-	176+05		764	1,926	1,712	_	
0010	176+05	-	177+05		18	44	40	_	
0010	180+06	-	181+06		18	44	40	_	
0010	181+06	-	217+25		483	1,217	1,082	_	
0010	208+00	-	217+25		_	_	_	71	NORTHBOUND APPROACH TO CTH H
0010				PROJECT	_	_	_	_	
				TOTAL 0010	2,896	6,537	6,296	142	


	PROJECT NO: 7849-03-73	HWY: CTH Y	COUNTY: CLARK	MISCELLANEOUS QUANTITIES	SHEET	E	
--	------------------------	------------	---------------	--------------------------	-------	---	--


FILE NAME : PLOT DATE : \_\_\_\_\_ PLOT BY : \_\_\_\_ PLOT NAME : \_\_\_\_ ORG DATE : \_\_\_\_ ORIGINATOR : DIST PLOT SCALE : 1:1


	643	.0900 - TRAFFIC CON	TROL						<u>628 - E</u>	ROSION CONTROL		
CATEGORY	LOCATION	643.0900 TRAFFIC CONTROL SIGN DAY		REMARKS		CATEGORY	LOCATION	628.1 SILT FE LF	SILT FEI ENCE MAINTEN	ICE EROSION MAT		REMARKS
0010 0010 0010	7849-03-73 STA 10+00 TO STA 217+25 STA 107+00 TO STA 120+15 TOTAL 0010	1,464 126 182 1,772	ADVANCED WA LOOSE GRAV MILLED SURFA	EL, ASSUME 14	1 DAYS	0010	CTH Y (AS DIRECTED) TOTAL 0010		50	100	2 2	UNDISTRIBUTED
						<u>646.1020 - PAVEMENT</u>	MARKING					
						646.1020 - PAVEMENT		646.1020 KING LINE EPOXY 4- 12.5 FT	-INCH			
		CATEGORY	STATION	ТО	STATION	646.1020 - PAVEMENT			-INCH WHITE LF	REMARKS		
		0010 0010	10+00 15+00	-	15+00 18+00	LOCATION CTH Y CTH Y	YELLOW LF 1,000 300	AING LINE EPOXY 4- 12.5 FT 37.5 FT YELLOW LF — 75	WHITE LF 1,000 600	REMARKS  DOUBLE YELLOW		
		0010 0010 0010 0010 0010	10+00 15+00 18+00 37+00 56+00		15+00 18+00 37+00 56+00 60+00	LOCATION  CTH Y  CTH Y  CTH Y  CTH Y  CTH Y	YELLOW LF 1,000 300 — 1,900 —	12.5 FT 37.5 FT YELLOW LF  - 75 475 475 100	WHITE LF 1,000 600 3,800 3,800 800			
		0010 0010 0010 0010 0010 0010 0010	10+00 15+00 18+00 37+00 56+00 60+00 8000 171+00	- - - - -	15+00 18+00 37+00 56+00 60+00 80+00 171+00 185+00	LOCATION  CTH Y  CTH Y	YELLOW LF 1,000 300 — 1,900 — 2,000 — 1,400	12.5 FT 37.5 FT YELLOW LF  - 75 475 475 100 500 2,275 350	WHITE LF 1,000 600 3,800 3,800 800 4,000 18,200 2,800			
		0010 0010 0010 0010 0010 0010 0010	10+00 15+00 18+00 37+00 56+00 60+00 8000	- - - - -	15+00 18+00 37+00 56+00 60+00 80+00 171+00	LOCATION  CTH Y	YELLOW LF  1,000 300 — 1,900 — 2,000 —	12.5 FT 37.5 FT YELLOW LF  - 75 475 475 100 500 2,275	WHITE LF 1,000 600 3,800 3,800 800 4,000 18,200			


FILE NAME : PLOT DATE : \_\_\_\_\_ PLOT BY : \_\_\_\_ PLOT NAME : \_\_\_\_ ORG DATE : \_\_\_\_ ORIGINATOR : DIST PLOT SCALE : 1:1


					648.0100	- LOCATE NO PASSING							
		CATECORY	CTATION	TO	CTATION	LOCAL	LO PAS	648.0100 CATING NO- SSING ZONES	DEMANUS				
		CATEGORY 0010	STATION 1000	TO -	STATION 217+25	LOCAT CTH TOTAL (	Υ	3.96 3.96	REMARKS				
					650 - CONSTI	RUCTION STAKING	650.8000  CONSTRUCTION STAKING RESURFACING REFERENCE	650.9911.01 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) (01. 7849-03-73)					
	CATEGOR 0010	Y STATION 10+00		217+25		LOCATION  PROJECT  TOTAL 0010	LF 20,725 20,725	EACH  1  1	REMARKS	<u> </u>			
	<u>690 - SAW</u>	/ING ASPHALT											
CATEGORY	LOCATION	690.0150 SAWING ASPHALT LF	REMARKS						<u>SAN</u>	ITARY MANHOLE			
0010 0010 0010 0010 0010 0010 0010	STA 10+00 STA 40+49 LT STA 103+92 LT STA 107+00 STA 120+15 STA 177+05 STA 188+06	22 16 18 24 24 38 38	MAINLINE DRIVEWAY DRIVEWAY MAINLINE MAINLINE MAINLINE MAINLINE				CATEGORY 0020	STATION 119+85	LOCATION 18'LT	611.8110 ADJUSTING MANHOLE COVERS EACH	611.8120.S  COVER PLATES TEMPORARY EACH	REMARKS	
0010	STA 217+25 TOTAL 0010	22 202	MAINLINE						TOTAL 0020	1	1		

















## Standard Detail Drawing List

08E09-06	SILT FENCE
13A08-01	ASPHALTIC RUMBLE STRIPS AT INTERSECTION
13C19-03	HMA LONGITUDINAL JOINTS
15C04-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 M.P.H. OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC
15C05-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 40 M.P.H. OR LESS
15C08-21A	LONGITUDINAL MARKING (MAINLINE)
15C12-09A	TRAFFIC CONTROL FOR LÂNE CLOSURE WITH FLAGGING OPERATION
15C19-07A	MOVING PAVEMENT MARKING OPERATION TWO-LANE TWO-WAY ROADWAY
15C35-05A	PAVEMENT MARKING (INTERSECTIONS)
15D44-02	TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH MILLED SURFACES
15D45-03	TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH LOOSE GRAVEL

6

### TYPICAL APPLICATION OF SILT FENCE

6

b

Ō

Ш





## PLAN VIEW SILT FENCE AT MEDIAN SURFACE DRAINS



#### GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- $\bigcirc$  HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- 3 WOOD POSTS SHALL BE A MINIMUM SIZE OF 11/8" X 11/8" OF OAK OR HICKORY.
- 4) SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- (5) CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.



TRENCH DETAIL



SILT FENCE TIE BACK


(WHEN REQUIRED BY THE ENGINEER)





6


ထ


D.D. 8 E 9-6











2 15C08 SDD

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

/S/ Jeannie Silver
STATEWIDE SIGNING AND MARKING
ENGINEER

APPROVED

May 2022 DATE

6

RUMBLE

STRIPS

ROAD

WORK

#### **GENERAL NOTES FLAGGING LEGEND** DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY SIGN ON PORTABLE OR PERMANENT SUPPORT UNIFORM TRAFFIC CONTROL DEVICES. PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING. ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED. TEMPORARY PORTABLE RUMBLE WORK OPERATION OR AS APPROVED BY THE ENGINEER. STRIP ARRAY "WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE. (2) SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA. THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE DIRECTION OF TRAFFIC ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER. WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED. THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP WORK AREA TEMPORARY PORTABLE RUMBLE STRIPS WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS. TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED FLAGGER, EQUIPPED WITH STOP/SLOW ③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT PADDLE FASTENED ON SUPPORT STAFF THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST. INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS. PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS. DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS. SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE 5' MIN BE SPEED LIMIT SPACING "A" USE OF WO3-4 SIGN IS OPTIONAL. WHEN USED, PREPARED THIS SIGN SHALL BE LOCATED BETWEEN THE 25-30 MPH TO STOP W20-7A AND W20-4A SIGNS, USING SPACING "A". 35-40 MPH 350' STOP/SLOW PADDLE ŔUMBLĖ 45-55 MPH 500' WO3-4 WORK **ON SUPPORT STAFF** ROAD STRIPS 1 VARIABLE DISTANCE - 200' - 300' (TYP.) END ROAD WORK |||3 WORK AREA A/2 END ROAD WORK 200' - 300' (TYP.) VARIABLE DISTANCE

#### TRAFFIC CONTROL FOR LANE CLOSURE WITH **FLAGGING OPERATION**


0


2

Ŋ

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED	
May 2022	/S/ Andrew Heidtke
DATE	WORK ZONE ENGINEER
FHWA	





DRAWING NOT TO SCALE. ALL SIGNS AND POSTS ON THIS SHEET SHALL BE PAID FOR WITH 'TRAFFIC CONTROL SIGNS' BID ITEM. ALL SIDE ROADS WHICH ARE UNDER CONSTRUCTION OF CURB AND GUTTER AND/OR GRADING SHALL BE ADEQUATELY SIGNED.

ALL SIGNS AND DEVICES SHALL BE IN CONFORMANCE WITH THE WISCONSIN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (WMUTCD). SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE WISDOT STANDARD SIGN PLATES.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THAT THE BACKGROUND IS ORANGE.


THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE

ALL SIGNS INAPPROPRIATE TO THE STATUS OF THE CONTROL ZONE, INCLUDING PRE-EXISTING SIGNS IN THE VICINITY, SHALL BE COVERED

SEE 15C34 FOR ADDITIONAL TRAFFIC CONTROL SIGNING WHEN CENTERLINE PAVEMENT MAKINGS ARE MISSING. 'DO NOT PASS' SIGNS MUST BE INSTALLED ON THE SAME DAY AS MILLING OPERATIONS.

- (1) PLACE SIGNS 350' IN ADVANCE OF MILLED SURFACES AND AT 1 MILE INTERVALS, OR AS DIRECTED BY THE ENGINEER.
- (2) PLACE SIGN 200' MIN. FROM INTERSECTION AND 200' MIN. AFTER ADVANCE WARNING SIGN SHOWN IN SDD 15C04.

DIRECTION OF TRAFFIC



#### **DETAIL FOR SIGNING ON MILLED SURFACES**

TRAFFIC CONTROL, **SIGNING ON ROADWAYS WITH MILLED SURFACES** 

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED February 2020 DATE /S/ Andrew Heidtke WORK ZONE ENGINEER

 $\perp \!\!\! \perp$ 

**TYPICAL SIDE ROAD APPROACH SIGN DETAIL** 


**PAVEMENT** 

Ò D

45

50

Notes



# Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

http://www.dot.wisconsin.gov