

# **Wisconsin Department of Transportation**

January 5, 2023

#### Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

## **NOTICE TO ALL CONTRACTORS:**

Proposal #02: 1016-01-62, WISC 2023135

Tomah - Portage

**Camp Douglas to Seven Mile Creek** 

IH 90

**Juneau County** 

# Letting of January 10, 2023

This is Addendum No. 01, which provides for the following:

# **Special Provisions:**

	Revised Special Provisions
Article No.	Description
5	Traffic

	Added Special Provisions
Article No.	Description
19	Basic Queue Warning System, Item 643.1205.S

## Schedule of Items:

Added Bid Item Quantities												
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum							
643.1205.S	Basic Traffic Queue Warning System	DAYS	0	80	80							

# Plan Sheets:

	Revised Plan Sheets
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
23	Corrected Asphalt Item (MQ sheet incorrectly called for SMA, correct item appears elsewhere)
25	Added "Basic Traffic Queue Warning System"

Added Plan Sheets									
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)								
50A	SDD Traffic Control, Lane Closure, Basic Traffic Queue Warning System								

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

# ADDENDUM NO. 01 1016-01-61 January 05, 2023

# **Special Provisions**

# 5. Traffic.

Replace entire table following after sentence stating IH 90 lane closures shall be permitted as follows:

EASTBOUND	WESTBOUND							
Ma	rch							
Sunday 6 pm to Wednesday 2 pm	Sunday 6 pm to Wednesday 2 pm							
Wednesday 5 pm to Thursday 1 pm	Wednesday 5 pm to Thursday 11 am							
Thursday 6 pm to Friday 10 am	Thursday 5 pm to Friday 10 am							
April (excluding	Easter holiday)							
Sunday 6 pm to Wednesday 2 pm	Sunday 6 pm to Wednesday 2 pm							
Wednesday 5 pm to Thursday 11 am	Wednesday 6 pm to Thursday 11 am							
Thursday 6 pm to Friday 10 am	Thursday 6 pm to Friday 9 am							
May (excluding Mei	morial Day holiday)							
Sunday 7 pm to Monday 10 am	Sunday 7 pm to Monday 10 am							
Monday 6 pm to Tuesday 12 noon	Monday 5 pm to Tuesday noon							
Tuesday 5 pm to Wednesday 11 am	Tuesday 5 pm to Wednesday 1 pm							
Wednesday 5 pm to Thursday 10 am	Wednesday 5 pm to Thursday 9 am							
Thursday 6 pm to Friday 9 am	Thursday 6 pm to Friday 8 am							
Ju	une							
Sunday 7 pm to Monday 9 am	Sunday 7 pm to Monday 9 am							
Monday 7 pm to Tuesday 9 am	Monday 7 pm to Tuesday 9 am							
Tuesday 6 pm to Wednesday 9 am	Tuesday 6 pm to Wednesday 9 am							
Wednesday 7 pm to Thursday 9 am	Wednesday 7 pm to Thursday 8 am							
Thursday 7 pm to Friday 8 am	Thursday 7 pm to Friday 8 am							
July (excluding Indep	endence Day holiday)							
Sunday 7 pm to Monday 9 am	Sunday 8 pm to Monday 9 am							
Monday 7 pm to Tuesday 9 am	Monday 7 pm to Tuesday 9 am							
Tuesday 7 pm to Wednesday 9 am	Tuesday 6 pm to Wednesday 9 am							
Wednesday 7 pm to Thursday 9 am	Wednesday 7 pm to Thursday 8 am							
Thursday 7 pm to Friday 9 am	Thursday 7 pm to Friday 8 am							
Aug	ust							
Sunday 8 pm to Monday 9 am	Sunday 8 pm to Monday 9 am							
Monday 7 pm to Tuesday 10 am	Monday 6 pm to Tuesday 10 am							
Tuesday 6 pm to Wednesday 9 am	Tuesday 5 pm to Wednesday 9 am							
Wednesday 7 pm to Thursday 9 am	Wednesday 6 pm to Thursday 9 am							
Thursday 8 pm to Friday 9 am	Thursday 8 pm to Friday 8 am							
September (excludin	g Labor Day holiday)							
Sunday 7 pm to Monday 9 am	Sunday 7 pm to Monday 9 am							

Monday 6 pm to Tuesday 11 am	Monday 6 pm to Tuesday 12 noon					
Tuesday 5 pm to Wednesday 11 am	Tuesday 5 pm to Wednesday 11 am					
Wednesday 5 pm to Thursday 10 am	Wednesday 5 pm to Thursday 10 am					
Thursday 7 pm to Friday 9 am	Thursday 7 pm to Friday 8 am					
Octo	bber					
Sunday 7 pm to Monday 10 am	Sunday 7 pm to Monday 10 am					
Monday 5 pm to Tuesday 12 noon	Monday 5 pm to Tuesday 12 noon					
Tuesday 5 pm to Wednesday 10 am	Tuesday 5 pm to Wednesday 10 am					
Wednesday 6 pm to Thursday 10 am	Wednesday 6 pm to Thursday 9 am					
Thursday 6 pm to Friday 9 am	Thursday 7 pm to Friday 9 am					

# 19. Basic Traffic Queue Warning System, Item 643.1205.S.

#### **A Description**

This special provision describes providing, repositioning, operating, maintaining, monitoring, calibrating, testing and removing a basic traffic queue warning system (QWS) capable of measuring vehicular speeds at downstream sections of a roadway, and activating the system.

#### **B** Materials

Provide Basic Traffic QWS components and software that is National Transportation Communications for ITS Protocol (NCTIP) compliant.

### **B.1 Portable Traffic Sensors (PTS)**

Provide PTS that are nonintrusive and capable of capturing vehicle speed in mph. Integrate each sensor with a modem to communicate with the automated system manager.

#### B.2 Static Traffic Control Signs with Temporary Flashing Beacon Signs (FBS)

Provide static traffic control signs with temporary flashing beacon signs conforming to standard spec 658.2(2) for Traffic Signal Faces. Ensure each FBS is integrated with a modem, and other equipment (e.g., automated system manager) mounted on it, and acts as a single device for communicating with similarly integrated devices and displaying real-time traffic conditions.

#### **B.3 Automated System Manager (ASM)**

Provide an ASM that assesses current traffic data captured by the PTS and activates/deactivates the FBS based on predetermined speed thresholds.

#### **B.4 System Communications**

Ensure Basic Traffic QWS communications meet the following requirements:

- 1. Perform required configuration of the Basic Traffic QWS's communication system automatically during system initialization.
- 2. Communication between the server and any individual FBS or PTS are independent through the full range of deployed locations, and do not rely upon communications with any other FBS or PTS.
- 3. Incorporate an error detection/correction mechanism into the Basic Traffic QWS communication system to ensure the integrity of all traffic condition data.

#### **B.5 System Acceptance**

Submit vendor verification to the engineer and Bureau of Traffic Operations (<a href="DOTBTOworkzone@dot.wi.gov">DOTBTOworkzone@dot.wi.gov</a>)
14 calendar days before the pre-construction meeting that the system will adequately perform the functions specified in this special provision. Adequate verification includes past successful performance of the system, literature and references from successful use of the system by other agencies, and/or demonstration of the system.

Provide contact information for a designated representative responsible for monitoring the performance of the system and for making modifications to the operational settings as the engineer directs. Provide all testing and calibration equipment.

#### **C** Construction

#### C.1 General

Install and reposition Basic Traffic Queue Warning System per plan or as the engineer directs. Provide plan to the engineer and Bureau of Traffic Operations (<a href="mailto:DOTBTOworkzone@dot.wi.gov">DOTBTOworkzone@dot.wi.gov</a>) 14 calendar days before the pre-construction meeting.

PTS may be mounted on FBS, arrow board or other trailer devices.

Install PTS at the following locations:

- 1. Place first PTS within the lane closure taper.
- 2. Place second PTS 5,700 feet upstream of the lane closure taper or on FBS #3.
- 3. Place third PTS 2 miles upstream of the lane closure taper or on FBS #2.

Install FBS at the following locations, delineated by 5 drums:

- 1. Place first FBS (FBS #3) 5,700 feet upstream of the lane closure taper.
- 2. Place second FBS (FBS #2) 2 miles upstream of the lane closure taper.
- 3. Place third FBS (FBS #1) 3 miles upstream of the lane closure taper.

If there are more than 2 lanes or specified in the plans, place FBS on both sides of the roadway.

Number the devices in chronological order so they are visible from the shoulder with 6-inch white high reflective sheeting.

Provide technical personnel for all system calibration, operation, maintenance, and timely on-call support services.

Promptly correct the system within 24 hours of becoming aware of a deficiency in the operation or individual part of the system. A minimum of three days before deployment, place the Basic Traffic QWS and demonstrate to the Department that the Basic Traffic QWS is operational.

Maintain the Basic Traffic QWS for the duration of the project. Ensure the system operates continuously (24 hours, 7 days a week) in the automated mode throughout the duration of the project.

Remove the system upon completion.

### C.2 Reports

Provide an electronic copy of a weekly summary report of all data via email to the engineer. Ensure the report includes, at a minimum, the average speed per sensor, time in congestive state per sensor and number of triggers per day.

#### C.3 Meetings

Attend mandatory in-person pre-construction meetings with the department. Attend additional meetings as deemed necessary by the department. These meetings may be held in person or via teleconference, as scheduled by the department.

#### **C.4 Programming**

#### C.4.1 General

Program the Basic Traffic QWS to ensure that the following general operations are performed:

- Provide a password protected login to the ASM, website and all other databases.
- 2. Automatic setting of the FBS to reflect current traffic flow status updated every 60 seconds for congestion. Ensure to remove a congestion message when 180 seconds of average traffic speeds above the current level are observed, or utilize a customized frequency as determined by the engineer.
- 3. The FBS activate based on pre-determined speed thresholds from the next downstream sensor.
  - FBS #3 shall activate based on traffic speeds at the PTS located within the lane closure taper.
  - FBS #2 shall activate based on traffic speeds at the PTS located approximately 1 mile upstream of lane closure taper, or at FBS #3.
  - FBS #1 shall activate based on traffic speeds at the PTS located 2 miles upstream of lane closure taper, or at FBS #2.
- 4. Provide real-time data from the ASM to a website with a full color mapping feature and refresh every 60 seconds. Make data on website available to the department staff at all times for the duration of the work zone activity. Ensure website includes:
  - Vehicle speeds
  - FBS triggers
  - Device locations
- 5. Archive all traffic data in a Microsoft Excel format with date and time stamps.
- 6. Configure the website to quantify system failures which includes communication disruption between any devices in the system configuration, FBS malfunctioning, PTS malfunction, loss of power, low battery, etc.
- 7. Automatically generate and send an email alert any time a user specified queue is detected by the system.
- 8. Ensure the system autonomously restarts in case of any power failure.

#### C.4.2 System Operation Strategy

Arrange for the vendor/manufacturer to coordinate system operation, detection, and trends/thresholds with the engineer.

The sequences below are a minimum requirement, but can be adjusted at the discretion of the engineer, are as follows:

#### Free Flow:

If the current PTS speed on a downstream section is at or above 40 mph, the next upstream FBS will not flash.

#### Slow or Stopped Traffic:

If the current PTS speed on a downstream section of the roadway is between the 39 mph and 0 mph (for example, 35 mph), the next upstream FBS shall flash.

#### C.5 Calibration and Testing

At the beginning of the project perform a successful field test and calibration at the Basic Traffic QWS location to verify the system is detecting accurate vehicle speeds, and accurately relaying the information to the ASM and the FBS.

Send email of successful calibration and testing to the engineer.

#### **D** Measurement

The department will measure Basic Traffic Queue Warning System by the day, acceptably completed, measured as each complete system per roadway.

### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT643.1205.SBasic Traffic Queue Warning SystemDAY

Payment is full compensation for providing, repositioning, operating, maintaining, monitoring, calibrating, testing, and removing the complete system consisting of FBS, PTS, ASM, and system communications.

Failure to correct a deficiency to the FBS, PTS, or ASM within 24 hours after notification from the engineer or the department will result in a one-day deduction of the measured quantity for each day in which the deficiency is not corrected.

Failure to correct the website within 24 hours after notification from the engineer will result in a 10% reduction of the day quantity for each day the website is down.

The engineer will have sole discretion to assess the deductions for an improperly working Basic Traffic QWS. stp-643-046 (20210113)

#### Schedule of Items

Attached, dated January 5, 2023, are the revised Schedule of Items Page 4.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:


Revised: 23, 25. Added: 50A


**END OF ADDENDUM** 

	•

SEUMMARY   SES.0605   460.5224   460.7624   465.0400   624.0100	SHEEL: 43  PLOT SCALE: 1:1
5 460.5224 460.7624 465.0400 624.010 PAWEMENT PAYEMENT RIMBLE AT LTSS-28S HTSS-28 STRIPS WATER AT LTSS-28S HTSS-28 STRIPS WATER AT LTSON TON LF MGAL ATON - 46,249 150 Z700 - 87,263 150 Z700 - 87,263 150 Z50 - 200 Z700 - 90 200 - 90 200 - 90 200 - 35,500 - 90 200 - 35,500 - 36,0220 - 36,0220 - 36,0220 - 37,000 - 37,000 - 37,000 - 38,000 - 300 - 300 - 31,000 - 300 -	PLOT SCALE: 1:1
5 460.5224 466.04 PAREMENTA PAVENENTA RUNB ALT ITSB-28 HTSB-28 V STRIP TON TON 46,24 4,100 - 46,24 4,100 - 46,24 8,100 - 87,26 50 - 200 50 - 300 50 - 300 50 - 300 50 - 200 50 - 200 50 - 300 50 - 200 50 - 300 50 - 200 50 - 300 50	
5 466.5224 HMA HMA NT 176-28 5	
5 460.5224 HMA HMA NT 1758-28 5 1158-28 5 1158-28 5 1700 8,100 8,100 8,100 13,300 50 60 13,300 60 13,300 60 13,300 60 13,300 8,100 8,100 8,100 8,100 8,100 8,100 8,100 8,100 8,100 8,100 9,20 13,300 60 60 60 13,300 60 60 13,300 60 60 60 60 8,100 8,	
2 17 2	WE:
S S S S S S S S S S S S S S S S S S S	ME
[	PLOT NAME:
ASPHALT AND SHI ASPHALT AND SHI BASE BASE BASE BASE BASE BASE BASE BASE	ANIIIEO
204.0120 3 REMOVING ASPHALITC AG SURFACE DI MILLING SY SY 30,800 41,100 58,200 77,600 77,600 77,600 500 500 51,260 570 51,260 570 500 500 500 500 629,0210 629,0210	MISCELLANEOUS QUANIIIES PLOT BY: AR.H.
20 20 8EP 8EP 8SI	CELLAN
	-
### STATION LOCATION LOCATION  ### STATION LOCATION  ### STATION  ###	PLOT DATE : February 22, 2022
### STATION    STATION	COUNTY: JUNEAU
8.8.15.20 TI FERCE TO 100	3
SAW  SAW  CONGINE  1,13,23,11,33,11,34,11,	
IV (TOTALS)  CONCRETE PAVEMENT REPLACEMENT SY SY SY 1,478 1,034 4,00 4,03 4,03 4,03 4,03 4,03 1,011 1,011 1,019 6,53 1,011 1,019 6,53 1,011 1,019 6,23 1,011 1,019 6,23 1,011 1,019 6,23 1,011 1,019 6,23 1,011 1,019 6,23 1,011 1,019 1,0	
CONCRETE REPAIR SUMMARRY (TOTALS)  BARS REPAIR SHES  CONCRETE  CON	HW Y: IH - 90
CONCRET  416.0620  DRILLED DOWEL BARS EACH 640 656 656 640 640 640 640 640 640 640 640 640 64	
A16.0610 4.16.00  ORULED TIE DAILL  BARS EACH  382 646  382 647  383 657  265 647  271 77  266 647  42 666  27 666  28 7 667  28 666  29 7 667  20 7  20 7	
	ـ م
SUBTOTAL 1 SUBTOTAL 2 SUBTOTAL 3 SUBTOTAL 3 SUBTOTAL 4 SUBTOTAL 5 SUBTOTAL 6 SUBTOTAL 1 SUBTOTAL 2 SUBTOTAL 3	_0-U1
8 80 8 80 8 80 8 80 8 80 8 80 8 80 8 8	FROJECT NO: 1016-01-61

				(*)	)																				IC	) 1	01	6-0	1-6									u	ה
																									R Ja	ev anı	ise uar	d S y 5	he , 20	et 2 023	25								1
	REMARKS		YELLOW	3. MINI SKIPS, WHITE	YELLOW	WHITE		YELLOW	3' MINI SKIPS, WHITE		YELLOW	WHITE		YELLOW	3' MINI SKIPS, WHITE		YELLOW	WHITE		YELLOW	3' MINI SKIPS, WHITE		YELLOW	WHILE									REMARKS		DAILY SETUP/TEARDO WN (EASTBOUND)	DO WN (WESTBOUND)		SHEET: 25	
(MMPS)	646.9400 MARKING REMOVAL PLOWABLE RAISED PAVEMENT MARKERS EACH		1			•			,					ı					,	•			•		,	0	1,400	1,400					RE		DAILY SETUP/TEAF	DAILY SETUP/TEAR			
PAVEMENT MARKING SUMMARY (RAMPS)	646.3020 MARKING LINE EPOXY 8-INCH LF			262	262	1	674 674		,	261		851			- 6	293	,	- 803	803	1	- 237	237	,	721	721	8,300	0	8,300		643.4100.S		TRAFFIC CONTROL INTERIM LANE CLOSURE			30	50	80		
PAVEMENT	646.1020 MARKING LINE EPOXY 4-INCH LF		547	/TT	573	1136		657	153		551	1239		793	126		871	1641	,	475	141		929	1493	,	11,500	300,400	311,900		643.1051	TRAFFIC CONTROL	SIGNS PCMS WITH CELLULAR COMMUNICATIONS	ату рау	2 60			160		
	LOCATION	NEW LISBON EXIT 61	EB OFF RAMP LT	EB OFF KAMP EB MAINLINE @ OFF RAMP	EB OFF RAMP EB ON RAMP LT	EB RT EDGE: GORE TO GORE	EB MAINLINE @ ON RAMP EB ON RAMP	WB OFF RAMP LT	WB OFF RAMP	WB MAINLINE @ OFF RAMP	ON RAMP LT	WB RT EDGE: GORE TO GORE WB MAINLINE @ ON RAMP	MALISTON FXIT 69	EB OFF RAMP LT	EB OFF RAMP	EB OFF RAMP	EB ON RAMP LT	EB RT EDGE: GORE TO GORE	EB ON RAMP	WB OFF RAMP LT	WB OFF RAMP	WB OFF RAMP	WB ON RAMP LT	WB KI EDGE: GOKE TO GOKE	WB ON RAMP	SUBTO TAL RAMPS:	SUBTOTAL MAINLINE:	TOTAL 0010		643.0900		TRAFFIC CONTROL SIGNS		16 480			1,280	MISCELL ANEOLIS OLIANTITIES	11:::::::::::::::::::::::::::::::::::::
		ļ	89 8		E E	EB	8 8	WB	WB	WB	wa WB	WB		EB	89 6	9 89	EB	EB EB	8 8	WB	WB	WB	MB.	ew ew	WB				.χ	643.0800		TRAFFIC CONTROL ARROW BOARDS		900			160	MISCELLA	1
		REMARKS	YELLOW	WHITE	YELLOW	WHILE	WHITE																						TRAFFIC CONTROL SUMMARY	643.0715		TRAFFIC CONTROL WARNING LIGHTS TYPE C	Y DAY QTY	4 120 2	· ·		320		
	646.9400 MARKING REMOVAL PLOWABLE RAISED PAVEMENT MARKERS	EACH	,				462 873		1,400																					643.0705		TRAFFIC CONTROL WARNING LIGHTS TYPE A	ату рау ату	70 2,100			8,700	COLINTY: ILINEAL	? i i :
JMMARY	646.3020 MARKING LINE EPOXY 8-INCH	LF	1						0						KING		650.9910.01	CONSTRUCTION	STAKING SUPPLEMENTAL	CONTROL	(PROJECT) (01.	LS LS	,	-						643.0420		TRAFFIC CONTROL BARRICADES TYPE		35 1,050			4,350		_
PAVEMENT MARKING SUMMARY	646.1020 MARKING LINE EPOXY 4-INCH	I.F	46,249	46,249	87,253	87,753	11,562 21,816		300,400						CONSTRUCTION STAKING		650.8000 65		CONSTRUCTION SUP		RESURFACING (PR	ner enemone LF	1	141,/85						643.0300		TRAFFIC CONTROL DRUMS		462 13,860 873 43,650			57,510	HWY: IH - 90	
		LOCATION	EB LT EDGELINE	EB RT EDGELINE	WB LT EDGELINE	WB KI EDGELINE	EB CL SKIPS WB CL SKIPS		SUBTOTAL MAINLINE:													ļ										SERVICE		30				Ĭ	-
			EB						SUBTO														FFIC	SNING	_								LOCATION	EB WAR	!		TOTAL 0010		
		TO STATION	09+269 -	- 697+60	- 1107+64A	- IIU/+64A	- 697+60 - 1107+64A															643 130E c	BASIC TRAFFIC	QUEUE WARNING	SYSTEM DAY		20	S					STATION	697+60				11-61	-
		STATION TO	235+11 -	235+11	235+11A -	- VTT+557	235+11 - 235+01A -																		LOCATION	EASTBOILIND	WESTBOUND	O TOT I A TOT O					STATION TO	235+11 -				PRO IECT NO: 1016-01-61	, , , , , , , , ,





01/05/2023 13:23:50



# Proposal Schedule of Items

Page 4 of 4

Federal ID(s): WISC 2023135

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	643.1205.S Basic Traffic Queue Warning System	80.000 DAY		
	Section:	0001	Total:	·
			Total Bid:	