

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
4085-60-71	WISC2023287	1

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

KIEL - NEW HOLSTEIN

CTH AA - JORDAN AVENUE

STH 32

CALUMET COUNTY

STATE PROJECT NUMBER
4085-60-71

ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 158



DESIGN DESIGNATION 4085-60-00

A.A.D.T.	2024	=	5730
A.A.D.T.	2044	=	6620
D.H.V.		=	936
D.D.		=	59/41
T.		=	7.1%
DESIGN SPEED		=	55 MPH
ESALS		=	980,000



CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	
PROPERTY LINE	
LOT LINE	
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	
PROPOSED OR NEW R/W LINE	
SLOPE INTERCEPT	
REFERENCE LINE	
EXISTING CULVERT	
PROPOSED CULVERT (Box or Pipe)	
COMBUSTIBLE FLUIDS	
MARSH AREA	
WOODED OR SHRUB AREA	

PROFILE	
GRADE LINE	
ORIGINAL GROUND	
MARSH OR ROCK PROFILE (To be noted as such)	
SPECIAL DITCH	
GRADE ELEVATION	
CULVERT (Profile View)	
UTILITIES	
ELECTRIC	
FIBER OPTIC	
GAS	
SANITARY SEWER	
STORM SEWER	
TELEPHONE	
WATER	
UTILITY PEDESTAL	
POWER POLE	
TELEPHONE POLE	

END PROJECT
STA 139+85.00
Y=446,722.894
X=915,340.220

BEGIN PROJECT
STA 17+87.17
Y=438,440.497
X=923,657.046



HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), CALUMET COUNTY NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A.

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY	Surveyor	NE REGION
Designer	T. MAATTA	
Project Manager	K. BERG, P.E.	
Regional Examiner		
Regional Supervisor	D. SEGERSTROM, P.E.	

APPROVED FOR THE DEPARTMENT
DATE: 7/14/2022

PROJECT ID: 4085-60-71

COUNTY: CALUMET

GENERAL NOTES

THE LOCATIONS OF EXISTING UTILITY FACILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY FACILITIES WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT APPROVAL OF THE ENGINEER.

EROSION CONTROL FEATURES ARE AT SUGGESTED LOCATIONS AND THE EXACT LOCATION WILL BE DETERMINED BY THE ENGINEER.

ORDER OF SECTION 2 DETAIL SHEETS

- GENERAL NOTES
- PROJECT OVERVIEW
- TYPICAL SECTIONS
- CONSTRUCTION DETAILS
- INTERSECTION DETAILS
- PLAN DETAILS
- EROSION CONTROL
- DETOUR SIGN DETAILS

DNR LIAISON

MATT SCHAEVE
DNR NORTHEAST REGIONAL HEADQUARTERS
2984 SHAWANO AVE.
GREEN BAY, WI 54313
(920) 366-1544
matthew.schaeve@wisconsin.gov

COUNTY HIGHWAY COMMISSIONER

BRIAN P. GLAESER
241 E CHESTNUT ST
CHILTON, WI 53014-1554
(920) 849-1463
glaeser.brian@co.calumet.wi.us

NE REGION SURVEY COORDINATOR

CORMAC MCINNIS, RLS
944 VANDERPERREN WAY
GREEN BAY, WI 54304
(920) 492-5638
cormac.mcinnis@dot.wi.gov

NE REGION DESIGN PROJECT MANAGER

KRISTEN E. BERG, P.E.
944 VANDERPERREN WAY
GREEN BAY, WI 54304
(920) 492-0139
kristen.berg@dot.wi.gov

UTILITIES CONTACTS

TODD HILDEBRANDT
CHARTER COMMUNICATIONS -
COMMUNICATION LINE
3520 E DESTINATION DR
APPLETON, WI 54915
(920) 794-4946
Todd.hildebrandt@charter.com

KRIS AUGUST (PRIMARY CONTACT)
CITY OF KIEL - ELECTRICITY
621 SIXTH ST
KIEL, WI 53042
(920) 894-2909
kris.august@kielwi.gov

KRIS AUGUST (PRIMARY CONTACT)
CITY OF KIEL - SEWER
621 SIXTH ST
Kiel, WI 53042
(920) 894-2909
kris.august@kielwi.gov

KRIS AUGUST (PRIMARY CONTACT)
CITY OF KIEL - WATER
621 SIXTH ST
KIEL, WI 53042
(920) 894-2909
kris.august@kielwi.gov

CAL KLADE
FRONTIER COMMUNICATIONS OF WI LLC
- COMMUNICATION LINE
521 4th ST
WAUSAU, WI 54401
(715) 573-2110
Calvin.klade@ftr.com

ELECTRIC OPERATIONS SUPERVISOR
NEW HOLSTEIN PUBLIC UTILITIES -
ELECTRICITY
2110 WASHINGTON ST
NEW HOLSTEIN, WI 53061
(920) 898-5776
Nh_electric@wppienergy.org

WATER/WASTEWATER SUPERVISOR
NEW HOLSTEIN PUBLIC UTILITIES - SEWER
2110 WASHINGTON ST
NEW HOLSTEIN, WI 53061
(920) 898-5776
Nh_treatment@wppienergy.org

WATER/WASTEWATER SUPERVISOR
NEW HOLSTEIN PUBLIC UTILITIES -
WATER
2110 WASHINGTON ST
NEW HOLSTEIN, WI 53061
(920) 898-5776
Nh_water@wppienergy.org

NICK WILBERT
WISCONSIN PUBLIC SERVICE
CORPORATION - GAS/PETROLEUM
933 S WILDWOOD AVE
SHEBOYGAN, WI 53081
(920) 946-5410
Nicholas.wilbert@wisconsinpublicservice.com


CASEY SCHWANDT (PRIMARY CONTACT)
WEST SHORE PIPE LINE COMPANY -
GAS/PETROLEUM
11115 WEST COUNTY LINE RD
MILWAUKEE, WI 53224
(920) 655-1428
cschwandt@buckeye.com

RUNOFF COEFFICIENT TABLE

	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER									
ROW CROPS	.08 .22	.16 .30	.22 .38	.12 .26	.20 .34	.27 .44	.15 .30	.24 .37	.33 .50	.19 .34	.28 .41	.38 .56
MEDIAN STRIP- TURF	.19 .24	.20 .26	.24 .30	.19 .25	.22 .28	.26 .33	.20 .26	.23 .30	.30 .37	.20 .27	.25 .32	.30 .40
SIDE SLOPE- TURF			.25 .32			.27 .34			.28 .36			.30 .38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											

TOTAL PROJECT AREA = 28.00 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.80 ACRES






END PROJECT
 STA 139+85.00
 Y=446,722.894
 X=915,340.220




BEGIN PROJECT
 STA 17+87.17
 Y=438,440.497
 X=923,657.046


STRUCTURE B-08-0009
 STA 55+42 - STA 57+57

PROJECT NO: 4085-60-71	HWY: STH 32	COUNTY: CALUMET	PROJECT OVERVIEW	SHEET	E
------------------------	-------------	-----------------	------------------	-------	----------







EXISTING TYPICAL SECTION STH 32
STA 32+07 TO STA 34+64




EXISTING TYPICAL SECTION STH 32
STA 34+64 TO STA 85+50




BEAM GUARD SECTION
STA 40+73 TO STA 55+06
STA 57+36 TO STA 67+82




BEAM GUARD SECTION
STA 38+75 TO STA 55+62
STA 57+93 TO STA 66+01





EXISTING TYPICAL SECTION STH 32
STA 85+50 TO STA 139+85



PROPOSED TYPICAL SECTION STH 32
STA 17+87 TO STA 32+07




PROPOSED TYPICAL SECTION STH 32
STA 32+07 TO STA 34+64




BEAM GUARD SECTION
STA 39+50 TO STA 55+06
STA 57+36 TO STA 67+79

BEAM GUARD SECTION
STA 37+00 TO 55+62
STA 57+93 TO 67+50

PROPOSED TYPICAL SECTION STH 32
STA 34+64 TO STA 85+50



PROPOSED TYPICAL SECTION STH 32
 STA 85+50 TO STA 139+85




⊕ SEE TYPICAL CROSS SECTION FOR PAVEMENT TYPE AND THICKNESS OF INDIVIDUAL LAYERS


REMOVING ASPHALTIC SURFACE, MILLING

REMOVE ASPHALTIC SURFACE WEDGE AT BUTT JOINT TO CREATE VERTICAL EDGE

BUTT JOINT DETAIL FOR ASPHALTIC PAVEMENTS (NO PROFILE CHANGE)




SECTION A-A




DETAIL FOR ASPHALTIC SHOULDER AT BEAM GUARD

STA 36+79 RT - STA 49+14 RT
 STA 39+35 LT - STA 55+10 LT
 STA 53+43 RT - STA 55+61 RT
 STA 57+90 RT - STA 67+64 RT
 STA 57+38 LT - STA 67+99 LT







DETAIL FOR TRANSITION FROM BRIDGE TO ROADWAY

STA 54+56 - STA 55+06
 STA 57+94 - STA 58+44



TYPICAL PAVEMENT CROSS SECTIONS OF TAPERED AND NOTCHED LONGITUDINAL JOINTS





PROJECT NO: 4085-60-71


HWY: STH 32

COUNTY: CALUMET

INTERSECTION DETAILS

SHEET

E



2

2

TECKLA PL

MARKING CROSSWALK EPOXY
TRANSVERSE LINE 6-INCH

MIN
10'

CURB RAMP DETECTABLE WARNING
FIELD RADIAL NATURAL PATINA

R41.68'
CL 10.80'
Xr 5.77'

41LF CONCRETE CURB & GUTTER
30-INCH TYPE D

REMOVING CURB & GUTTER

STH 32

EXISTING R/W

EXISTING ASPHALTIC
SURFACE TRAIL

32+96.25
-38.44' LT
913.76

32+94.17
-37.05' LT
913.34

32+97.08
-33.20' LT
913.43

32+97.40
-36.81' LT
913.80

32+99.31
-34.43' LT
913.36

33+01.10
-35.41' LT
913.39

33+04.77
-26.02' LT
913.62

33+07.20
-27.35' LT
913.56

33+10.10
-25.52' LT
914.13

33+14.03
-42.46' LT
913.33


33+09.63
-40.08' LT
913.42

33+18.81
-33.74' LT
913.50

33+14.43
-31.32' LT
913.57



33+30.59
-19.98' LT
914.05

33+30.57
-17.48' LT
914.13





LEGEND



⚡	TYPE II BARRICADE WITH SIGN (ALL WITH ONE WARNING LIGHT, TYPE A, LOW-INTENSITY FLASHING)
●	DRUM
➔	DIRECTION OF TRAFFIC
- - -	PEDESTRIAN CHANNELIZING DEVICE
▨	WORK AREA



PROJECT NO: 4085-60-71	HWY: STH 32	COUNTY: CALUMET	BEAM GUARD DETAILS	SHEET	E
------------------------	-------------	-----------------	--------------------	-------	---



PROJECT NO: 4085-60-71 HWY: STH 32 COUNTY: CALUMET BEAM GUARD DETAILS SHEET E



PROJECT NO: 4085-60-71


HWY: STH 32

COUNTY: CALUMET

BEAM GUARD DETAILS

SHEET


E




LEGEND

INLET PROTECTION, TYPE C

SURFACE WATER FLOW




PROJECT NO: 4085-60-71	HWY: STH 32	COUNTY: CALUMET	EROSION CONTROL	SHEET	E
------------------------	-------------	-----------------	-----------------	-------	---



LEGEND

INLET PROTECTION, TYPE C

SURFACE WATER FLOW



2

2


MATCH LINE 77+25.00

MATCH LINE 92+50.00

MATCH LINE 107+75.00


MATCH LINE 92+50.00

PROJECT NO: 4085-60-71	HWY: STH 32	COUNTY: CALUMET	EROSION CONTROL	SHEET	E
------------------------	-------------	-----------------	-----------------	-------	---



LEGEND

	INLET PROTECTION, TYPE C
	SURFACE WATER FLOW



LEGEND

- ⊗ SIGN NUMBER, REFER TO MISCELLANEOUS QUANTITY SHEET
- ▲ PCMS PORTABLE CHANGEABLE MESSAGE SIGN
- ↔ SIGN MOUNTED ON TYPE III BARRICADE
- POST MOUNTED SIGN

PLAN SHEET PRODUCED BY WisDOT-NE REGION

Estimate Of Quantities

4085-60-71

Line	Item	Item Description	Unit	Total	Qty
0002	203.0211.S	Abatement of Asbestos Containing Material (structure) 01. B-08-0009	EACH	1.000	1.000
0004	203.0220	Removing Structure (structure) 01. B-08-0009	EACH	1.000	1.000
0006	203.0330	Debris Containment (structure) 01. B-08-0009	EACH	1.000	1.000
0008	204.0110	Removing Asphaltic Surface	SY	17.000	17.000
0010	204.0115	Removing Asphaltic Surface Butt Joints	SY	89.000	89.000
0012	204.0120	Removing Asphaltic Surface Milling	SY	48,588.000	48,588.000
0014	204.0150	Removing Curb & Gutter	LF	41.000	41.000
0016	204.0165	Removing Guardrail	LF	4,873.000	4,873.000
0018	204.0270	Abandoning Culvert Pipes	EACH	2.000	2.000
0020	206.1001	Excavation for Structures Bridges (structure) 01. B-08-0009	EACH	1.000	1.000
0022	210.1500	Backfill Structure Type A	TON	355.000	355.000
0024	211.0101	Prepare Foundation for Asphaltic Paving (project) 01. 4085-60-71	EACH	1.000	1.000
0026	211.0400	Prepare Foundation for Asphaltic Shoulders	STA	150.000	150.000
0028	213.0100	Finishing Roadway (project) 01. 4085-60-71	EACH	1.000	1.000
0030	305.0110	Base Aggregate Dense 3/4-Inch	TON	1,748.000	1,748.000
0032	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	118.000	118.000
0034	390.0303	Base Patching Concrete	SY	384.000	384.000
0036	415.0120	Concrete Pavement 12-Inch	SY	123.000	123.000
0038	415.0410	Concrete Pavement Approach Slab	SY	196.000	196.000
0040	416.0610	Drilled Tie Bars	EACH	2.000	2.000
0042	416.0620	Drilled Dowel Bars	EACH	768.000	768.000
0044	416.1010	Concrete Surface Drains	CY	8.000	8.000
0046	450.4000	HMA Cold Weather Paving	TON	2,400.000	2,400.000
0048	455.0605	Tack Coat	GAL	6,455.000	6,455.000
0050	460.2000	Incentive Density HMA Pavement	DOL	6,128.000	6,128.000
0052	460.6224	HMA Pavement 4 MT 58-28 S	TON	9,575.000	9,575.000
0054	465.0425	Asphaltic Shoulder Rumble Strips 2-Lane Rural	LF	17,283.000	17,283.000
0056	465.0475	Asphalt Centerline Rumble Strips 2-Lane Rural	LF	8,428.000	8,428.000
0058	502.0100	Concrete Masonry Bridges	CY	142.000	142.000
0060	502.3200	Protective Surface Treatment	SY	1,092.000	1,092.000
0062	502.3210	Pigmented Surface Sealer	SY	197.000	197.000
0064	502.4204	Adhesive Anchors No. 4 Bar	EACH	920.000	920.000
0066	502.4205	Adhesive Anchors No. 5 Bar	EACH	112.000	112.000
0068	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	15,080.000	15,080.000
0070	506.2605	Bearing Pads Elastomeric Non-Laminated	EACH	10.000	10.000
0072	506.7050.S	Removing Bearings (structure) 01. B-08-0009	EACH	10.000	10.000
0074	509.0301	Preparation Decks Type 1	SY	102.000	102.000
0076	509.0302	Preparation Decks Type 2	SY	41.000	41.000
0078	509.0500	Cleaning Decks	SY	1,003.000	1,003.000
0080	509.1200	Curb Repair	LF	62.000	62.000
0082	509.1500	Concrete Surface Repair	SF	23.000	23.000
0084	509.2000	Full-Depth Deck Repair	SY	3.000	3.000
0086	509.2500	Concrete Masonry Overlay Decks	CY	103.000	103.000
0088	509.9050.S	Cleaning Parapets	LF	411.000	411.000
0090	516.0500	Rubberized Membrane Waterproofing	SY	32.000	32.000
0092	520.8000	Concrete Collars for Pipe	EACH	1.000	1.000
0094	522.1024	Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	EACH	1.000	1.000
0096	524.0124	Culvert Pipe Salvaged 24-Inch	LF	8.000	8.000
0098	524.0136	Culvert Pipe Salvaged 36-Inch	LF	16.000	16.000

Estimate Of Quantities

4085-60-71

Line	Item	Item Description	Unit	Total	Qty
0100	524.0148	Culvert Pipe Salvaged 48-Inch	LF	32.000	32.000
0102	524.0624	Apron Endwalls for Culvert Pipe Salvaged 24-Inch	EACH	2.000	2.000
0104	524.0636	Apron Endwalls for Culvert Pipe Salvaged 36-Inch	EACH	2.000	2.000
0106	524.0648	Apron Endwalls for Culvert Pipe Salvaged 48-Inch	EACH	2.000	2.000
0108	601.0411	Concrete Curb & Gutter 30-Inch Type D	LF	41.000	41.000
0110	601.0588	Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	LF	130.000	130.000
0112	601.0590	Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	LF	60.000	60.000
0114	602.0415	Concrete Sidewalk 6-Inch	SF	152.000	152.000
0116	602.0615	Curb Ramp Detectable Warning Field Radial Natural Patina	SF	21.000	21.000
0118	606.0200	Riprap Medium	CY	12.000	12.000
0120	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	205.000	205.000
0122	614.0010	Barrier System Grading Shaping Finishing	EACH	6.000	6.000
0124	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0126	614.2300	MGS Guardrail 3	LF	4,587.500	4,587.500
0128	614.2500	MGS Thrie Beam Transition	LF	157.584	157.584
0130	614.2610	MGS Guardrail Terminal EAT	EACH	6.000	6.000
0132	618.0100	Maintenance And Repair of Haul Roads (project) 01. 4085-60-71	EACH	1.000	1.000
0134	619.1000	Mobilization	EACH	1.000	1.000
0136	624.0100	Water	MGAL	19.000	19.000
0138	628.1504	Silt Fence	LF	1,693.000	1,693.000
0140	628.1520	Silt Fence Maintenance	LF	1,693.000	1,693.000
0142	628.1905	Mobilizations Erosion Control	EACH	9.000	9.000
0144	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0146	628.7015	Inlet Protection Type C	EACH	9.000	9.000
0148	633.5200	Markers Culvert End	EACH	7.000	7.000
0150	642.5001	Field Office Type B	EACH	1.000	1.000
0152	643.0300	Traffic Control Drums	DAY	1,743.000	1,743.000
0154	643.0410	Traffic Control Barricades Type II	DAY	40.000	40.000
0156	643.0420	Traffic Control Barricades Type III	DAY	1,440.000	1,440.000
0158	643.0705	Traffic Control Warning Lights Type A	DAY	2,540.000	2,540.000
0160	643.0715	Traffic Control Warning Lights Type C	DAY	200.000	200.000
0162	643.0900	Traffic Control Signs	DAY	5,215.000	5,215.000
0164	643.0920	Traffic Control Covering Signs Type II	EACH	3.000	3.000
0166	643.1000	Traffic Control Signs Fixed Message	SF	18.000	18.000
0168	643.1050	Traffic Control Signs PCMS	DAY	14.000	14.000
0170	643.3105	Temporary Marking Line Paint 4-Inch	LF	41,651.000	41,651.000
0172	643.3120	Temporary Marking Line Epoxy 4-Inch	LF	17,255.000	17,255.000
0174	643.5000	Traffic Control	EACH	1.000	1.000
0176	644.1410	Temporary Pedestrian Surface Asphalt	SF	280.000	280.000
0178	644.1601	Temporary Pedestrian Curb Ramp	DAY	20.000	20.000
0180	644.1810	Temporary Pedestrian Barricade	LF	145.000	145.000
0182	645.0120	Geotextile Type HR	SY	24.000	24.000
0184	646.1020	Marking Line Epoxy 4-Inch	LF	17,255.000	17,255.000
0186	646.1040	Marking Line Grooved Wet Ref Epoxy 4-Inch	LF	21,429.000	21,429.000
0188	646.3040	Marking Line Grooved Wet Ref Epoxy 8-Inch	LF	817.000	817.000
0190	646.6120	Marking Stop Line Epoxy 18-Inch	LF	42.000	42.000
0192	646.7420	Marking Crosswalk Epoxy Transverse Line 6-Inch	LF	142.000	142.000
0194	650.6501	Construction Staking Structure Layout (structure) 01. B-08-0009	EACH	1.000	1.000
0196	650.7000	Construction Staking Concrete Pavement	LF	130.000	130.000

Estimate Of Quantities

4085-60-71

Line	Item	Item Description	Unit	Total	Qty
0198	650.8000	Construction Staking Resurfacing Reference	LF	11,895.000	11,895.000
0200	650.9000	Construction Staking Curb Ramps	EACH	1.000	1.000
0202	650.9500	Construction Staking Sidewalk (project) 01. 4085-60-71	EACH	1.000	1.000
0204	650.9911	Construction Staking Supplemental Control (project) 01. 4085-60-71	EACH	1.000	1.000
0206	650.9920	Construction Staking Slope Stakes	LF	659.000	659.000
0208	690.0150	Sawing Asphalt	LF	1,608.000	1,608.000
0210	690.0250	Sawing Concrete	LF	293.000	293.000
0212	715.0502	Incentive Strength Concrete Structures	DOL	852.000	852.000
0214	715.0720	Incentive Compressive Strength Concrete Pavement	DOL	672.000	672.000
0216	740.0440	Incentive IRI Ride	DOL	18,482.000	18,482.000
0218	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	1,200.000	1,200.000
0220	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	600.000	600.000
0222	SPV.0035	Special 01. Slope Paving Repair Select Crushed Aggregate	CY	85.000	85.000
0224	SPV.0060	Special 01. Grading, Shaping, and Finishing Culverts and Endwalls	EACH	7.000	7.000
0226	SPV.0060	Special 02. Cleaning Ditch	EACH	1.000	1.000
0228	SPV.0060	Special 03. Curb Ramp Restoration	EACH	1.000	1.000
0230	SPV.0090	Special 01. Temporary Marking Crosswalk Paint Transverse Line 6-Inch	LF	196.000	196.000

3

3

ABANDONING CULVERT PIPES

CATEGORY	STATION	OFFSET	LOCATION	204.0270 ABANDONING CULVERT PIPES EACH	REMARKS
0010	54+83	LT	STH 32 LT	1	
0010	55+57	RT	STH 32 RT	1	
TOTAL 0010				2	

REMOVING ASPHALTIC SURFACE

CATEGORY	STATION	TO	STATION	LOCATION	204.0110 REMOVING ASPHALTIC SURFACE SY	REMARKS
0010	32+99	-	33+07	TECKLA PLACE SIDEWALK	17	
TOTAL 0010					17	

REMOVING APSHALTIC SURFACE BUTT JOINTS

CATEGORY	STATION	OFFSET	LOCATION	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS SY	REMARKS
0010	17+87	0.00'	STH 32	10	
0010	32+68	61.97' LT	TECKLA PL	8	
0010	32+65	90.44' RT	TECKLA PL	7	
0010	50+08	89.85' RT	FRONTIER HEIGHTS LANE	5	
0010	54+97	0.00'	STH 32	9	
0010	58+00	0.00'	STH 32	9	
0010	84+89	84.24' LT	SEVEN CORNERS RD	6	
0010	86+28	101.12' RT	SEVEN CORNERS RD	6	
0010	98+95	92.66' LT	FUR FARM RD	8	
0010	98+15	91.28' RT	FUR FARM RD	6	
0010	110+50	LT	DRIVEWAY	4	
0010	131+63	79.60' RT	CLARK DR	6	
0010	139+85	0.00'	STH 32	7	
TOTAL 0010				89	

REMOVING ASPHALTIC SURFACE MILLING

CATEGORY	STATION	TO	STATION	LOCATION	204.0120 REMOVING ASPHALTIC SURFACE MILLING SY	REMARKS
0010	17+87	-	54+97	STH 32	16,022	
0010	58+00	-	193+85	STH 32	32,566	
TOTAL 0010					48,588	

REMOVING CURB & GUTTER

CATEGORY	STATION	TO	STATION	LOCATION	204.0150 REMOVING CURB & GUTTER LF	REMARKS
0010	32+96	-	33+31	STH 32 LT	41	STH 32 / TECKLA LN
TOTAL 0010					41	

REMOVING GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	204.0165 REMOVING GUARDRAIL LF	REMARKS
0010	38+75	-	49+58	STH 32 RT	1,091	
0010	50+60	-	55+62	STH 32 RT	502	
0010	40+73	-	55+06	STH 32 LT	1,426	
0010	57+37	-	67+82	STH 32 LT	1,052	
0010	57+94	-	66+01	STH 32 RT	802	
TOTAL 0010					4,873	

PREPARE FOUNDATION FOR ASPHALTIC PAVING

CATEGORY	STATION	TO	STATION	LOCATION	211.0100.01 PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) (01. 4085-60-71) LS	REMARKS
0010	17+87	-	139+85	4085-60-71	1	ENTIRE PROJECT LENGTH
				TOTAL 0010	1	

FINISHING ROADWAY

CATEGORY	STATION	TO	STATION	LOCATION	213.0100.01 FINISHING ROADWAY (PROJECT) (01. 4085-60-71) EACH	REMARKS
0010	17+87	-	139+58	STH 32	1	ENTIRE PROJECT
				TOTAL 0010	1	

BASE AGGREGATE

CATEGORY	STATION	TO	STATION	OFFSET	LOCATION	305.0110	*	REMARKS
						BASE AGGREGATE DENSE 3/4-INCH TON	624.0100 WATER MGAL	
0010	18+32	-	31+86	RT	STH 32	21	0.2	
0010	33+26	-	49+99	RT	STH 32	163	1.6	
0010	33+31	-	55+06	LT	STH 32	219	2.2	
0010	50+21	-	55+54	RT	STH 32	38	0.4	
0010	57+42	-	84+43	LT	STH 32	211	2.1	
0010	57+99	-	84+95	RT	STH 32	203	2.0	
0010	85+82	-	98+02	LT	STH 32	89	0.9	
0010	86+57	-	97+63	RT	STH 32	84	0.8	
0010	99+03	-	131+51	RT	STH 32	292	2.9	
0010	99+65	-	139+85	LT	STH 32	350	3.5	
0010	131+75	-	139+85	RT	STH 32	78	0.8	
TOTAL 0010						1,748	17.50	

* QUANTITIES SHOWN ELSEWHERE

CONCRETE BASE PATCHING

CATEGORY	STATION	OFFSET	390.0303	416.0620	*	690.0250	REMARKS
			BASE PATCHING CONCRETE SY	DRILLED DOWEL BARS EACH	SAWING ASPHALT LF	SAWING CONCRETE LF	
0010	34+64	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	39+48	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	50+64	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	63+82	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	65+48	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	67+77	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	72+28	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	77+80	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	84+00	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	89+60	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	92+27	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	94+11	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	96+04	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	96+35	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	101+12	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	104+65	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	109+00	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	109+35	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	132+46	STH 32 LT & RT	16	32	48	12	6-FT X 24-FT
0010	UNDISTRIBUTED	STH 32 LT & RT	80	160	240	60	5 LOCATIONS AT 6-FT X 24-FT
TOTAL 0010			384	768	1,152	288	

* QUANTITIES SHOWN ELSEWHERE

MISC CONCRETE ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	305.0120	415.0120	415.0410	416.1010	601.0588	601.0590	606.0200	*	645.0120	REMARKS
					BASE AGGREGATE DENSE 1 1/4- INCH TON	CONCRETE PAVEMENT 12- INCH SY	CONCRETE PAVEMENT APPROACH SLAB SY	CONCRETE SURFACE DRAINS CY	CONCRETE CURB & GUTTER 4- INCH SLOPED 36- INCH TYPE TBT LF	CONCRETE CURB & GUTTER 4- INCH SLOPED 36- INCH TYPE TBT LF	RIPRAP MEDIUM CY	WATER MGAL	GEOTEXTILE TYPE HR SY	
0010	55+06	-	55+70	STH 32	55	-	97	-	-	-	-	0.75	-	
0010	57+28	-	57+94	STH 32	56	-	99	-	-	-	-	0.75	-	
0010	54+56	-	55+07	42.00' LT	-	15	-	2	47	-	3	-	6	
0010	55+07	-	55+57	42.00' RT	-	46	-	2	16	30	3	-	6	
0010	57+42	-	57+92	42.00' LT	-	47	-	2	16	30	3	-	6	
0010	57+93	-	58+44	42.00" RT	-	15	-	2	51	-	3	-	6	
TOTAL 0010					112	123	196	8	130	60	12	1.50	24	

* QUANTITIES SHOWN ELSEWHERE

HMA

CATEGORY	STATION	TO	STATION	OFFSET	211.0400	450.4000	455.0605	460.6224	REMARKS
					PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS STA	HMA COLD WEATHER PAVING TON	TACK COAT GAL	HMA PAVEMENT 4 MT 58-28 S TON	
0010	17+87	-	54+97	LT/RT	-	-	1,928	2859	MAINLINE (3")
0010	36+15	-	51+61	RT	15	-	106	158	RT SHOULDER EXTENSION
0010	38+67	-	55+06	LT	16	-	106	157	LT SHOULDER EXTENSION
0010	52+74	-	55+26	RT	3	-	16	24	RT SHOULDER EXTENSION
0010	57+73	-	68+75	LT	11	-	73	109	LT SHOULDER EXTENSION
0010	58+00	-	141+18	LT/RT	-	-	3,912	5803	MAINLINE (3")
0010	58+00	-	68+27	RT	10	-	66	98	RT SHOULDER EXTENSION
0010	87+01	-	94+64	RT	8	-	20	29	RT SHOULDER EXTENSION
0010	88+50	-	97+70	LT	9	-	23	34	LT SHOULDER EXTENSION
0010	99+03	-	130+45	RT	31	-	83	123	RT SHOULDER EXTENSION
0010	101+95	-	139+85	LT	38	-	100	149	LT SHOULDER EXTENSION
0010	132+07	-	139+85	RT	8	-	21	31	RT SHOULDER EXTENSION
0010	17+87	-	139+85	LT/RT	-	2,400	-	-	PROJECT WIDE
TOTAL 0010					150	2,400	6,455	9,575	

RUMBLE STRIPS

CATEGORY	STATION	TO	STATION	OFFSET	465.0425	465.0475	REMARKS
					ASPHALTIC SHOULDER RUMBLE STRIPS 2-LANE RURAL LF	ASPHALT CENTERLINE RUMBLE STRIPS 2-LANE RURAL LF	
0010	34+68	-	48+08	LT/RT	-	1,340	
0010	52+08	-	54+72	LT/RT	-	264	
0010	58+26	-	83+03	LT/RT	-	2,477	
0010	88+02	-	96+37	LT/RT	-	835	
0010	100+73	-	129+31	LT/RT	-	2,858	
0010	133+31	-	139+85	LT/RT	-	654	
0010	35+12	-	48+33	RT	1,326	-	
0010	52+13	-	54+72	RT	259	-	
0010	58+26	-	81+46	RT	2,310	-	
0010	87+82	-	94+41	RT	659	-	
0010	100+22	-	129+80	RT	2,963	-	
0010	132+73	-	139+85	RT	714	-	
0010	34+31	-	54+72	LT	2,036	-	
0010	58+26	-	83+20	LT	2,504	-	
0010	89+08	-	96+73	LT	765	-	
0010	102+31	-	139+85	LT	3,747	-	
TOTAL 0010					17,283	8,428	

CULVERT SUMMARY

CATEGORY	STATION	OFFSET	LOCATION	520.8000 CONCRETE COLLARS FOR PIPE EACH	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24- INCH EACH	524.0124 CULVERT PIPE SALVAGED 24- INCH LF	524.0136 CULVERT PIPE SALVAGED 36- INCH LF	524.0148 CULVERT PIPE SALVAGED 48- INCH LF	524.0624 APRON ENDWALLS FOR CULVERT PIPE SALVAGED 24- INCH EACH	524.0636 APRON ENDWALLS FOR CULVERT PIPE SALVAGED 36- INCH EACH	524.0648 APRON ENDWALLS FOR CULVERT PIPE SALVAGED 48- INCH EACH	633.5200 MARKERS CULVERT END EACH	SPV.0060.01 SPECIAL (01. GRADING, SHAPING, AND FINISHING CULVERTS AND ENDWALLS) EACH	REMARKS
0010	41+12	LT & RT	STH 32 LT & RT	-	-	-	16	-	-	2	-	2	2	
0010	80+73	LT & RT	STH 32 LT & RT	-	-	8	-	-	2	-	-	2	2	
0010	105+44	LT	STH 32 LT	-	-	-	-	24	-	-	1	1	1	
0010	105+56	RT	STH 32 RT	-	-	-	-	8	-	-	1	1	1	
0010	113+00	LT	STH 32 LT	1	1	-	-	-	-	-	-	1	1	
TOTAL 0010				1	1	8	16	32	2	2	2	7	7	

CURB RAMP

CATEGORY	STATION	TO	STATION	LOCATION	305.0120 * BASE AGGREGATE DENSE 1 1/4- INCH TON	416.0610 DRILLED TIE BARS EACH	601.0411 CONCRETE CURB & GUTTER 30- INCH TYPE D LF	602.0415 CONCRETE SIDEWALK 6- INCH SF	602.0615 CURB RAMP DETECTABLE WARNING FIELD RADIAL NATURAL PATINA SF	SPV.0060.03 SPECIAL (03. CURB RAMP RESTORATION) EACH	REMARKS
0010	32+96	-	33+31	STH 32 LT	6	2	41	152	21	1	TECKLA PL INTERSECTION
TOTAL 0010					6	2	41	152	21	1	

* QUANTITIES SHOWN ELSEWHERE

BEAM GUARD

CATEGORY	STATION	TO	STATION	LOCATION	614.0010	614.2300	614.2500	614.2610	REMARKS
					BARRIER SYSTEM GRADING SHAPING FINISHING EACH	MGS GUARDRAIL 3 LF	MGS THRIE BEAM TRANSITION LF	MGS GUARDRAIL TERMINAL EAT EACH	
0010	39+35	-	55+10	STH 32 LT	1	1,475.00	39.396	1	
0010	57+38	-	67+99	STH 32 LT	1	975.00	39.396	1	
0010	36+79	-	49+14	STH 32 RT	2	1,137.50	-	2	
0010	53+43	-	55+61	STH 32 RT	1	125.00	39.396	1	
0010	57+90	-	67+64	STH 32 RT	1	875.00	39.396	1	
TOTAL 0010					6	4,587.5	157.584	6	

BARRIER SYSTEM GRADING SHAPING AND FINISHING

CATEGORY	STATION	TO	STATION	LOCATION	*	*	**	**	**	**	**	REMARKS
					EXCAVATION COMMON CY	BORROW CY	TOPSOIL SY	EROSION MAT CLASS I TYPE B SY	FERTILIZER TYPE B CWT	SEEDING MIXTURE NO. 20 LB	SEED WATER MGAL	
0010	35+61	-	37+80	STH 32 RT	107	140	254	254	0.16	6.86	5.7	TOPSOIL PLACED 6" DEEP
0010	37+83	-	40+63	STH 32 LT	107	300	282	282	0.18	7.62	6.3	TOPSOIL PLACED 6" DEEP
0010	48+00	-	49+85	STH 32 RT	25	70	315	315	0.20	8.50	7.0	TOPSOIL PLACED 6" DEEP
0010	52+45	-	54+35	STH 32 RT	60	70	369	369	0.23	9.96	8.3	TOPSOIL PLACED 6" DEEP
0010	66+00	-	68+90	STH 32 RT	69	90	735	735	0.46	19.85	16.5	TOPSOIL PLACED 6" DEEP
0010	67+00	-	69+50	STH 32 LT	79	194	341	341	0.22	9.22	7.6	TOPSOIL PLACED 6" DEEP
TOTAL 0010					447	864	2,297	2,297	1.45	62	51.40	

PAYMENT FOR FURNISHING AND PLACING TOPSOIL, FERTILIZER TYPE B, SEEDING MIXTURE NO. 20, SEED WATER, EXCAVATION, BORROW, AND EROSION MAT CLASS 1 TYPE B IS INCIDENTAL TO ITEM NO. 'S 614.0010-BARRIER SYSTEM GRADING SHAPING FINISHING

* ITEMS AND QUANTITIES ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY

** QUANTITIES SHOWN ELSEWHERE

MOBILIZATION

CATEGORY	STATION	TO	STATION	LOCATION	619.1000 MOBILIZATION EACH	REMARKS
0010	17+87	-	139+85	STH 32	1	
				TOTAL 0010	<u>1</u>	

FIELD OFFICE

CATEGORY	LOCATION	642.5001 FIELD OFFICE TYPE B EACH	REMARKS
0010	STH 32	1	
	TOTAL 0010	<u>1</u>	

CLEANING DITCH

CATEGORY	STATION	LOCATION	SPV.0060.02 SPECIAL (02. CLEANING DITCH) EACH	REMARKS
0010	56+80	STH 32	1	RAILROAD DITCH
		TOTAL 0010	<u>1</u>	

EROSION CONTROL

CATEGORY	STATION	TO	STATION	LOCATION	628.1504	628.1520	628.1905	628.1910	628.7015	REMARKS
					SILT FENCE LF	SILT FENCE MAINTENANCE LF	MOBILIZATIONS EROSION CONTROL EACH	MOBILIZATIONS EMERGENCY EROSION CONTROL EACH	INLET PROTECTION TYPE C EACH	
0010		18+11		STH 32, LT & RT	-	-	-	-	2	
0010		23+72		STH 32, LT	-	-	-	-	1	
0010		26+73		STH 32, LT	-	-	-	-	1	
0010		27+97		STH 32, LT	-	-	-	-	1	
0010		32+50		STH 32, LT	-	-	-	-	1	
0010		32+86		STH 32, LT	-	-	-	-	1	
0010	35+61	-	37+80	STH 32 RT	225	225	-	-	-	
0010	37+83	-	40+63	STH 32 LT	277	277	-	-	-	
0010	47+82	-	49+89	STH 32 RT	210	210	-	-	-	
0010	52+20	-	54+50	STH 32 RT	239	239	-	-	-	
0010	65+75	-	69+10	STH 32 RT	344	344	-	-	-	
0010	66+86	-	69+84	STH 32 LT	312	312	-	-	-	
0010	UNDISTRIBUTED						9	3	2	
TOTAL 0010					1,607	1,607	9	3	9	

* QUANTITIES SHOWN ELSEWHERE

RESTORATION

CATEGORY	STATION	LOCATION	** *	** *	** *	** *	** *	REMARKS
			TOPSOIL SY	EROSION MAT CLASS I TYPE B SY	FERTILIZER TYPE B CWT	SEEDING MIXTURE NO. 20 LB	SEED WATER MGAL	
0010	40+83	STH 32 RT	122	122	0.08	3.29	3	PAID UNDER SPV.0060.01
0010	41+36	STH 32 LT	188	188	0.12	5.07	4	PAID UNDER SPV.0060.01
0010	80+73	STH 32 LT	182	182	0.11	4.92	4	PAID UNDER SPV.0060.01
0010	80+74	STH 32 RT	100	100	0.06	2.69	2	PAID UNDER SPV.0060.01
0010	105+44	STH 32 LT	182	182	0.11	4.92	4	PAID UNDER SPV.0060.01
0010	105+56	STH 32 RT	228	228	0.14	6.17	5	PAID UNDER SPV.0060.01
0010	113+00	STH 32 LT	106	106	0.07	2.87	2	PAID UNDER SPV.0060.01
TOTAL 0010			1,108	1,108	0.70	30	25	

PAYMENT FOR FURNISHING AND PLACING TOPSOIL, FERTILIZER TYPE B, SEED MIXTURE NO. 20, SEED WATER, AND EROSION MAT CLASS I TYPE B IS INCIDENTAL TO ITEM NO.'S SPV.0060.01- GRADING, SHAPING AND FINISHING APRON ENDWALLS
 * ITEMS AND QUANTITIES ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY
 ** QUANTITIES SHOWN ELSEWHERE

TECKLA PLACE CURB RAMP RESTORATION

CATEGORY	STATION	TO	STATION	LOCATION	TOPSOIL SY	SILT FENCE LF	MAINTENANCE LF	EROSION MAT CLASS I TYPE B SY	FERTILIZER TYPE B CWT	SEEDING MIXTURE NO. 20 LB	SEED WATER MGAL	REMARKS
0010	32+96	-	33+43	TECKLA PL CURB RAMP	49	86	86	49	0.05	1.35	1.1	PAID UNDER SPV.0060.03
TOTAL 0010					49	86	86	49	0.05	1.35	1.1	

PAYMENT FOR FURNISHING AND PLACING TOPSOIL, FERTILIZER TYPE B, SEED MIXTURE NO. 20, SEED WATER, AND EROSION MAT CLASS I TYPE B IS INCIDENTAL TO ITEM NO.'S SPV.0060.03- CURB RAMP RESTORATION
 * ITEMS AND QUANTITIES ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY
 ** QUANTITIES SHOWN ELSEWHERE

TRAFFIC CONTROL

CATEGORY	STATION	LOCATION	TRAFFIC CONTROL DRUMS DAY	TRAFFIC CONTROL BARRICADES TYPE III DAY	TRAFFIC CONTROL WARNING LIGHTS TYPE A DAY	TRAFFIC CONTROL SIGNS DAY	REMARKS
0010	16+00	CTH AA	--	--	--	90	
0010	32+65	TECKLA PL	--	180	360	225	
0010	50+10	Fontier Heights LN	--	--	--	45	
0010	56+50	STH 32	--	450	540	90	
0010	86+25	SEVEN CORNERS RD	--	180	360	225	
0010	98+50	FUR FARM RD	--	180	360	225	
0010	131+50	CLARK DR	--	180	360	180	
0010	140+00	STH 32	--	90	180	45	
0010	39+35	STH 32 LT	405	--	--	10	BEAM GUARD SHOULDER CLOSURE
0010	57+38	STH 32 LT	302	--	--	10	BEAM GUARD SHOULDER CLOSURE
0010	36+79	STH 32 RT	337	--	--	10	BEAM GUARD SHOULDER CLOSURE
0010	53+43	STH 32 RT	134	--	--	10	BEAM GUARD SHOULDER CLOSURE
0010	57+90	STH 32 RT	285	--	--	10	BEAM GUARD SHOULDER CLOSURE
TOTAL 0010			1,463	1,260	2,160	1,175	

* QUANTITIES SHOWN ELSEWHERE

3

3

PEDESTRIAN ACCOMODATION

CATEGORY	STATION	TO	STATION	LOCATION	643.0300 TRAFFIC CONTROL DRUMS DAY	643.0410 TRAFFIC CONTROL BARRICADES TYPE II DAY	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A DAY	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C DAY	643.0900 TRAFFIC CONTROL SIGNS DAY	644.1410 TEMPORARY PEDESTRIAN SURFACE ASPHALT SF	644.1601 TEMPORARY PEDESTRIAN CURB RAMP DAY	644.1810 TEMPORARY PEDESTRIAN BARRICADE LF	SPV.0090.01 SPECIAL (01. TEMPORARY MARKING CROSSWALK PAINT TRANSVERSE LINE 6-INCH) LF	REMARKS
0010	32+29	-	33+93	STH 32 LT	280	40	40	200	20	280	20	145	196	STH 32 / TECKLA PL INTERSECTION
TOTAL 0010					280	40	40	200	20	280	20	145	196	

* QUANTITIES SHOWN ELSEWHERE

PAVEMENT MARKING

CATEGORY	STATION	TO	STATION	LOCATION	643.3105 TEMPORARY MARKING LINE PAINT 4-INCH LF	643.3120 TEMPORARY MARKING LINE EPOXY 4-INCH LF	646.1020 MARKING LINE EPOXY 4-INCH LF	646.1040 MARKING LINE GROOVED WET REFLECTIVE EPOXY 4-INCH LF	646.3040 MARKING LINE GROOVED WET REFLECTIVE EPOXY 8-INCH LF	646.6120 MARKING STOP LINE EPOXY 18-INCH LF	646.7420 MARKING CROSSWALK EPOXY TRANSVERSE LINE 6-INCH LF	REMARKS
0010	17+87	-	21+18	STH 32	414	414	414	-	-	-	-	CENTERLINE 1 SOLID, 1 DASHED
0010	21+18	-	30+78	STH 32	240	240	240	-	-	-	-	CENTERLINE 1 DASHED
0010	30+78	-	39+76	STH 32	1,122	1,122	1,122	-	-	-	-	CENTERLINE 1 SOLID, 1 DASHED
0010	39+76	-	77+78	STH 32	7,604	7,604	7,604	-	-	-	-	CENTERLINE 2 SOLID
0010	77+78	-	88+63	STH 32	1,356	1,356	1,356	-	-	-	-	CENTERLINE 1 SOLID, 1 DASHED
0010	88+63	-	101+75	STH 32	328	328	328	-	-	-	-	CENTERLINE 1 DASHED
0010	101+75	-	111+69	STH 32	1,243	1,243	1,243	-	-	-	-	CENTERLINE 1 SOLID, 1 DASHED
0010	111+69	-	130+72	STH 32	3,806	3,806	3,806	-	-	-	-	CENTERLINE 2 SOLID
0010	130+72	-	139+85	STH 32	1,142	1,142	1,142	-	-	-	-	CENTERLINE 1 SOLID, 1 DASHED
0010	18+32	-	31+86	STH 32	-	-	-	1,354	-	-	-	RIGHT EDGELINE
0010	33+25	-	49+35	STH 32	-	-	-	1,614	-	-	-	RIGHT EDGELINE
0010	50+59	-	84+95	STH 32	-	-	-	3,427	-	-	-	RIGHT EDGELINE
0010	87+32	-	97+63	STH 32	-	-	-	1,032	-	-	-	RIGHT EDGELINE
0010	99+72	-	130+09	STH 32	-	-	-	3,042	-	-	-	RIGHT EDGELINE
0010	132+27	-	139+85	STH 32	-	-	-	760	-	-	-	RIGHT EDGELINE
0010	30+31	-	83+70	STH 32	-	-	-	5,044	-	-	-	LEFT EDGELINE
0010	85+82	-	97+23	STH 32	-	-	-	1,141	-	-	-	LEFT EDGELINE
0010	99+65	-	139+85	STH 32	-	-	-	4,015	-	-	-	LEFT EDGELINE
0010	82+50	-	84+94	STH 32	-	-	-	-	244	-	-	TURN LANE
0010	85+85	-	87+71	STH 32	-	-	-	-	186	-	-	TURN LANE
0010	95+64	-	97+61	STH 32	-	-	-	-	196	-	-	TURN LANE
0010	99+65	-	101+56	STH 32	-	-	-	-	191	-	-	TURN LANE
0010	31+86	-	33+25	STH 32	-	-	-	-	-	42	142	TECKLA PL INTERSECTION
0010	17+87	-	139+85	STH 32	24,396	-	-	-	-	-	-	TEMPORARY CENTERLINE (2 SOLID) MILLED SURF
TOTAL 0010					41,651	17,255	17,255	21,429	817	42	142	

SAWING

CATEGORY	STATION	OFFSET	LOCATION	* * 690.0150 690.0150		REMARKS
				SAWING ASPHALT LF	SAWING CONCRETE LF	
0010	17+87	0.00'	STH 32	44		
0010	32+68	61.97' LT	TECKLA PL	38		
0010	32+65	90.44' RT	TECKLA PL	32		
0010	33+18	33.74' LT	TECKLA PL SIDEWALK	10		
0010			TECKLA PL CURB AREA	45	5	
0010	50+08	89.85' RT	FRONTIER HEIGHTS LANE	22		
0010	54+97	0.00'	STH 32	39		
0010	58+00	0.00'	STH 32	39		
0010	84+89	84.24' LT	SEVEN CORNERS RD	29		
0010	86+28	101.12' RT	SEVEN CORNERS RD	27		
0010	98+95	92.66' LT	FUR FARM RD	34		
0010	98+15	91.28' RT	FUR FARM RD	26		
0010	110+50	LT	DRIVEWAY	16		
0010	131+63	79.60' RT	CLARK DR	25		
0010	139+85	0.00'	STH 32	30		
TOTAL 0010				456	5	

* QUANTITIES SHOWN ELSEWHERE

CONSTRUCTION STAKING

CATEGORY	STATION	TO	STATION	LOCATION	650.6500.01	650.7000	650.8000	650.9000	650.9500	650.9911.01	650.9920	REMARKS
					CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) (01. B-08-0009) EACH	CONSTRUCTION STAKING CONCRETE PAVEMENT LF	CONSTRUCTION STAKING RESURFACING REFERENCE LF	CONSTRUCTION STAKING CURB RAMPS EACH	CONSTRUCTION STAKING SIDEWALK (PROJECT) (01. 4085-60-71) EACH	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) (01. 4085-60-71) EACH	CONSTRUCTION STAKING SLOPE STAKES LF	
0010	17+87	-	54+97	STH 32	-	-	3,710	-	-	1	-	
0010	32+96	-	33+31	STH 32 LT	-	-	-	1	1	-	-	TECKLA PL INTERSECTION
0010	36+15	-	37+39	STH 32 RT	-	-	-	-	-	-	124	
0010	38+67	-	39+92	STH 32 LT	-	-	-	-	-	-	125	
0010	48+61	-	49+84	STH 32 RT	-	-	-	-	-	-	123	
0010	52+74	-	53+98	STH 32 RT	-	-	-	-	-	-	124	
0010	55+06	-	55+70	STH 32	-	64	-	-	-	-	-	B-08-0009 CONCRETE APPROACH SLAB
0010	57+28	-	57+94	STH 32	-	66	-	-	-	-	-	B-08-0009 CONCRETE APPROACH SLAB
0010	55+42	-	57+57	STH 32	1	-	-	-	-	-	-	
0010	58+00	-	139+85	STH 32	-	-	8,185	-	-	-	-	
0010	67+07	-	68+70	STH 32 LT & RT	-	-	-	-	-	-	163	
TOTAL 0010					1	130	11,895	1	1	1	659	

3

TRAFFIC CONTROL DETOUR SIGN SUMMARY

3

SIGN NO.	LOCATION	SIGN CODE	SIZE W X H	NUMBER IN SERVICE	APPROX. SERVICE PERIOD 60 DAYS	643.0900 SIGNS DAYS	643.0420 BARRICADES TYPE III DAYS	643.0705 WARNING LIGHTS TYPE A DAYS	643.1000 FIXED MESSAGE SIGN SF	643.1050 SIGNS PORTABLE CHANGEABLE MESSAGE DAYS	NO. OF CYCLES	643.0920 COVERING SIGNS TYPE II EACH	REMARKS
1	STH 32/57, N. OF CTH X, PLACE 2000' N. OF CTH X INTERSECTION	W 20-2A	48"X48"	1	60	60							
2	STH 32/57, N. OF CTH X, PLACE 1500' N. OF CTH X INTERSECTION	FMS	54"X24"	1					9				SEE SIGN DETAIL SHEET
3	STH 32/57, N. OF CTH X, MODIFY EXISTING J2-1 SIGN AS SHOWN	M 4-8	24"X12"	1	60	60							
	"	MO 5-1R	21"X21"	1	60	60							
4	STH 32/57, N. OF CTH X, MODIFY EXISTING J3-1 SIGN AS SHOWN	M 4-8	24"X12"	1	60	60							
	"	MO 6-1	21"X21"	1	60	60							RIGHT
5	STH 32/57, AT CTH J, PLACE IN SW QUADRANT OF CTH INTERSECTION	R 11-3B	60"X30"	1	60	60	60	120					2 1/4 MILES AHEAD
	"	M 4-9R	30"X24"	1	60	60							
6	CTH J, AT STH 32/57, PLACE RIGHT OF EXISTING R1-1 SIGN	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 6-1	21"X21"	1	60	60							LEFT
7	STH 32/57, S. OF CTH J, COVER EXISTING J4-2 SIGN AS SHOWN										1	1	COVER ENTIRE SIGN
8	CTH J, S. OF STH 32/57, PLACE 250' S. OF STH 32/57 INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-3	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
9	CTH J, S. OF STH 32/57, MODIFY EXISTING J1-1 SIGN AS SHOWN	M 4-8A	24"X18"	1	60	60							
10	CTH J, N. OF FOUNDRY RD, PLACE 150' N. OF FOUNDRY RD INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-3	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 6-1	21"X21"	1	60	60							AHEAD
11	CTH J, S. OF FOUNDRY RD, PLACE 150' S. OF FOUNDRY RD INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-1	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 6-1	21"X21"	1	60	60							AHEAD
12	CTH J, N. OF CTH HH, PLACE 500' N. OF CTH HH INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-3	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 5-1L	21"X21"	1	60	60							
13	CTH J, N. OF CTH HH, PLACE 250' N. OF CTH HH INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-1	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
14	CTH J, AT CTH HH, PLACE RIGHT OF EXISTING J13-1 SIGN	M 4-8	24"X12"	1	60	60							
	"	M 3-3	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 6-1	21"X21"	1	60	60							LEFT
PAGE SUBTOTALS				40		2,340	60	120	9	0		1	



PLAN SHEET PRODUCED
BY WisDOT - NE REGION

TRAFFIC CONTROL DETOUR SIGN SUMMARY

SIGN NO.	LOCATION	SIGN CODE	SIZE W X H	NUMBER IN SERVICE	APPROX. SERVICE PERIOD 60 DAYS	643.0900 SIGNS DAYS	643.0420 BARRICADES TYPE III DAYS	643.0705 WARNING LIGHTS TYPE A DAYS	643.1000 FIXED MESSAGE SIGN SF	643.1050 SIGNS PORTABLE CHANGEABLE MESSAGE DAYS	NO. OF CYCLES	643.0920 COVERING SIGNS TYPE II EACH	REMARKS
15	CTH HH, AT CTH J, PLACE RIGHT OF EXISTING J13-1 SIGN	M 4-8	24"X12"	1	60	60							
	"	M 3-1	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 6-1	21"X21"	1	60	60							RIGHT
16	CTH HH, E. OF CTH J, PLACE 250' E. OF CTH J INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-3	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
17	CTH HH, E. OF CTH J, PLACE 500' E. OF CTH J INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-1	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
	"	MO 5-1R	21"X21"	1	60	60							
18	CTH HH, W. OF STH 32/57, MODIFY EXISTING J1-1 SIGN AS SHOWN	M 4-8A	24"X18"	1	60	60							
19	CTH HH, W. OF STH 32/57, PLACE 100' W. OF STH 32/57 INTERSECTION	M 4-8	24"X12"	1	60	60							
	"	M 3-1	24"X12"	1	60	60							
	"	M 1-6	24"X24"	1	60	60							32
	"	M 1-6	24"X24"	1	60	60							57
20	CTH HH, AT STH 32/57, MODIFY EXISTING J3-1 SIGN AS SHOWN	MO 6-1	21"X21"	1	60	60							AHEAD
21	STH 32/57, AT CTH HH, PLACE IN NE QUADRANT OF CTH HH INTERSECTION	R 11-3B	60"X30"	1	60	60	60	120					2 1/4 MILES AHEAD
	"	M 4-9R	30"X24"	1	60	60							
22	STH 32/57, N. OF CTH HH, COVER EXISTING J4-2 SIGN AS SHOWN			1							1	1	COVER ENTIRE SIGN
23	STH 32/57, AT CTH AA, PLACE IN NE QUADRANT OF CTH AA INTERSECTION	R 11-3B	60"X30"	1	60	60	60	120					3/4 MILES AHEAD
24	STH 32/57, S. OF STRUCTURE, PLACE ON RIGHT SHOULDER, FIELD DETERMINE LOCATION	PCMS		1						7			PLACE IN ADVANCE OF CLOSURE
25	STH 32/57, N. OF STRUCTURE, PLACE ON RIGHT SHOULDER, FIELD DETERMINE LOCATION	PCMS		1						7			PLACE IN ADVANCE OF CLOSURE
26	STH 32/57, AT CTH HH, MODIFY EXISTING J3-1 SIGN AS SHOWN	M 4-8	24"X12"	1	60	60							
	"	MO 6-1	21"X21"	1	60	60							AHEAD
27	STH 32/57, S. OF CTH HH, COVER EXISTING D1-3 SIGN AS SHOWN										1	1	COVER "CHILTON-GREEN BAY"
28	STH 32/57, S. OF CTH HH, MODIFY EXISTING J2-1 SIGN AS SHOWN	M 4-8	24"X12"	1	60	60							
	"	MO 6-1	21"X21"	1	60	60							AHEAD
29	STH 32/57, S. OF CTH HH, PLACE 1500' S. OF CTH HH INTERSECTION	FMS	54"X24"	1					9				SEE SIGN DETAIL SHEET
30	STH 32/57, S. OF CTH HH, PLACE 2000' S. OF CTH HH INTERSECTION	W 20-2A	48"X48"	1	60	60							
PAGE SUBTOTALS				32		1,680	120	240	9.0	14		2	
PROJECT TOTALS				72		4,020	180	360	18	14		3	


PLAN SHEET PRODUCED
BY WisDOT - NE REGION

BENCHMARK TABLE						
POINT	STATION	OFFSET	Y COORDS	X COORDS	ELEV	DESCRIPTION
BM 202	28+01.45	32.58 LT	439100.472	922886.164	916.44	NE BOLT ON HYD
CP 112	27+61.16	43.56 RT	439129.517	922967.256	910.17	1 M FENO W ALUM CAP SET



BENCHMARK TABLE						
POINT	STATION	OFFSET	Y COORDS	X COORDS	ELEV	DESCRIPTION
BM 200	55+62.64	23.18 RT	440522.856	920574.079	962.10	CHISELED BOX ON SE COR OF PARAPET
CP 111	49+61.55	34.56 RT	440350.753	921150.216	950.94	1 M FENO W ALUM CAP SET


CURVE 3
 PI STA = 70+98.57
 Y = 440971.134
 X = 919104.982
 DELTA = 47°32'29"
 D = 1°07'40"
 T = 1118.72'
 L = 2107.58'
 R = 2540.00'
 PC STA = 59+79.84
 Y = 440627.629
 X = 920169.663
 PT STA = 80+87.42
 Y = 441988.504
 X = 918639.688
 BK = N72°07'06.3"W
 AH = N24°34'37.1"W
 SE = 6.9%




LEGEND

INLET PROTECTION, TYPE C

SURFACE WATER FLOW



BENCHMARK TABLE						
POINT	STATION	OFFSET	Y COORDS	X COORDS	ELEV	DESCRIPTION
BM 201	80+73.88	62.34 LT	441949.971	918588.803	925.86	CHISELED BOX ON RCCP
CP 110	84+44.50	75.87 LT	442281.680	918422.180	930.23	1 M FENO W ALUM CAP SET




LEGEND

INLET PROTECTION, TYPE C

SURFACE WATER FLOW

CURVE 4
PI STA = 116+13.25
Y = 445194.900
X = 917173.243
DELTA = 21°12'56"
D = 0°30'33"
T = 1053.99'
L = 2083.83'
R = 5627.73'
PC STA = 105+59.26
Y = 444236.402
X = 917611.612
PT STA = 126+43.09
Y = 445929.802
X = 916417.727
BK = N24°34'37.1"W
AH = N45°47'32.8"W
SE = 3.8%




LEGEND


INLET PROTECTION, TYPE C

SURFACE WATER FLOW

CURVE 5
 PI STA = 132+22.46
 Y = 446334.153
 X = 916002.795
 DELTA = 13°51'33"
 D = 0°36'03"
 T = 579.37'
 L = 1153.08'
 R = 4766.96'
 PC STA = 126+43.09
 Y = 445929.802
 X = 916417.727
 PT STA = 137+96.17
 Y = 446627.339
 X = 915503.085
 BK = N45°44'23.9"W
 AH = N59°35'57.4"W
 SE=4.6%

BENCHMARK TABLE						
POINT	STATION	OFFSET	Y COORDS	X COORDS	ELEV	DESCRIPTION
BM 1000	127+67.77	64.74 RT	446063.175	916371.261	928.38	RR SPIKE IN PPOL # 305638
BM 1001	137+94.24	54.35 LT	446579.493	915477.231	931.67	RR SPIKE IN PPOL # P19418





LEGEND

 INLET PROTECTION, TYPE C


 SURFACE WATER FLOW

Standard Detail Drawing List


08D01-22A	CONCRETE CURB & GUTTER
08D01-22B	CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS
08D02-07A	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D02-07B	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D02-07C	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D04-06	CONCRETE SURFACE DRAINS & ASPHALTIC FLUMES
08D05-20A	CURB RAMPS TYPES 1 AND 1-A
08D05-20B	CURB RAMPS TYPES 2 AND 3
08D05-20C	CURB RAMPS TYPES 4A AND 4A1
08D05-20D	CURB RAMPS TYPE 4B AND 4B1
08D05-20E	CURB RAMPS TYPES 5, 6, 7A, 7B & 8
08D05-20F	CURB RAMPS RADIAL DETECTABLE WARNING FIELD APPLICATIONS
08D05-20G	CURB RAMPS RECTANGULAR AND RADIAL DETECTABLE WARNING PLATES
08E09-06	SILT FENCE
08E10-02	INLET PROTECTION TYPE A, B, C AND D
08F01-11	APRON ENDWALLS FOR CULVERT PIPE
08F04-08	JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL
12A03-10	NAME PLATE (STRUCTURES)
13A03-07	CONCRETE PAVEMENT SHOULDERS
13A10-02A	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02B	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02C	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02D	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A11-03A	2-LANE RURAL CENTER LINE RUMBLE STRIP, MILLING
13A11-03B	2-LANE RURAL CENTER LINE RUMBLE STRIP, MILLING
13B02-09A	CONCRETE PAVEMENT APPROACH SLAB
13C01-19	CONCRETE PAVEMENT LONGITUDINAL JOINTS AND TIES
13C14-07A	BASE PATCHING CONCRETE
13C14-07B	BASE PATCHING CONCRETE
13C14-07C	BASE PATCHING CONCRETE
13C19-03	HMA LONGITUDINAL JOINTS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15A03-02A	FLEXIBLE MARKER POST FOR CULVERT END
15A03-02B	FLEXIBLE MARKER POST FOR CULVERT END
15C02-08A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-08B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C02-08C	DETOUR SIGNING FOR MAINLINE CLOSURES
15C04-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 M.P.H. OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC
15C05-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 40 M.P.H. OR LESS
15C08-22A	LONGITUDINAL MARKING (MAINLINE)
15C08-22B	TEMPORARY LONGITUDINAL PAVEMENT MARKING
15C08-22C	PAVEMENT MARKING (TURN LANES)
15C08-22D	PAVEMENT MARKING (TURN LANES)
15C11-10B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C12-09A	TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION
15C19-07A	MOVING PAVEMENT MARKING OPERATION TWO-LANE TWO-WAY ROADWAY
15C33-04	STOP LINE AND CROSSWALK PAVEMENT MARKING
15C35-05A	PAVEMENT MARKING (INTERSECTIONS)
15D28-04	TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY

Standard Detail Drawing List


15D30-07A	TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION
15D30-07B	TRAFFIC CONTROL, TEMPORARY ADA COMPLIANT PEDESTRIAN ACCOMMODATION
15D30-07J	TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION
15D44-02	TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH MILLED SURFACES




TYPES A¹ & D




6" SLOPED CURB TYPES G¹ & J




4" SLOPED CURB TYPES G¹ & J




TYPES K¹ & L
(OPTIONAL CURB SHAPE)




TYPES K¹ & L
CONCRETE CURB AND GUTTER 30"




TYPES A¹ & D
CONCRETE CURB AND GUTTER 18"



6" SLOPED CURB TYPES A¹ & D




4" SLOPED CURB TYPES A¹ & D
CONCRETE CURB AND GUTTER 36"



4" SLOPED CURB TYPES R¹ & T


TBT & TBTT	X
30"	22"
36"	28"



TYPES TBT & TBTT¹
CONCRETE CURB AND GUTTER


PAVEMENT THICKNESS
AND MAXIMUM CONCRETE
PANEL WIDTH TABLE

PAVEMENT THICKNESS	MAXIMUM PANEL WIDTH
LESS THAN 10"	12'
10" & ABOVE	15'



PARTIAL SECTION OF PAVEMENT *
WITH INTEGRAL CURB AND GUTTER

* BIKE LANE IS NOT SHOWN



REVERSE SLOPE GUTTER⁶
(TYPICAL FOR ALL CURB & GUTTER TYPES)

GENERAL NOTES


DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.


INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ CONCRETE CURB AND GUTTER 4-INCH SLOPED 30-INCH TYPE "R" AND "T" = 17 INCHES
CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE "R" AND "T" = 23 INCHES



END SECTION CURB AND GUTTER



DETAIL OF CURB AND GUTTER AT INLETS
(TYPICAL H INLET COVER SHOWN)


GENERAL NOTES

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.


PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑨ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.



TYPICAL TIE BAR LOCATION ①




TYPES A ① & D




TYPES G ① & J

CONCRETE CURB




PLAN VIEW



SECTION A - A

TIE BARS DRILLED INTO EXISTING PAVEMENT



DRIVEWAY ENTRANCE CURB ⑨
(WHEN DIRECTED BY THE ENGINEER)

CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2021 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.

- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2' - 0" TIE BARS SPACED AT 3' - 0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)




**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

SDD 08D02 - 07a


SDD 08D02 - 07a




SECTION A - A




SECTION G - G




SECTION H - H



SECTION I - I



**PLAN VIEW
PERPENDICULAR FLUME**



**PLAN VIEW
SKEWED FLUME**

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2'-0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2'-0" TIE BARS SPACED AT 3'-0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.


- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH AS REQUIRED.
- ⑮ GEOTEXTILE FABRIC TYPE HR.

**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**CURB AND GUTTER TRANSITION SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**



**CURB AND GUTTER END SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**




**CURB AND GUTTER FLOW LINE DEPRESSION
AT FLUMES CONCRETE CURB AND GUTTER
4-INCH SLOPED 36 INCH TYPE TBT OR TBTT**

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.


- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2' - 0" TIE BARS SPACED AT 3' - 0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH IS REQUIRED.
- ⑮ GEOTEXTILE FABRIC TYPE HR.
- ⑯ MINIMUM REINFORCEMENT SHALL BE 6" X 6" - W4.0 X W4.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑰ MSG THRIE BEAM TRANSITION POST 1. SEE SDD 14B45 FOR ADDITIONAL CONSTRUCTION DETAILS AND ACCEPTABLE MATERIALS.
- ⑱ MAINTAIN WIDTH, THICKNESS AND CROSS SLOPE OF ADJACENT TYPE TBT OR TBTT CURB. SEE NOTE 6 FOR TIE BAR SPACING.
- ⑲ ALIGN FACE OF POST BLOCK WITH FLOW LINE.
- ⑳ MAINTAIN FLOW LINE AT EDGE OF PAVEMENT/FACE OF BEAM GUARD AS APPLICABLE.
- ㉑ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING HMA PAVEMENTS.




SECTION B-B




**SECTION C - C
JOINT DETAIL FOR BRIDGE WITH STRUCTURAL
APPROACH SLAB AND CONCRETE APPROACH SLAB**




**SECTION C - C
JOINT DETAIL FOR BRIDGE APPROACH
WITH CONCRETE SHOULDERS**



SECTION D - D



SECTION E - E



SECTION F - F

**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER

FHWA

NOTE: TAPER CURB ENDS TO GUTTER IN 1' - 0"

ASPHALTIC FLUME



**PLAN VIEW
CURB OPENING
FOR FLUME**


**PLAN VIEW
FLUME AT CURB END**

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

4" X 4" - W3.0 X W3.0 CONCRETE REINFORCEMENT SHALL BE IN ACCORDANCE WITH AASHTO SPECIFICATION M55.


- ① JOINTS SHALL BE 1/8" TO 1/4" WIDE BY 1 1/2" DEEP AND SPACED AT UNIFORM INTERVALS OF APPROXIMATELY 4 FEET.
- ② GEOTEXTILE TYPE "R" SHALL UNDERLAY THE FULL LENGTH AND WIDTH OF THE CONCRETE SURFACE DRAIN AND RIPRAP.
- ③ CONCRETE SURFACE DRAIN WITHOUT CURB AND GUTTER MAY BE USED ON BACKSLOPES WHEN SPECIFIED.
- ④ ANGLE OF FLUME IN RELATION TO BACK OF CURB TO BE CONSTRUCTED PER THE PLAN DETAILS OR AS DIRECTED BY THE ENGINEER. ANGLE OF FLUME MAY BE OTHER THAN 90 DEGREES AS SHOWN.




SECTION A - A




SECTION B - B



**PLAN VIEW
CONCRETE SURFACE DRAIN**



SECTION C - C



SECTION D - D

MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE, SPACING 12" C-C


MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE, SPACING 12" C-C

CONCRETE SURFACE DRAINS AND ASPHALTIC FLUMES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2021 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER


FHWA



**PLAN VIEW
CURB RAMP TYPE 1
(CENTER OF CORNER RADIUS)**




**PLAN VIEW
CURB RAMP TYPE 1 - A
(NO TERRACE)**



VIEW A - A FOR TYPE 1


** WIDTH SHOWN ELSEWHERE
IN THE PLANS




SECTION C - C FOR TYPE 1 - A

LEGEND

- 1/2" EXPANSION JOINT SIDEWALK
- CONTRACTION JOINT FIELD LOCATED
- PAVEMENT MARKING CROSSWALK (WHITE)



SECTION B - B FOR TYPE 1




VIEW D - D FOR TYPE 1 - A

GENERAL NOTES


- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- WHEN NECESSARY, THE SIDEWALK ELEVATION MAY BE LOWERED TO MEET THE HIGH POINT ON THE RAMP.
- TYPE 1 CURB RAMPS SHALL HAVE A NORMAL SIDEWALK APRON AND CURB ON BOTH SIDES OF RAMP.
- DETECTABLE WARNING FIELD SHALL BE MEASURED AND PAID BY THE SQUARE FOOT AS "CURB RAMP DETECTABLE WARNING FIELD". THE CONCRETE PEDESTRIAN CURB, IF NEEDED, SHALL BE MEASURED AND PAID BY THE LINEAR FOOT AS "CONCRETE CURB PEDESTRIAN". CONCRETE SIDEWALK IN THE CURB RAMP AREA SHALL BE MEASURED AND PAID BY THE SQUARE FOOT AS CONCRETE SIDEWALK, INCLUDING THE AREA UNDER THE DETECTABLE WARNING FIELD.
- SELECT CURB RAMP DETECTABLE WARNING FIELD MATERIALS AND DEVICES FROM THE DEPARTMENT'S APPROVED MATERIALS LIST. THE COLOR OF THE DETECTABLE WARNING FIELD IS SPECIFIED ELSEWHERE AND IS INCIDENTAL TO THE BID ITEM OF "CURB RAMP DETECTABLE WARNING FIELD"
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- SURFACE TEXTURE OF THE RAMP SHALL BE OBTAINED BY COARSE BROOMING TRANSVERSE TO THE SLOPE OF THE RAMP.
- ① THIS POINT IS AN EXTENSION OF OUTSIDE EDGE OF APPROACHING SIDEWALK WHERE IT MEETS THE BACK OF CONCRETE CURB. POINT LOCATION MAY BE ADJUSTED TO ALIGN WITH BEGINNING OF FULL-HEIGHT CURB IF THIS DISTANCE IS SHORT.
 - ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4" INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
 - ③ MAXIMUM 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
 - ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
 - ⑤ PROVIDE A LEVEL LANDING IN THE STREET AND GUTTER AREA (2% MAXIMUM SLOPE IN ANY DIRECTION). WHEN THE GUTTER SLOPE EXCEEDS 2%, CONSTRUCT THE LEVEL LANDING IN THE STREET AREA.
 - ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
 - ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.

**CURB RAMPS
TYPE 1 AND 1-A**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PLAN VIEW CURB RAMP TYPE 2 (CENTER OF CORNER RADIUS)



PLAN VIEW CURB RAMP TYPE 3 (OUTSIDE OF CROSSWALK AREA)




DETAIL B




DETAIL A

GENERAL NOTES


- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE SHALL BE FROM THE SAME MANUFACTURER.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE (2.67% OR LESS) AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET X 5 FEET.
- ⑦ WHEN GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- ⑨ WHEN DISTANCE IS LESS THAN 6' - 0", IT MAY BE DIFFICULT TO ACHIEVE A 7% SLOPE OR FLATTER ALONG THE RAMP. REDUCE CURB HEIGHT IN TRIANGLE AREA TO ACHIEVE 7% SLOPE OR FLATTER ON RAMP. CONSTRUCT 2-INCH MINIMUM CURB HEIGHT BETWEEN 10:1 FLARES.



SECTION A - A FOR TYPE 2



SECTION B - B FOR TYPE 3



VIEW C - C FOR TYPE 3


- * MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IN FRONT OF GRADE BREAK
- ** WIDTH SHOWN ELSEWHERE IN THE PLANS

LEGEND

- 1/2" EXPANSION JOINT SIDEWALK
- - - CONTRACTION JOINT SIDEWALK
- ||||| PAVEMENT MARKING CROSSWALK (WHITE)

**CURB RAMPS
TYPE 2 AND 3**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**PLAN VIEW
CURB RAMP TYPE 4A**

RADIUS (AT CURB FACE)	X
10 FEET	4' - 7"
15 FEET	6' - 5 1/2"

INTERMEDIATE RADII CAN BE INTERPOLATED




SECTION A - A FOR TYPE 4A

GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4" INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- ⑦ WHEN THIS GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- ⑩ INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.


LEGEND

- 1/2" EXPANSION JOINT SIDEWALK
- - - CONTRACTION JOINT SIDEWALK
- ||||| PAVEMENT MARKING CROSSWALK (WHITE)




SECTION C - C FOR TYPE 4A

* MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IF FRONT OF GRADE BREAK




**SECTION B - B FOR
TYPE 4A AND TYPE 4A1**


** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED



**PLAN VIEW
CURB RAMP TYPE 4A1**




ISOMETRIC VIEW FOR TYPE 4A




ISOMETRIC VIEW FOR TYPE 4A1

**CURB RAMPS
TYPE 4A AND 4A1**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**PLAN VIEW
CURB RAMP TYPE 4B**



SECTION A - A FOR TYPE 4B




**SECTION B - B FOR
TYPE 4B AND TYPE 4B1**

** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED


* MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IF FRONT OF GRADE BREAK

RADIUS (AT CURB FACE)	W = 3' - 0"		W = 4' - 0"		W = 5' - 0"		W = 6' - 0"		W = 7' - 0"		W = 8' - 0"		W = 9' - 0"		W = 10' - 0"	
	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y
10 FEET	2' - 10 1/4"	0' - 5"	2' - 1"	1' - 4 1/2"	1' - 5"	2' - 1"	0' - 10"	2' - 7 1/2"	0' - 3 1/4"	3' - 0 1/4"						
15 FEET	4' - 6 3/4"	2' - 1 3/4"	3' - 9"	3' - 5 3/4"	3' - 1 1/4"	4' - 6"	2' - 6 3/4"	5' - 4 1/2"	2' - 1"	6' - 1"	1' - 8"	6' - 8 1/2"	1' - 3 1/4"	7' - 2 1/2"	0' - 10 3/4"	7' - 7 1/4"
20 FEET	5' - 9 3/4"	3' - 6 1/2"	4' - 11 1/2"	5' - 1 3/4"	4' - 3 3/4"	6' - 5 1/2"	3' - 8 3/4"	7' - 7"	3' - 3"	8' - 6 1/2"	2' - 10"	9' - 4 1/2"	2' - 5 1/2"	10' - 1 1/4"	2' - 1 1/4"	10' - 9"
30 FEET			6' - 9 1/4"	7' - 11 1/4"	6' - 0 1/4"	9' - 8"	5' - 5"	11' - 1 3/4"	4' - 10 3/4"	12' - 5 3/4"	4' - 5 1/2"	13' - 7 3/4"	4' - 0 3/4"	14' - 8 1/2"	3' - 8 1/2"	15' - 8 1/4"
40 FEET									6' - 1 3/4"	15' - 8 1/2"	5' - 8"	17' - 2"	5' - 3"	18' - 5 3/4"	4' - 10 3/4"	19' - 8 1/4"
50 FEET															5' - 10 1/4"	23' - 2"


INTERMEDIATE RADII CAN BE INTERPOLATED
DIMENSION "Y" IS CALCULATED BASED ON 6'-0" RAMP LENGTH
DIMENSION "X" IS CALCULATED BASED ON 5'-0" SIDEWALK WIDTH




SECTION C - C FOR TYPE 4B



**PLAN VIEW
CURB RAMP TYPE 4B1**



ISOMETRIC VIEW FOR TYPE 4B



ISOMETRIC VIEW FOR TYPE 4B1

LEGEND


- 1/2" EXPANSION JOINT SIDEWALK
- CONTRACTION JOINT SIDEWALK
- PAVEMENT MARKING CROSSWALK (WHITE)

GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/2 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- WHEN THIS GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.


**CURB RAMPS
TYPE 4B AND 4B1**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



CURB RAMP TYPE 8


DETECTABLE WARNINGS AT RAILROAD CROSSING



CURB RAMP TYPE 6

DETECTABLE WARNING AT ISLANDS


REFER TO GENERAL NOTES (2) AND (3) FOR ALL ISLAND CURB RAMPS



SECTION A - A FOR TYPE 5


CURB RAMP TYPE 5

**MEDIAN ISLAND
NON-ELEVATED PEDESTRIAN CROSSING**



CURB RAMP TYPE 7A

MID BLOCK CROSSING



CURB RAMP TYPE 7B

MID BLOCK CROSSING

NOTE: THESE PARALLEL AND PARALLEL/PERPENDICULAR CURB RAMPS MAY BE USED AT INTERSECTIONS AND MID BLOCK LOCATIONS.

GENERAL NOTES

AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.

DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.

- (2) GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- (3) AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- (4) ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- (6) PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- (10) INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.
- (11) SLOPE SIDEWALK TOWARD LANDING AS SHOWN WHERE THERE IS NO TERRACE OR WHERE THE TERRACE WIDTH IS LESS THAN 6 FEET WIDE.
- (12) THE EDGE OF THE DETECTABLE WARNING FIELD NEAREST TO A RAILROAD CROSSING SHALL BE 1.5 FEET ±0.1' FROM THE FACE OF THE GATE ARM IF THE GATE ARM EXTENDS ACROSS THE SIDEWALK. WHERE THERE IS NO PEDESTRIAN GATE, THE EDGE OF THE DETECTABLE WARNING FIELD NEAREST TO THE RAILROAD CROSSING SHALL BE 15 FEET FROM THE NEAREST RAIL.
- (13) DO NOT INSTALL DETECTABLE WARNING FIELDS AT THE EDGES OF STREET-LEVEL PEDESTRIAN REFUGE ISLANDS IF A MINIMUM 2 FOOT CONCRETE SURFACE WITHOUT DETECTABLE WARNINGS (MEASURED IN THE DIRECTION OF PEDESTRIAN TRAVEL) CANNOT BE ACHIEVED.

LEGEND

- ===== 1/2" EXPANSION JOINT SIDEWALK
- - - - - CONTRACTION JOINT FIELD LOCATED
- ||||||| PAVEMENT MARKING CROSSWALK (WHITE)




SECTION B - B FOR TYPE 7A


**CURB RAMPS
TYPE 5, 6, 7A, 7B & 8**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-c IS EXCEEDED



**PLAN VIEW
CURB RAMP TYPE 4A1
(GRADE BREAK DISTANCE GREATER THAN 5 FEET)**




SECTION A - A FOR TYPE 4A1

**** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED

*** MAXIMUM 8.33%

- LEGEND**
- 1/2" EXPANSION JOINT SIDEWALK
 - - - - - CONTRACTION JOINT SIDEWALK
 - ||||| PAVEMENT MARKING CROSSWALK (WHITE)




DETAIL A


GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- APPLY RADIAL DETECTABLE WARNING PLACEMENT SIMILARLY FOR TYPE 4A AND 4A1 CURB RAMPS AND SIMILARLY FOR TYPE 4B AND 4B1 CURB RAMPS. TYPE 4A AND 4B RAMPS ARE NOT SHOWN.
- REFER TO SDD 8D5-g FOR ADDITIONAL RADIAL PLATE REQUIREMENTS.
- FIELD CUTS AT INTERMEDIATE JOINTS WITHIN THE RADIAL DETECTABLE WARNING FILED ARE PROHIBITED.
- DETERMINE FINAL RADIAL WARNING FIELD CONFIGURATION AND ITS INDIVIDUAL PLATE LOCATIONS. PERFORM PRE-LAYOUT PRIOR TO PLACEMENT IN PLASTIC CONCRETE. FOLLOW MANUFACTURER'S PRODUCT LIST AND INSTALLATION RECOMMENDATIONS.
- 2 GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
 - 3 AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
 - 4 ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
 - 6 PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LANDING SIZE IS 5 FEET BY 5 FEET.
 - 8 PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
 - 14 CONSULT ENGINEER IF GRADE BREAK LOCATION (END OF LANDING DIMENSION "XR") REQUIRES FIELD ADJUSTMENT WHEN ESTABLISHING FINAL RADIAL DETECTABLE WARNING FIELD LOCATION.
 - 15 FIELD SAW CUTS ALONG RADIAL DETECTABLE WARNING PLATES WILL BE NECESSARY TO MATCH EACH CURB RAMP EDGE. AVOID CUTTING THROUGH DOMES WHENEVER POSSIBLE. MAKE FIELD CUTS TRUE TO LINE AND WITHIN 1/8" DEVIATION. SMOOTH EDGES OF FIELD CUT PLATES.
 - 16 USE 1' X 2" RECTANGULAR END PLATE AT END OF TYPE 4A1 RAMP AND PROVIDE MINIMUM 2' - 0" DETECTABLE WARNING FIELD COVERAGE (IN DIRECTION OF PEDESTRIAN TRAVEL) ALONG THE ENTIRE CURB RAMP WIDTH.
 - 17 A MAXIMUM 3 INCH CONCRETE BORDER WITH IS ALLOWABLE IN FROM OF RADIAL DETECTABLE WARNING FIELD FOR CONSTRUCTABILITY PURPOSES. CONCRETE BORDER WIDTH MAY VARY UP TO 1 INCH.

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-d IS EXCEEDED




**PLAN VIEW
CURB RAMP TYPE 4B1
(GRADE BREAK DISTANCE GREATER THAN 5 FEET)**



SECTION B - B FOR TYPE 4B1


**** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED

*** MAXIMUM 8.33%




DETAIL B

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-b IS EXCEEDED




**PLAN VIEW
CURB RAMP TYPE 2
(GRADE BREAK DISTANCE GREATER THAN 5 FEET)
(ON LINE WITH SIDEWALK)**

NOTE: SECOND TYPE 2 RAMP NOT SHOWN



SECTION C - C FOR TYPE 2

- * MAXIMUM 2% SLOPE IN ALL DIRECTIONS IN FRONT OF GRADE BREAK
- ** WIDTH SHOWN ELSEWHERE IN THE PLANS
- *** MAXIMUM 8.33%




DETAIL C

**CURB RAMPS
RADIAL DETECTABLE WARNING
FIELD APPLICATIONS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

	MIN.	MAX.
A	1.6"	2.4"
B	0.65"	1.5"
C	*	*
D	0.9"	1.4"

* THE C DIMENSION IS 50% TO 65% OF THE D DIMENSION.




PLAN VIEW




ELEVATION VIEW

**TRUNCATED DOMES
DETECTABLE WARNING PATTERN DETAIL**




RECTANGULAR
PLATES




RADIAL
PLATES

PLAN VIEW
DETECTABLE WARNING FIELDS (TYPICAL)



PLAN VIEW
RADIAL DETECTABLE
WARNING FIELD ATTRIBUTES



PLAN VIEW
RADIAL WEDGE PLATE
CONNECTION DETAIL

GENERAL NOTES

DETECTABLE WARNING FIELDS THAT ARE INSTALLED AT A CURB RAMP SHALL BE FROM THE SAME MANUFACTURER.

PLACE ALL DETECTABLE WARNING FIELD SYSTEMS IN ACCORDANCE TO THE MANUFACTURER'S RECOMMENDATION.

FIELD CUTS AT INTERMEDIATE JOINTS WITHIN THE RADIAL DETECTABLE WARNING FIELD ARE PROHIBITED.

DETERMINE FINAL RADIAL WARNING FIELD CONFIGURATION AND ITS INDIVIDUAL PLATE LOCATIONS. PERFORM PRE-LAYOUT PRIOR TO PLACEMENT IN PLASTIC CONCRETE. FOLLOW MANUFACTURER'S PRODUCT LIST AND INSTALLATION RECOMMENDATIONS.

FOR RADIAL DETECTABLE WARNING FIELD APPLICATIONS WHERE STANDARD RADIAL PLATES ARE NOT AVAILABLE AT AN INTERSECTION CURB RADIUS, A COMBINATION OF SQUARE OR RECTANGULAR PLATES AND RADIAL PLATES MAY BE USED TO FORM RADIAL CONFIGURATION. RADIAL WEDGE PLATES IN COMBINATION WITH SQUARE PLATES ARE ALSO ACCEPTABLE. FOLLOW MANUFACTURER'S RECOMMENDATIONS.

REFER TO CONTRACT AND STANDARD SPECIFICATIONS FOR FIELD CUTTING REQUIREMENTS.


DO NOT EMBED IN CONCRETE ANY FIELD-CUT PLATES WITH CUT EDGES SHORTER THAN 6 INCHES. CONSULT WITH MANUFACTURER FOR RE-DRILLING AND ANCHORING REQUIREMENTS OF FIELD-CUT PLATES.

15 FIELD SAW CUTS ALONG RADIAL DETECTABLE WARNING PLATES WILL BE NECESSARY TO MATCH EACH CURB RAMP EDGE. AVOID CUTTING THROUGH DOMES WHENEVER POSSIBLE. MAKE FIELD CUTS TRUE TO LINE AND WITHIN 1/8" DEVIATION. SMOOTH EDGES OF FIELD CUT PLATES.


**CURB RAMPS
RECTANGULAR AND RADIAL
DETECTABLE WARNING PLATES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2019 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL

NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS




SILT FENCE

* NOTE: 8'-0" POST SPACING ALLOWED IF A WOVEN GEOTEXTILE FABRIC IS USED.



JOINING TWO LENGTHS OF SILT FENCE ⑤





SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
4-29-05 /S/ Beth Canestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



INLET PROTECTION, TYPE A


GENERAL NOTES

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED.


WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- ① FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- ② FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- ③ FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.



**INLET PROTECTION, TYPE B
(WITHOUT CURB BOX)**

(CAN BE INSTALLED IN ANY INLET WITHOUT A CURB BOX)



INLET PROTECTION, TYPE C (WITH CURB BOX)

INSTALLATION NOTES

TYPE B & C

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D

DO NOT INSTALL INLET PROTECTION TYPE D IN INLETS SHALLOWER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.

THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3" CLEARANCE. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.



INLET PROTECTION, TYPE D

(CAN BE INSTALLED IN ANY INLET TYPE WITH OR WITHOUT A CURB BOX AS PER NOTE ②)


INLET PROTECTION TYPE A, B, C, AND D	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 10/16/02 DATE	/S/ Beth Conestra CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA	

METAL APRON ENDWALLS											
PIPE DIA. (IN.)	MIN. THICK. (Inches)		DIMENSIONS (Inches)							APPROX. SLOPE	BODY
	STEEL	ALUM.	A (±1")	B (MAX.)	H (±1")	L (±1 1/2")	L1	L2	W (±2")		
12	.064	.060	6	6	6	21	12	17 1/2	24	2 1/2 to 1	1 Pc.
15	.064	.060	7	8	6	26	14	21 3/4	30	2 1/2 to 1	1 Pc.
18	.064	.060	8	10	6	31	15	28 1/4	36	2 1/2 to 1	1 Pc.
21	.064	.060	9	12	6	36	18	29 5/8	42	2 1/2 to 1	1 Pc.
24	.064	.075	10	13	6	41	18	37 1/4	48	2 1/2 to 1	1 Pc.
30	.079	.075	12	16	8	51	18	52 1/4	60	2 1/2 to 1	1 Pc.
36	.079	.105	14	19	9	60	24	59 3/4	72	2 1/2 to 1	2 Pc.
42	.109	.105	16	22	11	69	24	75 5/8	84	2 1/2 to 1	2 Pc.
48	.109	.105	18	27	12	78	24	81	90	2 1/4 to 1	3 Pc.
54	.109	.105	18	30	12	84	30	85 1/2	102	2 1/4 to 1	3 Pc.
60	.109x	.105x	18	33	12	87	—	—	114	2 to 1	3 Pc.
66	.109x	.105x	18	36	12	87	—	—	120	2 to 1	3 Pc.
72	.109x	.105x	18	39	12	87	—	—	126	2 to 1	3 Pc.
78	.109x	.105x	18	42	12	87	—	—	132	1 1/2 to 1	3 Pc.
84	.109x	.105x	18	45	12	87	—	—	138	1 1/2 to 1	3 Pc.
90	.109x	.105x	18	37	12	87	—	—	144	1 1/2 to 1	3 Pc.
96	.109x	.105x	18	35	12	87	—	—	150	1 1/2 to 1	3 Pc.


* EXCEPT CENTER PANEL SEE GENERAL NOTES

REINFORCED CONCRETE APRON ENDWALLS									
PIPE DIA. (IN.)	DIMENSIONS (Inches)							APPROX. SLOPE	
	T	A	B	C	D	E	G		
12	2	4	24	48 1/8	72 1/8	24	2	3 to 1	
15	2 1/4	6	27	46	73	30	2 1/4	3 to 1	
18	2 1/2	9	27	46	73	36	2 1/2	3 to 1	
21	2 3/4	9	36	37 1/2	73 1/2	42	2 3/4	3 to 1	
24	3	9 1/2	43 1/2	30	73 1/2	48	3	3 to 1	
27	3 1/4	10 1/2	49 1/2	24	73 1/2	54	3 1/4	3 to 1	
30	3 1/2	12	54	19 3/4	73 1/2	60	3 1/2	3 to 1	
36	4	15	63	34 3/4	97 3/4	72	4	3 to 1	
42	4 1/2	21	63	35	98	78	4 1/2	3 to 1	
48	5	24	72	26	98	84	5	3 to 1	
54	5 1/2	27	65	33 1/4-35	98 1/4-100	90	5 1/2	2 1/2 to 1	
60	6	30-35	60	39	99	96	5	2 to 1	
66	6 1/2	24-30	72-78	21-27	99	102	5 1/2	2 to 1	
72	7	24-36	78	21	99	108	6	2 to 1	
78	7 1/2	24-36	78	21	99	114	6 1/2	2 to 1	
84	8	36	90 1/2	21	111 1/2	120	6 1/2	1 1/2 to 1	
90	8 1/2	41	87 1/2	24	111 1/2	132	6 1/2	1 1/2 to 1	


* MINIMUM
** MAXIMUM




END CORNER PLATES MAY BE FASTENED TO APRON PROPER BY BOLTS, RIVETS, OR RESISTANCE SPOT WELDS WHICH WILL HOLD THE SURFACES TIGHTLY TOGETHER



SIDE ELEVATION
METAL ENDWALLS




END VIEW




LONGITUDINAL SECTION
CONCRETE ENDWALLS


1" WIDE, 12 GA. (0.109" THICK) GALVANIZED STRAP WITH STANDARD 6" X 1/2" BAND BOLT AND NUT




ALTERNATE FOR TYPE 1 CONNECTION
END SECTION CONNECTOR STRAP




TYPE 1
FOR 12" THRU 24" CORR. PIPE



TYPE 2
FOR 30" THRU 96" CORR. PIPE



TYPE 3
FOR 42" THRU 96" CORR. PIPE



ALTERNATE FOR:
ALL SIZES CORRUGATED CIRCULAR PIPE


NOTE: DIMPLED BAND FITS OVER OUTSIDE OF ENDWALL, AND CORRUGATED BAND FITS INSIDE ENDWALL. DIMPLED BAND MAY BE USED WITH HELICALLY CORRUGATED PIPE.

FOR CIRCUMFERENTIALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2, 3 OR 5 AS APPLICABLE.

FOR HELICALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2 OR 5.

FOR HELICALLY CORRUGATED PIPES WITH TWO CIRCUMFERENTIAL CORRUGATIONS AT EACH END USE ENDWALL CONNECTION DETAILS 1, 2 OR 3.

CONNECTION DETAILS



SECTION A-A

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT ENDWALLS MAY NOT BE USED WITH GALVANIZED STEEL OR ALUMINUM CULVERT PIPE OR VICE VERSA. GALVANIZED STEEL OR ALUMINUM ENDWALLS SHALL NORMALLY BE INSTALLED ON CULVERT PIPE OF THE SAME METAL.

ALL THREE PIECE STEEL APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.109" SIDES AND 0.138" CENTER PANELS. ALL THREE PIECE ALUMINUM APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.105" SIDES AND 0.134" CENTER PANELS. THE WIDTH OF CENTER PANELS SHALL BE GREATER THAN 20 PERCENT OF THE PIPE PERIMETER.

LAP SEAMS SHALL BE TIGHTLY JOINED BY GALVANIZED RIVETS OR BOLTS FOR STEEL UNITS AND ALUMINUM RIVETS AND BOLTS FOR ALUMINUM UNITS. FOR THE 60" THROUGH 96" DIAMETER APRON ENDWALL SIZES, THE REINFORCED EDGES AND CENTER PANEL SEAMS SHALL BE FURTHER REINFORCED WITH GALVANIZED STEEL OR ALUMINUM STIFFENER ANGLES. THE ANGLES SHALL BE ATTACHED BY GALVANIZED NUTS AND BOLTS FOR STEEL UNITS AND ALUMINUM NUTS AND BOLTS FOR ALUMINUM UNITS.


WHERE TWO OR MORE PIPES WITH APRON ENDWALLS ARE LAID ADJACENT TO EACH OTHER, THEY SHALL BE SEPARATED BY A DISTANCE SUFFICIENT TO PROVIDE A MINIMUM CLEARANCE OF 6 INCHES BETWEEN APRON ENDWALLS.

① FOR PIPE SIZES UP TO 60" DIAMETER, A 180° ROLLED EDGE MAY BE USED INSTEAD OF STEEL ROD REINFORCEMENT. SEE SECTION A-A.

APRON ENDWALLS FOR
CULVERT PIPE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
11/30/94 /S/ Rory L. Rhinesmith
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



EYE BOLTS AND TIE ROD

EYE BOLT AND TIE ROD ASSEMBLY (ALTERNATE NO. 1)



(CAST IN PLACE THREADED INSERT)
LONGITUDINAL SECTIONS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT AND STORM SEWER PIPE SHALL BE TIED TOGETHER IN THE MANNER ILLUSTRATED BY THIS DETAIL AT LOCATIONS DESIGNATED IN THE STANDARD SPECIFICATIONS AND THE PLAN. THE CONTRACTOR MAY USE EITHER ALTERNATE 1, 2 OR 3 FOR DRAINAGE STRUCTURES. ONLY ALTERNATE 1 AND 3 MAY BE USED FOR CATTLE PASSES, UNLESS OTHERWISE STATED IN THE CONTRACT. THE MATERIALS, FABRICATION AND WORK NECESSARY TO TIE THE PIPE BY THIS DETAIL WILL BE CONSIDERED INCIDENTAL TO THE PIPE AND APRON ENDWALLS IF REQUIRED.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR JOINT TIES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.

JOINT TIES TO BE HOT-DIP GALVANIZED PER ASTM A 153.


- ① CENTER LINE OF TONGUE AND GROOVE OR BELL AND SPIGOT JOINTS.
- ② THE INSIDE OF THE THREADED INSERTS SHALL BE CLEAN TO ALLOW THE INSERTION OF THREADED EYE BOLTS.
- ③ HOLES SHALL BE CAST-IN-PLACE OR DRILLED PER THE APPLICABLE DETAIL, AND EQUAL DISTANCE FROM THE CENTERLINE OF THE JOINT.
- ④ BOLT PROJECTION INSIDE OF PIPE SHALL NOT EXCEED 2 INCHES.
- ⑤ OPENING TO BE ROD DIAMETER PLUS 1 INCH.
- ⑥ LENGTH ADEQUATE TO EXTEND TO WITHIN 1/2 INCH OF THE INNER SURFACE OF THE PIPE.
- ⑦ EYE BOLT LENGTH DETERMINED BY WALL THICKNESS, BELL THICKNESS AND BOLT PROJECTION INSIDE PIPE.



EYE BOLT AND TIE ROD

EYE BOLT ⑦

NOTE: TWO EYE BOLTS MAY BE USED WITH A 30\"/>




LONGITUDINAL SECTION
(JOINT TIES FOR 18\"/>

EYE BOLT AND TIE ROD ASSEMBLY (ALTERNATE NO. 2)


ADJUSTABLE TIE ROD TABLE

PIPE DIAMETER	TIE ROD DIAMETER	D	L ₁	N
12 - 60	5/8	5/8	5	1/2
66 - 84	3/4	3/4	5	1/2
90 - 144	1	1	7	1 7/16


DIMENSIONS SHOWN ARE IN INCHES



RIGHT AND LEFT THREADS SLEEVE NUTS




LONGITUDINAL SECTION
ADJUSTABLE TIE ROD (ALTERNATE NO. 3)



PLACEMENT OF (2) CAST-IN-PLACE INSERTS OR HOLES DURING FABRICATION FOR PIPE SECTIONS REQUIRING TIE RODS

TRANSVERSE SECTION




SECTION A - A
CONCRETE COLLAR DETAIL

JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2021 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER




TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.



SECTION A-A



ALTERNATE LUG

6

6

FOR MULTI-UNIT STRUCTURES
LINE 3 ABOVE SHALL READ

B = BRIDGE
C = CULVERT
R = RETAINING WALL


COUNTY NO. BRIDGE NO.

UNIT NO. FOR MULTIPLE
UNIT BRIDGE

B-40-400-1A

**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)

NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE 3/26/10	/S/ Scot Becker CHIEF STRUCTURAL DEVELOPMENT ENGINEER
FHWA	

S.D.D. 12 A 3-10

S.D.D. 12 A 3-10



**PLAN VIEW
CONCRETE PAVEMENT SHOULDER**

**PAVEMENT DEPTH, DOWEL BAR SIZE
AND JOINT SPACING TABLE**

PAVEMENT DEPTH (D)	DOWEL BAR DIAMETER ***	CONTRACTION JOINT SPACING
6", 6 1/2"	NONE	12"
7", 7 1/2"	1"	14"
8" & ABOVE	1 1/4"	15"

*** FOR DOWELED CONCRETE SHOULDERS WITH TRAPEZOIDAL CROSS SECTIONS, CHOSE THE APPROPRIATE DOWEL BAR DIAMETER BASED ON THE SMALLER PAVEMENT DEPTH (LIKELY THE OUTSIDE EDGE OF THE SHOULDER). IF USING BASKETS, USE BASKETS FRO THE AVERAGE THICKNESS OF THE CROSS SECTION.

TIE BAR TABLE

PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
<10 1/2"	NO. 4	30"	36"
>10 1/2"	NO. 5	36"	36"
	NO. 4 *	30"	24" **

* SUBSTITUTE BENT BATS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES).

** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.


GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

TRANSVERSE JOINT DETAILS ARE SHOWN ELSEWHERE IN THE PLAN.

FINISH THE SHOULDER PAVEMENT CONFORMING TO SUBSECTION 415.3.8 OF THE STANDARD SPECIFICATIONS.

TIE BARS SHALL CONFORM TO SUBSECTION 505.2.4 OF THE STANDARD SPECIFICATIONS.




**SECTION A - A
LONGITUDINAL CONSTRUCTION JOINT**

**CONCRETE PAVEMENT
SHOULDERS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2022 /S/ Peter Kemp
DATE PAVEMENT SUPERVISOR

FHWA




PLAN VIEW SHOULDER WITH GROOVES
 PLAN VIEW (SINGLE GROOVE)

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

DO NOT MILL SHOULDER GROOVES THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



ISOMETRIC




TYPE 1
 2 - LANE SHOULDER RUMBLE STRIP



SECTION A - A

**2-LANE RURAL SHOULDER
 RUMBLE STRIP, MILLING**

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION




PLACEMENT DETAIL FOR TYPE 2 MILLED RUMBLE STRIP

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

DO NOT MILL SHOULDER GROOVES THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



ISOMETRIC




TYPE 2
2 - LANE SHOULDER RUMBLE STRIP




SECTION A - A

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SHOULDER GROOVES AT MISCELLANEOUS CROSSINGS



SHOULDER GROOVES AT RIGHT TURN LANE




SHOULDER GROOVES AT BRIDGES



* GREATER OF 100' OR APPROACH TAPER LENGTH

SHOULDER GROOVES AT INTERSECTIONS WITH APPROACH TAPER




SHOULDER GROOVES AT DRIVEWAYS^①

GENERAL NOTES


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



SHOULDER GROOVES AT RAILROADS



SHOULDER GROOVES AT PASSING AND CLIMBING LANES



SHOULDER GROOVES AT BYPASS LANES

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
ENGINEER

FHWA

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

DO NOT MILL CENTERLINE GROOVES THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.


INSTALL PAVEMENT MARKING AFTER THE GROOVES ARE INSTALLED.

SEE SIGNING PLAN FOR SIGN REQUIREMENTS THAT MAY BE NEEDED.


- ① CENTERLINE GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



**PLAN VIEW
SHOULDER WITH GROOVES**




**PLAN VIEW
(SINGLE GROOVE)**




ISOMETRIC


PLACEMENT DETAIL FOR TYPE 1 MILLED RUMBLE STRIP




CENTERLINE GROOVES ON TWO-WAY ROADWAYS



**SECTION B - B
SUPERELEVATED ROADWAY**




SECTION A - A




**SECTION B - B
CROWNED ROADWAY**

**2-LANE RURAL
CENTER LINE RUMBLE STRIP,
MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



CENTERLINE GROOVES AT INTERSECTIONS




**CENTERLINE GROOVES AT INTERSECTIONS
(WITH LEFT TURN LANES)**




CENTERLINE GROOVES AT DRIVEWAYS^①

GENERAL NOTES

- ① CENTERLINE GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



CENTERLINE GROOVES AT BRIDGES




CENTERLINE GROOVES AT RAILROADS


6

6


2-LANE RURAL CENTERLINE RUMBLE STRIP, MILLING	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 7/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT ENGINEER
<small>FHWA</small>	



**SKewed Approach
(Pavement more than two lanes)**




**SKews > 20°
(Pavement width ≤ 30')**




**SKews ≤ 20°
(Pavement width ≤ 30')**
Approach Slab and Adjacent Pavement


- * (RS) = REINFORCED CONCRETE SLAB
- * (PS) = PAVED CONCRETE SHOULDER OR CONCRETE DRAINAGE SLAB
- * (NRS) = NON - REINFORCED CONCRETE SLAB
- *** STANDARD DOWEL BAR DIAMETER (SEE SDD 13C11 AND SDD 13C13)



**SECTION A - A
REINFORCEMENT POSITIONING DETAIL**




**SECTION B - B
BEND DETAIL
BOTTOM REINFORCEMENT**




**SECTION C - C
TRANSITION DETAIL
Approach Slab to Adjacent Pavement**

GENERAL NOTES

- THE CONTRACTOR MAY SPLICE NO. 6 BARS IN THE APPROACH SLAB FOR SKEWED STRUCTURES ONLY. STAGGER SPLICES WITH A MAXIMUM OF ONE SPLICE PER BAR. THE LENGTH OF LAP IS 20 INCHES.
- TACK WELD DOWEL BARS TO THE BASKETS ON ALTERNATE ENDS.
- ① THE CONTRACTOR MAY USE NO. 4 BARS SPACED AT 2' - 0" C - C IN BOTH THE LONGITUDINAL AND TRANSVERSE DIRECTIONS FOR TOP REINFORCEMENT AS AN ALTERNATIVE TO THE WELDED WIRE FABRIC.
 - ② THE CONTRACTOR MAY OMIT THE BARS BETWEEN REINFORCED SLABS WHERE SLAB REINFORCEMENT BARS EXTEND ACROSS THE CENTERLINE OR REFERENCE LINE.
 - ③ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING AN HMA PAVEMENT.
 - ④ USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
 - ⑤ PLACE EXPANSION CAP ON THE END OF THE DOWEL THAT IS NOT TACK WELDED TO THE BASKET. DO NOT FORCE DOWEL BAR PAST THE DOWEL STOP.
 - ⑥ EXTEND EXPANSION JOINT THROUGH ANY ADJACENT TIED CONCRETE.
 - (A) STANDARD CONTRACTION JOINT NORMAL TO \mathcal{C} OR \mathcal{R} .
 - (B) STANDARD LONGITUDINAL JOINT WITH TIE BARS.
 - (C) 1 1/2" EXPANSION JOINT WITH DOWEL BARS NORMAL TO \mathcal{C} OR \mathcal{R} .



**SECTION D - D
CONTRACTION JOINT**




EXPANSION JOINT DETAIL

**CONCRETE PAVEMENT
APPROACH SLAB**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Peter Kemp, P.E.
DATE DATE PAVEMENT SUPERVISOR

FHWA



CONSTRUCTION JOINT




SAWED JOINT

GENERAL NOTES

CREATE A LONGITUDINAL JOINT FOR PAVEMENT WIDTHS GREATER THAN 15 FEET.


CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.

- ① ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.
- ② PAVEMENT THAT WAS IN PLACE PRIOR TO THE CONTRACT.




PLAN VIEW


NO. 6 TIE BARS SPACED 30" C-C, INSTALLED PERPENDICULAR TO THE LONGITUDINAL JOINT. ①




**SECTION A-A
LONGITUDINAL CONSTRUCTION JOINT
TIE BARS ANCHORED
INTO EXISTING PAVEMENT**



DETAIL "A"



DETAIL "B"




DETAIL "C"

TIE BAR TABLE

PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4 *	30"	24" **

* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)

** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.




**PLAN VIEW
SHOWING LOCATION OF TIE BARS**


**CONCRETE PAVEMENT
LONGITUDINAL JOINTS AND TIES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR
FHWA




**PLAN VIEW
DOUBLE LANE REPAIR**



**PLAN VIEW
SINGLE LANE REPAIR**

FULL DEPTH CONCRETE PAVEMENT REMOVAL



**SECTION B - B
CONCRETE REMOVAL**


GENERAL NOTES

SAW CUT, DRILL, AND LIFT OUT EXISTING CONCRETE PAVEMENT WITHIN THE BOUNDARIES OF CONCRETE REPAIR AREAS. THE CONTRACTOR MAY MAKE ADDITIONAL SAW CUTS INSIDE THE REPAIR LIMITS TO REDUCE WEIGHT AND SIZE OF CONCRETE PIECES.


PROVIDE A 6 FOOT MINIMUM DISTANCE FROM BOUNDARIES OF CONCRETE REPAIR AREA TO ADJACENT TRANSVERSE JOINT OR CRACK.

THE LENGTH OF THE REPAIRS MAY VARY FROM THE DIMENSIONS SHOWN IF THE EXISTING CONCRETE PAVEMENT IS NON-DOWELED AND THE PAVEMENT IS TO BE OVERLAID AFTER REPAIRING.

① DOWEL BARS MAY NOT BE PRESENT.



PLAN VIEW




SECTION A - A


HMA PATCH REMOVAL

BASE PATCHING CONCRETE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




TRANSVERSE JOINTS



LONGITUDINAL JOINTS



**SECTION C - C
SAWED LONGITUDINAL JOINT**



**SECTION F - F
CONTRACTION JOINT**

GENERAL NOTES


INSTALL DOWEL BARS PARALLEL TO THE PAVEMENT CENTERLINE AND PAVEMENT SURFACE.

CONCRETE BASE PATCHES OF EXISTING NON-DOWELED CONCRETE PAVEMENTS DO NOT NEED TO BE DOWELED.


ANCHOR DOWEL BARS AND TIE BARS INTO DRILLED HOLES WITH AN EPOXY.

PROVIDE A MINIMUM DISTANCE OF 15 INCHES FROM ALL TRANSVERSE JOINTS OR EDGES OF REPLACEMENT TO THE CENTER OF THE TIE BAR NEAREST THAT JOINT OR EDGE.


- ① APPLY A THIN UNIFORM COATING OF SURFACE TREATMENT TO THE FREE END OF DOWEL BARS TO PREVENT BONDING.



SECTION D - D



**SECTION E - E
SPACING OF DOWEL BARS
ANCHORED INTO EXISTING PAVEMENT**




**PLAN VIEW
MULTILANE CONCRETE BASE PATCH
15' MAXIMUM LENGTH**

**PLAN VIEW
MULTILANE CONCRETE BASE PATCH
GREATER THAN 15' IN LENGTH**

BASE PATCHING CONCRETE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SECTION G - G
TIE BARS ANCHORED INTO EXISTING PAVEMENT

GENERAL NOTES

- ① WITH THE APPROVAL OF THE ENGINEER, FOR SINGLE LANE PAVEMENT REPLACEMENTS LESS THAN 30 FEET IN LENGTH, THE CONTRACTOR MAY INSTALL DRILLED TIE BARS ON 6:1 SKEW HORIZONTALLY, DIRECTION OF SKEW ALTERNATING WITH EACH SUCCESSIVE BAR. DRIVE SKEWED TIE BARS TO A DEPTH OF 6 INCHES IN A HOLE OF SUCH A DIAMETER AS TO PROVIDE A TIGHT DRIVEN FIT.
- ② USE AN ENGINEER APPROVED BOND BREAKER (E.G. RELEASE AGENT, CURING COMPOUND) FOR SINGLE LANE REPAIRS UP TO 15 FEET IN LENGTH.
- ③ ANCHOR TIE BARS INTO DRILLED HOES WITH AN EPOXY.



PLAN VIEW
SINGLE LANE CONCRETE BASE PATCH
15' MAXIMUM LENGTH




PLAN VIEW
SINGLE LANE CONCRETE BASE PATCH
GREATER THAN 15' LENGTH

BASE PATCHING CONCRETE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR


FHWA



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY $0.1"$ AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO $2"$ FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)


6

6


SDD 13C19 - 03

SDD 13C19 - 03

HMA LONGITUDINAL JOINTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2020 DATE	/S/ Steven Hefel HMA PAVEMENT ENGINEER
FHWA	




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
MID-SPAN BEAM SPLICE**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 3/8" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAIL



**FRONT VIEW
QUARTER POST SPACING (QS)**



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

SDD 14B42 - 07b

SDD 14B42 - 07b




DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.


NOTE:

1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 3/16".
2. IF THE BOLT EXTENDS MORE THAN 1/4" FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"




ALTERNATE BOLT HEAD



**PLAN VIEW
BEAM LAPPING DETAIL**




**POST DRIVING FOR CONTINUOUS
UNDERGROUND OBSTRUCTION**




DETAIL FOR 36" BLOCKOUT DEPTH

NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.
DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.



**POST BOLT, SPLICE BOLT
AND RECESS NUT**




**ALTERNATE WOOD
BLOCKOUT DETAIL**


⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL)

- 400 MAX SPAN 12' - 6"
- 401 2' MIN.
- 402 MGS GUARDRAIL 3
- 403 NESTING BEAM GUARD
- 404 ASYMMETRIC TRANSITION
- 405 SOIL WELL DRAINED AND COMPACTED
- 406 SEE OTHER DRAWINGS IN THIS SDD
- 407 SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
- 408 SEE SDD 14B44
- 409 SEE SDD 14B45
- 410 SEE SDD 14B47
- 411 MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
 - (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
 - (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
 - (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
 - (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.
- DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.

SEE SDD 14B42 FOR MORE INFORMATION.


* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.

DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.


SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.

THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.


CLEAR ZONE LIMITS, EITHER AS SHOWN ELSEWHERE IN THE PLANS OR, IF NOT SHOWN ELSEWHERE IN THE PLANS, 15 FEET BEYOND THE HINGE POINT LINE




PLAN




ELEVATION




DETAIL "A"




**SECTION C - C
TYPICAL AT POST NOS. 3 - 9**



**SECTION B - B
TYPICAL AT POST NO. 2***



**SECTION A - A
TYPICAL AT POST NO. 1***



DETAIL "B"

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

SDD 14B44 - 04a


SDD 14B44 - 04a

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2




GENERIC GROUND STRUT ⑨ ⑤




GENERIC ANCHOR CABLE BOX ⑨ ⑤




BEARING PLATE ⑥ ⑤




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9



UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)



WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2


6




W5 - 59
REFLECTIVE SHEETING DETAIL ^(E)

TYPE H
YELLOW REFLECTIVE
SHEETING 3" X 9".
SEE STANDARD
SPECIFICATION 637.


E.A.T. MARKER
POST (YELLOW)



FRONT VIEW SIDE VIEW
E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW



TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

6

SDD 14B44 - 04c


SDD 14B44 - 04c

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR

FHWA



TWO WAY TRAFFIC



ONE WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES


IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY

- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 14 B 45-5a


S.D.D. 14 B 45-5a

GENERAL NOTES


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ④ TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42



**SECTION A-A
POSTS 1-5**



**SECTION B-B
POST 6**



**SECTION C-C
POSTS 7-11**







PLATE WASHER DETAIL



SPLICE DETAIL




**THRIE BEAM
TERMINAL CONNECTOR**




**SECTION THRU THRIE
BEAM RAIL ELEMENT**

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3\"/>




12'-6\"/>




ALTERNATE WOOD BLOCKOUT DETAIL




STEEL POSTS 1-5




STEEL POSTS 6-17




TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 1-5**



TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 6-17**

GENERAL NOTES

- STEEL POSTS ARE W6X9 OR W6X8.5.
- BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

S.D.D. 14 B 45-5c



S.D.D. 14 B 45-5c




FRONT VIEW
THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS

GENERAL NOTES


- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
 - (4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
 - (6) DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - (7) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - (8) THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".



SECTION F-F



FRONT VIEW
W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



DRILL HOLE LOCATION

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

6

6


S.D.D. 14 B 45-5d

S.D.D. 14 B 45-5d

GENERAL NOTES


THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PAPAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



SECTION G-G



FRONT VIEW


THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

ONE WAY
TRAFFIC



FRONT VIEW

**W BEAM CONNECTION TO
PARAPETS WITH SLOPED ENDS**


(USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)

WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.


⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(4 REQ'D.)

GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



**DRILL HOLE LOCATION AND PATTERN
FOR THRIE BEAM CONNECTION**




FRONT VIEW

**THRIE BEAM CONNECTION TO BRIDGE
PARAPETS WITH SLOPED ENDS**

WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.

⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(5 REQ'D.)




SECTION I-I


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



BACK-UP PLATE DETAIL




SECTION J-J




BACK-UP PLATE MOUNTING ONTO BRIDGE RAILING

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1'$.
- ⑥ DRILLING HOLES THROUGH THE PAPER, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




**FRONT VIEW
THRIE BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**THRIE BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

6


6

S.D.D. 14 B 45-59


S.D.D. 14 B 45-59

GENERAL NOTES


(4) TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".



FRONT VIEW




**PLAN VIEW
BACK-UP PLATE DETAIL, TYPE "M"**




FRONT VIEW

**ANCHOR
PLATE DETAIL,
TYPE "M"**




SECTION M-M




SECTION L-L

FRONT VIEW

ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW



PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

6

6

S.D.D. 14 B 45-5h



S.D.D. 14 B 45-5h

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE	/s/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

GENERAL NOTES

- COVER PLATE PANELS ARE 3/16" THICK.
- ALL STIFFENERS ARE 1/4" THICK.
- CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.
- FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.
- ALL HOLE DIAMETERS SHALL BE 1".
- FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

- (10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND 3/16" FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.
- (11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
3/16" FILLET WELD BY 1" LONG SPACED AT 2".



WELDING INSTRUCTION
(VIEWED FROM BACK SIDE OF PLATE)




PLATE AND STIFFENER IDENTIFICATION
(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 3/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 7/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 1/16" x 10 3/8" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 3/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 1/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 3/16" x 6" x 3 5/8" x 5 1/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 3/32"	1/4"
S10	1		1 7/8" x 9 7/8" x 3 5/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 3/16"	1/4"

SINGLE SLOPE CONNECTION PLATE

**MIDWEST GUARDRAIL SYSTEM
THREE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018
DATE

/S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR


FHWA

GENERAL NOTES


CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.



⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTION PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER



SECTION N-N




SINGLE SLOPE CONNECTION PLATE PLACEMENT


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



**ELEVATION OF DETAIL AT NY3 END POST
THRIE BEAM RAIL ATTACHMENT**



**ELEVATION OF DETAIL AT NY4 END POST
THRIE BEAM RAIL ATTACHMENT**

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS ± 1".
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND 1/2-INCH BEYOND NUT.

6

6


S.D.D. 14 B 45-5k

S.D.D. 14 B 45-5k

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.

FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION


APPROVED
 DATE 7/2018 /S/ Rodney Taylor
 ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR
 FHWA




PLAN VIEW
DIVIDED HIGHWAY



PLAN VIEW
UNDIVIDED HIGHWAY




DETAIL A
(TYPICAL)




GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.



PLAN VIEW
CONCRETE MASONRY ENDWALLS FOR
CULVERT PIPE AND PIPE ARCH

FLEXIBLE MARKER POST LOCATION



CROSS SECTION
FLEXIBLE MARKER POST

**FLEXIBLE MARKER POST
FOR CULVERT END**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 15 A 3-2a


S.D.D. 15 A 3-2a




FRONT VIEW SIDE VIEW
ALTERNATE 1




FRONT VIEW SIDE VIEW
ALTERNATE 2




FRONT VIEW SIDE VIEW
ALTERNATE 3




DETAIL B




DETAIL C




SECTION A-A




SECTION B-B




SECTION C-C



FRONT VIEW SIDE VIEW
ALTERNATE 1




FRONT VIEW SIDE VIEW
ALTERNATE 2



FRONT VIEW SIDE VIEW
ALTERNATE 3


FLEXIBLE MARKER POST ANCHORS

FLEXIBLE MARKER POST FOR CULVERT END	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 10/1/2012 DATE	/S/ Travis Feltes STATE TRAFFIC ENGINEER OF DESIGN
FHWA	




**DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)



**DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)



**DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR**

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)
- M4 - 8
- M3 - X
- M1 - 4 OR M1 - 6 OR M1 - 5A
- M05 - 1 OR M06 - 1

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750


SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦

**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE DATE WORK ZONE ENGINEER

FHWA



**DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW**



**DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW**

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:

- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

**BARRICADES AND SIGNS
FOR
VARIOUS CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.


SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.


- * OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS
- ** PLACE AN ADDITIONAL W20-1A "ROAD WORK AHEAD" SIGN IF WORK AREA WITHIN THE PROJECT IS SEPARATED BY MORE THAN 2 MILES FROM PREVIOUS WORK AREA.

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC
-  WORK AREA



TYPICAL SIDE ROAD APPROACH WARNING SIGN DETAIL



TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45MPH OR GREATER

TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 MPH OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE July 2018 /S/ Andrew Heidtke
WORK ZONE ENGINEER

FHWA

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS.


THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS, 36"X36" SIGNS MAY BE USED INSTEAD OF 48" X 48" SIGNS.

SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.


* THE THIRD W20-1 SIGN IS REQUIRED ONLY IF THERE IS AN INTERSECTION BETWEEN THE "ROAD WORK 500 FEET" SIGN AND THE WORK ZONE. ADJUST THE PLACEMENT OF THIS SIGN BASED ON INTERSECTION LOCATION AND OTHER FIELD CONDITIONS.



**TYPICAL SIDE ROAD APPROACH
WARNING SIGN DETAIL**

LEGEND

- SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC
- WORK AREA



TRAFFIC CONTROL, ADVANCE WARNING SIGNS 40MPH OR LESS

TRAFFIC CONTROL, ADVANCE WARNING SIGNS 40 MPH OR LESS TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE July 2018	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.


- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.

LEGEND

-  "T" MARKING
-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC




TWO WAY TRAFFIC



ONE WAY TRAFFIC


PERMANENT PAVEMENT MARKING



PERMANENT LONGITUDINAL PAVEMENT MARKINGS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE: May 2022 /S/ Jeannie Silver
STATEWIDE SIGNING AND MARKING ENGINEER




TEMPORARY BARRIER OFFSET FROM EDGELINE

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

LEGEND


➡ DIRECTION OF TRAFFIC



TWO WAY TRAFFIC



ONE WAY TRAFFIC



FREEWAYS AND EXPRESSWAYS

TEMPORARY PAVEMENT MARKING

TEMPORARY LONGITUDINAL PAVEMENT MARKING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
May 2022 /S/ Jeannie Silver
DATE STATEWIDE SIGNING AND MARKING
ENGINEER

FHWA

GENERAL NOTES

- ① A SET OF ARROWS IS REQUIRED EVERY 400 FEET OR NEAR INTERSECTIONS OR DRIVEWAYS WITH TURNING TRAFFIC.
- ② 8" WHITE
- ③ TURN BAY LENGTH OF LESS THAN 48' DOES NOT REQUIRE PAVEMENT ARROWS OR TEXT.


➡ DIRECTION OF TRAFFIC



TWO WAY LEFT TURN LANE




**PAVEMENT MARKING
(TURN LANES)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



TURN LANE OPTIONS

LENGTH OF TURN BAY (L) OF 0 - 47' DOES NOT REQUIRE PAVEMENT MARKING ARROWS OR WORDS



*(SEE TURN LANE OPTIONS FOR PLACEMENT OF PAVEMENT MARKING ARROWS AND WORDS)

GENERAL NOTES


- ① 8" WHITE
- ② QUANTITY AND LOCATION OF TYPE 3 ARROWS ARE THE SAME AS THE TYPE II ARROWS IN THE ADJACENT TURN LANE. FOR TURN LANES WITH A PHYSICAL SEPARATION IN THE SAME DIRECTION OF TRAVEL, THE ARROWS AND "ONLY" MARKING MAY BE ELIMINATED.

➡ DIRECTION OF TRAFFIC

L = LENGTH OF TURN BAY


PAVEMENT MARKING (TURN LANES)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




DRUM

BALLAST WIDTHS
RANGE FROM 24"-36"



42" CONE

DO NOT USE IN TAPERS
1/2 SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2022 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

LEGEND

-  SIGN ON PORTABLE OR PERMANENT SUPPORT
-  TEMPORARY PORTABLE RUMBLE STRIP ARRAY
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.

WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

FLAGGING

FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.

- ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING WORK OPERATION OR AS APPROVED BY THE ENGINEER.
- ② SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.

WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

TEMPORARY PORTABLE RUMBLE STRIPS

UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.


- ③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER

ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.

INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS.

PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.

DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.




STOP/SLOW PADDLE ON SUPPORT STAFF

SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE

SPEED LIMIT	SPACING "A"
25-30 MPH	200'
35-40 MPH	350'
45-55 MPH	500'



USE OF W03-4 SIGN IS OPTIONAL. WHEN USED, THIS SIGN SHALL BE LOCATED BETWEEN THE W20-7A AND W20-4A SIGNS, USING SPACING "A".



6

6

SDD 15C12 - 09a

SDD 15C12 - 09a

TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE May 2022 /S/ Andrew Heidtke
WORK ZONE ENGINEER

FHWA

LEGEND

- V1 LEAD VEHICLE
- V2 MARKING VEHICLE
- V3 SHADOW VEHICLE
-  TRUCK MOUNTED ATTENUATOR (TMA)
-  SIGN ON TEMPORARY SUPPORT
-  DIRECTION OF TRAFFIC
-  FLASHING ARROW PANEL (CAUTION)

GENERAL NOTES

ALL VEHICLES SHALL BE EQUIPPED WITH TWO 360 DEGREE HIGH INTENSITY YELLOW FLASHING LIGHTS OR STROBE LIGHTS AND OPERATED WITH HEADLIGHTS TURNED ON.

ALL VEHICLES SHALL BE EQUIPPED WITH REAR FACING TYPE B OR C FLASHING ARROW PANEL OPERATING IN CAUTION MODE. SIGNS PLACED ON VEHICLES MUST NOT OBSCURE THE ARROW PANEL.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE SPECIFIED.

DISTANCE BETWEEN VEHICLES MAY VARY ACCORDING TO TERRAIN, SIGHT DISTANCE, PAINT DRYING TIME, AND OTHER FACTORS. WHENEVER ADEQUATE STOPPING SIGHT DISTANCE EXISTS TO THE REAR, SHADOW VEHICLES SHOULD MAINTAIN THE MINIMUM DISTANCE FROM THE WORK VEHICLE AND PROCEED AT THE SAME SPEED AS THE WORK VEHICLE. SHADOW VEHICLES SHOULD SLOW DOWN IN ADVANCE OF VERTICAL AND HORIZONTAL CURVES THAT RESTRICT SIGHT DISTANCE.

THE WORK AND SHADOW VEHICLES SHOULD PULL OVER PERIODICALLY TO ALLOW TRAFFIC TO PASS.

WHEN NO WORK ACTIVITY IS TAKING PLACE, REMOVE OR LAY STATIONARY SIGNS AND SUPPORTS FLAT ON THE GRADE WITH UPRIGHTS ORIENTED PARALLEL TO AND DOWNSTREAM FROM TRAFFIC.


CONES SHOULD BE USED BETWEEN THE MARKING AND SHADOW VEHICLE AT 100 FOOT SPACING. CONES MAY BE OMITTED ON PAINTED LINE IF APPROVED BY THE ENGINEER. CONSIDER PAVEMENT MARKING DRY OR CURE TIMES AND TRAFFIC VOLUME.

CONES SHALL BE A MINIMUM OF 28" FOR WET PAVEMENT MARKING .

- ① SIGNS SHALL BE REPEATED APPROXIMATELY EVERY THREE MILES.
- ② IF CONSTRUCTION WORK ZONE SIGNS ARE IN PLACE, W20-1A OR W21-63 ARE NOT REQUIRED.
- ③ V1 AND V2 CAN BE SWITCHED SO THAT THE MARKER IS THE LEAD VEHICLE.

6

6



**MOVING PAVEMENT MARKING OPERATIONS
TWO-LANE TWO-WAY ROADWAY**

SDD 15C19 - 07a


SDD 15C19 - 07a

MOVING PAVEMENT MARKING OPERATION TWO-LANE TWO-WAY ROADWAY	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2022 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	


GENERAL NOTES

STOP SIGN SHALL BE PLACED A MINIMUM OF 6 FEET TO A MAXIMUM OF 50 FEET FROM THE EDGELINE LOCATION.


- ① 18-INCH STOP LINES MAY BE DELETED OR ADDED BY THE REGION MARKING ENGINEER BASED ON VISIBILITY AND SIGHT LINES.
- ② NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 40 FEET FROM THE EDGELINE.
- ③ NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 30 FEET FROM THE FLANGELINE EXTENSION.
- ④ MOVE CLOSER TO THE EDGE OF TRAVEL LINE AS NEEDED FOR VISIBILITY AND SIGHT LINES (NO CLOSER THAN 4 FEET).
- ⑤ LADDER BAR CROSSWALKS SHOULD ONLY BE USED FOR MID BLOCK CROSSINGS. USE 2 - 6" TRANSVERSE LINES INSTEAD.



TYPICAL STOP LINE PAVEMENT MARKING WITH CURB AND GUTTER




TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH RIGHT TURN LANE



TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH CROSSWALK MARKING

TYPICAL PAVEMENT MARKING FOR MID-BLOCK CROSSWALK



TYPICAL STOP LINE PAVEMENT MARKING WITHOUT CURB AND GUTTER

STOP LINE AND CROSSWALK PAVEMENT MARKING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2019 /S/ Matthew Rauch
DATE STATE SIGNING AND MARKING ENGINEER

FHWA


GENERAL NOTES

OMIT EDGE LINES THROUGH INTERSECTIONS. CONTINUE EDGE LINES THROUGH DRIVEWAYS.


- ① WHEN DISTANCE "A" IS LESS THAN 250 FEET, OMIT LANE LINE.
- ② WHEN DISTANCE "B" IS LESS THAN 100 FEET, OMIT CHANNELIZING LANE LINE.
- ③ BARRIER LINE ENDS AT SIDE ROAD PAVEMENT / SURFACE EDGE EXTENSION.
- ④ BARRIER LINE STARTS 500 FEET PRIOR TO THE BYPASS TAPER.
- ⑤ WHEN DISTANCE "C" IS LESS THAN 4 FEET, OMIT DOTTED EXTENSION.
- ⑥ WHEN DISTANCE "D" IS LESS THAN 50 FEET, OMIT DOTTED EXTENSION.

LEGEND


➡ DIRECTION OF TRAVEL



MINOR INTERSECTION




INTERSECTION ON OUTSIDE OF CURVE



**MAJOR INTERSECTIONS
(INTERSECTION WITH FULL RIGHT TURN LANE OR BYPASS LANE)**

BYPASS LANE PAVED SHOULDER WIDTH (AS SHOWN ELSEWHERE IN PLANS) - PLUS 2 INCHES



**PAVEMENT MARKING
(INTERSECTIONS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  WORK ZONE

GENERAL NOTES

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY THE REGIONAL TRAFFIC UNIT.

"WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.


CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

W20-1A AND G20-2A SIGNS ARE NOT REQUIRED IF THE WORK AREA IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT. G20-2A SIGNS MAY ALSO BE OMITTED IF DURATION OF WORK IS LESS THAN 7 CONTINUOUS DAYS AND NIGHTS.

6

6



OR
IF TRAFFIC CONTROL DEVICES
ENCROACH ONTO TRAVELED WAY, USE

POSTED SPEED LIMIT PRIOR TO WORK STARTING (MPH)	ADVANCE WARNING SIGN SPACING (A) FEET	SHOULDER TAPER L / 3 W, LATERAL OFFSET (FT)						BUFFER SPACE (B) FEET
		3	4	5	6	7	8	
25	200'	10	14	17	21	24	28	55
30	200'	15	20	25	30	35	40	85
35	350'	20	27	34	40	47	54	120
40	350'	26	35	44	53	62	70	170
45	500'	45	59	74	89	104	119	220
50	500'	50	66	83	99	116	132	280
55	500'	54	73	91	109	127	145	335'

**TRAFFIC CONTROL, WORK ON
SHOULDER OR PARKING LANE,
UNDIVIDED ROADWAY**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2020 /S/ Andrew Heidtke
DATE STATEWIDE WORK ZONE TRAFFIC
SAFETY ENGINEER


FHWA

SDD 15D28 - 04

SDD 15D28 - 04




NARROW SIDEWALK PASSING DETAIL



TEMPORARY PEDESTRIAN ACCESS

GENERAL NOTES

- BARRICADE DEVICE SELECTED FROM APPROVED PRODUCT LIST
- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② SHEETING REQUIRED ON MORE THAN 50% OF BARRICADE WIDTH.
- ③ PLACE SHEETING ON BOTH SIDES OF THE BARRICADE.
- * USE THIS DETAIL FOR SHEETING PLACEMENT REFERENCE.




TEMPORARY PEDESTRIAN BARRICADE*


GENERAL NOTES

CURB RAMPS SHALL BE 48" MIN. WIDTH WITH A FIRM, STABLE AND SLIP RESISTANT SURFACE.
 CURB RAMPS AND LANDINGS SHALL HAVE A 1:50 (2%) MAX. CROSS-SLOPE.
 CLEAR SPACE OF 48" X 48" SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.
 LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN 1/2" WIDTH.
 CHANGES BETWEEN SURFACE HEIGHTS SHALL NOT EXCEED 1/2". LATERAL EDGES MAY BE VERTICAL UP TO 1/4" HIGH AND SHALL BE BEVELED AT 1:2 BETWEEN 1/4" AND 1/2".

- ① INSTALL CONTRASTING TEMPORARY DETECTABLE WARNING FIELD AT PEDESTRIAN STREET CROSSINGS, AS SHOWN IN THE PLANS.
- ② PROTECTIVE EDGING WITH A 2" MIN. HEIGHT SHALL BE INSTALLED WHEN A CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6" OR GREATER OR HAS A SIDE APRON SLOPE STEEPER THAN 1:3 (33%). PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3" OR MORE.
- ③ DETECTABLE EDGING WITH 6" MIN. HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- ④ DO NOT RESTRICT WATER FLOW IN THE GUTTER SYSTEM.
- ⑤ 6" MINIMUM BETWEEN CURB FACE AND EDGE OF RAMP
- ⑥ IF ONLY PART OF THE END PANEL OF TEMPORARY PEDESTRIAN BARRICADE PANEL IS NEEDED, EXTEND EXCESS PORTION OF TEMPORARY PEDESTRIAN BARRICADE PANEL HERE.



PERSPECTIVE VIEW



FRONT VIEW

SIDE VIEW

TEMPORARY CURB RAMP PARALLEL TO CURB

<p>TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION</p>
<p>STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION</p>

GENERAL NOTES

IF PEDESTRIAN PUSH BUTTONS ARE PRESENT ON THE EXISTING FACILITY, ENSURE THEY ARE MAINTAINED/ACCESSIBLE FOR PEDESTRIAN USE THROUGHOUT THE TEMPORARY PEDESTRIAN ACCOMMODATIONS.

SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE WISCONSIN STANDARD SIGN PLATES.


TYPICAL TEMPORARY PEDESTRIAN BARRICADE PANEL IS 6 FEET LONG

WHEN TEMPORARY PEDESTRIAN BARRICADE RUNS PARALLEL ALONG THE SIDEWALK, PLACE THE FACE OF THE BARRICADE AT THE EDGE OF THE SIDEWALK.

- ① SHOULDER OR LANE CLOSURE ADVANCE WARNING AND PROPER BUFFER SPACE REQUIRED.
- ② PROVIDE ADEQUATE SPACE FOR CONTRACTOR OPERATIONS
- ③ USE TEMPORARY PEDESTRIAN BARRICADE TO SEPARATE PEDESTRIANS FROM DROP OFFS OR FOR ADDITIONAL PEDESTRIAN CHANNELIZATION.
- ④ MOUNTING HEIGHT OF 5 FEET FROM SIDEWALK SURFACE TO BOTTOM OF SIGN.
- ⑤ PLACE EXCESS PORTION OF TEMPORARY PEDESTRIAN BARRICADE PANEL IN THE SIDEWALK TERRACE.
- ⑥ WHITE 6" TEMPORARY PAVEMENT MARKING
- ⑦ IF TEMPORARY PEDESTRIAN BARRICADE DOES NOT REACH THE FACE OF THE CURB, USE AN ADDITIONAL PANEL AND EXTEND INTO THE TERRACE.
- ⑧ 4 FEET MINIMUM, 5 FEET DESIRABLE
- ⑨ IF MINIMUM LANE WIDTHS CAN'T BE ATTAINED, CURB RAMPS MAY NEED TO BE CONSTRUCTED AT SEPARATE TIMES.

LEGEND

-  SIGN ON TEMPORARY SUPPORT
-  TRAFFIC CONTROL DRUM
-  WORK AREA
-  TEMPORARY CURB RAMP
-  TEMPORARY PEDESTRIAN SURFACE "A"
-  TEMPORARY PEDESTRIAN SURFACE "B"
-  TEMPORARY DETECTABLE WARNING FIELD
-  TEMPORARY PEDESTRIAN BARRICADE
-  OPTIONAL TEMPORARY PEDESTRIAN BARRICADE
-  DIRECTION OF TRAFFIC



CURB RAMP PEDESTRIAN TRAFFIC CONTROL

**TRAFFIC CONTROL,
PEDESTRIAN ACCOMMODATION**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

DRAWING NOT TO SCALE. ALL SIGNS AND POSTS ON THIS SHEET SHALL BE PAID FOR WITH 'TRAFFIC CONTROL SIGNS' BID ITEM. ALL SIDE ROADS WHICH ARE UNDER CONSTRUCTION OF CURB AND GUTTER AND/OR GRADING SHALL BE ADEQUATELY SIGNED.

ALL SIGNS AND DEVICES SHALL BE IN CONFORMANCE WITH THE WISCONSIN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (WMUTCD). SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE WISDOT STANDARD SIGN PLATES.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THAT THE BACKGROUND IS ORANGE.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.


ALL SIGNS INAPPROPRIATE TO THE STATUS OF THE CONTROL ZONE, INCLUDING PRE-EXISTING SIGNS IN THE VICINITY, SHALL BE COVERED OR REMOVED AS DIRECTED BY THE ENGINEER.

SEE 15C34 FOR ADDITIONAL TRAFFIC CONTROL SIGNING WHEN CENTERLINE PAVEMENT MAKINGS ARE MISSING. 'DO NOT PASS' SIGNS MUST BE INSTALLED ON THE SAME DAY AS MILLING OPERATIONS.


- ① PLACE SIGNS 350' IN ADVANCE OF MILLED SURFACES AND AT 1 MILE INTERVALS, OR AS DIRECTED BY THE ENGINEER.
- ② PLACE SIGN 200' MIN. FROM INTERSECTION AND 200' MIN. AFTER ADVANCE WARNING SIGN SHOWN IN SDD 15C04.

LEGEND

-  SIGN ON TEMPORARY SUPPORT
-  DIRECTION OF TRAFFIC



TYPICAL SIDE ROAD APPROACH SIGN DETAIL



DETAIL FOR SIGNING ON MILLED SURFACES

SEE SDD15C04 FOR ADVANCE WARNING SIGNS

SEE SDD15C04 FOR ADVANCE WARNING SIGNS

TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH MILLED SURFACES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

NOTES

- 1. Fixed Message Type II Sign - Type F Reflective
- 2. Color:
 - Background - Orange
 - Message - Black
- 3. Message Series - C




2.250" Radius, 0.625" Border, 0.500" Indent




7

7

URBAN AREA



RURAL AREA (See Note 2)



POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

- GENERAL NOTES
1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
 2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.
The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).
 3. For expressways and freeways, mounting height is 7'- 3" (±) or 6'-3" (±) depending upon existence of a sub-sign.
 4. Minimum mounting height for signs mounted on traffic signal poles is 5'- 3" (±).
 5. Offset distance shall be consistent with existing signs or consistent throughout length of project.
 6. The (±) tolerance for mounting height is 3 inches.
 7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the Engineer.

* * The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.


* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

TYPICAL INSTALLATION OF PERMANENT TYPE II SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer


DATE 5/13/2020 PLATE NO. A4-3.22



ELEVATION VIEW


DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT

- NOTES:**
1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
 2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
 3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



PLAN VIEW

FOR NEW CONCRETE/ ASPHALT INSTALLATIONS

**SIGN POST
BOX-OUTS
A4-3B**

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 1/27/14 PLATE NO. A4-3B.1



GENERAL NOTES

1. For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
2. See tables below for required number of posts.
3. For expressways and freeways, mounting height is 7'-3" (±) or 6'-3" (±) depending upon existence of sub-sign.
4. The (±) tolerance for mounting height is 3 inches.
5. J-Assemblies are considered to be one sign for mounting height.
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the engineer.
8. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).


URBAN AREA




RURAL AREA (See Note 3)



2' Min - 4' Max (See Note 6)



48" DIAMOND WARNING SIGN



48" DIAMOND WARNING SIGN

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

*** See A4-3 sign plate for signs 4' or less in width and less than 20 S.F. in area.

SIGN SHAPE OTHER THAN DIAMOND (TWO POSTS REQUIRED)	
L	E
Greater than 48" Less than 60"	12"
60" to 108"	L/5


SIGN SHAPE OTHER THAN DIAMOND (THREE POSTS REQUIRED)	
L	E
Greater than 108" to 144"	12"

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION OF TYPE II SIGNS ON MULTIPLE POSTS

WISCONSIN DEPT OF TRANSPORTATION
 APPROVED *Matthew R. Rauch*
 For State Traffic Engineer
 DATE 8/21/17 PLATE NO. A4-4.15



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)

MACHINE BOLTS - 5/16" X 1-3/4" Length w/ lock nuts

WOOD POSTS (4" x 6")

LAG SCREWS - 3/8" X 3" (NO STRINGERS ON BACK OF SIGN)
3/8" X 4" (STRINGERS ON BACK OF SIGN)

SQUARE STEEL POSTS (2" x 2")

MACHINE BOLTS - 3/8" X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
3/8" X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)

RIVETS - 9/32" (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL
O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH

WASHERS (ALL POSTS) -

1-1/4" O.D. X 3/8" I.D. X 1/16" STEEL

1-1/4" O.D. X 3/8" I.D. X .080 NYLON

* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.

ATTACHMENT OF SIGNS
TO POSTS


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
For State Traffic Engineer


DATE 4/1/2020 PLATE NO. A4-8.9

**TELESCOPIC TUBING ANCHORS
TWO PIECE SYSTEM**


2 1/4" SQUARE
12 GAUGE
PERFORATED
GALVANIZED FINISH





2 1/2" SQUARE
12 GAUGE
OMNI-DIRECTIONAL
PERFORATED
SOIL STABILIZING SLEEVE
GALVANIZED FINISH



**DETAIL OF TUBULAR STEEL SIGN POST
(IN POURED CONCRETE OR ASPHALT)**



**DETAIL OF TUBULAR STEEL SIGN POST
(IN LOCATIONS OTHER THAN POURED CONCRETE OR ASPHALT)**



Area of Sign Installation (Sq. Ft.)	Number of Required Posts
9 or less	1
Greater than 9 less than or equal to 18	2
Greater than 18 less than or equal to 27	3

Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

**TUBULAR STEEL
SIGN POST
A4-9**

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 2/05/15 PLATE NO. A4-9.9



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E




GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1½" diameter holes drilled perpendicular to the roadway centerline.

7

7

4 X 6 WOOD POST MODIFICATIONS	
<i>WISCONSIN DEPT OF TRANSPORTATION</i>	
APPROVED	<i>Chester J Spang</i> for State Traffic Engineer
DATE <u>3/27/97</u>	PLATE NO. <u>A4-11.2</u>






GENERAL NOTES

- ALL SIGNS OVER 60" IN WIDTH SHALL HAVE A 3" RADIUS ON THE OUTSIDE CORNERS OF THE ALUMINUM BLANK.
- MOUNTING HOLES SHALL BE $\frac{7}{16}$ " DIAMETER.
- SEE CHART FOR HOLE SPACING REQUIREMENTS
- FOR SIGN PANELS WITH DIMENSION (H) 36" AND OVER, DIMENSION E SHALL BE 6"
- FOR SIGN PANELS WITH DIMENSION (H) UNDER 36", DIMENSION E SHALL BE 4"
- SIGN STRINGER MATERIAL SHALL CONSIST OF STEEL CHANNEL POST SECTIONS, WEIGHING 1.12 LBS/FT IN ACCORDANCE WITH SECTION 633.2.1 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION.
- SEE SIGN PLATE A4-8 FOR SIGN STRINGER BOLTING REQUIREMENTS.

SIGN WIDTH	STRINGER WIDTH	POSTS	HOLE SPACING	MOUNTING HOLES
78"	72"	2	16"	15" 31" 47" 63"
84"	72"	2	17"	16 $\frac{1}{2}$ " 33 $\frac{1}{2}$ " 50 $\frac{1}{2}$ " 67 $\frac{1}{2}$ "
90"	72"	2	18"	18" 36" 54" 72"
96"	90"	2	19"	19 $\frac{1}{2}$ " 38 $\frac{1}{2}$ " 57 $\frac{1}{2}$ " 76 $\frac{1}{2}$ "
102"	90"	2	20"	21" 41" 61" 81"
108"	90"	2	21"	22 $\frac{1}{2}$ " 43 $\frac{1}{2}$ " 64 $\frac{1}{2}$ " 85 $\frac{1}{2}$ "
114"	108"	3	15"	12" 27" 42" 57" 72" 87" 102"
120"	108"	3	16"	12" 28" 44" 60" 76" 92" 108"
126"	108"	3	17"	12" 29" 46" 63" 80" 97" 114"
132"	126"	3	18"	12" 30" 48" 66" 84" 102" 120"
138"	126"	3	19"	12" 31" 50" 69" 88" 107" 126"
144"	126"	3	20"	12" 32" 52" 72" 92" 112" 132"

7



7

SIGN STRINGER MOUNTING REQUIREMENTS




WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 4/26/16 PLATE NO. A4-18.1

BANDING


SINGLE SIGN



GENERAL NOTES

1. Any sign over 3 feet in width shall use the V-Block banding method. See A5-10 standard plate.
2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
3. Banding and assembly bracket shall be stainless steel. All bands shall be $\frac{3}{4}$ " in width and 0.025" thickness.
4. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM designation: B 633, Type III, SC 3


"J" ASSEMBLY



CHANNEL
SEE TYPICAL PANEL
INSTALLATION SHEET



WASHER PLACEMENT




WASHERS (ALL POSTS) -
 1-1/4" O.D. X 3/8" I.D. X 1/16" STEEL
 1-1/4" O.D. X 3/8" I.D. X .080 NYLON
 FOR ALL TYPE H SIGNS

STANDARD SIGN
SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer


DATE 6/10/19 PLATE NO. A5-9.4



GENERAL NOTES

1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WISDOT STANDARD SPECIFICATIONS
2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, 3/4" WIDTH AND 0.025" THICKNESS
3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORMALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3
6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
7. STEEL WASHERS SHALL BE 1/4" O.D. X 3/8" I.D. X 1/16"
8. NYLON WASHERS SHALL BE 1/4" O.D. X 3/8" I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN

* LAG BOLTS SHALL BE 3/8" X 2 1/2"



BLOCK BANDING DETAIL
(V-BLOCK OPTION)



WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer

DATE 4/19/2022 PLATE NO. A5-10.3

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - D except 3 number signs Series C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24		1 1/2			12	5 1/2	6 1/2	10 1/4	2 1/2	8 7/8	11 1/2	1	1 7/8	11 1/4	21 7/8											4.0
3	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33											9.0
4	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33											9.0
5	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33											9.0


STATE ROUTE MARKER
M1-6 FOR ASSEMBLIES

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 3/16/18 PLATE NO. M1-6.10

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: _____ E



M1-6B


Metric equivalent for this sign is:

SIZE	
1	
2	600 mm X 600 mm
3	900 mm X 900 mm
4	900 mm X 900 mm
5	900 mm X 900 mm


SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.	Area m ²
1																												
2	24		1 1/2			12	5 1/2	6 1/2	10 1/4	2 1/2	8 7/8	11 1/2	1	1 7/8	11 1/4	21 7/8		5 1/8	3/4	1 7/8	1 1/2	5/8	5/8	9	1/2	10 1/2	4.0	.36
3	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33		7 1/2	1 1/2	2 1/2	2	7/8	3/4	13 1/2	3/4	15 1/2	9.0	.81
4	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33		7 1/2	1 1/2	2 1/2	2	7/8	3/4	13 1/2	3/4	15 1/2	9.0	.81
5	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33		7 1/2	1 1/2	2 1/2	2	7/8	3/4	13 1/2	3/4	15 1/2	9.0	.81

NOTES

- Sign is Type II - Type H - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- Color:
Background - White & Black
Message - Black
Arrow - Type H Reflective Red
- Message Series - D
- Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



32nd DIVISION ARROW
ACTUAL SIZE



STATE ROUTE MARKER "32"
M1-6B FOR ASSEMBLIES

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 12/5/05 PLATE NO. M1-6B.2

PROJECT NO:

HWY:


COUNTY:

SHEET NO:


E

NOTES


- All Signs Type II - Type H
- Color:
 - Background - See note 5
 - Message - See note 5
- Message Series - C
- Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- M3-1 thru M3-4 Background - White
 Message - Black
 MB3-1 thru MB3-4 Background - Blue
 Message - White
 MK3-1 thru MK3-4 Background - Green
 Message - White
 MM3-1 thru MM3-4 Background - White
 Message - Green
 MN3-1 thru MN3-4 Background - Brown
 Message - White
 MP3-1 thru MP3-4 Background - White
 Message - Blue
- Note the first letter of each direction is larger than the remainder of the message.




M3-1
MM3-1
MP3-1




MB3-1
MK3-1
MN3-1




M3-2
MM3-2
MP3-2




MB3-2
MK3-2
MN3-2




M3-3
MM3-3
MP3-3



MB3-3
MK3-3
MN3-3



M3-4
MM3-4
MP3-4



MB3-4
MK3-4
MN3-4

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24	12	1 1/8	3/8	3/8	6	7	2 1/4	2 3/4	10 1/4	7 7/8	8 3/8	10 1/4	9 3/4	8 3/4			1 1/2									2.00
3	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13			1 1/2									4.5
4	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13			1 1/2									4.5
5	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13			1 1/2									4.5

STANDARD SIGNS
M3-1 thru M3-4
SERIES


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 10/15/15 PLATE NO. M3-1.14

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - B
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



M4-8

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24	12	1 1/8	3/8	3/8	6	3	10	10 1/4																		2.0
3	36	18	1 1/8	3/8	1/2	9	4 1/2	14 5/8	14 1/2																		4.5
4																											
5																											

STANDARD SIGN
M4-8

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 11/10/10 PLATE NO. M4-8.2

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - B
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24	18	1 1/8	3/8	1/2	6	2	2	4 3/4	9 3/4																	3.0
3	30	24	1 1/8	3/8	1/2	8	2 1/2	3	6 3/4	13																	5.0
4																											
5																											

STANDARD SIGN
M4-8A

WISCONSIN DEPT OF TRANSPORTATION



APPROVED *Matthew R Rauch*
for State Traffic Engineer

DATE 3/9/11 PLATE NO. M4-8A.2

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. M4-9L is the same as M4-9R except the arrow is reversed.



Arrow Detail

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	30	24	1 1/8	3/8	1/2	5	4	7	8	11 1/2	12	9	3/4	4 7/8													5.00
3	30	24	1 1/8	3/8	1/2	5	4	7	8	11 1/2	12	9	3/4	4 7/8													5.00
4	48	36	1 3/8	1/2	5/8	8	6	10 1/2	11 5/8	20 5/8	20 1/2	13 1/4	1 1/8	6 7/8													12.0
5	48	36	1 3/8	1/2	5/8	8	6	10 1/2	11 5/8	20 5/8	20 1/2	13 1/4	1 1/8	6 7/8													12.0


STANDARD SIGN
M4-9 R & L

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 3/9/11 PLATE NO. M4-9R.4


PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**




M5-1L
MM5-1L
M05-1L
MP5-1L




M5-2L
MM5-2L
M05-2L
MP5-2L



MB5-1L
MK5-1L
MN5-1L
MR5-1L



MB5-2L
MK5-2L
MN5-2L
MR5-2L



NOTES

- Signs are Type II - Type H reflective except as shown
- Color:
 - Background - See note 4
 - Message - See note 4
- Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- M5-1 and M5-2 Background - White
Message - Black
 - MB5-1 and MB5-2 Background - Blue
Message - White
 - MK5-1 and MK5-2 Background - Green
Message - White
 - MM5-1 and MM5-2 Background - White
Message - Green
 - MN5-1 and MN5-2 Background - Brown
Message - White
 - M05-1 and M05-2 Background - Orange - Type F Reflective
Message - Black
 - MP5-1 and MP5-2 Background - White - Type H Reflective
Message - Blue
 - MR5-1 and MR5-2 Background - Brown
Message - Yellow
- M5-1R same as M5-1L except arrow points right.
- M5-2R same as M5-2L except arrow tilts right.


SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	21		1 1/8	3/8	3/8		7	3 3/8	5/8		2 1/8	4 1/2	6 3/8	5 1/4	5	2 1/2		1/2	2 5/8	3	1 1/2	1/2					3.06
3	30		1 3/8	1/2	5/8		10 1/8	4 7/8	7/8		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 7/8	1/2					6.25
4	30		1 3/8	1/2	5/8		10 1/8	4 7/8	7/8		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 7/8	1/2					6.25
5	30		1 3/8	1/2	5/8		10 1/8	4 7/8	7/8		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 7/8	1/2					6.25

STANDARD SIGN
M5-1 & M5-2


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer


DATE 10/15/15 PLATE NO. M5-1.13




M6-1
MM6-1
M06-1
MP6-1




M6-2
MM6-2
M06-2
MP6-2



MB6-1
MK6-1
MN6-1
MR6-1



MB6-2
MK6-2
MN6-2
MR6-2



NOTES

- Signs are Type II - Type H except as Shown
- Color:
Background - See note 4
Message - See note 4
- Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- M6-1 and M6-2 Background - White
Message - Black
MB6-1 and MB6-2 Background - Blue
Message - White
MK6-1 and MK6-2 Background - Green
Message - White
MM6-1 and MM6-2 Background - White
Message - Green
MN6-1 and MN6-2 Background - Brown
Message - White
M06-1 and M06-2 Background - Orange - Type F Reflective
Message - Black
MP6-1 and MP6-2 Background - White
Message - Blue
MR6-1 and MR6-2 Background - Brown
Message - Yellow

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	21		1 1/8	3/8	3/8		7 1/2	7 1/8	5 5/8	5	4 1/4	5 1/4	3	2 5/8	1/2						1 1/2	1/2					3.06
3	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 7/8	1/2					6.25
4	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 7/8	1/2					6.25
5	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 7/8	1/2					6.25

STANDARD SIGN
M6-1 & M6-2
SERIES


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 10/15/15 PLATE NO. M6-1.15


NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Substitute appropriate numerals to nearest quarter mile and optically adjust spacing to achieve proper balance.



** See Note 5

R11-3B



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	18	1 3/8	1/2	5/8	4	3	2 1/2	2	2	13 1/4	2 1/4	3	8	8	1 1/2	2	10 3/4	8 3/8	4 3/4	6 1/2	2	6 3/4	7 1/8		4.5	
2S	60	30	1 3/8	1/2	5/8	6	5	4	4 1/4	3 3/8	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8	13 1/8	8	10	3 1/2	11	11 7/8		12.5	
2M	60	30	1 3/8	1/2	5/8	6	5	4	4 1/4	3 3/8	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8	13 1/8	8	10	3 1/2	11	11 7/8		12.5	
3																											
4																											
5																											

STANDARD SIGN
R11-3B

WISCONSIN DEPT OF TRANSPORTATION







APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 3/21/17 PLATE NO. R11-3B.3

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**

7

7



NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - See note 5
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Line 1 is Series D.
Line 2 is Series D for AHEAD and Series C for all other distances.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	6	5	1	2 1/4	14 3/4	15	11 5/8	9	1 3/8	1 7/8	5 5/8	10 1/8	2 1/2	1 1/8	4 1/2	3 1/2	8	1 3/4	10 3/4			9.0
2S	48		2 1/4	3/4	1	8	7	1 1/4	3	19 3/4	20	15 1/2	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	10 5/8	2 3/8	14 3/8			16.0
2M	48		2 1/4	3/4	1	8	7	1 1/4	3	19 3/4	20	15 1/2	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	10 5/8	2 3/8	14 3/8			16.0
3	48		2 1/4	3/4	1	8	7	1 1/4	3	19 3/4	20	15 1/2	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	10 5/8	2 3/8	14 3/8			16.0
4	48		2 1/4	3/4	1	8	7	1 1/4	3	19 3/4	20	15 1/2	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	10 5/8	2 3/8	14 3/8			16.0
5	48		2 1/4	3/4	1	8	7	1 1/4	3	19 3/4	20	15 1/2	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	10 5/8	2 3/8	14 3/8			16.0

STANDARD SIGN
W20-2A, B, C, D, F & G

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Raub*
for State Traffic Engineer

DATE 3/18/11 PLATE NO. W20-2.6

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: _____ E

DESIGN DATA


LIVE LOAD:
INVENTORY RATING: HS-16
OPERATING RATING: HS-31
MAXIMUM STANDARD PERMIT VEHICLE LOAD: 200 (KIPS)

MATERIAL PROPERTIES:
CONCRETE MASONRY:
OVERLAY DECKS $f'c = 4,000$ P.S.I.
SUPERSTRUCTURE $f'c = 4,000$ P.S.I.
ALL OTHER $f'c = 3,500$ P.S.I.

BAR STEEL REINFORCEMENT:
GRADE 60 $f_y = 60,000$ P.S.I.
STEEL SHIM PLATES - ASTM A709:
GRADE 50 $f_y = 50,000$ P.S.I.


TRAFFIC VOLUME

STH 32
ADT = 6,500 (2032)
R.D.S. = 60 M.P.H.



GENERAL NOTES

- DRAWINGS SHALL NOT BE SCALED.
- BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
- THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.
- BEVEL EXPOSED EDGES OF CONCRETE $\frac{3}{4}$ " UNLESS OTHERWISE NOTED.
- THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.
- ELASTOMERIC BEARING PADS NEED NOT BE INDIVIDUALLY MOLDED PROVIDED THE CUT EDGES ARE SMOOTH AND TRUE.
- PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO THE ENTIRE EXPOSED TOP OF DECK/OVERLAY AND TO THE VERTICAL AND HORIZONTAL SURFACES OF THE PAVING NOTCHES AT ABUTMENT DIAPHRAGMS.
- PIGMENTED SURFACE SEALER TO BE APPLIED TO THE FRONT FACE AND THE TOP OF THE PARAPETS, INCLUDING PARAPETS ON WINGS.
- DIMENSIONS SHOWN ARE BASED ON THE ORIGINAL STRUCTURE PLANS.
- A MINIMUM OF 1-INCH OF CONCRETE SHALL BE REMOVED FROM THE ENTIRE BRIDGE DECK UNDER THE BID ITEM "CLEANING DECKS".
- THE CONTRACTOR SHALL SUPPLY A NEW NAME PLATE IN ACCORDANCE WITH SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS AND THE STANDARD DETAIL DRAWINGS. NAME PLATE TO SHOW ORIGINAL CONSTRUCTION YEAR 1970.
- UTILIZE EXISTING BAR STEEL REINFORCEMENT WHERE SHOWN.
- IF EXISTING BAR STEEL REINFORCEMENT IS SEVERELY CORRODED OR DAMAGED DURING CONCRETE REMOVAL, REPLACE WITH EPOXY ANCHORED BARS OF THE SAME SIZE. EMBED 1'-6" INTO EXISTING CONCRETE.
- REMOVE ANY LOOSE CONCRETE AT GIRDER ENDS PRIOR TO POURING ABUTMENT DIAPHRAGMS. WORK TO BE PAID FOR UNDER "REMOVING STRUCTURE B-8-9" BID ITEM.
- SEAL ALL HORIZONTAL AND VERTICAL JOINTS ON BACKFACE OF WINGS/ABUTMENTS WITH "RUBBERIZED MEMBRANE WATERPROOFING".
- DELAMINATIONS UNDER DECK TO BE REPAIRED WITH "FULL-DEPTH DECK REPAIR". EXACT LOCATIONS TO BE DETERMINED BY ENGINEER.
- SEAL OVERLAY CONSTRUCTION JOINTS ACCORDING TO SECTION 502.3.13.1 OF THE STANDARD SPECIFICATION. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY OVERLAY DECKS".
- THE AVERAGE OVERLAY THICKNESS IS BASED ON THE MINIMUM OVERLAY THICKNESS PLUS $\frac{1}{2}$ -INCH TO ACCOUNT FOR VARIATIONS IN THE DECK SURFACE.
- PREPARATION DECKS TYPE 1, PREPARATION DECKS TYPE 2, AND FULL-DEPTH DECK REPAIR AREAS ARE ESTIMATES BASED ON INSPECTION REPORTS AND ARE TO BE DETERMINED BY THE ENGINEER. DECK PREPARATION AND FULL-DEPTH DECK REPAIRS SHALL BE FILLED WITH "CONCRETE MASONRY OVERLAY DECKS".
- PROFILE GRADE LINE SHALL BE DETERMINED IN THE FIELD BASED ON A MINIMUM OVERLAY THICKNESS OF $\frac{1}{2}$ " PLACED ABOVE THE DECK SURFACE AFTER SURFACE PREPARATION. EXPECTED AVERAGE OVERLAY THICKNESS IS $\frac{3}{8}$ ". IF EXPECTED AVERAGE OVERLAY THICKNESS IS EXCEEDED BY MORE THAN $\frac{1}{2}$ ", CONTACT THE STRUCTURES DESIGN SECTION.
- QUANTITIES FOR "CURB REPAIR", "CONCRETE SURFACE REPAIR" ON SUBSTRUCTURES, & "SLOPE PAVING REPAIR SELECT CRUSHED AGGREGATE" ARE ESTIMATES. ACTUAL QUANTITY AND LOCATION WILL BE DETERMINED BY THE ENGINEER BASED ON FIELD CONDITIONS AND NEEDS.
- DEBRIS CONTAINMENT IS FOR FULL DEPTH DECK REPAIR AREAS ABOVE RAILROAD.



ABUTMENT BACKFILL DIAGRAM FOR WINGS PARALLEL TO ROADWAY

L = OUT TO OUT OF ABUTMENT, INCLUDING WINGS (FT)
H = AVERAGE ABUTMENT FILL HEIGHT (FT). AN ESTIMATED HEIGHT OF 4.75 FT WAS USED.
EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
 $V_{CF} = (L)(3.0)(H) + (L)(0.5)(1.5)(H)$
 $V_{CY} = V_{CF}(EF)/27$
 $V_{TON} = V_{CY}(2.0)$

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	TOTALS
203.0220	REMOVING STRUCTURE B-8-9	EACH	1
203.0211.S	ABATEMENT OF ASBESTOS CONTAINING MATERIAL B-8-9	EACH	1
203.0330	DEBRIS CONTAINMENT B-8-9	EACH	1
206.1000	EXCAVATION FOR STRUCTURES BRIDGES B-8-9	LS	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	355
502.0100	CONCRETE MASONRY BRIDGES	CY	142
502.3200	PROTECTIVE SURFACE TREATMENT	SY	1,092
502.3210	PIGMENTED SURFACE SEALER	SY	197
502.4204	ADHESIVE ANCHORS NO. 4 BAR	EACH	920
502.4205	ADHESIVE ANCHORS NO. 5 BAR	EACH	112
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	15,080
506.2605	BEARING PADS ELASTOMERIC NON-LAMINATED	EACH	10
506.7050.S	REMOVING BEARINGS B-8-9	EACH	10
509.0301	PREPARATION DECKS TYPE 1	SY	102
509.0302	PREPARATION DECKS TYPE 2	SY	41
509.0500	CLEANING DECKS	SY	1,003
509.1200	CURB REPAIR	LF	62
509.1500	CONCRETE SURFACE REPAIR	SF	23
509.2000	FULL-DEPTH DECK REPAIR	SY	3
509.2500	CONCRETE MASONRY OVERLAY DECKS	CY	103
509.9050.S	CLEANING PARAPETS	LF	411
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	32
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	205
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4
SPV.0035	SLOPE PAVING REPAIR SELECT CRUSHED AGGREGATE	CY	85
NON-BID ITEMS			
	FILLER	SIZE	$\frac{1}{2}$ ", $\frac{3}{4}$ "

LIST OF DRAWINGS

1. CONCRETE OVERLAY
2. OVERLAY & CONCRETE REMOVAL
3. CONCRETE REMOVAL
4. ABUTMENT BEARING MODIFICATION DETAILS
5. DECK & DIAPHRAGM DETAILS
6. PARAPET DETAILS
7. WING & PARAPET RETROFIT DETAILS
8. BAR DETAILS
9. CLEANING PARAPETS & CURB REPAIR
10. SLOPE REPAIR
11. DECK SCANS

STRUCTURE DESIGN CONTACTS:


JONATHON RESHESKE (608) 266-8491
LAURA SHADEWALD (608) 267-9592

NO.	DATE	REVISION	BY
ACCEPTED		1/10/23	
CHIEF STRUCTURES DESIGN ENGINEER		DATE	
STRUCTURE B-8-9			
STH 32 OVER CANADIAN NATIONAL RAILROAD			
COUNTY	CALUMET	TOWN	NEW HOLSTEIN
DESIGN SPEC. REHABILITATION N/A			
DESIGNED BY	JLR	DESIGNED CK'D.	ETP
DRAWN BY	JLR	PLANS CK'D.	ETP
CONCRETE OVERLAY			SHEET 1 OF 11

8


8

SCALE = 1/4"=1'-0"



CROSS SECTION THRU BRIDGE

CONCRETE OVERLAY DETAILS
(LOOKING UPSTATION)



PLAN

SHOWING TYPICAL REMOVAL AT ABUTMENTS


CONCRETE REMOVAL LIMITS

* DIMENSION IS TAKEN NORMAL TO CL ABUTMENT


■ EXISTING #5 LONGITUDINAL BARS. SAVE AND INCORPORATE, IF BARS ARE UNUSABLE, REPLACE IN KIND AND LAP 2'-7". REPLACEMENT BARS ARE INCIDENTAL TO "REMOVING STRUCTURE B-8-9" BID ITEM.

● EXISTING #6 TRANSVERSE BARS. SAVE AND INCORPORATE 1'-6" MIN.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY		JLR	PLANS CKD. ETP
OVERLAY & CONCRETE REMOVAL		SHEET 2	




TYPICAL ABUTMENT REMOVAL ELEVATION




TYPICAL ABUTMENT REMOVAL ELEVATION

NORMAL TO ABUTMENT BODY AT BEAM SEAT



TYPICAL ABUTMENT REMOVAL ELEVATION


PERPENDICULAR TO GIRDER AT CL GIRDER



TYPICAL WING PARAPET REMOVAL ELEVATION

TYPICAL WING PARAPET REMOVAL SECTION

SOME "CONCRETE SURFACE REPAIR" WORK MAY BE NECESSARY ON BACK FACE, TO BE DETERMINED BY ENGINEER.




TYPICAL PARAPET/CURB REMOVAL & REPAIR ON BRIDGE DECK


CONCRETE REMOVAL LIMITS

* DIMENSION IS TAKEN NORMAL TO CL ABUTMENT

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY		JLR	PLANS CKD. ETP
CONCRETE REMOVAL		SHEET 3	



EAST ABUTMENT PLAN




RODENT SHIELD DETAIL

* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING, ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

EXISTING BEARINGS TO BE REPLACED WITH STEEL SHIMS AND 1/2" NON-LAMINATED ELASTOMERIC BEARING PAD. SEE DETAILS ON THIS SHEET.



EAST ABUTMENT ELEVATION

(A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.

(MO2) ADHESIVE ANCHORS NO. 4 BAR, EMBED 6" MIN. IN CONCRETE.


⊖ INDICATES WING NUMBER

○ INDICATES GIRDER NUMBER


● PLACE A DEPARTMENT APPROVED NON-SHRINK COMMERCIAL GROUT OVER THE WIDTH OF ABUTMENT TOP BETWEEN EXISTING BEAM SEATS PRIOR TO PLACING POLYETHYLENE SHEETS. PLACE GROUT AS REQUIRED TO PRODUCE A SMOOTH SLIDING SURFACE FREE OF PROTRUSIONS. REMOVE DELAMINATED OR LOOSE CONCRETE AND CLEAN THE SURFACE PRIOR TO PLACING GROUT. ADDITIONAL SURFACE PREPARATION MAY BE REQUIRED PER THE MANUFACTURER'S INSTRUCTION. MIX, PLACE, AND CURE NON-SHRINK COMMERCIAL GROUT UNTIL A MINIMUM COMPRESSIVE STRENGTH OF 3,500 P.S.I. IS ACHIEVED. NON-SHRINK COMMERCIAL GROUT AND SURFACE PREPARATION IS INCLUDED IN THE BID ITEM "CONCRETE MASONRY BRIDGES".

◆ PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING BEARING PADS. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03".

◆ STEEL SHIMS SHALL BE ASTM A709 GRADE 50. SHIM PLATES SHALL BE CONNECTED USING 2 - 1/2" DIA. PINTLES OR OTHER ENGINEER APPROVED METHODS. STEEL PINTLES SHALL CONFORM TO ASTM A449 OR MATERIAL OF EQUIVALENT YIELD STRENGTH AND ELONGATION. STEEL SHIMS INCLUDED IN BID ITEM "BEARING PADS ELASTOMERIC NON-LAMINATED".




BEARING PLAN




SHEAR KEY PLAN

NON-SHRINK COMMERCIAL GROUT (TYP.)




SHEAR KEY ELEVATION

PERPENDICULAR TO GIRDER



SECTION THRU ABUTMENT

TYP. BOTH ABUTMENTS




BEARING ELEVATION

PERPENDICULAR TO GIRDER

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY JLR		PLANS CK'D. ETP	
ABUTMENT BEARING MODIFICATION DETAILS			SHEET 4


8

SCALE = 5.00




PLAN AT PPT. WING 1

WING 3 SIMILAR




PLAN AT PPT. WING 2


WING 4 SIMILAR




SECTION A-A




SECTION B-B



SECTION C-C



SECTION D-D



SECTION E-E

(A17) 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.

■ S524 BARS MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. USE CARE TO PLACE S524 BARS CORRECTLY ALONG TRANSITION OF PARAPET.


▽ S522 AND S523 BARS TO BE TIED TO WING STEEL BEFORE WING IS POURED

● CONST. JOINT - STRIKE OFF AS SHOWN

★ EXISTING #5 HORIZONTAL CURB BAR. SAVE AND INCORPORATE, IF BAR IS UNUSABLE, REPLACE IN KIND AND LAP 2'-7". REPLACEMENT BARS ARE INCIDENTAL TO "REMOVING STRUCTURE B-8-9" BID ITEM.


■ DIMENSION IS TO ORIGINAL DECK SURFACE.

● DIMENSION IS TO TOP OF WING.



INSIDE ELEVATION


TYPICAL ALL WINGS



OUTSIDE ELEVATION

TYPICAL ALL WINGS

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY		PLANS CK'D.	ETP
JLR			
PARAPET DETAILS			SHEET 6




ESTIMATED TOP OF WING HEIGHTS


WING	DIMENSION A	DIMENSION B
WING 1	4'-8 ⁵ / ₈ "	4'-8 ³ / ₄ "
WING 2	4'-8"	4'-8 ⁵ / ₈ "
WING 3	4'-9 ¹ / ₄ "	4'-9 ¹ / ₈ "
WING 4	4'-8 ³ / ₈ "	4'-9"

TYPICAL WING ELEVATION

TYPICAL WING SECTION



TYPICAL SECTION THRU PARAPET RETROFIT ON BRIDGE DECK





TYPICAL ELEVATION OF PARAPET RETROFIT

- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (M03) ADHESIVE ANCHORS NO. 5 BAR. EMBED 1'-0" IN CONCRETE.
- (M04) ADHESIVE ANCHORS NO. 4 BAR. EMBED 10" IN CONCRETE.


◆ DIMENSIONS BASED ON EXISTING PLANS AND INCLUDE 1/2" ADDITIONAL HEIGHT TO ACCOUNT FOR OVERLAY. TOP OF WING TO ALIGN WITH TOP OF DECK/PAVEMENT. ENGINEER TO VERIFY WING HEIGHTS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY JLR		PLANS CK'D. ETP	
WING & PARAPET RETROFIT DETAILS			SHEET 7


S401




S609




S610




S511, S512, S513, S514, S515, S516, S517




S518




S519




S520




S522




S523




S524



S525




S526




S528




S529




S432



S433



S434



DETAIL OF ANCHOR ASSEMBLY

NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.

ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.


BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE


BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
(M02) S401	X	96	3'-2"	X		ABUTMENT - VERT. - SHEAR KEY
S402	X	32	6'-8"			ABUTMENT - HORIZ - SHEAR KEY
S603	X	44	39'-4"			SUPERSTRUCTURE - HORIZ. - TRANSVERSE
S504	X	20	6'-0"			DIAPHRAGM - HORIZ. - THRU GIRDER
S605	X	48	8'-1"			DIAPHRAGM - HORIZ.
S606	X	16	4'-0"			DIAPHRAGM - HORIZ.
S607	X	24	39'-4"			DIAPHRAGM - HORIZ.
S608	X	20	8'-1"			DIAPHRAGM - HORIZ.
S609	X	8	16'-1"	X		DIAPHRAGM - HORIZ. - NE & SW CORNERS
S610	X	8	14'-8"	X		DIAPHRAGM - HORIZ. - SE & NW CORNERS
S511	X	76	21'-0"	X		DIAPHRAGM - VERT.
S512	X	24	20'-0"	X		DIAPHRAGM - VERT. - OVER SHEAR KEY
S513	X	2	15'-4"	X		DIAPHRAGM - VERT. - NE & SW CORNERS
S514	X	2	16'-8"	X		DIAPHRAGM - VERT. - NE & SW CORNERS
S515	X	2	14'-4"	X		DIAPHRAGM - VERT. - SE & NW CORNERS
S516	X	2	12'-2"	X		DIAPHRAGM - VERT. - SE & NW CORNERS
S517	X	20	17'-4"	X		DIAPHRAGM - VERT.
S518	X	108	8'-0"	X		DIAPHRAGM/DECK - VERT.
S519	X	30	4'-5"	X		PARAPET - VERT. - DECK
S520	X	44	5'-2"	X		PARAPET - VERT. - DECK/WINGS
S521	X	24	4'-5"			PARAPET - HORIZ. - DECK
S522	X	14	5'-10"	X		PARAPET - VERT. - WINGS
S523	X	68	5'-8"	X		PARAPET - VERT. - WINGS
S524	X	48	3'-0"	X		PARAPET - VERT. - WINGS
S525	X	24	4'-10"	X		PARAPET - VERT. - WINGS
S526	X	44	4'-7"	X		PARAPET - VERT. - WINGS
S527	X	20	9'-8"			PARAPET - HORIZ. - WINGS
S528	X	4	9'-6"	X		PARAPET - HORIZ. - WINGS
(M03) S529	X	112	6'-8"	X		WINGS - VERT.
S430	X	44	9'-8"			WINGS - HORIZ.
S631	X	8	9'-8"			WINGS - HORIZ. - TOP
(M04) S432	X	412	1'-7"	X		PARAPET RETROFIT - VERT.
(M04) S433	X	412	2'-1"	X		PARAPET RETROFIT - VERT.
(M04) S434	X	412	2'-8"	X		PARAPET RETROFIT - VERT.
S435	X	40	42'-5"			PARAPET RETROFIT - HORIZ.

- (M02) ADHESIVE ANCHORS NO. 4 BAR. EMBED 6" IN CONCRETE.
- (M03) ADHESIVE ANCHORS NO. 5 BAR. EMBED 1'-0" IN CONCRETE.
- (M04) ADHESIVE ANCHORS NO. 4 BAR. EMBED 10" IN CONCRETE.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY		JLR	PLANS CHECKED ETP
BAR DETAILS		SHEET 8	



BRIDGE PARAPET ELEVATION
LOOKING AT FRONT FACE




CURB REPAIR DETAIL

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY JLR		PLANS CK'D. ETP	
CLEANING PARAPETS & CURB REPAIR			SHEET 9



**TYPICAL
BOTH ABUTMENTS**

**TYPICAL
BOTH ABUTMENTS**

SECTION F-F

PLAN
SHOWING EAST ABUTMENT
WEST ABUTMENT SIMILAR

SLOPE PAVING REPAIR TO BE DONE ACCORDING TO ENGINEER.


AREAS WITH SIGNIFICANT EROSION SHOULD BE FILLED WITH BACKFILL BEFORE PLACEMENT OF CRUSHED AGGREGATE. COST INCIDENTAL TO "SLOPE PAVING REPAIR SELECT CRUSHED AGGREGATE" BID ITEM.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY JLR		PLANS CK'D. ETP	
SLOPE REPAIR		SHEET 10	

8

8


SCALE = 7.00



PLAN



PATCHING



DELAMINATION DETECTED BY IR



REBAR DETERIORATION DETECTED BY GPR

NOTE: THIS SHEET IS FOR INFORMATION ONLY. ENGINEER SHALL DETERMINE LOCATIONS OF DECK REPAIR.


INSPECTION DATE - NOV/2021

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-8-9			
DRAWN BY		JLR	PLANS CK'D. ETP
DECK SCANS		SHEET 11	



8



8

SCALE = 10.00





PROJECT NO: 4085-60-71 HWY: STH 32 COUNTY: CALUMET CROSS SECTIONS: SHEET E







PROJECT NO: 4085-60-71	HWY: STH 32	COUNTY: CALUMET	CROSS SECTIONS:	SHEET	E
------------------------	-------------	-----------------	-----------------	-------	----------





9 9

PROJECT NO: 4085-60-71 HWY: STH 32 COUNTY: CALUMET CROSS SECTIONS: SHEET **E**




9 9

PROJECT NO: 4085-60-71 HWY: STH 32 COUNTY: CALUMET CROSS SECTIONS: SHEET E



Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>