

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

TOMAH - MAUSTON

CTH M BRIDGES B-29-48 & B-29-49

IH 090

JUNEAU COUNTY

STATE PROJECT NUMBER
1016-04-63

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
1016-04-63		

ORDER OF SHEETS





Section No. 1	Title	
Section No. 2	Typical Sections and Details	
Section No. 3	Estimate of Quantities	
Section No. 3	Miscellaneous Quantities	
Section No. 4	Right of Way Plat	
Section No. 5	Plan and Profile	
Section No. 6	Standard Detail Drawings	
Section No. 7	Sign Plates	
Section No. 8	Structure Plans	
Section No. 9	Computer Earthwork Data	
Section No. 9	Cross Sections	

TOTAL SHEETS = 48




DESIGN DESIGNATION	IH 90/94	CTH M
A.A.D.T. (2025)	= 36,800	470
A.A.D.T. (2045)	= 40,400	470
D.H.V.	= 19.9	
D.D.	= 58/42	
T.	= 40.7	10
DESIGN SPEED	= 70 MPH	50 MPH
ESALS	= 33,000,000	110,000

CONVENTIONAL SYMBOLS

PLAN CORPORATE LIMITS PROPERTY LINE LOT LINE LIMITED HIGHWAY EASEMENT EXISTING RIGHT OF WAY PROPOSED OR NEW R/W LINE SLOPE INTERCEPT REFERENCE LINE EXISTING CULVERT PROPOSED CULVERT (Box or Pipe) COMBUSTIBLE FLUIDS MARSH AREA WOODED OR SHRUB AREA	            	PROFILE GRADE LINE ORIGINAL GROUND MARSH OR ROCK PROFILE (To be noted as such) SPECIAL DITCH GRADE ELEVATION CULVERT (Profile View) UTILITIES ELECTRIC FIBER OPTIC GAS SANITARY SEWER STORM SEWER TELEPHONE WATER UTILITY PEDESTAL POWER POLE TELEPHONE POLE
---	---	---

BEGIN PROJECT
STA. 15+58
X = 455,964.045
Y = 175,298.001

END PROJECT
STA. 28+20
X = 456,640.976
Y = 175,279.277



SCALE 0 1 MILE

TOTAL NET LENGTH OF CENTERLINE = 0.000 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, JUNEAU COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY	
Surveyor	WSDOT
Designer	BRIAN DAHL
Project Manager	CORY MIKSHOWSKY
Regional Examiner	SW REGION
Regional Supervisor	JOHN BANTER

APPROVED FOR THE DEPARTMENT
DATE: 4/4/2024 
(Signature)

E

PROJECT ID: 1016-04-63

COUNTY: JUNEAU

01

GENERAL NOTES

- THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.
- THERE ARE UTILITY FACILITIES WITHIN THE PROJECT AREA THAT ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL COORDINATE THEIR CONSTRUCTION ACTIVITIES WITH A CALL TO DIGGERS HOTLINE AND/OR A DIRECT CALL TO THE UTILITIES THAT HAVE FACILITIES IN THE AREA. NOT ALL UTILITIES ARE MEMBERS OF DIGGERS HOTLINE.
- PRIOR TO THE PLACEMENT OF STEEL PLATE BEAM GUARD OR MGS GUARDRAIL, THE SHOULDERS SHALL BE IN PLACE, SHAPED AND COMPACTED UNLESS SHOWN OTHERWISE.
- HMA PAVEMENT WEIGHT CALCULATIONS ARE BASED ON 112 LB/SY/IN.
- DISTURBED AREAS WITHIN THE RIGHT OF WAY ARE TO BE TOPSOILED (SALVAGED), FERTILIZED, SEEDED, AND MULCHED OR SODDED AS DIRECTED BY THE ENGINEER.
- APPLY TACK COAT AT A RATE OF 0.07 GAL/SY TO MILLED PAVEMENT SURFACES AND 0.05 GAL/SY BETWEEN LAYERS OF NEW HMA PAVEMENT

STANDARD ABBREVIATIONS

AC	ACRE	LC.	LONG CHORD
AGG	AGGREGATE	LS	LUMP SUM
<	ANGLE	M.P.	MARKER POST
AE, AEW	APRON ENDWALL	MGAL	1000 GALLONS
ASPH.	ASPHALTIC	N.C.	NORMAL CROWN
A.D.T.	AVERAGE DAILY TRAFFIC	N	NORTH
A.A.D.T.	ANNUAL AVERAGE DAILY TRAFFIC	NB	NORTHBOUND
B.F.	BACK FACE	NOR	NORMAL
BM	BENCHMARK	NO.	NUMBER
BTWN	BETWEEN	PAV/T	PAVEMENT
CTR.	CENTER	P.L.E.	PERMANENT LIMITED EASEMENT
C/L	CENTER LINE	P.C.	POINT OF CURVATURE
Δ	CENTRAL ANGLE OR DELTA	P.I.	POINT OF INTERSECTION
C.E.	COMMERCIAL ENTRANCE	P.T.	POINT OF TANGENCY
CONST.	CONSTRUCTION	PCC	PORTLAND CEMENT CONCRETE
CMCP	CORRUGATED METAL CULVERT PIPE	P.E.	PRIVATE ENTRANCE
CMP	CORRUGATED METAL PIPE	PGL	PROFILE GRADE LINE
CO.	COUNTY	P.L.	PROPERTY LINE
CTH	COUNTY TRUNK HIGHWAY	R	RADIUS OR RANGE
CR.	CREEK	R/L	REFERENCE LINE
CABC	CRUSHED AGGREGATE BASE COURSE	R.C.C.P.	REINFORCED CONCRETE CULVERT PIPE
CY	CUBIC YARD	REQ'D	REQUIRED
CP	CONTROL POINT OR CULVERT PIPE	RT	RIGHT
C&G	CURB AND GUTTER	R.H.F.	RIGHT HAND FORWARD
D	DEGREE OF CURVE	R/W	RIGHT OF WAY
D.H.V.	DESIGN HOURLY VOLUME	RD.	ROAD
DIA.	DIAMETER	SHLD.	SHOULDER(S)
D.D.	DIRECTIONAL DISTRIBUTION	SHR.	SHRINKAGE
DISCH.	DISCHARGE	S	SOUTH
DMS	DYNAMIC MESSAGE SIGN	SB	SOUTHBOUND
EA	EACH	S.F.	SQUARE FOOT (FEET)
E	EAST	SDD	STANDARD DETAIL DRAWING(S)
EB	EASTBOUND	STH	STATE TRUNK HIGHWAY
ELEC.	ELECTRIC(AL), ELEC. CABLE	STA.	STATION
EL., ELEV.	ELEVATION	S.E.	SUPERELEVATION
ESALS	EQUIVALENT SINGLE AXLE LOADS	S/L	SURVEY LINE
EXC.	EXCAVATION	SYM	SYMMETRICAL
EXIST	EXISTING	T.	PERCENT TRUCKS
F.F.	FACE TO FACE	TEL.	TELEPHONE
FERT.	FERTILIZER	TEMP.	TEMPORARY
F.E.	FIELD ENTRANCE	T.L.E.	TEMPORARY LIMITED EASEMENT
F/L, F.L.	FLOW LINE	T.O.C.	TOP OF CURB
GALV.	GALVANIZE	TYP	TYPICAL
H.S.	HIGH STRENGTH	UNCL.	UNCLASSIFIED
CWT	HUNDRED WEIGHT	U.G.	UNDERGROUND (CABLE)
INL	INLET	VAR	VARIABLE
INTER.	INTERSECTION	V.C.	VERTICAL CURVE
IH	INTERSTATE HIGHWAY	V.P.C.	VERTICAL POINT OF CURVATURE
JT.	JOINT	V.P.I.	VERTICAL POINT OF INTERSECTION
LT	LEFT	V.P.T.	VERTICAL POINT OF TANGENCY
L.H.F.	LEFT HAND FORWARD	Wt.	WEIGHT
L.	LENGTH OF CURVE	W	WEST
L.F.	LINEAR FOOT(FEET)	WB	WESTBOUND

UTILITY CONTACTS

Kenneth Nine (1078 Contact)
 AT&T Legacy - Communication Line
 110 main Street
 Culver, In 46511
 574-842-8830
 knine@jmceainc.com

Doug Vosberg (1078 Contact)
 ATC Management, Inc. - Electricity-transmission
 5303 Fen Oak Dr
 Madison, WI 53718
 (608) 877-7650
 dvosberg@atcllc.com

Matt Riggs (1078 Contact)
 Oakdale Electric Cooperative - Electricity
 489 Oakwood St.
 Tomah, WI 54660
 (608) 372-8828
 mriggs@oakdalerec.com

DNR LIAISON

KAREN KALVELAGE
 ENVIRONMENTAL ANALYSIS & REVIEW SPECIALIST
 WISCONSIN DEPT. OF NATURAL RESOURCES
 WEST CENTRAL REGION
 3550 MORMON COULEE ROAD
 LA CROSSE, WI 54601
 608-785-9115
 karen.kalvelage@wisconsin.gov


DESIGN CONTACTS

CORY MIKSHOWSKY
 PROJECT MANAGER
 WISDOT SW REGION
 3550 MORMON COULEE RD
 LA CROSSE, WI 54601
 608-789-6335
 cory.mikshowsky@dot.wi.gov

BRIAN DAHL
 PROJECT DESIGNER
 WISDOT SW REGION
 3550 MORMON COULEE RD
 LA CROSSE, WI 54601
 608-785-9074
 brian.dahl@dot.wi.gov








TYPICAL EXISTING SECTION


CTH M (CUTLER ROAD)
 STA. 15+58 - STA. 19+26
 STA. 20+45 - STA. 22+79
 STA. 24+00 - STA. 28+19




TYPICAL PROPOSED SECTION

CTH M (CUTLER ROAD)
 STA. 15+58 - STA. 19+26
 STA. 20+45 - STA. 22+79
 STA. 24+00 - STA. 28+19


NOT TO SCALE




TYPICAL SECTION: IH 90/94 OUTSIDE LANE CLOSED
SLOPE PAVING REPAIR
STRUCTURE REPAIRS (AWAY FROM CENTERLINE)



TYPICAL SECTION: IH 90/94 OUTSIDE LANE CLOSED
STRUCTURE REPAIR (NEAR CENTERLINE)




TYPICAL SECTION: IH 90/94 MEDIAN LANE CLOSED
SLOPE PAVING REPAIR
STRUCTURE REPAIRS (AWAY FROM CENTERLINE)




TYPICAL SECTION: IH 90/94 MEDIAN LANE CLOSED
STRUCTURE REPAIR (NEAR CENTERLINE)

NOT TO SCALE



NOTE:
SILT FENCE POSTS FOR THE TURN-AROUND SHOULD
BE ON THE OUTSIDE OF THE TURN-AROUND.

PLAN VIEW



SIDE VIEW

TEMPORARY SMALL ANIMAL TURN-AROUND

GENERAL NOTES:
SILT FENCE POSTS FOR THE TURN-AROUND SHOULD BE ON THE OUTSIDE OF THE
TURN-AROUND AND TRENCHED IN ACCORDING TO SILT FENCE REQUIREMENTS.

Estimate Of Quantities By Plan Sets

1016-04-63

Line	Item	Item Description	Unit	Total	Qty
0006	204.0110	Removing Asphaltic Surface	SY	2,510.000	2,510.000
0008	204.0165	Removing Guardrail	LF	1,920.000	1,920.000
0010	204.0175	Removing Concrete Slope Paving	SY	720.000	720.000
0012	213.0100	Finishing Roadway (project) 01. 1016-04-63	EACH	1.000	1.000
0016	305.0110	Base Aggregate Dense 3/4-Inch	TON	40.000	40.000
0018	455.0605	Tack Coat	GAL	200.000	200.000
0020	460.2000	Incentive Density HMA Pavement	DOL	180.000	180.000
0022	460.5224	HMA Pavement 4 LT 58-28 S	TON	281.000	281.000
0024	509.1500	Concrete Surface Repair	SF	100.000	100.000
0036	604.0400	Slope Paving Concrete	SY	720.000	720.000
0038	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	453.000	453.000
0040	614.0010	Barrier System Grading Shaping Finishing	EACH	4.000	4.000
0042	614.2300	MGS Guardrail 3	LF	1,400.000	1,400.000
0044	614.2500	MGS Thrie Beam Transition	LF	320.000	320.000
0046	614.2610	MGS Guardrail Terminal EAT	EACH	4.000	4.000
0048	618.0100	Maintenance and Repair of Haul Roads (project) 01. 1016-04-63	EACH	1.000	1.000
0052	619.1000	Mobilization	EACH	0.600	0.600
0054	624.0100	Water	MGAL	1.000	1.000
0056	628.1504	Silt Fence	LF	1,200.000	1,200.000
0058	628.1520	Silt Fence Maintenance	LF	1,200.000	1,200.000
0060	628.1905	Mobilizations Erosion Control	EACH	2.000	2.000
0062	628.1910	Mobilizations Emergency Erosion Control	EACH	2.000	2.000
0064	643.0300	Traffic Control Drums	DAY	700.000	700.000
0066	643.0420	Traffic Control Barricades Type III	DAY	210.000	210.000
0068	643.0705	Traffic Control Warning Lights Type A	DAY	420.000	420.000
0070	643.0715	Traffic Control Warning Lights Type C	DAY	170.000	170.000
0072	643.0800	Traffic Control Arrow Boards	DAY	20.000	20.000
0074	643.0900	Traffic Control Signs	DAY	130.000	130.000
0076	643.1050	Traffic Control Signs PCMS	DAY	60.000	60.000
0078	643.1205.S	Basic Traffic Queue Warning System	DAY	10.000	10.000
0080	643.5000	Traffic Control	EACH	0.600	0.600
0082	646.2020	Marking Line Epoxy 6-Inch	LF	2,520.000	2,520.000
0084	690.0150	Sawing Asphalt	LF	48.000	48.000
0086	SPV.0060	Special 01. Tubular Rail and Posts Spot Cleaning and Painting B-29-48	EACH	1.000	1.000
0088	SPV.0060	Special 02. Tubular Rail and Posts Spot Cleaning and Painting B-29-49	EACH	1.000	1.000
0090	SPV.0060	Special 03. Verify Landmark Reference Monuments	EACH	1.000	1.000
0094	SPV.0070	Special 01. Epoxy Injection PC Overlay B-29-48	GAL	71.000	71.000
0096	SPV.0070	Special 02. Epoxy Injection PC Overlay B-29-49	GAL	84.000	84.000

3

3

ASPHALT SUMMARY

STATION	TO	STATION	LOCATION	204.0110 REMOVING ASPHALTIC SURFACE SY	305.0110 BASE AGGREGATE DENSE 3/4- INCH TON	455.0605 TACK COAT GAL	460.5224 HMA PAVEMENT 4 LT 58-28 S TON	624.0100 WATER MGAL	690.0150 SAWING ASPHALT LF	REMARKS
15+58	-	19+26	NORTH APPROACH	900	10	70	101	0.2	24	
20+45	-	22+79	MEDIAN	580	10	50	65	0.2	-	
24+00	-	28+19	SOUTH APPROACH	1,030	20	80	115	0.4	24	
TOTAL 0010				2,510	40	200	281	1	48	

GUARDRAIL SUMMARY

STATION	TO	STATION	LOCATION	204.0165 REMOVING GUARDRAIL LF	614.0010 BARRIER SYSTEM GRADING SHAPING FINISHING EACH	614.2300 MGS GUARDRAIL 3 LF	614.2500 MGS THRIE BEAM TRANSITION LF	614.2610 MGS GUARDRAIL TERMINAL EAT EACH	REMARKS
15+58	-	19+16	CTH M	320	1	230	40	1	WEST END, RIGHT SIDE
15+79	-	19+26	CTH M	540	1	450	40	1	WEST END, LEFT SIDE
20+45	-	22+70	CTH M	225	-	145	80	-	MEDIAN, RIGHT SIDE
20+54	-	22+79	CTH M	225	-	145	80	-	MEDIAN, LEFT SIDE
24+00	-	28+19	CTH M	280	1	190	40	1	EAST END, RIGHT SIDE
24+08	-	28+18	CTH M	330	1	240	40	1	EAST END, LEFT SIDE
TOTAL 0010				1,920	4	1,400	320	4	

PAVEMENT MARKING

STATION	TO	STATION	LOCATION	646.2020 MARKING LINE EPOXY 6-INCH LF	REMARKS
15+58	-	28+19	CTH M	2,520	DOUBLE YELLOW CENTERLINE
TOTAL				2,520	

EROSION CONTROL SUMMARY


STATION	TO	STATION	LOCATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL EACH	REMARKS
-	-	-	PROJECT	-	-	2	2	
15+79	-	17+47	CTH M LT	300	300	-	-	
15+58	-	17+25	CTH M RT	300	300	-	-	
26+50	-	28+18	CTH M LT	300	300	-	-	
26+51	-	28+19	CTH M RT	300	300	-	-	
TOTAL 0010				1,200	1,200	2	2	

FOR REFERENCE ONLY

LOCATION	BARRIERS SYSTEM GRADING, SHAPING, FINISHING							REMARKS
	205.0100 EXCAVATION COMMON CY	208.0100 BORROW CY	625.0100 TOPSOIL SY	627.0200 MULCHING SY	629.0205 FERTILIZER TYPE A CWT	630.0110 SEEDING MIXTURE NO. 10 LB	630.0500 SEED WATER MGAL	
CTH M:								
NW QUADRANT	1	77	660	660	0.41	9	15	
SW QUADRANT	2	210	490	490	0.31	7	11	
NE QUADRANT	1	125	560	560	0.35	8	13	
SE QUADRANT	3	145	510	510	0.32	7	11	
TOTAL 0010	7	557	2,220	2,220	1	31	50	

TRAFFIC CONTROL SUMMARY


STATION	TO	STATION	LOCATION	SERVICE DAYS	643.0300 TRAFFIC CONTROL DRUMS DAY	643.0420 TRAFFIC CONTROL BARRICADES TYPE III QTY	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A QTY	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C QTY	643.0800 TRAFFIC CONTROL ARROW BOARDS DAY	643.0900 TRAFFIC CONTROL SIGNS DAY	643.1050 TRAFFIC CONTROL SIGNS PCMS DAY	643.1205.S BASIC TRAFFIC QUEUE WARNING SYSTEM DAY	REMARKS						
15+58	-	28+19	CTH M	20	13	260	10	200	20	400	-	-	-	2	40	60	-	CLOSED ROAD	
451+00E	-	509+50E	IH 90 EB RT	3	44	132	1	3	2	6	17	51	2	6	9	27	0	3	LANE CLOSURE
451+00E	-	509+50E	IH 90 EB LT	2	44	88	1	2	2	4	17	34	2	4	9	18	0	2	LANE CLOSURE
496+50W	-	555+00W	IH 90 WB RT	3	44	132	1	3	2	6	17	51	2	6	9	27	0	3	LANE CLOSURE
496+50W	-	555+00W	IH 90 WB LT	2	44	88	1	2	2	4	17	34	2	4	9	18	0	2	LANE CLOSURE
TOTAL 0010					700	210	420	170	20	130	60	10							



LEGEND

- xxxx xxxx SAWING ASPHALT
- SILT FENCE

PROJECT NO: 1016-04-63	HWY: IH-90	COUNTY: JUNEAU	PLAN VIEW	SHEET	E
------------------------	------------	----------------	-----------	-------	----------



MGS GUARDRAIL 3
MGS THRIE BEAM TRANSITION
STA. 20+54 TO STA. 22+79

MGS GUARDRAIL 3
MGS THRIE BEAM TRANSITION
STA. 20+45 TO STA. 22+70

STRUCTURE B-29-49
SEE STRUCTURE PLANS

AT&T LEGACY COMMUNICATION

OAKDALE ELECTRIC

MGS GUARDRAIL TERMINAL EAT
BARRIER SYSTEM GRADING SHAPING FINISHING
SILT FENCE, REQ'D
STA. 26+50 TO STA. 28+18

REMOVING GUARDRAIL
MGS GUARDRAIL 3
MGS THRIE BEAM TRANSITION
STA. 24+08 TO STA. 26+50

REMOVING GUARDRAIL
MGS GUARDRAIL 3
MGS THRIE BEAM TRANSITION
STA. 24+00 TO STA. 26+51

MGS GUARDRAIL TERMINAL EAT
BARRIER SYSTEM GRADING SHAPING FINISHING
SILT FENCE, REQ'D
STA. 26+51 TO STA. 28+19

END PROJECT
STA 28+19
MATCH EXISTING
SAW CUT REQ'D

POST 9 POST 5 POST 1

POST 9 POST 5 POST 1

SIGN


LEGEND

XXXX XXXX SAWING ASPHALT


SILT FENCE

Standard Detail Drawing List

08E09-06	SILT FENCE
13C19-03	HMA LONGITUDINAL JOINTS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15C02-09A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-09B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C06-12	SIGNING & MARKING FOR TWO LANE BRIDGES
15C08-23A	PERMANENT LONGITUDINAL PAVEMENT MARKINGS
15C11-10B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15D12-12A	TRAFFIC CONTROL, LANE CLOSURE, WITH TEMPORARY RUMBLE STRIPS
15D12-12D	TRAFFIC CONTROL, PARALLEL ENTRANCE RAMP WITHIN LANE CLOSURE



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.


- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL



SILT FENCE




JOINING TWO LENGTHS OF SILT FENCE ⑤




SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)


SILT FENCE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 4-29-05 DATE	/S/ Beth Canestra CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA	



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY $0.1"$ AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO $2"$ FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)

6










6

SDD 13C19 - 03

SDD 13C19 - 03


HMA LONGITUDINAL JOINTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2020 DATE	/S/ Steven Hefel HMA PAVEMENT ENGINEER
FHWA	

- ① WOOD OR STEEL POSTS (w6X9 OR w6X8.5) MAY BE USED. DO NOT INTERMIX WOOD AND STEEL POSTS. INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- ② USE WOOD OR APPROVED PLASTIC BLOCKOUTS. WOOD BLOCKOUTS MAY BE CONSTRUCTED OUT OF TWO OR MORE WOOD BLOCKOUTS. SEE ALTERNATE WOOD BLOCKOUT DETAIL. DIMENSIONS OF APPROVED PLASTIC BLOCKOUTS MAY VARY.
- ③ IF ROCK IS ENCOUNTERED DURING EXCAVATION, PROVIDE A HOLE 12 INCHES IN DIAMETER EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE APPROXIMATELY 2 1/2" INCHES OF GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE. CUT THE POSTS THE TO LENGTH AND INSTALL. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT. BACKFILL IS TO BE FREE OF LARGE ROCKS.
- ④ WHEN THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING (K).
- ⑤ FOR NEW MGS INSTALLATION TOP OF W-BEAM RAIL TOLERANCE IS $\pm 1"$. FOR EXISTING MGS INSTALLATION TOP OF W-BEAM IS BETWEEN 27 3/4" TO 32".
- ⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ⑦ TOTAL POST LENGTH FOR TYPE K IS 7' - 0". TOTAL POST LENGTH FOR OTHER MGS TYPES IS 6' - 0".




**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
MID-SPAN BEAM SPLICE**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 3/8" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAIL



**FRONT VIEW
QUARTER POST SPACING (QS)**



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

SDD 14B42 - 07b

SDD 14B42 - 07b





DETAIL FOR 16" BLOCKOUT DEPTH


IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.

NOTE:


1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 3/16".
2. IF THE BOLT EXTENDS MORE THAN 1/4" FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.



**PLAN VIEW
BEAM LAPPING DETAIL**



**POST DRIVING FOR CONTINUOUS
UNDERGROUND OBSTRUCTION**




DETAIL FOR 36" BLOCKOUT DEPTH


NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.
DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.

POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"




ALTERNATE BOLT HEAD



**POST BOLT, SPLICE BOLT
AND RECESS NUT**



SIDE VIEW




PLAN VIEW

**ALTERNATE WOOD
BLOCKOUT DETAIL**


6 WHEN USING STEEL POST AND WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL)

- ④00 MAX SPAN 12' - 6"
- ④01 2' MIN.
- ④02 MGS GUARDRAIL 3
- ④03 NESTING BEAM GUARD
- ④04 ASYMMETRIC TRANSITION
- ④05 SOIL WELL DRAINED AND COMPACTED
- ④06 SEE OTHER DRAWINGS IN THIS SDD
- ④07 SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
- ④08 SEE SDD 14B44
- ④09 SEE SDD 14B45
- ④10 SEE SDD 14B47
- ④11 MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

6

6

SDD 14B42 - 07d

SDD 14B42 - 07d

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/s/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
 - (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
 - (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
 - (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
 - (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.
- DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.

SEE SDD 14B42 FOR MORE INFORMATION.


* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.

DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.


SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.

THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.


CLEAR ZONE LIMITS, EITHER AS SHOWN ELSEWHERE IN THE PLANS OR, IF NOT SHOWN ELSEWHERE IN THE PLANS, 15 FEET BEYOND THE HINGE POINT LINE




PLAN




ELEVATION




DETAIL "A"




**SECTION C - C
TYPICAL AT POST NOS. 3 - 9**



**SECTION B - B
TYPICAL AT POST NO. 2***



**SECTION A - A
TYPICAL AT POST NO. 1***



DETAIL "B"

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

SDD 14B44 - 04a


SDD 14B44 - 04a

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2




GENERIC GROUND STRUT ⑨ ⑤




GENERIC ANCHOR CABLE BOX ⑨ ⑤




BEARING PLATE ⑥ ⑤




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9



UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)



WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2


6




W5 - 59
REFLECTIVE SHEETING DETAIL ^(E)

TYPE H
YELLOW REFLECTIVE
SHEETING 3" X 9".
SEE STANDARD
SPECIFICATION 637.


E.A.T. MARKER
POST (YELLOW)



FRONT VIEW SIDE VIEW
E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW



TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

6

SDD 14B44 - 04c


SDD 14B44 - 04c

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR

FHWA



TWO WAY TRAFFIC



ONE WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES


IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY

- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ④ TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42




**SECTION A-A
POSTS 1-5**



**SECTION B-B
POST 6**



**SECTION C-C
POSTS 7-11**



**THRIE BEAM
TERMINAL CONNECTOR**






PLATE WASHER DETAIL




SPLICE DETAIL




**SECTION THRU THRIE
BEAM RAIL ELEMENT**

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3\"/>




12'-6\"/>





ALTERNATE WOOD BLOCKOUT DETAIL





STEEL POSTS 1-5



STEEL POSTS 6-17



BLOCKOUT POSTS 1-5



BLOCKOUT POSTS 6-17

GENERAL NOTES

- STEEL POSTS ARE W6X9 OR W6X8.5.
- BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

S.D.D. 14 B 45-5c

S.D.D. 14 B 45-5c





FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS

SECTION E-E

GENERAL NOTES


- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
 - (4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
 - (6) DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - (7) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - (8) THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".



FRONT VIEW

**W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**

SECTION F-F



DRILL HOLE LOCATION

6

6

S.D.D. 14 B 45-5d


S.D.D. 14 B 45-5d

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PAPAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET

(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



SECTION G-G



FRONT VIEW

THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS


- ⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE) WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER 7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED 1" DIA. HOLES DRILLED THRU PARAPET (4 REQ'D.)

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

ONE WAY
TRAFFIC



WHEN RETROFITTING A TRANSITION TO AN EXISTING RIGID BARRIER, INSTALL PLATE WASHERS ON BACKSIDE OF RIGID BARRIER.


FRONT VIEW

W BEAM CONNECTION TO PARAPETS WITH SLOPED ENDS


(USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)

GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.




DRILL HOLE LOCATION AND PATTERN FOR THRIE BEAM CONNECTION



WHEN RETROFITTING A TRANSITION TO AN EXISTING RIGID BARRIER, INSTALL PLATE WASHERS ON BACKSIDE OF RIGID BARRIER.

FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPETS WITH SLOPED ENDS




SECTION I-I


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



BACK-UP PLATE DETAIL




SECTION J-J




BACK-UP PLATE MOUNTING ONTO BRIDGE RAILING

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1'$.
- ⑥ DRILLING HOLES THROUGH THE PAPER, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




**FRONT VIEW
THRIE BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**THRIE BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


(4) TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".



FRONT VIEW




**PLAN VIEW
BACK-UP PLATE DETAIL, TYPE "M"**




FRONT VIEW

**ANCHOR
PLATE DETAIL,
TYPE "M"**




SECTION M-M



SECTION L-L


FRONT VIEW

ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW

M



PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES

- COVER PLATE PANELS ARE 3/16" THICK.
- ALL STIFFENERS ARE 1/4" THICK.
- CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.
- FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.
- ALL HOLE DIAMETERS SHALL BE 1".
- FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

- (10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND 3/16" FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.
- (11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
3/16" FILLET WELD BY 1" LONG SPACED AT 2".



WELDING INSTRUCTION
(VIEWED FROM BACK SIDE OF PLATE)




PLATE AND STIFFENER IDENTIFICATION
(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 3/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 7/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 1/16" x 10 3/8" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 3/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 7/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 3/16" x 6" x 3 5/8" x 5 7/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 3/32"	1/4"
S10	1		1 7/8" x 9 7/8" x 3 3/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 3/16"	1/4"

SINGLE SLOPE CONNECTION PLATE

**MIDWEST GUARDRAIL SYSTEM
THREE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
7/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.



⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTION PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER



SECTION N-N




SINGLE SLOPE CONNECTION PLATE PLACEMENT


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



**ELEVATION OF DETAIL AT NY3 END POST
THRIE BEAM RAIL ATTACHMENT**



**ELEVATION OF DETAIL AT NY4 END POST
THRIE BEAM RAIL ATTACHMENT**


GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

APPROVED
 DATE 7/2018 /S/ Rodney Taylor
 ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR
 FHWA



**DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

**DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR**


WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750

- M4 - 8
- M3 - X
- M1 - 4
- M1 - 6
- M1 - 5A
- M05 - 1
- M06 - 1



**DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR**


SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦

**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidtke
DATE DATE WORK ZONE ENGINEER

FHWA



**DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW**



**DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW**

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:


- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.


**BARRICADES AND SIGNS
FOR
VARIOUS CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER



SITUATION 1
 WARRANTING CRITERIA:
 BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.



SITUATION 2
 WARRANTING CRITERIA:
 1. BRIDGE WIDTH IS AT LEAST 24 FEET AND
 2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THE DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W5-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.

ON BRIDGE ONLY PROJECTS, PLACE 300 FEET OF EDGELINE.

OMIT EDGELINES ON ROADWAYS WITHOUT EXISTING EDGELINES.

① OMIT ON ONE-WAY TRAVELED WAYS.

LEGEND

- SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC

DISTANCE TABLE

POSTED OR 85TH PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	700'

SIGNING AND MARKING FOR TWO LANE BRIDGES

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

APPROVED
 May 2023 /S/ Jeannie Silver
 DATE ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR

FHWA

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.


LEGEND

-  "T" MARKING
-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC

* CONFIRM MARKING LINE WIDTH WITH THE MISCELLANEOUS QUANTITIES



TWO WAY TRAFFIC



ONE WAY TRAFFIC

PERMANENT PAVEMENT MARKING

6

6

SDD 15C08-23a

SDD 15C08-23a

PERMANENT LONGITUDINAL PAVEMENT MARKINGS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Jeannie Silver
DATE STATEWIDE SIGNING AND MARKING ENGINEER

FHWA


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.




DRUM

BALLAST WIDTHS
RANGE FROM 24"-36"




42" CONE

DO NOT USE IN TAPERS
½ SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2022 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.

ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.


CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TYPE "A" WARNING LIGHT (FLASHING)
-  REMOVING PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLASHING ARROW BOARD

6

SDD 15D12-12a



6

SDD 15D12-12a

TRAFFIC CONTROL LANE CLOSURE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED September 2023 DATE	/s/ Andrew Heidtke ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TYPE "A" WARNING LIGHT (FLASHING)
-  REMOVING PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLASHING ARROW BOARD
-  PORTABLE TRAFFIC SENSOR (PTS)
-  FLASHING BEACON SIGN

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS, INCLUDING FBS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER. NO WARNING LIGHTS SHALL BE WORKING ON "COVERED" OR "DOWNED" SIGNS.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS. WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.


IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.

CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

PORTABLE TRAFFIC SENSOR (PTS) MAY BE MOUNTED ON THE FBS, ARROW BOARD OR OTHER TRAILER DEVICES.

- ① 5 DRUMS SPACED AT 10 FOOT INTERVALS AS NEEDED.
- ② IF THERE ARE MORE THAN TWO LANES OR IF SPECIFIED IN THE PLANS, PLACE FBS ON BOTH SIDES OF THE ROADWAY.
- ③ IF THERE IS AN APPROVED TEMPORARY SPEED DECLARATION, ADD WO-3-5 SIGNS 400 FEET AFTER THE W20-5G SIGNS AND ADD R2-1 SIGNS (48"x60") 700 FEET AFTER THE WO3-5 SIGNS. A SPEED LIMIT SIGN SHALL BE LOCATED 1500 FEET BEYOND THE END OF THE ACCELERATION LANE OF EACH ENTRANCE RAMP. PLACE A SPEED LIMIT SIGN A MINIMUM OF EVERY 3 MILES. INCLUDE A "RESUME SPEED LIMIT" SIGN 200 FEET MINIMUM (800 FEET DESIRABLE) BEYOND THE G30-3A "END ROAD WORK" SIGN.




SDD 15D12-12d

SDD 15D12-12d

TRAFFIC CONTROL, LANE CLOSURE, BASIC TRAFFIC QUEUE WARNING SYSTEM	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED September 2023 DATE	/s/ Erin Schwark ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

INDICATES WING NUMBER



PLAN

3 SPAN - HAUNCHED CONCRETE SLAB

DESIGN DATA

LIVE LOAD:

INVENTORY RATING: HS-11
 OPERATING RATING: HS-19
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 110 (KIPS)
 (3/15/2017 RATING, FROM HS15)

MATERIAL PROPERTIES:

CONCRETE MASONRY:
 SUPERSTRUCTURE $f'_c = 4,000$ PSI
 ALL OTHER $f'_c = 3,500$ PSI

TRAFFIC DATA

CTH M:

ADT = 470 (2010)
 R.D.S. = 50 MPH

IH 90 EB:

ADT = 17,300 (2016)
 R.D.S. = 70 MPH

GENERAL NOTES

DRAWING SHALL NOT BE SCALED.

CHAMFER EXPOSED EDGES OF CONCRETE $\frac{3}{4}$ " UNLESS SPECIFIED OTHERWISE.


DIMENSIONS SHOWN ARE BASED ON ORIGINAL STRUCTURE PLANS.

ANY EXCAVATION NECESSARY TO COMPLETE CONCRETE SURFACE REPAIRS IS CONSIDERED INCIDENTAL TO BID ITEM "CONCRETE SURFACE REPAIR".

TUBULAR RAIL AND POSTS SPOT CLEANING AND PAINTING, AS DIRECTED BY ENGINEER OVER LENGTH OF ENTIRE BRIDGE. FINISH COLOR SHALL BE SIMILAR TO EXISTING, AND APPROVED BY ENGINEER.

LEGEND

- CONCRETE SURFACE REPAIR REQUIRED. LOCATIONS NOTED MAY NOT BE ALL INCLUSIVE, AND QUANTITIES SHOWN ON SHEET ARE APPROXIMATE. ADDITIONAL REPAIRS MAY BE REQUIRED DURING CONSTRUCTION AND SHOULD BE PERFORMED AS DIRECTED BY THE FIELD ENGINEER.
- REMOVE & REPLACE EXIST. CONC. SLOPE PAVING. SEE "SLOPE PAVING CONCRETE" SHEET FOR DETAILS.
- ▨ ESTIMATED OVERLAY EPOXY INJECTION REPAIR AREAS. SURVEY TYPE: ADVANCED BRIDGE INSPECTION (ABI) RAPID AUTOMATED SOUNDING (RAS). INSPECTION DATE: 5/13/21.
- ▩ ESTIMATED OVERLAY EPOXY INJECTION REPAIR AREAS. SURVEY TYPE: INFRARED (IR) THERMOGRAPHIC SURVEY. INSPECTION DATE: 8/17/21.



ELEVATION


(LOOKING WEST)

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	TOTALS
204.0175	REMOVING CONCRETE SLOPE PAVING	SY	363
509.1500	CONCRETE SURFACE REPAIR	SF	50
604.0400	SLOPE PAVING CONCRETE	SY	363
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	227
SPV.0060	TUBULAR RAIL AND POSTS SPOT CLEANING AND PAINTING B-29-48	EACH	1
SPV.0070	EPOXY INJECTION CONCRETE OVERLAY REPAIR B-29-48	GAL	71

STRUCTURE DESIGN CONTACTS:

ALEX CRABTREE (608) 266-3686
 KYLE BUSCH (608) 267-0465



CROSS SECTION THRU ROADWAY

(LOOKING NORTH)

LIST OF DRAWINGS:

1. GENERAL PLAN
2. SLOPE PAVING CONCRETE

NO.	DATE	REVISION	BY

BUREAU OF STRUCTURES

ACCEPTED *[Signature]* 7/26/23
 CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-29-48


CTH M OVER IH 90/94 EB

COUNTY JUNEAU TOWN LISBON


DESIGN SPEC. REHABILITATION

DESIGNED BY ARC CK'D MWB DRAWN BY MJH PLANS CK'D MWB

GENERAL PLAN SHEET 1 OF 2



SECTION A-A




RODENT SHIELD DETAIL


* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".


THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.



CONSTRUCTION JOINT



PLAN



TYPICAL SECTION

PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN


NOTE

BID ITEMS SHALL BE "SLOPE PAVING CONCRETE" AND "PIPE UNDERDRAIN WRAPPED 6-INCH"

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-29-48			
DRAWN BY MJH		PLANS CK'D MWB	
SLOPE PAVING CONCRETE			SHEET 2


SCALE =

INDICATES WING NUMBER




PLAN

3 SPAN - HAUNCHED CONCRETE SLAB



ELEVATION

(LOOKING WEST)



CROSS SECTION THRU ROADWAY

(LOOKING NORTH)

DESIGN DATA

LIVE LOAD:

INVENTORY RATING: HS-11
 OPERATING RATING: HS-19
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 110 (KIPS)
 (3/15/2017 RATING, FROM HSIS)

MATERIAL PROPERTIES:

CONCRETE MASONRY: _____
 SUPERSTRUCTURE _____ $f'_c = 4,000$ PSI
 ALL OTHER _____ $f'_c = 3,500$ PSI

TRAFFIC DATA

CTH M:

ADT = 470 (2010)
 R.D.S. = 50 MPH

IH 90 WB:

ADT = 17,300 (2016)
 R.D.S. = 70 MPH

GENERAL NOTES

DRAWING SHALL NOT BE SCALED.

CHAMFER EXPOSED EDGES OF CONCRETE $\frac{3}{4}$ " UNLESS SPECIFIED OTHERWISE.

DIMENSIONS SHOWN ARE BASED ON ORIGINAL STRUCTURE PLANS.

ANY EXCAVATION NECESSARY TO COMPLETE CONCRETE SURFACE REPAIRS IS CONSIDERED INCIDENTAL TO BID ITEM "CONCRETE SURFACE REPAIR".

TUBULAR RAIL AND POSTS SPOT CLEANING AND PAINTING, AS DIRECTED BY ENGINEER OVER LENGTH OF ENTIRE BRIDGE. FINISH COLOR SHALL BE SIMILAR TO EXISTING, AND APPROVED BY ENGINEER.

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	TOTALS
204.0175	REMOVING CONCRETE SLOPE PAVING	SY	357
509.1500	CONCRETE SURFACE REPAIR	SF	50
604.0400	SLOPE PAVING CONCRETE	SY	357
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	226
SPV.0060	TUBULAR RAIL AND POSTS SPOT CLEANING AND PAINTING B-29-49	EACH	1
SPV.0070	EPOXY INJECTION CONCRETE OVERLAY REPAIR B-29-49	GAL	84

LEGEND

- CONCRETE SURFACE REPAIR REQUIRED. LOCATIONS NOTED MAY NOT BE ALL INCLUSIVE, AND QUANTITIES SHOWN ON SHEET ARE APPROXIMATE. ADDITIONAL REPAIRS MAY BE REQUIRED DURING CONSTRUCTION AND SHOULD BE PERFORMED AS DIRECTED BY THE FIELD ENGINEER.
- REMOVE & REPLACE EXIST. CONC. SLOPE PAVING. SEE "SLOPE PAVING CONCRETE" SHEET FOR DETAILS.
- ▒ ESTIMATED OVERLAY EPOXY INJECTION REPAIR AREAS. SURVEY TYPE: ADVANCED BRIDGE INSPECTION (ABI) RAPID AUTOMATED SOUNDING (RAS). INSPECTION DATE: 5/13/21.
- ▨ ESTIMATED OVERLAY EPOXY INJECTION REPAIR AREAS. SURVEY TYPE: INFRARED (IR) THERMOGRAPHIC SURVEY. INSPECTION DATE: 8/17/21.

STRUCTURE DESIGN CONTACTS:

ALEX CRABTREE (608) 266-3686
 KYLE BUSCH (608) 267-0465

NO.	DATE	REVISION	BY

BUREAU OF STRUCTURES

ACCEPTED *[Signature]* 7/26/23
 CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-29-49

CTH M OVER IH 90/94 WB

COUNTY JUNEAU TOWN LISBON

DESIGN SPEC. REHABILITATION

DESIGNED BY ARC CK'D MWB DRAWN BY MJH PLANS CK'D MWB

GENERAL PLAN

SHEET 1 OF 2


LIST OF DRAWINGS:

1. GENERAL PLAN
2. SLOPE PAVING CONCRETE


8

8

SCALE =



SECTION A-A




RODENT SHIELD DETAIL


* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".


THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.



CONSTRUCTION JOINT



PLAN




TYPICAL SECTION

PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN





NOTE

BID ITEMS SHALL BE "SLOPE PAVING CONCRETE" AND "PIPE UNDERDRAIN WRAPPED 6-INCH"

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-29-49			
DRAWN BY MJH		PLANS CK'D MWB	
SLOPE PAVING CONCRETE			SHEET 2



PROJECT NO: 1016-04-63 HWY: IH-90 COUNTY: JUNEAU CROSS SECTIONS: CTH M SHEET: E



PROJECT NO: 1016-04-63


HWY: IH-90

COUNTY: JUNEAU

CROSS SECTIONS: CTH M

SHEET

E



9


9

PROJECT NO: 1016-04-63	HWY: IH-90	COUNTY: JUNEAU	CROSS SECTIONS: CTH M	SHEET	E
------------------------	------------	----------------	-----------------------	-------	---

FILE NAME : C:\BOXDRV\BOX\BRIAN DAHL\BOX-C3D\10160433\DESIGN\SURFAES\BG-SURFACE4.DWG PLOT DATE : 7/25/2023 12:35 PM PLOT BY : DAHL, BRIAN D PLOT NAME : PLOT SCALE : 1 IN:20 FT HORZ. / 1 IN:20 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 03

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

TOMAH - MAUSTON

43RD STREET BRIDGES B-29-41 & B-29-42

IH 090

JUNEAU COUNTY

STATE PROJECT NUMBER
1016-05-65

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
1016-05-65		

ORDER OF SHEETS

- Section No. 1 Title
- Section No. 2 Typical Sections and Details
- Section No. 3 Estimate of Quantities
- Section No. 3 Miscellaneous Quantities
- ~~Section No. 4 Right of Way Plat~~
- Section No. 5 Plan and Profile
- Section No. 6 Standard Detail Drawings
- ~~Section No. 7 Sign Plates~~
- Section No. 8 Structure Plans
- ~~Section No. 9 Computer Earthwork Data~~
- Section No. 9 Cross Sections


TOTAL SHEETS = 46



DESIGN DESIGNATION	IH 90/94	43RD STREET
A.A.D.T. (2025)	= 36,800	470
A.A.D.T. (2045)	= 40,400	470
D.H.V.	= 19.9	
D.D.	= 58/42	
T.	= 40.7	10
DESIGN SPEED	= 70 MPH	50 MPH
ESALS	= 33,000,000	110,000

BEGIN PROJECT
STA. 12+52.0
X = 455,964.045
Y = 175,298.001

END PROJECT
STA. 28+44.5
X = 456,640.976
Y = 175,279.277



SCALE 0 1 MILE

TOTAL NET LENGTH OF CENTERLINE = 0.000 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, JUNEAU COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

CONVENTIONAL SYMBOLS

- | | | |
|---|--|----------------------------|
| <p>PLAN</p> <p>CORPORATE LIMITS </p> <p>PROPERTY LINE </p> <p>LOT LINE </p> <p>LIMITED HIGHWAY EASEMENT </p> <p>EXISTING RIGHT OF WAY </p> <p>PROPOSED OR NEW R/W LINE </p> <p>SLOPE INTERCEPT </p> <p>REFERENCE LINE </p> <p>EXISTING CULVERT </p> <p>PROPOSED CULVERT (Box or Pipe) </p> <p>COMBUSTIBLE FLUIDS </p> <p>MARSH AREA </p> <p>WOODED OR SHRUB AREA </p> | <p>PROFILE</p> <p>GRADE LINE </p> <p>ORIGINAL GROUND </p> <p>MARSH OR ROCK PROFILE (To be noted as such) </p> <p>SPECIAL DITCH </p> <p>GRADE ELEVATION </p> <p>CULVERT (Profile View) </p> <p>UTILITIES</p> <p>ELECTRIC </p> <p>FIBER OPTIC </p> <p>GAS </p> <p>SANITARY SEWER </p> <p>STORM SEWER </p> <p>TELEPHONE </p> <p>WATER </p> <p>UTILITY PEDESTAL </p> <p>POWER POLE </p> <p>TELEPHONE POLE </p> | <p>ROCK </p> <p>LABEL </p> |
|---|--|----------------------------|

**STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION**

PREPARED BY

Surveyor	WISDOT
Designer	BRIAN DAHL
Project Manager	CORY MIKSHOWSKY
Regional Examiner	SW REGION
Regional Supervisor	JOHN BAINTER

APPROVED FOR THE DEPARTMENT

DATE: 4/4/2024

E

PROJECT ID: 1016-05-65

COUNTY: JUNEAU

01

GENERAL NOTES

- THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.
- THERE ARE UTILITY FACILITIES WITHIN THE PROJECT AREA THAT ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL COORDINATE THEIR CONSTRUCTION ACTIVITIES WITH A CALL TO DIGGERS HOTLINE AND/OR A DIRECT CALL TO THE UTILITIES THAT HAVE FACILITIES IN THE AREA. NOT ALL UTILITIES ARE MEMBERS OF DIGGERS HOTLINE.
- PRIOR TO THE PLACEMENT OF STEEL PLATE BEAM GUARD OR MGS GUARDRAIL, THE SHOULDERS SHALL BE IN PLACE, SHAPED AND COMPACTED UNLESS SHOWN OTHERWISE.
- HMA PAVEMENT WEIGHT CALCULATIONS ARE BASED ON 112 LB/SY/IN.
- DISTURBED AREAS WITHIN THE RIGHT OF WAY ARE TO BE TOPSOILED (SALVAGED), FERTILIZED, SEEDED, AND MULCHED OR SODDED AS DIRECTED BY THE ENGINEER.
- APPLY TACK COAT AT A RATE OF 0.07 GAL/SY TO MILLED PAVEMENT SURFACES AND 0.05 GAL/SY BETWEEN LAYERS OF NEW HMA PAVEME

UTILITY CONTACTS

Kenneth Nine (1078 Contact)
 AT&T Legacy - Communication Line
 110 main Street
 Culver, In 46511
 574-842-8830
 knine@jmceainc.com

Jeremy Zehm
 Frontier Communications of WI LLC - Communication Line
 154 East 2nd Street
 New Richmond, Wi 54017
 715-243-9243
 Jeremy.zehm@ftr.com

Doug Vosberg (1078 Contact)
 ATC Management, Inc. - Electricity-transmission
 5303 Fen Oak Dr
 Madison, WI 53718
 (608) 877-7650
 dvosberg@atcllc.com

Tyler B. Donovan (1078 Contact)
 Alliant Energy - Electricity
 338 East State Street
 Mauston, Wi 53948
 (608) 963-9585
 tylerdonovan@alliantenergy.com



Dial **811** or (800) 242-8511
 www.DiggersHotline.com

DNR LIAISON

KAREN KALVELAGE
 ENVIRONMENTAL ANALYSIS & REVIEW SPECIALIST
 WISCONSIN DEPT. OF NATURAL RESOURCES
 WEST CENTRAL REGION
 3550 MORMON COULEE ROAD
 LA CROSSE, WI 54601
 608-785-9115
 karen.kalvelage@wisconsin.gov


DESIGN CONTACTS

CORY MIKSHOWSKY
 PROJECT MANAGER
 WISDOT SW REGION
 3550 MORMON COULEE RD
 LA CROSSE, WI 54601
 608-789-6335
 cory.mikshowsky@dot.wi.gov


BRIAN DAHL
 PROJECT DESIGNER
 WISDOT SW REGION
 3550 MORMON COULEE RD
 LA CROSSE, WI 54601
 608-785-9074
 brian.dahl@dot.wi.gov

STANDARD ABBREVIATIONS

AC	ACRE	LC.	LONG CHORD
AGG	AGGREGATE	LS	LUMP SUM
<	ANGLE	M.P.	MARKER POST
AE, AEW	APRON ENDWALL	MGAL	1000 GALLONS
ASPH.	ASPHALTIC	N.C.	NORMAL CROWN
A.D.T.	AVERAGE DAILY TRAFFIC	N	NORTH
A.A.D.T.	ANNUAL AVERAGE DAILY TRAFFIC	NB	NORTHBOUND
B.F.	BACK FACE	NOR	NORMAL
BM	BENCHMARK	NO.	NUMBER
BTWN	BETWEEN	PAVT	PAVEMENT
CTR.	CENTER	P.L.E.	PERMANENT LIMITED EASEMENT
C/L	CENTER LINE	P.C.	POINT OF CURVATURE
Δ	CENTRAL ANGLE OR DELTA	P.I.	POINT OF INTERSECTION
C.E.	COMMERCIAL ENTRANCE	P.T.	POINT OF TANGENCY
CONST.	CONSTRUCTION	PCC	PORTLAND CEMENT CONCRETE
CMCP	CORRUGATED METAL CULVERT PIPE	P.E.	PRIVATE ENTRANCE
CMP	CORRUGATED METAL PIPE	PGL	PROFILE GRADE LINE
CO.	COUNTY	P.L.	PROPERTY LINE
CTH	COUNTY TRUNK HIGHWAY	R	RADIUS OR RANGE
CR.	CREEK	R/L	REFERENCE LINE
CABC	CRUSHED AGGREGATE BASE COURSE	R.C.C.P.	REINFORCED CONCRETE CULVERT PIPE
CY	CUBIC YARD	REQ'D	REQUIRED
CP	CONTROL POINT OR CULVERT PIPE	RT	RIGHT
C&G	CURB AND GUTTER	R.H.F.	RIGHT HAND FORWARD
D	DEGREE OF CURVE	R/W	RIGHT OF WAY
D.H.V.	DESIGN HOURLY VOLUME	RD.	ROAD
DIA.	DIAMETER	SHLD.	SHOULDER(S)
D.D.	DIRECTIONAL DISTRIBUTION	SHR.	SHRINKAGE
DISCH.	DISCHARGE	S	SOUTH
DMS	DYNAMIC MESSAGE SIGN	SB	SOUTHBOUND
EA	EACH	S.F.	SQUARE FOOT (FEET)
E	EAST	SDD	STANDARD DETAIL DRAWING(S)
EB	EASTBOUND	STH	STATE TRUNK HIGHWAY
ELEC.	ELECTRIC(AL), ELEC. CABLE	STA.	STATION
EL., ELEV.	ELEVATION	S.E.	SUPERELEVATION
ESALS	EQUIVALENT SINGLE AXLE LOADS	S/L	SURVEY LINE
EXC.	EXCAVATION	SYM	SYMMETRICAL
EXIST	EXISTING	T.	PERCENT TRUCKS
F.F.	FACE TO FACE	TEL.	TELEPHONE
FERT.	FERTILIZER	TEMP.	TEMPORARY
F.E.	FIELD ENTRANCE	T.L.E.	TEMPORARY LIMITED EASEMENT
F/L, F.L.	FLOW LINE	T.O.C.	TOP OF CURB
GALV.	GALVANIZE	TYP	TYPICAL
H.S.	HIGH STRENGTH	UNCL.	UNCLASSIFIED
CWT	HUNDRED WEIGHT	U.G.	UNDERGROUND (CABLE)
INL	INLET	VAR	VARIABLE
INTER.	INTERSECTION	V.C.	VERTICAL CURVE
IH	INTERSTATE HIGHWAY	V.P.C.	VERTICAL POINT OF CURVATURE
JT.	JOINT	V.P.I.	VERTICAL POINT OF INTERSECTION
LT	LEFT	V.P.T.	VERTICAL POINT OF TANGENCY
L.H.F.	LEFT HAND FORWARD	Wt.	WEIGHT
L.	LENGTH OF CURVE	W	WEST
L.F.	LINEAR FOOT(FEET)	WB	WESTBOUND




PCMS BOARDS TO INFORM
OF CLOSURE BEGINNING 7
DAYS PRIOR TO
CONSTRUCTION



TYPICAL EXISTING SECTION


WELCH PRAIRIE ROAD (43rd STREET)
 STA. 12+52 - STA. 19+24
 STA. 20+66 - STA. 22+40
 STA. 23+84 - STA. 28+45




TYPICAL PROPOSED SECTION

WELCH PRAIRIE ROAD (43rd STREET)
 STA. 12+52 - STA. 19+24
 STA. 20+66 - STA. 22+40
 STA. 23+84 - STA. 28+45


NOT TO SCALE




TYPICAL SECTION: IH 90/94 OUTSIDE LANE CLOSED
SLOPE PAVING REPAIR
STRUCTURE REPAIRS (AWAY FROM CENTERLINE)



TYPICAL SECTION: IH 90/94 OUTSIDE LANE CLOSED
STRUCTURE REPAIR (NEAR CENTERLINE)




TYPICAL SECTION: IH 90/94 MEDIAN LANE CLOSED
SLOPE PAVING REPAIR
STRUCTURE REPAIRS (AWAY FROM CENTERLINE)




TYPICAL SECTION: IH 90/94 MEDIAN LANE CLOSED
STRUCTURE REPAIR (NEAR CENTERLINE)

NOT TO SCALE



NOTE:
SILT FENCE POSTS FOR THE TURN-AROUND SHOULD
BE ON THE OUTSIDE OF THE TURN-AROUND.

PLAN VIEW



SIDE VIEW

TEMPORARY SMALL ANIMAL TURN-AROUND

GENERAL NOTES:
SILT FENCE POSTS FOR THE TURN-AROUND SHOULD BE ON THE OUTSIDE OF THE
TURN-AROUND AND TRENCHED IN ACCORDING TO SILT FENCE REQUIREMENTS.

Estimate Of Quantities By Plan Sets

1016-05-65

Line	Item	Item Description	Unit	Total	Qty
0002	203.0211.S	Abatement of Asbestos Containing Material (structure) 01. B-29-0041	EACH	1.000	1.000
0004	203.0211.S	Abatement of Asbestos Containing Material (structure) 02. B-29-0042	EACH	1.000	1.000
0006	204.0110	Removing Asphaltic Surface	SY	3,210.000	3,210.000
0008	204.0165	Removing Guardrail	LF	1,860.000	1,860.000
0014	213.0100	Finishing Roadway (project) 02. 1016-05-65	EACH	1.000	1.000
0016	305.0110	Base Aggregate Dense 3/4-Inch	TON	50.000	50.000
0018	455.0605	Tack Coat	GAL	230.000	230.000
0020	460.2000	Incentive Density HMA Pavement	DOL	240.000	240.000
0022	460.5224	HMA Pavement 4 LT 58-28 S	TON	370.000	370.000
0024	509.1500	Concrete Surface Repair	SF	100.000	100.000
0026	517.3001.S	Structure Overcoating Cleaning and Priming (structure) 01. B-29-41	EACH	1.000	1.000
0028	517.3001.S	Structure Overcoating Cleaning and Priming (structure) 02. B-29-42	EACH	1.000	1.000
0030	517.4001.S	Containment and Collection of Waste Materials (structure) 01. B-29-41	EACH	1.000	1.000
0032	517.4001.S	Containment and Collection of Waste Materials (structure) 02. B-29-42	EACH	1.000	1.000
0034	517.6001.S	Portable Decontamination Facility	EACH	2.000	2.000
0040	614.0010	Barrier System Grading Shaping Finishing	EACH	4.000	4.000
0042	614.2300	MGS Guardrail 3	LF	1,340.000	1,340.000
0044	614.2500	MGS Thrie Beam Transition	LF	320.000	320.000
0046	614.2610	MGS Guardrail Terminal EAT	EACH	4.000	4.000
0050	618.0100	Maintenance and Repair of Haul Roads (project) 02. 1016-05-65	EACH	1.000	1.000
0052	619.1000	Mobilization	EACH	0.400	0.400
0054	624.0100	Water	MGAL	1.000	1.000
0056	628.1504	Silt Fence	LF	1,200.000	1,200.000
0058	628.1520	Silt Fence Maintenance	LF	1,200.000	1,200.000
0060	628.1905	Mobilizations Erosion Control	EACH	2.000	2.000
0062	628.1910	Mobilizations Emergency Erosion Control	EACH	2.000	2.000
0064	643.0300	Traffic Control Drums	DAY	760.000	760.000
0066	643.0420	Traffic Control Barricades Type III	DAY	210.000	210.000
0068	643.0705	Traffic Control Warning Lights Type A	DAY	260.000	260.000
0070	643.0715	Traffic Control Warning Lights Type C	DAY	170.000	170.000
0072	643.0800	Traffic Control Arrow Boards	DAY	20.000	20.000
0074	643.0900	Traffic Control Signs	DAY	130.000	130.000
0076	643.1050	Traffic Control Signs PCMS	DAY	60.000	60.000
0078	643.1205.S	Basic Traffic Queue Warning System	DAY	10.000	10.000
0080	643.5000	Traffic Control	EACH	0.400	0.400
0084	690.0150	Sawing Asphalt	LF	48.000	48.000
0092	SPV.0060	Special 04. Cleaning and Painting Bearings	EACH	32.000	32.000

3

ASPHALT SUMMARY

STATION	TO	STATION	LOCATION	204.0110 REMOVING ASPHALTIC SURFACE SY	305.0110 BASE AGGREGATE DENSE 3/4-INCH TON	455.0605 TACK COAT GAL	460.5224 HMA PAVEMENT 4 LT 58-28 S TON	624.0100 WATER MGAL	690.0150 SAWING ASPHALT LF	REMARKS
12+52	-	19+24	WEST APPROACH	1,650	20	120	190	0.4	24	
20+66	-	22+40	MEDIAN	430	10	30	50	0.2	-	
23+84	-	28+45	EAST APPROACH	1,130	20	80	130	0.4	24	
TOTAL 0010				3,210	50	230	370	1	48	

GUARDRAIL SUMMARY

STATION	TO	STATION	LOCATION	204.0165 REMOVING GUARDRAIL LF	614.0010 BARRIER SYSTEM GRADING SHAPING FINISHING EACH	614.2300 MGS GUARDRAIL 3 LF	614.2500 MGS THRIE BEAM TRANSITION LF	614.2610 MGS GUARDRAIL TERMINAL EAT EACH	REMARKS
14+76	-	19+24	WELCH PRAIRIE RD	320	1	230	40	1	SOUTH END, RIGHT SIDE
12+52	-	19+08	WELCH PRAIRIE RD	600	1	510	40	1	SOUTH END, LEFT SIDE
20+80	-	22+40	WELCH PRAIRIE RD	160	-	80	80	-	MEDIAN, RIGHT SIDE
20+66	-	22+26	WELCH PRAIRIE RD	160	-	80	80	-	MEDIAN, LEFT SIDE
23+98	-	28+45	WELCH PRAIRIE RD	320	1	230	40	1	NORTH END, RIGHT SIDE
23+84	-	27+76	WELCH PRAIRIE RD	300	1	210	40	1	NORTH END, LEFT SIDE
TOTAL 0010				1,860	4	1,340	320	4	

EROSION CONTROL SUMMARY


STATION	TO	STATION	LOCATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL EACH	REMARKS
PROJECT				-	-	2	2	
14+76	-	16+74	WELCH PRAIRIE RD RT	310	310	-	-	
12+52	-	14+09	WELCH PRAIRIE RD LT	320	320	-	-	
26+79	-	28+45	WELCH PRAIRIE RD RT	280	280	-	-	
26+12	-	27+76	WELCH PRAIRIE RD LT	290	290	-	-	
TOTAL 0010				1,200	1,200	2	2	

FOR REFERENCE ONLY

LOCATION	BARRIERS SYSTEM GRADING, SHAPING, FINISHING							REMARKS
	205.0100 EXCAVATION COMMON CY	208.0100 BORROW CY	625.0100 TOPSOIL SY	627.0200 MULCHING SY	629.0205 FERTILIZER TYPE A CWT	630.0110 SEEDING MIXTURE NO. 10 LB	630.0500 SEED WATER MGAL	
WELCH PRAIRIE ROAD:								
NW QUADRANT	2	51	320	320	0.20	5	7	
SW QUADRANT	3	95	380	380	0.24	5	9	
NE QUADRANT	0	109	340	340	0.21	5	8	
SE QUADRANT	3	65	350	350	0.22	5	8	
TOTAL 0010	8	320	1,390	1,390	1	20	31	

TRAFFIC CONTROL SUMMARY


STATION	TO	STATION	LOCATION	643.0300 SERVICE DAYS	643.0420 TRAFFIC CONTROL BARRICADES TYPE III QTY	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A QTY	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C QTY	643.0800 TRAFFIC CONTROL ARROW BOARDS QTY	643.0900 TRAFFIC CONTROL SIGNS QTY	643.1050 TRAFFIC CONTROL SIGNS PCMS QTY	643.1205.S BASIC TRAFFIC QUEUE WARNING SYSTEM QTY	REMARKS							
12+52	-	28+45	WELCH PRAIRIE RD	20	16	320	10	200	12	240	-	CLOSED ROAD							
641+50E	-	700+00E	IH 90 EB RT	3	44	132	1	3	2	6	17	51	2	6	9	27	0	3	LANE CLOSURE
641+50E	-	700+00E	IH 90 EB LT	2	44	88	1	2	2	4	17	34	2	4	9	18	0	2	LANE CLOSURE
691+00W	-	749+50W	IH 90 WB RT	3	44	132	1	3	2	6	17	51	2	6	9	27	0	3	LANE CLOSURE
691+00W	-	749+50W	IH 90 WB LT	2	44	88	1	2	2	4	17	34	2	4	9	18	0	2	LANE CLOSURE
TOTAL 0010					760	210	260	170	20	130	60	10							



LEGEND

- XXXX XXXX SAWING ASPHALT
- SILT FENCE

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	PLAN SHEETS	SHEET	E
------------------------	------------	----------------	-------------	-------	----------




5

5

Arch. Site 47JU228 (Hoover II) -
See special provisions for requirements.

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	PLAN SHEETS	SHEET	E
------------------------	------------	----------------	-------------	-------	---



5


5

LEGEND

XXXX XXXX . SAWING ASPHALT

—●—●—●— SILT FENCE

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	PLAN SHEETS	SHEET	E
------------------------	------------	----------------	-------------	-------	----------




5

5

Arch. Site 47JU228 (Hoover II) -
See special provisions for requirements.

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	PLAN SHEETS	SHEET	E
------------------------	------------	----------------	-------------	-------	---




LEGEND

- XXXX XXXX SAWING ASPHALT
- SILT FENCE


PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	PLAN SHEETS	SHEET	E
------------------------	------------	----------------	-------------	-------	----------

Standard Detail Drawing List

08E09-06	SILT FENCE
13C19-03	HMA LONGITUDINAL JOINTS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15C02-09A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-09B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C11-10B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15D12-12A	TRAFFIC CONTROL, LANE CLOSURE, WITH TEMPORARY RUMBLE STRIPS
15D12-12D	TRAFFIC CONTROL, PARALLEL ENTRANCE RAMP WITHIN LANE CLOSURE



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL


NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS



SILT FENCE



JOINING TWO LENGTHS OF SILT FENCE ⑤




SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)


SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
4-29-05 /S/ Beth Canestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY 0.1" AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO 2" FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)


6

6


SDD 13C19 - 03

SDD 13C19 - 03

HMA LONGITUDINAL JOINTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2020 DATE	/S/ Steven Hefel HMA PAVEMENT ENGINEER
FHWA	




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
MID-SPAN BEAM SPLICE**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 3/8" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAIL



**FRONT VIEW
QUARTER POST SPACING (QS)**



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

SDD 14B42 - 07b

SDD 14B42 - 07b




DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.


NOTE:

1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 3/16".
2. IF THE BOLT EXTENDS MORE THAN 1/4" FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"




ALTERNATE BOLT HEAD



**PLAN VIEW
BEAM LAPPING DETAIL**




**POST DRIVING FOR CONTINUOUS
UNDERGROUND OBSTRUCTION**




DETAIL FOR 36" BLOCKOUT DEPTH


NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.
DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.



**POST BOLT, SPLICE BOLT
AND RECESS NUT**



SIDE VIEW




PLAN VIEW

**ALTERNATE WOOD
BLOCKOUT DETAIL**


6 WHEN USING STEEL POST AND WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL)

- 400 MAX SPAN 12' - 6"
- 401 2' MIN.
- 402 MGS GUARDRAIL 3
- 403 NESTING BEAM GUARD
- 404 ASYMMETRIC TRANSITION
- 405 SOIL WELL DRAINED AND COMPACTED
- 406 SEE OTHER DRAWINGS IN THIS SDD
- 407 SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
- 408 SEE SDD 14B44
- 409 SEE SDD 14B45
- 410 SEE SDD 14B47
- 411 MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
 - (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
 - (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
 - (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
 - (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.
- DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.


SEE SDD 14B42 FOR MORE INFORMATION.

* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.


DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.

SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.


THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.




PLAN




ELEVATION




DETAIL "A"




**SECTION C - C
TYPICAL AT POST NOS. 3 - 9**



**SECTION B - B
TYPICAL AT POST NO. 2***



**SECTION A - A
TYPICAL AT POST NO. 1***



DETAIL "B"

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

SDD 14B44 - 04a


SDD 14B44 - 04a

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2




GENERIC GROUND STRUT ⑨ ⑤




GENERIC ANCHOR CABLE BOX ⑨ ⑤




BEARING PLATE ⑥ ⑤




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9



UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)



WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2


6




W5 - 59
REFLECTIVE SHEETING DETAIL ^(E)

TYPE H
YELLOW REFLECTIVE
SHEETING 3" X 9".
SEE STANDARD
SPECIFICATION 637.


E.A.T. MARKER
POST (YELLOW)



FRONT VIEW SIDE VIEW
E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW



TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

6

SDD 14B44 - 04c


SDD 14B44 - 04c

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR

FHWA



TWO WAY TRAFFIC



ONE WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES


IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY

- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ④ TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42



**SECTION A-A
POSTS 1-5**



**SECTION B-B
POST 6**



**SECTION C-C
POSTS 7-11**







PLATE WASHER DETAIL



SPLICE DETAIL




**THRIE BEAM
TERMINAL CONNECTOR**




**SECTION THRU THRIE
BEAM RAIL ELEMENT**

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3\"/>




12'-6\"/>




ALTERNATE WOOD BLOCKOUT DETAIL




STEEL POSTS 1-5




STEEL POSTS 6-17




TOP VIEW



BLOCKOUT POSTS 1-5



TOP VIEW



BLOCKOUT POSTS 6-17

GENERAL NOTES

- STEEL POSTS ARE W6X9 OR W6X8.5.
- BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

S.D.D. 14 B 45-5c

S.D.D. 14 B 45-5c




FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS


SECTION E-E

GENERAL NOTES

- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
 - (4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
 - (6) DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - (7) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - (8) THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".




SECTION F-F



FRONT VIEW

**W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**



DRILL HOLE LOCATION

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

6

6


S.D.D. 14 B 45-5d

S.D.D. 14 B 45-5d

GENERAL NOTES


THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PAPAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



SECTION G-G



FRONT VIEW


THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

ONE WAY
TRAFFIC



WHEN RETROFITTING A TRANSITION TO AN EXISTING RIGID BARRIER, INSTALL PLATE WASHERS ON BACKSIDE OF RIGID BARRIER.


FRONT VIEW

W BEAM CONNECTION TO PARAPETS WITH SLOPED ENDS


(USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)

GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.




DRILL HOLE LOCATION AND PATTERN FOR THRIE BEAM CONNECTION



WHEN RETROFITTING A TRANSITION TO AN EXISTING RIGID BARRIER, INSTALL PLATE WASHERS ON BACKSIDE OF RIGID BARRIER.

FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPETS WITH SLOPED ENDS




SECTION I-I


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



BACK-UP PLATE DETAIL




SECTION J-J




BACK-UP PLATE MOUNTING ONTO BRIDGE RAILING

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1'$.
- ⑥ DRILLING HOLES THROUGH THE PAPER, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




**FRONT VIEW
THRIE BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**THRIE BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


(4) TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".



FRONT VIEW




**PLAN VIEW
BACK-UP PLATE DETAIL, TYPE "M"**




FRONT VIEW

**ANCHOR
PLATE DETAIL,
TYPE "M"**




SECTION M-M



SECTION L-L


FRONT VIEW

ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW

M



PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES

- COVER PLATE PANELS ARE 3/16" THICK.
- ALL STIFFENERS ARE 1/4" THICK.
- CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.
- FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.
- ALL HOLE DIAMETERS SHALL BE 1".
- FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

- (10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND 3/16" FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.
- (11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
3/16" FILLET WELD BY 1" LONG SPACED AT 2".



WELDING INSTRUCTION
(VIEWED FROM BACK SIDE OF PLATE)




PLATE AND STIFFENER IDENTIFICATION
(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 3/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 7/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 1/16" x 10 3/8" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 3/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 1/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 3/16" x 6" x 3 5/8" x 5 1/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 3/32"	1/4"
S10	1		1 7/8" x 9 7/8" x 3 5/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 3/16"	1/4"

SINGLE SLOPE CONNECTION PLATE

**MIDWEST GUARDRAIL SYSTEM
THREE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
7/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.



⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTION PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER



SECTION N-N




SINGLE SLOPE CONNECTION PLATE PLACEMENT


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



ELEVATION OF DETAIL AT NY3 END POST
THRIE BEAM RAIL ATTACHMENT



ELEVATION OF DETAIL AT NY4 END POST
THRIE BEAM RAIL ATTACHMENT

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.


6

6

S.D.D. 14 B 45-5k

S.D.D. 14 B 45-5k


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 7/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	



GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.

FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

APPROVED
 DATE 7/2018 /S/ Rodney Taylor
 ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR
 FHWA



**DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

**DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR**


WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750

- M4 - 8
- M3 - X
- M1 - 4
- M1 - 6
- M1 - 5A
- M05 - 1
- M06 - 1




**DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR**

SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦


**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidtke
DATE DATE WORK ZONE ENGINEER



**DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW**



**DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW**

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:


- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

**BARRICADES AND SIGNS
FOR
VARIOUS CLOSURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER




DRUM

BALLAST WIDTHS
RANGE FROM 24"-36"



42" CONE

DO NOT USE IN TAPERS
½ SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
 November 2022 /S/ Andrew Heidtke
 DATE WORK ZONE ENGINEER
 FHWA

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.

ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.


CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TYPE "A" WARNING LIGHT (FLASHING)
-  REMOVING PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLASHING ARROW BOARD

6

SDD 15D12-12a



6

SDD 15D12-12a

TRAFFIC CONTROL LANE CLOSURE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED September 2023 DATE	/s/ Andrew Heidtke ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TYPE "A" WARNING LIGHT (FLASHING)
-  REMOVING PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLASHING ARROW BOARD
-  PORTABLE TRAFFIC SENSOR (PTS)
-  FLASHING BEACON SIGN

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS, INCLUDING FBS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER. NO WARNING LIGHTS SHALL BE WORKING ON "COVERED" OR "DOWNED" SIGNS.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS. WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.


IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.

CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

PORTABLE TRAFFIC SENSOR (PTS) MAY BE MOUNTED ON THE FBS, ARROW BOARD OR OTHER TRAILER DEVICES.

- ① 5 DRUMS SPACED AT 10 FOOT INTERVALS AS NEEDED.
- ② IF THERE ARE MORE THAN TWO LANES OR IF SPECIFIED IN THE PLANS, PLACE FBS ON BOTH SIDES OF THE ROADWAY.
- ③ IF THERE IS AN APPROVED TEMPORARY SPEED DECLARATION, ADD WO-3-5 SIGNS 400 FEET AFTER THE W20-5G SIGNS AND ADD R2-1 SIGNS (48"x60") 700 FEET AFTER THE WO3-5 SIGNS. A SPEED LIMIT SIGN SHALL BE LOCATED 1500 FEET BEYOND THE END OF THE ACCELERATION LANE OF EACH ENTRANCE RAMP. PLACE A SPEED LIMIT SIGN A MINIMUM OF EVERY 3 MILES. INCLUDE A "RESUME SPEED LIMIT" SIGN 200 FEET MINIMUM (800 FEET DESIRABLE) BEYOND THE G30-3A "END ROAD WORK" SIGN.



SDD 15D12-12d

SDD 15D12-12d

TRAFFIC CONTROL, LANE CLOSURE, BASIC TRAFFIC QUEUE WARNING SYSTEM	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED September 2023 DATE	/s/ Erin Schwark ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

DESIGN DATA

LIVE LOAD:

INVENTORY RATING: HS-10
 OPERATING RATING: HS-17
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 90 (KIPS)

6/12/2020 RATINGS RETRIEVED FROM HSIS.

MATERIAL PROPERTIES:

CONCRETE MASONRY:
 SURFACE REPAIR $f'_c = 4,000$ PSI


TRAFFIC DATA

43RD STREET/WELCH PRAIRIE ROAD:


ADT = 150 (2008)
 R.D.S. = 55 MPH

IH 90:

ADT = 17,300 (2016)
 R.D.S. = 70 MPH



PLAN
 3 SPAN - STEEL GIRDER



CROSS SECTION THRU ROADWAY
 LOOKING EAST

LIST OF DRAWINGS:

- 1 MISC. REPAIRS

STRUCTURE DESIGN CONTACTS:

MICAH BROOKS 608-266-5080
 KYLE BUSCH 608-267-0465

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

DIMENSIONS SHOWN ARE BASED ON THE ORIGINAL STRUCTURE PLANS.

SPOT PAINT GIRDERS & DIAPHRAGMS AS REQUIRED BY THE ENGINEER UNDER BID ITEM "STRUCTURE OVERCOATING CLEANING AND PRIMING". APPROXIMATELY 50 SF OF PAINTING EXPECTED. PAINT COLOR SHALL MATCH EXISTING GIRDERS.

* AREAS OF "CONCRETE SURFACE REPAIR" SHOWN ARE APPROXIMATE AND MAY NOT BE ALL INCLUSIVE. ADDITIONAL REPAIRS MAY BE REQUIRED DURING CONSTRUCTION AND SHALL BE PERFORMED AS DIRECTED BY THE FIELD ENGINEER.

CLEAN AND PAINT ALL STEEL BEARINGS AT BOTH ABUTMENTS AND BOTH PIERS UNDER BID ITEM "CLEANING AND PAINTING STEEL BEARINGS". PAINT SHALL BE AMS STD. COLOR NO. 36173 "NEUTRAL GRAY".

BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS SPECIFIED OTHERWISE.

ANY EXCAVATION NECESSARY TO COMPLETE CONCRETE SURFACE REPAIRS AT ABUTMENTS IS INCLUDED WITH THE BID ITEM "CONCRETE SURFACE REPAIR".

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	TOTALS
509.1500	CONCRETE SURFACE REPAIR	SF	50
517.3001.S.01	STRUCTURE OVERCOATING CLEANING AND PRIMING	EACH	1
517.4001.S.01	CONTAINMENT AND COLLECTION OF WASTE MATERIALS	EACH	1
517.6001.S.01	PORTABLE DECONTAMINATION FACILITY	EACH	1
SPV.0060	CLEANING AND PAINTING BEARINGS	EACH	16

NO.	DATE	REVISION	BY
<p>BUREAU OF STRUCTURES</p> <p>ACCEPTED <i>[Signature]</i> 7/26/23 CHIEF STRUCTURES DESIGN ENGINEER DATE</p>			
STRUCTURE B-29-41			
43RD STREET/WELCH PRAIRIE ROAD OVER IH 90 EB			
COUNTY JUNEAU		TOWN LISBON	
DESIGN SPEC. REHABILITATION N/A			
DESIGNED BY MWB	DESIGNED CK'D	DRAWN BY MWB	PLANS CK'D ARC
MISC. REPAIRS			SHEET 1 OF 1

DESIGN DATA

LIVE LOAD:

INVENTORY RATING: HS-10
 OPERATING RATING: HS-17
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 90 (KIPS)

6/12/2020 RATINGS RETRIEVED FROM HSIS.

MATERIAL PROPERTIES:

CONCRETE MASONRY: SURFACE REPAIR $f'_c = 4,000$ PSI


TRAFFIC DATA

43RD STREET/WELCH PRAIRIE ROAD:


ADT = 150 (2008)
 R.D.S. = 55 MPH

IH 90:

ADT = 17,300 (2016)
 R.D.S. = 70 MPH



PLAN
3 SPAN - STEEL GIRDER



CROSS SECTION THRU ROADWAY
LOOKING EAST

LIST OF DRAWINGS:

- 1 MISC. REPAIRS

STRUCTURE DESIGN CONTACTS:

MICAH BROOKS 608-266-5080
 KYLE BUSCH 608-267-0465

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

DIMENSIONS SHOWN ARE BASED ON THE ORIGINAL STRUCTURE PLANS.

SPOT PAINT GIRDERS & DIAPHRAGMS AS REQUIRED BY THE ENGINEER UNDER BID ITEM "STRUCTURE OVERCOATING CLEANING AND PRIMING". APPROXIMATELY 50 SF OF PAINTING EXPECTED. PAINT COLOR SHALL MATCH EXISTING GIRDERS.

* AREAS OF "CONCRETE SURFACE REPAIR" SHOWN ARE APPROXIMATE AND MAY NOT BE ALL INCLUSIVE. ADDITIONAL REPAIRS MAY BE REQUIRED DURING CONSTRUCTION AND SHALL BE PERFORMED AS DIRECTED BY THE FIELD ENGINEER.

CLEAN AND PAINT ALL STEEL BEARINGS AT BOTH ABUTMENTS AND BOTH PIERS UNDER BID ITEM "CLEANING AND PAINTING STEEL BEARINGS". PAINT SHALL BE AMS STD. COLOR NO. 36173 "NEUTRAL GRAY".

BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS SPECIFIED OTHERWISE.

ANY EXCAVATION NECESSARY TO COMPLETE CONCRETE SURFACE REPAIRS AT ABUTMENTS IS INCLUDED WITH THE BID ITEM "CONCRETE SURFACE REPAIR".

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	TOTALS
509.1500	CONCRETE SURFACE REPAIR	SF	50
517.3001.S.02	STRUCTURE OVERCOATING CLEANING AND PRIMING	EACH	1
517.4001.S.02	CONTAINMENT AND COLLECTION OF WASTE MATERIALS	EACH	1
517.6001.S.02	PORTABLE DECONTAMINATION FACILITY	EACH	1
SPV.0060	CLEANING AND PAINTING BEARINGS	EACH	16

NO.	DATE	REVISION	BY


ACCEPTED  7/26/23
 CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-29-42
 43RD STREET/WELCH PRAIRIE ROAD OVER IH 90 WB
 COUNTY JUNEAU TOWN LISBON

DESIGNED BY MWB
 DESIGNED CK'D
 DRAWN BY MWB
 PLANS CK'D ARC

MISC. REPAIRS

SHEET 1 OF 1




9

9

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	CROSS SECTIONS: SECTION VIEW GROUP - 1	SHEET E
------------------------	------------	----------------	--	---------

FILE NAME : C:\BOXDRV\BOX\BRIAN DAHL\BOX-C3D\10160535\DESIGN\SURFAES\BG-SURFACES.DWG PLOT DATE : 7/25/2023 12:58 PM PLOT BY : DAHL, BRIAN D PLOT NAME : PLOT SCALE : 1 IN:20 FT HORZ. / 1 IN:20 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 01




9

9

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	CROSS SECTIONS: SECTION VIEW GROUP - 1	SHEET E
------------------------	------------	----------------	--	---------

FILE NAME : C:\BOXDRV\BOX\BRIAN DAHL\BOX-C3D\10160535\DESIGN\SURFAES\BG-SURFACES.DWG PLOT DATE : 7/25/2023 12:58 PM PLOT BY : DAHL, BRIAN D PLOT NAME : PLOT SCALE : 1 IN:20 FT HORZ. / 1 IN:20 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 02




9

9

PROJECT NO: 1016-05-65	HWY: IH-90	COUNTY: JUNEAU	CROSS SECTIONS: SECTION VIEW GROUP - 1	SHEET E
------------------------	------------	----------------	--	---------

FILE NAME : C:\BOXDRV\BOX\BRIAN DAHL\BOX-C3D\10160535\DESIGN\SURFAES\BG-SURFACES.DWG PLOT DATE : 7/25/2023 12:58 PM PLOT BY : DAHL, BRIAN D PLOT NAME : PLOT SCALE : 1 IN:20 FT HORZ. / 1 IN:20 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 03



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>