



Wisconsin Department of Transportation

July 2, 2024

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #01: 1100-09-74
IH 94 East West Freeway
.2 MI East of Hawley Rd to Zablocki Dr
IH 94
Milwaukee County

Letting of July 9, 2024

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
14	Concrete Barrier Precast Left In Place, Item SPV.0090.01

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1100-09-74

July 2, 2024

Special Provisions

14. Concrete Barrier Precast Left In Place, Item SPV.0090.01

*Replace entire section titled **B Materials** with the following:*

B Materials

Provide Concrete Barrier Precast Left in Place that is according to the pertinent requirements of standard spec 603, SDD 14B07, SDD 14B08 and plans. Provide Concrete Barrier Precast Left in Place that has been manufactured no later than 6 years before installation. Ensure that Concrete Barrier Precast Left in Place has no markings other than what is indicated in standard detail drawing for concrete barrier temporary precast. Provide thrie beam connection that is according to the pertinent requirements of standard spec 614 and the standard detail drawing for concrete barrier temporary precast. Temporary barrier is to be in good condition when installed. Temporary Barrier is to be compliant with Buy American requirements.

END OF ADDENDUM