



Wisconsin Department of Transportation

September 5, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #14: 1520-00-77
Wisconsin Rapids – Pittsville
Industrial St – STH 186
STH 73
Wood County

Letting of September 10, 2024

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
416.0610	Drilled Tie Bars	Each	294	87	381

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
209.2100	Backfill Granular Grade 2	CY	0	5580	5580

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
209.2500	Backfill Granular Grade 2	Ton	5580	-5580	0

Plan Sheets:

Revised Plan Sheets		
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)	
59	Misc Qty Sheet	Updated drilled tie bar table to reflect new quantity. Corrected "Backfill Granular Grade 2" item number to 209.2100.

Schedule of Items

Attached, dated September 5, 2024, are the revised Schedule of Items Pages 1 – 9.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 59.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

* BASE COURSE ITEMS *											
CATEGORY	STATION	TO	STATION	LOCATION	TON	TON	BASE AGGREGATE DENSE 1 1/4-INCH	SHAPING SHOULDERS	624.0100	WATER	REMARKS
0010	1+55	-	4+04	LT	0	69	0	0	0.42	MGAL	WIDENING
0010	4+04	-	5+47	LT&RT	6	230	0	0	1.41		WIDENING
0010	5+47	-	6+17	LT&RT	3	184	0	0	1.12		WIDENING
0010	6+17	-	11+45	LT&RT	22	1,945	0	0	11.80		REPLACEMENT
0010	11+45	-	30+09	LT&RT	0	0	37	0	0.00		
0010	30+09	-	31+19	LT&RT	25	445	0	0	2.82		CULVERT REPLACEMENT
0010	31+19	-	32+75	LT&RT	0	0	3	0	0.00		
0010	32+75	-	46+02	LT&RT	191	0	0	0	1.15		
0010	47+21	-	55+56	LT&RT	120	0	0	0	0.72		
0010	55+56	-	59+82	LT&RT	0	0	9	0	0.00		
0010	59+82	-	60+91	LT&RT	25	441	0	0	2.79		CULVERT REPLACEMENT
0010	60+91	-	85+54	LT&RT	0	0	49	0	0.00		
0010	85+54	-	88+87	RT	8	0	0	0	0.05		
0010	88+87	-	93+92	LT	137	0	0	0	0.82		
0010	93+92	-	98+21	RT	11	0	0	0	0.07		
0010	98+21	-	107+86	LT	341	0	0	0	2.05		
0010	107+86	-	134+62	LT&RT	188	0	0	0	1.13		
0010	134+62	-	142+94	LT&RT	59	0	0	0	0.35		
0010	142+94	-	183+40	LT&RT	285	0	0	0	1.71		
0010	183+40	-	185+24	LT&RT	59	744	0	0	4.81		CULVERT REPLACEMENT
0010	185+24	-	188+13	LT&RT	20	0	0	0	0.12		
0010	188+13	-	206+79	LT&RT	594	0	0	0	3.56		
0010	206+79	-	207+93	LT	4	0	0	0	0.02		
0010	207+93	-	207+93	RT	1	0	0	0	0.00		
0010	207+93	-	211+95	LT&RT	21	0	0	0	0.13		
0010	211+95	-	225+36	LT&RT	94	0	0	0	0.57		
0010	226+10	-	233+55	LT&RT	52	0	0	0	0.31		
0010	233+55	-	242+22	LT&RT	0	0	17	0	0.00		
0010	242+22	-	246+46	LT&RT	30	0	0	0	0.18		
0010	246+46	-	248+54	LT&RT	66	841	0	0	5.44		CULVERT REPLACEMENT
0010	248+54	-	258+83	LT&RT	72	0	0	0	0.43		
0010	258+83	-	260+25	LT&RT	45	574	0	0	3.72		CULVERT REPLACEMENT
0010	260+25	-	270+06	LT&RT	69	0	0	0	0.41		
0010	270+06	-	271+19	LT&RT	36	457	0	0	2.96		CULVERT REPLACEMENT
0010	271+19	-	298+43	LT&RT	192	0	0	0	1.15		
0010	298+43	-	299+53	LT&RT	35	445	0	0	2.88		CULVERT REPLACEMENT
0010	299+53	-	310+30	LT&RT	76	0	0	0	0.45		
0010	310+30	-	311+37	LT&RT	34	433	0	0	2.80		CULVERT REPLACEMENT
0010	UNDISTRIBUTIVE				800	--	0	0	4.80		SHOULDER SLOPING
TOTAL 0010					3,755	6,806	116		63.37		
* ITEM IS INCLUDED IN DRIVEWAYS TABLE											
CONCRETE SURFACE DRAINS											
CATEGORY	STATION	TO	STATION	LOCATION	CY	REMARKS					
0010	5+05			LT	1						
0010	45+78			LT	1						
0010	225+14			LT	1						
0010	225+14			RT	1						
TOTAL					4						
* ITEM IS INCLUDED IN DRIVEWAYS TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-	226+30	LT	22	--					
0010	226+09	-	226+30	RT	21	--					
TOTAL					160	156					
* ITEM IS INCLUDED IN CONCRETE REPAIR/REPLACEMENT TABLE											
CONCRETE PAVEMENT											
CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS					
0010	1+55	-	5+47	LT	--	156					
0010	46+02	-	46+22	LT	17	--					
0010	46+02	-	46+22	RT	21	--					
0010	47+00	-	47+21	LT	24	--					
0010	47+00	-	47+21	RT	21	--					
0010	225+37	-	225+57	LT	17	--					
0010	225+37	-	225+57	RT	17	--					
0010	226+09	-</									



Proposal Schedule of Items

Page 1 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	9.000 EACH	_____.	_____.
0004	203.0220 Removing Structure (structure) 01. 72-Inch CPRC Cattle Pass	1.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	3,707.000 SY	_____.	_____.
0008	204.0110 Removing Asphaltic Surface	3,370.000 SY	_____.	_____.
0010	204.0115 Removing Asphaltic Surface Butt Joints	1,218.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	113,430.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	391.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	55.000 SY	_____.	_____.
0018	204.0165 Removing Guardrail	1,521.000 LF	_____.	_____.
0020	204.0170 Removing Fence	134.000 LF	_____.	_____.
0022	204.0180 Removing Delineators and Markers	16.000 EACH	_____.	_____.
0024	204.0246 Removing Ancillary Structure (structure) 01. S-71-30	1.000 EACH	_____.	_____.
0026	204.9060.S Removing (item description) 01. Removing Apron Endwalls for Underdrain Reinforced Concrete	12.000 EACH	_____.	_____.
0028	205.0100 Excavation Common	13,196.000 CY	_____.	_____.
0030	208.0100 Borrow	2,566.000 CY	_____.	_____.



Proposal Schedule of Items

Page 2 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 1520-00-77	1.000 EACH	_____.	_____.
0036	213.0100 Finishing Roadway (project) 01. 1520-00-77	1.000 EACH	_____.	_____.
0038	305.0110 Base Aggregate Dense 3/4-Inch	3,946.000 TON	_____.	_____.
0040	305.0120 Base Aggregate Dense 1 1/4-Inch	7,001.000 TON	_____.	_____.
0042	305.0500 Shaping Shoulders	116.000 STA	_____.	_____.
0044	415.0070 Concrete Pavement 7-Inch	160.000 SY	_____.	_____.
0046	415.0090 Concrete Pavement 9-Inch	156.000 SY	_____.	_____.
0048	416.0610 Drilled Tie Bars	381.000 EACH	_____.	_____.
0050	416.0620 Drilled Dowel Bars	366.000 EACH	_____.	_____.
0052	416.1710 Concrete Pavement Repair	174.000 SY	_____.	_____.
0054	416.1720 Concrete Pavement Replacement	362.000 SY	_____.	_____.
0056	450.4000 HMA Cold Weather Paving	29,990.000 TON	_____.	_____.
0058	455.0605 Tack Coat	6,780.000 GAL	_____.	_____.
0060	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0062	460.6223 HMA Pavement 3 MT 58-28 S	17,960.000 TON	_____.	_____.



Proposal Schedule of Items

Page 3 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	460.6224 HMA Pavement 4 MT 58-28 S	11,130.000 TON	_____.	_____.
0066	465.0105 Asphaltic Surface	1,742.000 TON	_____.	_____.
0068	465.0110 Asphaltic Surface Patching	900.000 TON	_____.	_____.
0070	465.0120 Asphaltic Surface Driveways and Field Entrances	310.000 TON	_____.	_____.
0072	465.0520 Asphaltic Rumble Strips, Shoulder	10,400.000 LF	_____.	_____.
0074	465.0560 Asphaltic Rumble Strips, Centerline	23,240.000 LF	_____.	_____.
0076	520.1030 Apron Endwalls for Culvert Pipe 30-Inch	6.000 EACH	_____.	_____.
0078	520.1036 Apron Endwalls for Culvert Pipe 36-Inch	4.000 EACH	_____.	_____.
0080	520.3430 Culvert Pipe Class III-A Non-metal 30-Inch	238.000 LF	_____.	_____.
0082	520.3436 Culvert Pipe Class III-A Non-metal 36-Inch	182.000 LF	_____.	_____.
0084	522.0160 Culvert Pipe Reinforced Concrete Class III 60-Inch	232.000 LF	_____.	_____.
0086	522.0436 Culvert Pipe Reinforced Concrete Class IV 36-Inch	168.000 LF	_____.	_____.
0088	522.1036 Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	4.000 EACH	_____.	_____.
0090	522.1060 Apron Endwalls for Culvert Pipe Reinforced Concrete 60-Inch	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0092	601.0409 Concrete Curb & Gutter 30-Inch Type A	413.000 LF	_____.	_____.
0094	601.0588 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	98.000 LF	_____.	_____.
0096	601.0590 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	61.000 LF	_____.	_____.
0098	602.0415 Concrete Sidewalk 6-Inch	125.000 SF	_____.	_____.
0100	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	20.000 SF	_____.	_____.
0102	602.3010 Concrete Surface Drains	4.000 CY	_____.	_____.
0104	606.0200 Riprap Medium	25.000 CY	_____.	_____.
0106	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	54.000 LF	_____.	_____.
0108	611.0430 Reconstructing Inlets	1.000 EACH	_____.	_____.
0110	611.0639 Inlet Covers Type H-S	1.000 EACH	_____.	_____.
0112	611.3230 Inlets 2x3-FT	1.000 EACH	_____.	_____.
0114	612.0204 Pipe Underdrain Unperforated 4-Inch	560.000 LF	_____.	_____.
0116	612.0804 Apron Endwalls for Underdrain Reinforced Concrete 4-Inch	16.000 EACH	_____.	_____.
0118	614.2300 MGS Guardrail 3	675.000 LF	_____.	_____.
0120	614.2500 MGS Thrie Beam Transition	315.000 LF	_____.	_____.



Proposal Schedule of Items

Page 5 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0122	614.2610 MGS Guardrail Terminal EAT	8.000 EACH	_____.	_____.
0124	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1520-00-77	1.000 EACH	_____.	_____.
0126	619.1000 Mobilization	1.000 EACH	_____.	_____.
0128	624.0100 Water	63.370 MGAL	_____.	_____.
0130	625.0100 Topsoil	8,620.000 SY	_____.	_____.
0132	628.1504 Silt Fence	6,200.000 LF	_____.	_____.
0134	628.1520 Silt Fence Maintenance	6,200.000 LF	_____.	_____.
0136	628.1905 Mobilizations Erosion Control	8.000 EACH	_____.	_____.
0138	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0140	628.2006 Erosion Mat Urban Class I Type A	1,150.000 SY	_____.	_____.
0142	628.2008 Erosion Mat Urban Class I Type B	7,143.000 SY	_____.	_____.
0144	628.2027 Erosion Mat Class II Type C	327.000 SY	_____.	_____.
0146	628.7010 Inlet Protection Type B	4.000 EACH	_____.	_____.
0148	628.7020 Inlet Protection Type D	3.000 EACH	_____.	_____.
0150	628.7504 Temporary Ditch Checks	280.000 LF	_____.	_____.
0152	628.7555 Culvert Pipe Checks	75.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 6 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0154	628.7570 Rock Bags	225.000 EACH	_____.	_____.
0156	629.0210 Fertilizer Type B	2.000 CWT	_____.	_____.
0158	630.0130 Seeding Mixture No. 30	339.000 LB	_____.	_____.
0160	630.0140 Seeding Mixture No. 40	53.000 LB	_____.	_____.
0162	630.0500 Seed Water	200.000 MGAL	_____.	_____.
0164	633.5200 Markers Culvert End	14.000 EACH	_____.	_____.
0166	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0168	643.0300 Traffic Control Drums	250.000 DAY	_____.	_____.
0170	643.0420 Traffic Control Barricades Type III	4,221.000 DAY	_____.	_____.
0172	643.0705 Traffic Control Warning Lights Type A	8,250.000 DAY	_____.	_____.
0174	643.0900 Traffic Control Signs	34,326.000 DAY	_____.	_____.
0176	643.0920 Traffic Control Covering Signs Type II	23.000 EACH	_____.	_____.
0178	643.1000 Traffic Control Signs Fixed Message	36.000 SF	_____.	_____.
0180	643.1050 Traffic Control Signs PCMS	48.000 DAY	_____.	_____.
0182	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0184	645.0120 Geotextile Type HR	50.000 SY	_____.	_____.



Proposal Schedule of Items

Page 7 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0186	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	89,550.000 LF	_____.	_____.
0188	646.3020 Marking Line Epoxy 8-Inch	6.000 LF	_____.	_____.
0190	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	324.000 LF	_____.	_____.
0192	646.5520 Marking Outfall Epoxy	100.000 EACH	_____.	_____.
0194	646.6120 Marking Stop Line Epoxy 18-Inch	48.000 LF	_____.	_____.
0196	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	240.000 LF	_____.	_____.
0198	646.9200 Marking Removal Line Wide	150.000 LF	_____.	_____.
0200	648.0100 Locating No-Passing Zones	5.840 MI	_____.	_____.
0202	650.4000 Construction Staking Storm Sewer	1.000 EACH	_____.	_____.
0204	650.4500 Construction Staking Subgrade	2,057.000 LF	_____.	_____.
0206	650.5000 Construction Staking Base	2,057.000 LF	_____.	_____.
0208	650.5500 Construction Staking Curb Gutter and Curb & Gutter	159.000 LF	_____.	_____.
0210	650.6000 Construction Staking Pipe Culverts	9.000 EACH	_____.	_____.
0212	650.7000 Construction Staking Concrete Pavement	392.000 LF	_____.	_____.



Proposal Schedule of Items

Page 8 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0214	650.8000 Construction Staking Resurfacing Reference	28,671.000 LF	_____.	_____.
0216	650.9000 Construction Staking Curb Ramps	1.000 EACH	_____.	_____.
0218	650.9500 Construction Staking Sidewalk (project) 01. 1520-00-77	1.000 EACH	_____.	_____.
0220	650.9911 Construction Staking Supplemental Control (project) 01. 1520-00-77	1.000 EACH	_____.	_____.
0222	650.9920 Construction Staking Slope Stakes	2,241.000 LF	_____.	_____.
0224	690.0150 Sawing Asphalt	1,519.000 LF	_____.	_____.
0226	690.0250 Sawing Concrete	1,712.000 LF	_____.	_____.
0228	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0230	740.0440 Incentive IRI Ride	11,560.000 DOL	1.00000	11,560.00
0232	SPV.0055 Special 01. Incentive Density PWL HMA Pavement	11,171.000 DOL	1.00000	11,171.00
0234	SPV.0055 Special 02. Incentive Air Voids, HMA Pavement	7,170.000 DOL	1.00000	7,170.00
0236	SPV.0055 Special 03. Incentive Density HMA Pavement Longitudinal Joints	6,060.000 DOL	1.00000	6,060.00
0238	SPV.0060 Special 01. Temporary Bypass Pumping STA 30+64	1.000 EACH	_____.	_____.
0240	SPV.0060 Special 02. Temporary Bypass Pumping STA 184+32	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 9 of 9

Proposal ID: 20240910014 Project(s): 1520-00-77

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0242	SPV.0060 Special 03. Temporary Water Diversion Twin Culvert Construction STA 247+51	1.000 EACH	_____.	_____.
0244	SPV.0060 Special 04. Temporary Water Diversion Twin Culvert Construction STA 259+53	1.000 EACH	_____.	_____.
0246	209.2100 Backfill Granular Grade 2	5,580.000 CY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.