



## Wisconsin Department of Transportation

---

October 30, 2024

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### **NOTICE TO ALL CONTRACTORS:**

**Proposal #08: 5780-03-72, WISC 2025027**  
**Wauzeka - Soldiers Grove,**  
**Sunny Ridge Road to Pleasant Street**  
**STH 131**  
**Crawford County**

### **Letting of November 12, 2024**

This is Addendum No. 01, which provides for the following:

#### **Special Provisions:**

Revised Special Provisions	
Article No.	Description
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**5780-03-72**

**October 30, 2024**

**Special Provisions**

**6. Utilities.**

*Replace entire section titled **Village of Soldiers Grove - Sewer** with the following:*

**Village of Soldiers Grove – Sewer** - has facilities within the project limits.

Station 767+10 LT – Village cannot lower gravity sanitary sewer. Sanitary sewer invert elevation at crossing station 767+10 LT is 11 ft. + deep to invert and storm sewer invert elevation is 6 ft +/- so adequate separation. Sanitary sewer invert elevation crossing at station 768+90 LT is 10 ft. + deep to invert and storm sewer invert elevation is less than 5 ft. so adequate separation.

Adjust manholes at Stations noted below to match the new finished pavement elevation. This work will be done as part of the construction project.

Station 761+60 RT – Adjust manhole to final grade.

Station 767+28 LT – Adjust manhole to final grade.

Station 768+88 LT – Adjust manhole to final grade.

Station 771+65 LT – Adjust manhole to final grade.

Station 774+35 LT – Adjust manhole to final grade.

Replace entire section titled **Village of Soldiers Grove -Water** with the following:

**Village of Soldiers Grove – Water** - has facilities within the project limits.

Village of Soldiers Grove will be doing the following work at the below stations. This work will be completed by the municipal contractor prior to construction.

Station 760+85 LT – Relocate existing fire hydrant to 5 ft past curb and gutter.

Station 766+95 LT – Relocate the water service curb box behind curb.

Station 748+50 to 775+00 LT & RT – Village of Soldiers Grove will confirm water main depths are adequate per grading, Municipal contractor will move the watermain.

Station 750+00RT – Village of Soldiers Grove will confirm water main depth at storm sewer inlet. Municipal contractor will move the water main.

Station 754+75 RT – Village of Soldiers Grove will confirm water main depth at storm sewer inlet. Municipal contractor will move the water main.

Station 766+85 LT – Village of Soldiers Grove will confirm water main depth at storm sewer crossing. Municipal contractor will move the water main.

Station 766+22 RT – Village of Soldiers Grove will confirm water main depth at storm sewer crossing. Municipal contractor will move the water main.

At the locations noted below. Install board polystyrene 2-inch insulation under the storm sewer inlet. This work will be done as part of the construction project.

Station 750+00 RT – Install insulation under storm sewer inlet.

Station 754+75 RT – Install insulation under storm sewer inlet.

Station 766+85 LT – Install insulation under storm sewer inlet.

Station 766+22 RT – Install insulation under storm sewer inlet.

At the locations listed below. Adjust water valves to match the new finished final grade elevation. This work will be done as part of the construction project.

Station 754+55 RT – Adjust water valve to final grade.

Station 760+30 LT – Adjust water valve to final grade.

Station 760+65 LT – Adjust water valve to final grade.

Station 760+85 LT – Adjust gate valve to final grade.

Station 766+60 LT – Adjust 2 water valves to final grade.

Station 766+95 LT – Adjust curb box to final grade.

Station 768+60 RT – Adjust water valve to final grade.

Station 768+65 RT – Adjust water valve to final grade.

Station 768+75 RT – Adjust water valve to final grade.

Station 771+15 LT – Adjust water service curb box to final grade.

Station 771+45 RT – Adjust water valve to final grade.

END OF ADDENDUM

