



Wisconsin Department of Transportation

November 6, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #10: 5845-16-77, WISC 2025030
Stoughton - Madison
Larson Beach Rd to Voges Rd
USH 51
Dane County

Letting of November 12, 2024

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Added Special Provisions	
Article No.	Description
54	Utility Line Opening (ULO), Item SPV.0060.10

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
SPV.0060.06	Concrete Supports	Each	3	1	4

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0060.10	Utility Line Opening (ULO)	Each	0	5	5

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
220	Miscellaneous Quantities (revised bid items for concrete supports)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

5845-16-77

November 6, 2024

Special Provisions

3. Prosecution and Progress.

*Replace bullet point 6 under subsection titled **Stage 2D** under section titled **Staged Construction** with the following:*

6. Prior to opening to Stage 3 traffic, install all permanent signing, permanent pavement marking, and lighting along Siggelkow Rd. Inclusion of temporary lighting would be considered incidental to construction.

54. Utility Line Opening (ULO), Item SPV.0060.10.

A Description

Excavate and uncover utilities for the purposes of determining elevation and potential conflicts, as directed by the engineer, and as hereinafter provided.

B (Vacant)

C Construction

The excavation will be done in such a manner that the utility in question is not damaged and the safety of the workers is not compromised.

The utility line openings will be performed as soon as possible and at least 10 days in advance of proposed utility construction to allow any conflicts to be resolved with minimal disruption. Where utilities are within 5 feet of each other at a potential conflict location, only one utility line opening will be called for. In these cases, a single utility line opening will be considered full payment to locate multiple utilities. Utility line openings will include a trench up to 5 feet long as measured at the trench bottom, and of any depth required to locate the intended utility.

Coordinate all utility line openings with the engineer. Do not perform ULOs without engineer's approval. Notify the utility engineers or their agents of this work a minimum of 3 days prior to the work so they may be present when the work is completed. Verify the need for performing ULOs with the engineer since some of the utilities may have been relocated prior to the start of construction.

Replace pavement open to traffic within 24 hours of the excavation.

D Measurement

The department will measure Utility Line Opening (ULO) by the unit, acceptably completed. Where utilities are within 5 feet of each other at a potential conflict location, only one utility line opening will be measured.

E Payment

The department will pay for measured quantities at the contract price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.10	Utility Line Opening (ULO)	EACH

Utility Line Opening, measured as provided above, will be paid for at the contract unit price each, which will be full compensation for the excavation required to expose the utility line, backfilling with existing material removed from the excavation, compacting the backfill material, restoring the site, and cleanup.

Schedule of Items

Attached, dated November 6, 2024, are the revised Schedule of Items Pages 22 and 24.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 220

END OF ADDENDUM

3

CATEGORY	STATION	LOCATION	EACH	
0010	49+04 'SGE'	SIGGEIKOW RD, 21.8' RT	1	
	48+87 'SGW'	SIGGEIKOW RD, 40.2' LT	1	
	921+69 'SB'	USH 51, 74.5' LT	1	
	940+27 'SB'	USH 51, 45.6' LT	1	
TOTAL 0010			4	



Proposal Schedule of Items

Page 22 of 24

Proposal ID: 20241112010 Project(s): 5845-16-77

Federal ID(s): WISC 2025030

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0620	801.0117 Railroad Flagging Reimbursement	90,000.000 DOL	1.00000	90,000.00
0622	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. 901+25 'NB'	1.000 EACH	_____.	_____.
0624	999.2000.S Installing and Maintaining Bird Deterrent System (station) 02. 901+50 'SB'	1.000 EACH	_____.	_____.
0626	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
0628	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	6,480.000 HRS	5.00000	32,400.00
0630	SPV.0060 Special 01. Cleaning and Painting Bearings	10.000 EACH	_____.	_____.
0632	SPV.0060 Special 02. Barrier Wall Delineation	164.000 EACH	_____.	_____.
0634	SPV.0060 Special 03. Settlement Guages	3.000 EACH	_____.	_____.
0636	SPV.0060 Special 04. Reconstructing Manholes	12.000 EACH	_____.	_____.
0638	SPV.0060 Special 05. Manhole Covers Type J-Special	13.000 EACH	_____.	_____.
0640	SPV.0060 Special 06. Concrete Supports	4.000 EACH	_____.	_____.
0642	SPV.0060 Special 07. Pipe Connection to Existing Structure	2.000 EACH	_____.	_____.
0644	SPV.0060 Special 08. Apron Endwalls for Culvert Pipe Horizontal Elliptical Salvaged 19x30-Inch	1.000 EACH	_____.	_____.
0646	SPV.0060 Special 09. Cover Plates	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 24 of 24

Proposal ID: 20241112010 Project(s): 5845-16-77

Federal ID(s): WISC 2025030

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0676	SPV.0060 Special 10. Utility Line Opening (ULO)	5.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

