



Wisconsin Department of Transportation

November 7, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #14: 5990-01-34, WISC 2025080
C Janesville, W Court Street
Waveland Road to Pearl Street
Local Street
Rock County

5990-01-36, WISC 2025081
C Janesville, W Court St Intersctns
N Crosby Av; N Arch St; N Pearl St
Local Street
Rock County

5990-01-37
C Janesville, W Court St
Crosby Avenue to Washington Street
Const/Local Pavement and Water Main
Rock County

Letting of November 12, 2024

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Common Excavation	CY	1,724	7,067	8,791
311.0110	Breaker Run	TON	140	264	404
624.0100	Water	MGAL	233.2	14.5	247.7

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
233	Miscellaneous Quantities (Revisions to quantities.)

Schedule of Items

Attached, dated November 7, 2024, are the revised Schedule of Items Pages 2, 3, and 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 233.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 5990-01-34/36/37
Revised Sheet 233
November 7, 2024

CATEGORY	ID: 5990-01-34	FROM/TO STATION	COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL	EXPANDED EBS BACKFILL		EXPANDED FILL		MASS ORDNATE +/-	WASTE (8 9)	311.0110 BREAKER RUN	*624.0100 WATER (FOR DUST)
			CUT (1)	LOCATION (2)			FACTOR 1.25	CY	FACTOR 1.25	CY				
0010	DIVISION 1	EASTBOUND WIDENING WEST OF WAVELAND RD	RT	8	0	0	8	0	0	0	8	0	1	0.0
		BUS PULL OUT	LT	57	3	7	50	5	11	39	39	5	0.1	0.1
		WEST COURT STREET SIDEWALK AND CURB & GUTTER	L/RT	58	3	0	58	4	0	0	58	5	0.1	0.1
		WEST COURT STREET SIDEWALK AND CURB & GUTTER	L/RT	66	3	0	66	4	0	0	66	6	0.1	0.1
		WEST COURT STREET SIDEWALK AND CURB & GUTTER	L/RT	208	10	0	208	6	0	0	208	6	0.2	0.2
DIVISION 1 SUBTOTAL			397	20	7	390	26	9	11	379	379	36	0.8	0.8
GRAND TOTAL			397	20	7	390	26	9	11	379	379	36	0.8	0.8
TOTAL COMMON EXC			417											

CATEGORY	ID: 5990-01-36	FROM/TO STATION	205.0100 COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL	EXPANDED EBS BACKFILL		EXPANDED FILL		MASS ORDNATE +/-	WASTE (8) (9)	311.0110 BREAKER RUN	*624.0100 WATER FOR DUST						
			CUT (1)	LOCATION (2)			CY	EBS CY	CY	CY					FACTOR 1.25	CY	FACTOR 1.25	(5)	(6)	(7)
0010	DIVISION 1	CROSBY EASTBOUND RIGHT-TURN LANE	RT	97	4	15	82	5	26	33	50	50	7	0.2						
		CROSBY WESTBOUND RIGHT-TURN LANE	LT	85	4	13	72	5	22	28	45	45	7	0.2						
		133+49.49/135+06.86	L/RT	96	5	39	57	6	0	0	57	57	9	0.2						
		130+54.00/135+80.00	L/RT	68	3	27	41	4	0	0	41	41	6	0.1						
		WEST COURT STREET SIDEWALK AND CURB & GUTTER	L/RT	68	3	27	41	4	0	0	41	41	6	0.1						
		148+40.00/153+76.00	L/RT	51	3	17	35	3	0	0	35	35	5	0.1						
		WEST COURT STREET SIDEWALK AND CURB & GUTTER	L/RT	51	3	17	35	3	0	0	35	35	5	0.1						
		EXCAVATION TO SUBGRADE FOR FULL DEPTH PAVEMENT REPLACEMENT AREAS	L/RT	19	1	6	13	1	0	0	13	13	2	0.0						
		EXCAVATION TO SUBGRADE FOR FULL DEPTH PAVEMENT REPLACEMENT AREAS	L/RT	19	1	6	13	1	0	0	13	13	2	0.0						
		EXCAVATION TO SUBGRADE FOR FULL DEPTH PAVEMENT REPLACEMENT AREAS	L/RT	96	5	31	65	6	0	0	65	65	9	0.2						
DIVISION 1 SUBTOTAL				609	29	161	448	37	48	60	388	388	53	1.3						
GRAND TOTAL				609	29	161	448	37	48	60	388	388	53	1.3						
TOTAL COMMON EXC				639																

CATEGORY	ID: 5990-01-37	DIVISION	FROM/TO STATION	205.0100 COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL	EXPANDED EBS BACKFILL		EXPANDED FILL		MASS ORDNATE +/-	WASTE (8 9)	311.0110 BREAKER RUN	*624.0100 WATER (FOR DUST)
				CUT (2)	EXCAVATION (3)			FACTOR 1.25	CY	FACTOR 1.25	CY				
0010	DIVISION 1	EASTBOUND PEARL STREET TERRACE WIDENING WESTBOUND WASHINGTON STREET TERRACE WIDENING WEST COURT STREET MEDIAN PAPER WEST COURT STREET SIDEWALK AND CURB & GUTTER	17+48.55/179+11.41	L/RT	306	19	198	198	24	190	238	0	0	24	0.8
			180+57.29/183+00.00	LT	60	4	60	60	0	0	0	60	60	7	0.1
			179+63.26/182+15.45	L/RT	208	10	0	208	0	0	0	208	208	18	0.4
			176+40/183+40	L/RT	74	4	0	74	5	0	0	74	74	7	0.2
			DIVISION 1 SUBTOTAL		738	37	198	540	28	238	342	342	342	66	1.5
CATEGORY 0010 SUBTOTAL				738	37	198	540	28	238	342	342	342	66	1.5	
0020	DIVISION 1	WEST COURT STREET SIDEWALK AND CURB & GUTTER EXCAVATION TO SUBGRADE FOR FULL DEPTH PAVEMENT REPLACEMENT AREAS DIVISION 1 SUBTOTAL	133+80/182+76	L/RT	65	3	0	65	4	0	0	65	65	6	0.1
			132+45/183+40	L/RT	6,757	135	2,207	4,551	169	0	0	4,551	4,551	243	13.8
				L/RT	6,822	138	2,207	4,616	173	0	0	4,616	4,616	249	13.9
			DIVISION 1 SUBTOTAL		6,822	138	2,207	4,616	173	0	0	4,616	4,616	249	14.0
			CATEGORY 0020 SUBTOTAL		7,560	175	2,405	5,156	201	238	4,958	4,958	315	15.5	
GRAND TOTAL				7,560	175	2,405	5,156	201	238	4,958	4,958	315	15.5		
TOTAL COMMON EXC				7,736											

NOTES:
(1) EXCAVATION COMMON IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100.
(2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
(3) EBS EXCAVATION TO BE BACKFILLED WITH BREAKER RUN.
(4) AVAILABLE MATERIAL - CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL - AVAILABLE STRUCTURE EXCAVATION
(5) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH BREAKER RUN. EBS BACKFILL FACTOR = 1.25. ITEM NUMBER 312.0110
(6) EXPANDED FILL = (UNEXPANDED FILL) * EXPANDED FILL FACTOR. EXPANDED FILL FACTOR = 1.25.
(7) MASS ORDNATE: MASS ORDNATE = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL - EXPANDED FILL AVAILABLE STRUCTURE EXCAVATION
(8) WASTE = MASS ORDNATE + EXPANDED EBS BACKFILL
(9) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR INFORMATION ONLY.
* ADDITIONAL QUANTITIES LISTED ELSEWHERE



Proposal Schedule of Items

Page 2 of 20

Proposal ID: 20241112014 Project(s): 5990-01-34, 5990-01-36, 5990-01-37

Federal ID(s): WISC 2025080, WISC 2025081, N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.9060.S Removing (item description) 06. Removing Loop Detector Wire and Lead-In Cable W Court St & Crosby Ave	1.000 EACH	_____.	_____.
0032	204.9060.S Removing (item description) 07. Removing Loop Detector Wire and Lead-In Cable W Court St & Arch St	1.000 EACH	_____.	_____.
0034	204.9060.S Removing (item description) 08. Removing Loop Detector Wire and Lead-In Cable W Court St & Pearl St	1.000 EACH	_____.	_____.
0036	204.9090.S Removing (item description) 01. Removing Landscaping Timbers	25.000 LF	_____.	_____.
0038	204.9090.S Removing (item description) 02. Removing Landscaping Block Wall	17.000 LF	_____.	_____.
0040	205.0100 Excavation Common	8,791.000 CY	_____.	_____.
0042	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 5990-01-34	1.000 EACH	_____.	_____.
0044	211.0101 Prepare Foundation for Asphaltic Paving (project) 02. 5990-01-36	1.000 EACH	_____.	_____.
0046	211.0101 Prepare Foundation for Asphaltic Paving (project) 03. 5990-01-37	1.000 EACH	_____.	_____.
0048	211.0500 Prepare Foundation for Base Aggregate	56.000 STA	_____.	_____.
0050	213.0100 Finishing Roadway (project) 01. 5990-01-34	1.000 EACH	_____.	_____.
0052	213.0100 Finishing Roadway (project) 02. 5990-01-36	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 20

Proposal ID: 20241112014 Project(s): 5990-01-34, 5990-01-36, 5990-01-37

Federal ID(s): WISC 2025080, WISC 2025081, N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0054	213.0100 Finishing Roadway (project) 03. 5990-01-37	1.000 EACH	_____.	_____.
0056	305.0110 Base Aggregate Dense 3/4-Inch	7.000 TON	_____.	_____.
0058	305.0120 Base Aggregate Dense 1 1/4-Inch	13,561.000 TON	_____.	_____.
0060	311.0110 Breaker Run	404.000 TON	_____.	_____.
0062	320.0145 Concrete Base 8-Inch	281.000 SY	_____.	_____.
0064	415.0080 Concrete Pavement 8-Inch	26.000 SY	_____.	_____.
0066	416.0610 Drilled Tie Bars	1,306.000 EACH	_____.	_____.
0068	416.0620 Drilled Dowel Bars	45.000 EACH	_____.	_____.
0070	455.0605 Tack Coat	3,432.000 GAL	_____.	_____.
0072	460.2000 Incentive Density HMA Pavement	6,290.000 DOL	1.00000	6,290.00
0074	460.6223 HMA Pavement 3 MT 58-28 S	2,524.000 TON	_____.	_____.
0076	460.6424 HMA Pavement 4 MT 58-28 H	7,200.000 TON	_____.	_____.
0078	465.0105 Asphaltic Surface	1,269.000 TON	_____.	_____.
0080	465.0110 Asphaltic Surface Patching	30.000 TON	_____.	_____.
0082	465.0120 Asphaltic Surface Driveways and Field Entrances	62.000 TON	_____.	_____.



Proposal Schedule of Items

Page 5 of 20

Proposal ID: 20241112014 Project(s): 5990-01-34, 5990-01-36, 5990-01-37

Federal ID(s): WISC 2025080, WISC 2025081, N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0114	611.1230 Catch Basins 2x3-FT	3.000 EACH	_____.	_____.
0116	611.3901 Inlets Median 1 Grate	1.000 EACH	_____.	_____.
0118	611.8110 Adjusting Manhole Covers	7.000 EACH	_____.	_____.
0120	611.8115 Adjusting Inlet Covers	1.000 EACH	_____.	_____.
0122	612.0902.S Insulation Board Polystyrene (inch) 01.2-Inch	29.000 SY	_____.	_____.
0124	619.1000 Mobilization	1.000 EACH	_____.	_____.
0126	620.0300 Concrete Median Sloped Nose	52.000 SF	_____.	_____.
0128	621.1100 Landmark Reference Monuments and Cast Iron Covers	2.000 EACH	_____.	_____.
0130	624.0100 Water	247.700 MGAL	_____.	_____.
0132	625.0100 Topsoil	7,830.000 SY	_____.	_____.
0134	627.0200 Mulching	18,600.000 SY	_____.	_____.
0136	628.1504 Silt Fence	550.000 LF	_____.	_____.
0138	628.1520 Silt Fence Maintenance	2,750.000 LF	_____.	_____.
0140	628.1905 Mobilizations Erosion Control	30.000 EACH	_____.	_____.
0142	628.1910 Mobilizations Emergency Erosion Control	15.000 EACH	_____.	_____.