



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

November 4, 2024

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

<p><b>Proposal #15: 5991-07-78, 2025082</b>  <b>City of La Crosse, Green Bay Street</b>  <b>22nd St S to Losey Blvd</b>  <b>Loc Str</b>  <b>La Crosse County</b></p>	<p><b>5991-07-79</b>  <b>City of La Crosse, Green Bay Street</b>  <b>22nd St S to Losey Blvd</b>  <b>Loc Str</b>  <b>La Crosse County</b></p>
--	---

### Letting of November 12, 2024

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
SPV.0090	Special 11. Sanitary Sewer Main PVC SDR 35 8-Inch	LF	652	-612	40

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
45	Miscellaneous Quantities – Updated Sanitary Sewer Pipe Summary

**Schedule of Items**

Attached, dated November 7, 2024, are the revised Schedule of Items Page 7.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 45.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

MUNICIPAL UTILITY ITEMS  
ID 5991-07-79

SANITARY SEWER STRUCTURE SUMMARY

STRUCTURE NUMBER	STATION	(A) STATION OFFSET	REMOVING				CONSTRUCTION				(B) SUMP		REMARKS
			SANITARY MANHOLES	SANITARY MANHOLES 4- FT DIAMETER	SANITARY MANHOLE COVERS	SANITARY MANHOLE COLLARS	CONCRETE MANHOLE	COVER PLATES	RIM ELEVATION	DEPTH	(C) ELEVATION	DEPTH	
0020	SAN 2	30+45	1	1	1	1	1	1	1	1	661.78	12.98	
0020	SAN 3	32+54	-	-	1	-	1	-	-	-	662.41	-	
0020	SAN 4	33+44	1	-	-	-	-	-	-	-	-	-	
PROJECT TOTALS =			2	1	2	1	2	1	2	1			

REMARKS

- (A) STATIONS AND OFFSETS ARE TO CENTER OF STRUCTURE
- (B) THE INVERT ELEVATION IS THE ELEVATION OF THE LOWEST PIPE FLOW LINE
- (C) DEPTH = RIM ELEV - TOP OF STRUCTURE BASE ELEV - COVER HEIGHT - 6 INCH ADJUSTMENT RING HEIGHT
- (D) CONTRACT ITEM SHOWN ELSEWHERE IN PLANS

SANITARY SEWER PIPE SUMMARY

CATEGORY	FROM	TO	SANITARY SEWER		SANITARY SEWER LATERAL		SANITARY SEWER TO EXISTING		CONNECTING TO EXISTING		INLET ELEVATION	DISCHARGE ELEVATION	SLOPE FT/FT	COMMENTS
			SPV.0090.04	SPV.0090.05	SPV.0090.06	SPV.0090.10	SPV.0090.11	SPV.0090.10	SPV.0090.11	SPV.0090.11				
0020	28+45	-	199	-	-	-	-	-	-	649.21	648.69	0.00261	REPLACE	
0020	28+05	-	29+45	-	80	-	-	-	-	-	-	-	-	
0020	SAN 2	-	SAN 3	-	209	-	-	-	-	648.68	648.08	0.00287	-	
0020	SAN 3	-	36+19	-	365	-	-	1	-	648.08	647.25	0.00227	-	
0020	33+35	-	SAN 4	-	30	-	-	-	-	-	-	-	-	
0020	SAN 2	-	NORTH STUB	-	-	-	-	-	40	653.18	652.94	0.0060	-	
PROJECT TOTALS =			773	38	110	2	40							

- NOTE 1: ASSUME 10' TRENCH WIDTH FOR SANITARY MAIN REPLACEMENT.
- NOTE 2: SANITARY SEWER LATERAL REPLACEMENT WITHIN THE 10' TRENCH WIDTH IS INCIDENTAL TO SANITARY MAIN REPLACEMENT. INDICATED LATERAL LENGTH DOES NOT INCLUDE THE INCIDENTAL LENGTH WITHIN THE TRENCH BOX.

Addendum No. 01  
ID 5991-07-78/79  
Revised Sheet 45  
November 7, 2024



Proposal Schedule of Items

Proposal ID: 20241112015 Project(s): 5991-07-78, 5991-07-79

Federal ID(s): WISC 2025082, N/A

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0180	SPV.0090 Special 04. Sanitary Sewer Main PVC SDR 35 10-Inch	773.000 LF	_____.	_____.
0182	SPV.0090 Special 05. Sanitary Sewer Lateral PVC SDR 35 6-Inch	38.000 LF	_____.	_____.
0184	SPV.0090 Special 06. Removing Sanitary Sewer Pipe	110.000 LF	_____.	_____.
0186	SPV.0090 Special 07. Water Main, 12-Inch	634.000 LF	_____.	_____.
0188	SPV.0090 Special 08. Water Main, 16-Inch	148.000 LF	_____.	_____.
0190	SPV.0090 Special 09. Water Service Copper, 1- Inch	371.000 LF	_____.	_____.
0192	SPV.0090 Special 10. Finishing for Curb and Gutter	1,582.000 LF	_____.	_____.
0194	SPV.0090 Special 11. Sanitary Sewer Main PVC SDR 35 8-Inch	40.000 LF	_____.	_____.
0196	SPV.0090 Special 12. Marking Stop Line Grooved Epoxy 12-Inch	37.000 LF	_____.	_____.
0198	SPV.0090 Special 13. Marking Crosswalk Transverse Line Grooved Epoxy 12-Inch	228.000 LF	_____.	_____.
0200	SPV.0090 Special 14. Water Main, 6-Inch	88.000 LF	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.