



Wisconsin Department of Transportation

December 4, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #09: 6160-00-70, WISC 2025098
Necedah - Coloma
Sheridan Street to East County Line
STH 21
Juneau County

Letting of December 10, 2024

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
204.0120	Removing Asphaltic Surface Milling	SY	59000	3300	55700
211.0400	Prepare Foundation for Asphaltic Shoulders	STA	24	101	125

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
250	Miscellaneous Quantities Table 'REMOVING ASPHALTIC SURFACE'
254	Miscellaneous Quantities Table 'HMA PAVEMENT'

Schedule of Items

Attached, dated December 4, 2024, are the revised Schedule of Items Pages 1 and 2.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 250 and 254.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

REMOVING ASPHALTIC SURFACE																
PROJECT	CATEGORY	LOCATION	STATION - STATION	BUTT JOINTS (SY)	MILLING (SY)	NOTES	PROJECT	CATEGORY	LOCATION	STATION - STATION	REMOVING GUARDRAIL FENCE LF	REMOVING GUARDRAIL FENCE LF				
6160-00-70	0010	204.0115			204.0120		204.0165			204.0170						
		STH 80 NORTH LEG					RR CROSSING - B-29-006									
		STAGE 2					B-29-006 - B-29-136									
		STAGE 3					B-29-100									
		STH 80 NORTH LEG					B-29-006 - B-29-136									
		STAGE 2					B-29-100									
		STAGE 3					STAGE 3 SUBTOTAL									
		STH 80 NORTH LEG					CAT 0010 TOTAL									
		STAGE 2					PROJECT 6160-00-70 TOTAL									
		STAGE 3														
PROJECT 6160-00-70					2,310	25	PROJECT 6160-00-70 TOTAL					25				
PROJECT 6160-00-70					2,310	25	PROJECT 6160-00-70 TOTAL					25				

REMOVING CURB AND GUTTER													
PROJECT	CATEGORY	LOCATION	STATION - STATION	LF	PROJECT	CATEGORY	LOCATION	STATION - STATION	LF				
6160-00-70	0010	STH 80 INTERSECTION			STH 80 INTERSECTION			650+00 - 651+00 '21'	162				
		STH 80 NORTH			STH 80 NORTH			227+00'B' - 230+96'B'	333				
		STAGE 1 SUBTOTAL			STAGE 1 SUBTOTAL				495				
		CAT 0010 TOTAL			CAT 0010 TOTAL				495				
		STAGE 1			STAGE 1			700+00 - 702+00 '21'	138				
		STAGE 2			STAGE 2			700+00 - 702+00 '21'	142				
		STAGE 3 SUBTOTAL			STAGE 3 SUBTOTAL				280				
		CAT 0020 TOTAL			CAT 0020 TOTAL				775				
		PROJECT 6160-00-70 TOTAL			PROJECT 6160-00-70 TOTAL				775				
PROJECT 6160-00-70					PROJECT 6160-00-70 TOTAL								
PROJECT 6160-00-70					PROJECT 6160-00-70 TOTAL								

Addendum No. 01
ID 6160-00-70
Revised Sheet 250
December 4, 2024

PROJECT NO: 6160-00-70	HWY: STH 21	COUNTY: JUNEAU	MISCELLANEOUS QUANTITIES	SHEET	250	E
------------------------	-------------	----------------	--------------------------	-------	-----	---

Addendum No. 01
ID 6160-00-70
Revised Sheet 250
December 4, 2024

CONCRETE PAVEMENT APPROACH SLAB								
PROJECT	CATEGORY	LOCATION	STATION - STATION	415.0410		416.0750.S		
				CONCRETE PAVEMENT APPROACH SLAB SY	CONCRETE PAVEMENT PARTIAL DEPTH REPAIR JOINT REPAIR LF			
6160-00-70	0010	STAGE 3						
		B-29-006	653+69 - 653+84 '21'	42	-	-		
		B-29-006	656+25 - 656+47 '21'	-	20	20		
		B-29-136	665+56 - 666+16 '21'	-	75	75		
		B-29-136	666+86 - 667+57 '21'	-	100	100		
		B-29-100	667+28 - 677+59 '21'	-	30	30		
		B-29-100	678+44 - 678+75 '21'	-	35	35		
		STAGE 3 SUBTOTAL		42	260	260		
		CAT 0010 TOTAL					42	260
		PROJECT 6160-00-70 TOTAL					42	260

Addendum No. 01

ID 6160-00-70

Revised Sheet 254

December 4, 2024

Addendum No. 01
ID 6160-00-70
Revised Sheet 254
December 4, 2024

HMA PAVEMENT											
PROJECT	CATEGORY	LOCATION	STATION - STATION	211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS (STA)	TACK COAT (GAL)	3 MT 58-28 S (TON)	4 MT 58-28 H (TON)	NOTES			
6160-00-70	0010										
		STAGE 2		227+61 - 229+87 'B'		-	38	50	26		
		STAGE 2 SUBTOTAL				0	38	50	26		
		STAGE 3									
		STH 80 NORTH LEG		227+61 - 229+87 'B'		-	19	25	13		
		STH 80 - B-29-006		649+84 - 653+84 '21'		-	46	42	32		
		B-29-006 - B-29-136		656+47 - 665+67 '21'		10	543	489	380		
		B-29-136 - B-29-100		667+57 - 677+27 '21'		-	624	562	437		
		B-29-100 - C-29-015		678+75 - 691+18 '21'		10	661	595	463		
		C-29-015 - RAB		691+31 - 694+18 '21'		3	138	124	97		
		RAB - 16TH AVE		708+95 - 732+63 '21'		24	1,177	1,060	824		
		16TH AVE - 17TH AVE		732+63 - 765+84 '21'		33	1,645	1,486	1,152		
		17TH AVE - EOP		765+84 - 818+04 '21'		45	2,809	2,528	1,966		
		STAGE 3 SUBTOTAL				125	7,663	6,910	5,364		
CAT 0010 TOTAL				125	7,700	6,960	5,390				
0020		STAGE 1									
		RAB WEST		694+18 - 700+53 '21'		-	97	205	89		
		RAB EAST		700+53 - 708+95 '21'		-	150	315	107		
		CTH G		10+66 - 17+15 GNS		-	252	227	177		
		STAGE 1 SUBTOTAL				0	500	747	353		
		STAGE 2									
		RAB WEST		694+18 - 700+53 '21'		-	133	279	93		
		RAB EAST		700+53 - 708+95 '21'		-	76	164	55		
		CTH G		20+00 - 26+51 GNN		-	234	230	179		
		STAGE 2 SUBTOTAL				0	465	673	327		
		CAT 0020 TOTAL				0	965	1,420	680		
		0040		STAGE 3							
				B-29-100 - C-29-015		678+75 - 691+18 '21'		-	67	60	45
				C-29-015 - RAB		691+31 - 694+18 '21'		-	17	15	13
RAB - 16TH AVE				708+95 - 732+63 '21'		-	114	102	82		
16TH AVE - 17TH AVE				732+63 - 765+84 '21'		-	212	191	150		
17TH AVE - EOP				765+84 - 818+04 '21'		-	215	191	151		
STAGE 3 SUBTOTAL						0	625	560	440		
CAT 0040 SUBTOTAL						0	625	560	440		
PROJECT 6160-00-70 TOTAL						125	9,290	8,940	6,510		

*ADDITIONAL QUANTITY FOUND IN "TEMPORARY ASPHALT ITEMS" & "REMOVING DISTRESS PAVEMENT MILLING"



Proposal Schedule of Items

Page 1 of 17

Proposal ID: 20241210009 Project(s): 6160-00-70

Federal ID(s): WISC 2025098

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0205 Grubbing	10.000 STA	_____.	_____.
0004	201.0220 Grubbing	66.000 ID	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0008	204.0100 Removing Concrete Pavement	9,490.000 SY	_____.	_____.
0010	204.0115 Removing Asphaltic Surface Butt Joints	2,120.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	55,700.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	775.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	400.000 SY	_____.	_____.
0018	204.0165 Removing Guardrail	2,310.000 LF	_____.	_____.
0020	204.0170 Removing Fence	25.000 LF	_____.	_____.
0022	204.0195 Removing Concrete Bases	9.000 EACH	_____.	_____.
0024	204.0220 Removing Inlets	6.000 EACH	_____.	_____.
0026	204.0245 Removing Storm Sewer (size) 01. (15-Inch)	72.000 LF	_____.	_____.
0028	204.9060.S Removing (item description) 01. Traffic Signals	8.000 EACH	_____.	_____.
0030	205.0100 Excavation Common	13,185.000 CY	_____.	_____.



Proposal Schedule of Items

Page 2 of 17

Proposal ID: 20241210009 Project(s): 6160-00-70

Federal ID(s): WISC 2025098

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	208.0100 Borrow	2,652.000 CY	_____.	_____.
0034	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 6160-00-70	1.000 EACH	_____.	_____.
0036	211.0201 Prepare Foundation for Concrete Pavement (project) 01. 6160-00-70	1.000 EACH	_____.	_____.
0038	211.0400 Prepare Foundation for Asphaltic Shoulders	125.000 STA	_____.	_____.
0040	213.0100 Finishing Roadway (project) 01. 6160-00-70	1.000 EACH	_____.	_____.
0042	305.0110 Base Aggregate Dense 3/4-Inch	1,830.000 TON	_____.	_____.
0044	305.0120 Base Aggregate Dense 1 1/4-Inch	10,950.000 TON	_____.	_____.
0046	305.0500 Shaping Shoulders	245.000 STA	_____.	_____.
0048	405.0100 Coloring Concrete WisDOT Red	270.000 CY	_____.	_____.
0050	415.0090 Concrete Pavement 9-Inch	13,500.000 SY	_____.	_____.
0052	415.0410 Concrete Pavement Approach Slab	42.000 SY	_____.	_____.
0054	415.1090 Concrete Pavement HES 9-Inch	2,200.000 SY	_____.	_____.
0056	415.2010 Concrete Truck Apron 12-inch	785.000 SY	_____.	_____.
0058	415.4100 Concrete Pavement Joint Filling	15,860.000 SY	_____.	_____.
0060	416.0610 Drilled Tie Bars	44.000 EACH	_____.	_____.