



Wisconsin Department of Transportation

December 3, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #11: 2120-18-70, WISC 2025100
Hales Corners - Milwaukee
USH 45 to 45th Street
STH 24
Milwaukee County

2160-07-73, WISC 2025101
C Greenfield, S 76th Street
Bridge Over STH 24 B-40-0164
CTH U
Milwaukee County

Letting of December 10, 2024

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
69	"Luminaire Arms Single Member 8-Ft." – under section "B Materials", replace "see plan set for detail drawing sheet 5 of 5" with "and drawing C-22-26".

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
465.0110	Asphaltic Surface Patching	TON	0	100	100

Plan Sheets:

Revised Plan Sheets 2120-18-70	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
235	Storm Sewer – updated construction detail for "Adjusting/Reconstructing Manholes – Monolithic Shim" to show a 6'x6' patch.
585	Miscellaneous Quantities – Added "Asphaltic Surface Patching".

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02
PROJECT ID 2120-18-70
December 3, 2024

Special Provisions

69. Luminaire Arms Single Member 8-Ft., Item SPV.0060.24.

*Replace paragraph one under section titled **B Materials** with the following:*

Fabricated for the City of Milwaukee per City Spec. and drawing C-22-26. Bracket Arm Base Coat – Hot Dip Galvanized to ASTM A123

Schedule of Items

Attached, dated December 3, 2024, are the revised Schedule of Items Page 23.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 235, 585.

END OF ADDENDUM

HMA PAVEMENT PWL

THE FOLLOWING ACCEPTANCE CRITERIA ARE APPLICABLE FOR THIS PROJECT:

LOCATION	STATION	MIXTURE USE	UNDERLYING SURFACE	BID ITEM	TONS	THICKNESS	QUALITY MANAGEMENT PROGRAM TO BE USED FOR:
11 - 12 FT DRIVING LANE	95+34 TO 366+74	LOWER	CONCRETE PAVEMENT	3 MT 58-28 S	26727	2 1/2"	MIXTURE ACCEPTANCE
11 - 12 FT DRIVING LANE	95+34 TO 366+74	UPPER	3 MT 58-28 S	5 MT 58-28 H	16419	1 1/2"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010
6 - 12 FT SHOULDER/ PARKING LANE	95+34 TO 366+74	LOWER	CONCRETE PAVEMENT	3 MT 58-28 S	7179	2 1/2"	ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
6 - 12 FT SHOULDER/ PARKING LANE	95+34 TO 366+74	UPPER	3 MT 58-28 S	5 MT 58-28 H	4308	1 1/2"	ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
RAMPS	LAYTON & CTH U	LOWER	CONCRETE PAVEMENT	3 MT 58-28 S	1613	2 1/2"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010 PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010
RAMPS	LAYTON & CTH U	UPPER	3 MT 58-28 S	5 MT 58-28 H	968	1 1/2"	ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
DRIVEWAYS	VARIOUS	UPPER	MILLED EXISTING HMA	ASPHALTIC SURFACE	213	1 1/2"	QMP PER SS 465 ACCEPTANCE BY ORDINARY COMPACTION

CATEGORY	PROJECT	MIX TYPE	460-0.105 S HMA PERCENT WITHIN LIMITS (PWA) TEST STRIP VOLUMETRICS EACH	460-0.110 S HMA PERCENT WITHIN LIMITS (PWA) TEST STRIP DENSITY EACH
1000	2120-18-70	5 MT 58-28 H 3 MT 58-28 S	1 1	1 1
	TOTAL		2	2



Proposal Schedule of Items

Page 23 of 23

Proposal ID: 20241210011 Project(s): 2120-18-70, 2160-07-73

Federal ID(s): WISC 2025100, WISC 2025101

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0628	SPV.0090 Special 41. Strip Seal Gland Replacement	74.000 LF	_____.	_____.
0630	SPV.0090 Special 90. Cable Type 1#6 AWG 5kV	6,850.000 LF	_____.	_____.
0632	SPV.0090 Special 91. Electrical Cable Type 3#6 AL Triplex	7,100.000 LF	_____.	_____.
0634	SPV.0090 Special 92. Electrical Cable Type 2#2/1#4 AL Triplex	2,975.000 LF	_____.	_____.
0636	SPV.0165 Special 40. Modular Block Wall Repair	257.000 SF	_____.	_____.
0638	SPV.0165 Special 41. Fiber Wrap Reinforcing Non-Structural	707.000 SF	_____.	_____.
0640	SPV.0165 Special 42. Repainting Decorative Steel Railing	25.000 SF	_____.	_____.
0642	SPV.0180 Special 40. Methacrylate Flood Seal	313.000 SY	_____.	_____.
0644	SPV.0195 Special 01. Management of Solid Waste	10.700 TON	_____.	_____.
0646	SPV.0195 Special 02. Joint and Crack Repair	63.000 TON	_____.	_____.
0648	465.0110 Asphaltic Surface Patching	100.000 TON	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

