



Wisconsin Department of Transportation

January 7, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #29: 9371-00-70, WISC 2025163
CTH J – STH 17
Prairie River Bridge, B-34-0064
CTH H
Langlade County

Letting of January 14, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
15	Asphaltic Surface

Deleted Special Provisions	
Article No.	Description
16	Salvaged Topsoil

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
201.0110	Clearing	SY	0	58	58
625.0100	Topsoil	SY	0	500	500

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
625.0500	Salvaged Topsoil	SY	500	-500	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
14	Miscellaneous Quantity - Added item for Clearing
17	Miscellaneous Quantity - Replaced Salvaged Topsoil with Topsoil

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

9371-00-70

January 7, 2025

Special Provisions

3. Prosecution and Progress.

Replace entire section titled Protection of Endangered Bats (Tree Clearing) with the following:

Protection of Endangered Bats (Tree Clearing)

Northern long-eared bats (*Myotis septentrionalis*, or NLEB) have the potential to inhabit the project limits because they roost in trees, bridges and culverts. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

Ensure all operators, employees, and subcontractors working in areas of known or presumed bat habitat are aware of environmental commitments and avoidance and minimization measures (AMMs) to protect both bats and their habitat.

Direct temporary lighting, if used, away from wooded areas during the bat active season April 1 to October 31, both dates inclusive.

To avoid adverse impacts upon the NLEBs, no tree clearing is allowed between April 1 and October 31, both dates inclusive. If the required tree clearing is not completed by March 31, the department will suspend all tree clearing and associated work directly impacted by clearing.

Tree clearing is limited to that which is specified in the plans. Contractor means and methods to remove additional trees will not be allowed. If it is determined that additional trees with a 3-inch or greater diameter at breast height (dbh) need to be removed beyond contractor means and methods, notify the engineer to coordinate with the WisDOT REC to determine if consultation with United States Fish and Wildlife Service (USFWS) is required. The contractor must be aware that the WisDOT REC and/or USFWS may not permit modifications.

Submit a schedule and description of clearing operations with the ECIP 14 days prior to any clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of clearing operations, and list those additional measures in the ECIP.

15. Asphaltic Surface.

Replace paragraph 2 with the following:

Under the Asphaltic Surface bid item submit a mix design. Furnish asphaltic mixture meeting the requirements specified for HMA Pavement Type LT 58-28 S for lower layer and LT 58-34 S for the upper layer under standard spec 460.2; except the engineer will not require the contractor to conform to the quality management program specified under standard spec 460.2.8. Use tack coat as required under 450.3.2.7.

16. DELETED

Schedule of Items


Attached, dated January 7, 2025, are the revised Schedule of Items Pages 1 – 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 14, and 17.

END OF ADDENDUM

CLEARING GRUBBING



CATEGORY	STATION	TO	STATION	LOCATION	SY	REMARKS
0010	8+16	-	9+75	CTH H	58	
				TOTAL 0010	58	

204.0165
REMOVING
GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	LF	REMARKS
0010	8+15.75	-	10+00	CTH H	80	
0010	10+00	-	11+84.25	CTH H	80	
				TOTAL 0010	160	

DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION		AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL		MASS ORDNATE/ WASTE +/- (14) (15)	COMMENT
			CUT (1)	(2)			(13) FACTOR 1.25			
DIVISION 1										
CTH H	9+10-9+65.75	CTH H	98		98	96	120	-22		
CTH H	10+34.25-10+90	CTH H	118		118	52	65	53		
DIVISION 1 SUBTOTAL			216		216	148	185	31		
DIVISION 3										
CTH H	7+75-9+10	CTH H	246		246	89	111	135		
CTH H	10+90-12+37	CTH H	213		213	76	95	118		
DIVISION 3 SUBTOTAL			459		459	165	206	253		
GRAND TOTAL			675		675	313	391	284		
TOTAL COMMON EXC			675							

NOTES:
UNITS ARE IN CUBIC YARDS
(1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
(5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
(13) EXPANDED FILL FACTOR = 1.25
DEPENDENT ON SELECTIONS:
OR
OR
OR

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH - REDUCED EBS) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED EBS) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK) * FILL FACTOR
(14) THE MASS ORDNATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL
(15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.

Addendum No. 01
ID 9371-00-70
Revised Sheet 14
January 7, 2025

PROJECT NO:	9371-00-70	HWY:	CTH H	COUNTY:	LANGUAGE	MISCELLANEOUS QUANTITIES	E	17
FILE NAME: LCLNENTS=0404W59306 WISDOT NC REGION - RHINE LAKEVIEW (2939701-00 CTH H - 5TH L7 PHARIE RIVER BRIDGE B-34-000 CTH H LANGUAGE CODE G001W700 C00D PROJECT NUMBER BASE E15F340007001W0012323666 PLOT BY: JORDAN EISENBART PLOT SCALE: 1" = 1'								

RESTORATION													
CATEGORY	STATION	TO	STATION	LOCATION	TOPSOIL		URBAN CLASS I TYPE B	FERTILIZER TYPE B		SEEDING MIXTURE NO. 20	SEED WATER MGAL	REMARKS	
					SY	CTH H		SY	CWT				LB
0010	7+75	-	10+00	CTH H	217	217	217	0.4	10	7			
0010	10+00	-	12+37	CTH H	283	283	283	0.5	13	8			
				TOTAL 0010	500	500	500	0.9	23	15			
EROSION/CONTROL													
CATEGORY	STATION	TO	STATION	LOCATION	SILT FENCE		SILT FENCE		MOBILIZATIONS		TURBIDITY BARRIERS	ROCK BAGS	REMARKS
					LF	WXH	LF	WXH	CONTROL	EMERGENCY			
0010	7+75	-	10+00	CTH H	275	275	3	3	3	71	17		EXCLUSIONARY FENCE TO REPTILES
0010	7+75	-	10+00	CTH H	40	40	-	-	-	-	-		EXCLUSIONARY FENCE TO REPTILES
0010	10+00	-	12+37	CTH H	400	400	-	-	-	89	34		EXCLUSIONARY FENCE TO REPTILES
0010	10+00	-	12+37	CTH H	40	40	-	-	-	-	-		EXCLUSIONARY FENCE TO REPTILES
				TOTAL 0010	755	755	3	3	3	160	51		
TYPE I SIGNING													
CATEGORY	STATION	SIDE	SIGN CODE	WXH	LOCATION	POSTS WOOD		SIGN TYPE II REFLECTIVE H	SIGN TYPE II REFLECTIVE F	REMOVING SIGN TYPE II	SMALL SIGN SUPPORTS	REMARKS	
						FT	4X6-INCH X 14-INCH						
0010	9+51.75	LT	W5-52L	12X36	CTH H	1	1	-	3	1	1	BRIDGE HASH MARKS	
0010	9+51.75	RT	W5-52L	12X36	CTH H	1	1	-	3	1	1	BRIDGE HASH MARKS	
0010	10+48.25	LT	W5-52L	12X36	CTH H	1	1	-	3	1	1	BRIDGE HASH MARKS	
0010	10+48.25	RT	W5-52L	12X36	CTH H	1	1	-	3	1	1	BRIDGE HASH MARKS	
0010	9+51.75	RT	I3-1	12X48	CTH H	1	1	4	-	-	-	PRAIRIE RIVER	
0010	10+48.25	LT	I3-1	12X48	CTH H	1	1	4	-	-	-	PRAIRIE RIVER	
0010	10+00	LT & RT	R12-53	24X30	BRIDGE	-	-	-	-	2	2	WEIGHT LIMIT 35 TONS	
0010	N/A	N/A	R12-55	48X18	CTH H & CTH Q	-	-	-	-	1	1	35 TON BRIDGE 1 MILES AHEAD	
0010	N/A	N/A	R12-55	48X18	PARRISH DR	-	-	-	-	1	1	35 TON BRIDGE 1/4 MILES AHEAD	
0010	N/A	N/A	R12-55	48X18	CTH H & CTH T	-	-	-	-	1	1	35 TON BRIDGE 5 1/2 MILES AHEAD	
					TOTAL 0010	5	5	8	12	10	10		



Proposal Schedule of Items

Page 1 of 5

Proposal ID: 20250114029 Project(s): 9371-00-70

Federal ID(s): WISC 2025163

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0210 Grubbing	58.000 SY	_____.	_____.
0004	203.0270 Removing Structure Over Waterway Debris Capture (structure) 01. B-34-0006	1.000 EACH	_____.	_____.
0006	204.0165 Removing Guardrail	160.000 LF	_____.	_____.
0008	205.0100 Excavation Common	675.000 CY	_____.	_____.
0010	206.1001 Excavation for Structures Bridges (structure) 01. B-34-0064	1.000 EACH	_____.	_____.
0012	210.1500 Backfill Structure Type A	490.000 TON	_____.	_____.
0014	213.0100 Finishing Roadway (project) 01. 9371- 00-70	1.000 EACH	_____.	_____.
0016	305.0110 Base Aggregate Dense 3/4-Inch	30.000 TON	_____.	_____.
0018	305.0120 Base Aggregate Dense 1 1/4-Inch	1,026.000 TON	_____.	_____.
0020	455.0605 Tack Coat	70.000 GAL	_____.	_____.
0022	465.0105 Asphaltic Surface	223.000 TON	_____.	_____.
0024	502.0100 Concrete Masonry Bridges	227.000 CY	_____.	_____.
0026	502.3200 Protective Surface Treatment	320.000 SY	_____.	_____.
0028	502.3210 Pigmented Surface Sealer	148.000 SY	_____.	_____.
0030	503.0137 Prestressed Girder Type I 36W-Inch	335.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 5

Proposal ID: 20250114029 Project(s): 9371-00-70

Federal ID(s): WISC 2025163

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	505.0400 Bar Steel Reinforcement HS Structures	5,300.000 LB	_____.	_____.
0034	505.0600 Bar Steel Reinforcement HS Coated Structures	26,070.000 LB	_____.	_____.
0036	506.2605 Bearing Pads Elastomeric Non-Laminated	10.000 EACH	_____.	_____.
0038	506.4000 Steel Diaphragms (structure) 01. B-34-0064	4.000 EACH	_____.	_____.
0040	513.4056 Railing Tubular Type H	96.000 LF	_____.	_____.
0042	516.0500 Rubberized Membrane Waterproofing	22.000 SY	_____.	_____.
0044	550.0500 Pile Points	18.000 EACH	_____.	_____.
0046	550.1100 Piling Steel HP 10-Inch X 42 Lb	360.000 LF	_____.	_____.
0048	606.0300 Riprap Heavy	310.000 CY	_____.	_____.
0050	612.0406 Pipe Underdrain Wrapped 6-Inch	240.000 LF	_____.	_____.
0052	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____.	_____.
0054	614.2300 MGS Guardrail 3	53.100 LF	_____.	_____.
0056	614.2350 MGS Guardrail Short Radius	12.500 LF	_____.	_____.
0058	614.2500 MGS Thrie Beam Transition	157.600 LF	_____.	_____.
0060	614.2610 MGS Guardrail Terminal EAT	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 5

Proposal ID: 20250114029 Project(s): 9371-00-70

Federal ID(s): WISC 2025163

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	614.2630 MGS Guardrail Short Radius Terminal	1.000 EACH	_____.	_____.
0064	616.0205 Fence Chain Link 5-FT	64.000 LF	_____.	_____.
0066	618.0100 Maintenance and Repair of Haul Roads (project) 01. 9371-00-70	1.000 EACH	_____.	_____.
0068	619.1000 Mobilization	1.000 EACH	_____.	_____.
0070	624.0100 Water	16.000 MGAL	_____.	_____.
0074	628.1504 Silt Fence	755.000 LF	_____.	_____.
0076	628.1520 Silt Fence Maintenance	755.000 LF	_____.	_____.
0078	628.1905 Mobilizations Erosion Control	3.000 EACH	_____.	_____.
0080	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0082	628.2008 Erosion Mat Urban Class I Type B	500.000 SY	_____.	_____.
0084	628.6005 Turbidity Barriers	160.000 SY	_____.	_____.
0086	628.7570 Rock Bags	51.000 EACH	_____.	_____.
0088	629.0210 Fertilizer Type B	0.900 CWT	_____.	_____.
0090	630.0120 Seeding Mixture No. 20	23.000 LB	_____.	_____.
0092	630.0500 Seed Water	15.000 MGAL	_____.	_____.
0094	634.0614 Posts Wood 4x6-Inch X 14-FT	6.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 5

Proposal ID: 20250114029 Project(s): 9371-00-70

Federal ID(s): WISC 2025163

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	637.2210 Signs Type II Reflective H	8.000 SF	_____.	_____.
0098	637.2230 Signs Type II Reflective F	12.000 SF	_____.	_____.
0100	638.2602 Removing Signs Type II	10.000 EACH	_____.	_____.
0102	638.3000 Removing Small Sign Supports	10.000 EACH	_____.	_____.
0104	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0106	643.0420 Traffic Control Barricades Type III	480.000 DAY	_____.	_____.
0108	643.0705 Traffic Control Warning Lights Type A	960.000 DAY	_____.	_____.
0110	643.0900 Traffic Control Signs	720.000 DAY	_____.	_____.
0112	643.1000 Traffic Control Signs Fixed Message	36.000 SF	_____.	_____.
0114	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0116	645.0111 Geotextile Type DF Schedule A	60.000 SY	_____.	_____.
0118	645.0120 Geotextile Type HR	530.000 SY	_____.	_____.
0120	650.4500 Construction Staking Subgrade	394.000 LF	_____.	_____.
0122	650.5000 Construction Staking Base	394.000 LF	_____.	_____.
0124	650.6501 Construction Staking Structure Layout (structure) 01. B-34-0064	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 5 of 5

Proposal ID: 20250114029 Project(s): 9371-00-70

Federal ID(s): WISC 2025163

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	650.9911 Construction Staking Supplemental Control (project) 01. 9371-00-70	1.000 EACH	_____.	_____.
0128	650.9920 Construction Staking Slope Stakes	394.000 LF	_____.	_____.
0130	690.0150 Sawing Asphalt	44.000 LF	_____.	_____.
0132	715.0502 Incentive Strength Concrete Structures	1,362.000 DOL	1.00000	1,362.00
0134	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. 10+00	1.000 EACH	_____.	_____.
0136	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0138	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0140	201.0110 Clearing	58.000 SY	_____.	_____.
0142	625.0100 Topsoil	500.000 SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

