



Wisconsin Department of Transportation

January 9, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #31: 1195-05-60, WISC 2025165
Rice Lake – Spooner
Oaklawn Rd/22nd 1/2 Ave SB
B030050
USH 053
Barron County

1196-06-60, WISC 2025166
Rice Lake – Spooner
Oaklawn Rd/22nd 1/2 Ave NB
B030051
USH 053
Barron County

Letting of January 14, 2025

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
305.0110	Base Aggregate Dense 3/4-Inch	TON	0	140	140
460.2000	Incentive Density HMA Pavement	DOL	0	660	660
643.3180	Temporary Marking Line Removable Tape 6-Inch	LF	0	18,131	18,131

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
643.3170	Temporary Marking Line Epoxy 6-Inch	LF	18,131	-18,131	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
5	Added Base Aggregate Dense 3/4-Inch shoulders to proposed typical sections.
44	Added Base Aggregate Dense 3/4-Inch to Misc. Quantities "Shoulders" table.
46	Replaced 643.3170 with 643.3180 in Misc. Quantities "Traffic Control" table.

Schedule of Items

Attached, dated January 9, 2025, are the revised Schedule of Items Pages 1 – 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 5, 44 and 46.


The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

[illegible]

PROPOSED TYPICAL SECTION US 53 NB
STA 489+04 - 500+10
STA 501+64 - 503+93

PROJECT NO:	1195-05-60, 1195-06-60	HWY:	USH 53	COUNTY:	BARRON	TYPICAL SECTIONS		
FILE NAME:	N:\9053\CD\11950505-05-60\SETUP\020300_1195-06-60.LAYOUT NAME - 02-10T							
					PLOT DATE:	4/8/2025 12:44 PM	PLOT BY:	MAK, NICHOLAS DANIE
							PLOT SCALE:	1 IN=10 FT
								SHEET 5
								WSDOT/CADDIS SHEET 47

Addendum No. 01
ID 1195-05-60 &
ID 1195-06-60
Revised Sheet 44
January 9, 2025

SHOULDERS

CATEGORY	STATION	TO	STATION	LOCATION	SY	REMOVING ASPHALTIC SURFACE MILLING	PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS	MT 58-34 S	HMA PAVEMENT 4	TON	LF	SAWING ASPHALT	REMARKS
PROJECT 1195-05-60 SOUTHBOUND													
0010	497+18	-	499+82	LT	234			3	52	264	8		INSTALL RUMBLE STRIPS AFTER TRAFFIC IS NO LONGER ON SHOULDER
0010	498+58	-	499+85	RT	86			2	19	127	4		SAW AT STA. 497+18
0010	501+33	-	514+79	LT	1,196			14	268	1,346	8		SAW AT STA. 498+58
0010	501+27	-	512+93	RT	776			12	174	1,166	4		SAW AT STA. 514+79
TOTAL 0010										513	2,903	24	SAW AT STA. 512+93
PROJECT 1195-06-60 NORTHBOUND													
0010	488+59	-	500+09	LT	761			11	170	1,150	4		INSTALL RUMBLE STRIPS AFTER TRAFFIC IS NO LONGER ON SHOULDER
0010	486+69	-	500+13	RT	1,195			15	268	1,344	8		SAW AT STA. 488+59
0010	501+61	-	502+88	LT	81			2	18	127	4		SAW AT STA. 486+69
0010	501+56	-	504+28	RT	241			4	54	272	8		SAW AT STA. 502+88
TOTAL 0010										510	2,893	24	SAW AT STA. 504+28
PROJECTS 1195-05-60 & 1195-06-60										1,023	5,796	48	

3

305.0110
3/4 INCH
TON

1195-05-60 SOUTHBOUND
497+18 - 499+82 LT 6
498+58 - 499+85 RT 3
501+33 - 514+79 LT 31
501+27 - 512+93 RT 27
UNDISTRIBUTED 3
TOTAL 0010 70

305.0110
3/4 INCH
TON

1195-06-60 NORTHBOUND
488+59 - 500+09 LT 26
486+69 - 500+13 RT 31
501+61 - 502+88 LT 3
501+56 - 504+28 RT 6
UNDISTRIBUTED 4
TOTAL 0010 70

PROJECTS 1195-05-60 & 1195-06-60 140

CONCRETE BARRIER

CATEGORY	STATION	TO	STATION	LOCATION	LF	CONCRETE BARRIER DELIVERED	CONCRETE BARRIER TEMPORARY PRECAST	CONCRETE BARRIER TEMPORARY PRECAST INSTALLED	ANCHORING CONCRETE BARRIER TEMPORARY PRECAST ON BRIDGE DECKS	LF
PROJECT 1195-05-60										
0010	499+63	-	504+34	USH 53 SB STAGE 2	475			475		125
0010	499+63	-	503+88	USH 53 SB STAGE 3				438		125
PROJECT 1195-05-60					475			913		250
PROJECT 1195-06-60										
0010	497+14	-	501+83	USH 53 NB STAGE 2	475			475		125
0010	497+64	-	501+83	USH 53 NB STAGE 3				438		125
PROJECT 1195-06-60					475			913		250
PROJECTS 1195-05-60 & 1195-06-60					950			1,826		500

GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	LF	REMOVING GUARDRAIL	GUARDRAIL POSTS AND BLOCKS EACH	REPLACING GUARDRAIL (SALVAGE AND REINSTALL GUARDRAIL)	SPV.0090 SPECIAL
PROJECT 1195-05-60									
0010	501+25	-	501+25	MEDIAN	98				
0010	501+23	-	501+57	USH 53 SB RT					
0010	501+28	-	501+62	USH 53 SB LT					
PROJECT 1195-05-60					98				
PROJECT 1195-06-60									
0010	499+88	-	500+22	USH 53 NB LT					
0010	499+83	-	500+17	USH 53 NB RT					
0010	500+25	-	500+25	MEDIAN	98				
PROJECT 1195-06-60					98				
PROJECTS 1195-05-60 & 1195-06-60					196				

STEEL PLATE BEAMGUARD
STEEL THRIE BEAM
STEEL THRIE BEAM

STEEL THRIE BEAM
STEEL THRIE BEAM
STEEL PLATE BEAMGUARD

PROJECT NO: 1195-05-60, 1195-06-60

HWY: USH 53

COUNTY: BARRON

MISCELLANEOUS QUANTITIES

SHEET: 44

FILE NAME : N:\PDS\11_030200_mq.pdk
PLOT DATE : November 11, 2024
PLOT BY : MAKI, NICHOLAS DANIEL
PLOT SCALE : 1:1

3

CATEGORY	STATION	LOCATION	STAGE DURATION CALENDAR DAYS	643.0300	643.0420	643.0705	643.0715	643.0800	643.0900	643.1050	643.3180 643.3170	643.5000	646.9000	REMARKS
				TRAFFIC CONTROL BARRICADES TYPE III	TRAFFIC CONTROL WARNING LIGHTS TYPE A	TRAFFIC CONTROL WARNING LIGHTS TYPE B	TRAFFIC CONTROL WARNING LIGHTS TYPE C	TRAFFIC CONTROL ARROW BOARDS	TRAFFIC CONTROL SIGNS	TRAFFIC CONTROL SIGNS	TEMPORARY MARKING LINE SPOTTING LINE	TRAFFIC CONTROL SIGNS	MARKING REMOVAL LINE 4 INCH	

FILE NAME : N:\PDS...\030200_mg.pptx
PLOT DATE : November 11, 2024
PLOT BY : MAKI, NICHOLAS DANIEL
PLOT SCALE : 1:1



Proposal Schedule of Items

Page 1 of 5

Proposal ID: 20250114031 Project(s): 1195-05-60, 1195-06-60

Federal ID(s): WISC 2025165, WISC 2025166

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0330 Debris Containment (structure) 01. B-03-0050	1.000 EACH	_____.	_____.
0004	203.0330 Debris Containment (structure) 02. B-03-0051	1.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	84.000 SY	_____.	_____.
0008	204.0120 Removing Asphaltic Surface Milling	4,570.000 SY	_____.	_____.
0010	204.0165 Removing Guardrail	196.000 LF	_____.	_____.
0012	211.0400 Prepare Foundation for Asphaltic Shoulders	63.000 STA	_____.	_____.
0014	213.0100 Finishing Roadway (project) 01. 1195-05-60	1.000 EACH	_____.	_____.
0016	213.0100 Finishing Roadway (project) 02. 1195-06-60	1.000 EACH	_____.	_____.
0018	305.0120 Base Aggregate Dense 1 1/4-Inch	30.000 TON	_____.	_____.
0020	415.0060 Concrete Pavement 6-Inch	84.000 SY	_____.	_____.
0022	415.0410 Concrete Pavement Approach Slab	194.000 SY	_____.	_____.
0024	416.0610 Drilled Tie Bars	53.000 EACH	_____.	_____.
0026	460.6244 HMA Pavement 4 MT 58-34 S	1,023.000 TON	_____.	_____.
0028	465.0510 Asphaltic Rumble Strips, Shoulder Divided Roadway	5,796.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 5

Proposal ID: 20250114031 Project(s): 1195-05-60, 1195-06-60

Federal ID(s): WISC 2025165, WISC 2025166

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	502.3200 Protective Surface Treatment	1,080.000 SY	_____.	_____.
0032	502.3205 Pigmented Surface Sealer Reseal	244.000 SY	_____.	_____.
0034	509.0301 Preparation Decks Type 1	80.000 SY	_____.	_____.
0036	509.0302 Preparation Decks Type 2	40.000 SY	_____.	_____.
0038	509.0505.S Cleaning Decks to Reapply Concrete Masonry Overlay	1,080.000 SY	_____.	_____.
0040	509.1500 Concrete Surface Repair	100.000 SF	_____.	_____.
0042	509.2000 Full-Depth Deck Repair	4.000 SY	_____.	_____.
0044	509.2500 Concrete Masonry Overlay Decks	60.000 CY	_____.	_____.
0046	509.9005.S Removing Concrete Masonry Deck Overlay (structure) 01. B-03-0050	540.000 SY	_____.	_____.
0048	509.9005.S Removing Concrete Masonry Deck Overlay (structure) 02. B-03-0051	540.000 SY	_____.	_____.
0050	603.8000 Concrete Barrier Temporary Precast Delivered	950.000 LF	_____.	_____.
0052	603.8125 Concrete Barrier Temporary Precast Installed	1,826.000 LF	_____.	_____.
0054	603.8505 Anchoring Concrete Barrier Temporary Precast on Bridge Decks	500.000 LF	_____.	_____.
0056	611.0430 Reconstructing Inlets	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 5

Proposal ID: 20250114031 Project(s): 1195-05-60, 1195-06-60

Federal ID(s): WISC 2025165, WISC 2025166

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0058	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____.	_____.
0060	614.0950 Replacing Guardrail Posts and Blocks	72.000 EACH	_____.	_____.
0062	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1195-05-60	1.000 EACH	_____.	_____.
0064	618.0100 Maintenance and Repair of Haul Roads (project) 02. 1195-06-60	1.000 EACH	_____.	_____.
0066	619.1000 Mobilization	1.000 EACH	_____.	_____.
0068	628.1504 Silt Fence	446.000 LF	_____.	_____.
0070	628.1520 Silt Fence Maintenance	446.000 LF	_____.	_____.
0072	628.1905 Mobilizations Erosion Control	2.000 EACH	_____.	_____.
0074	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0076	628.7015 Inlet Protection Type C	2.000 EACH	_____.	_____.
0078	628.7570 Rock Bags	6.000 EACH	_____.	_____.
0080	638.2102 Moving Signs Type II	4.000 EACH	_____.	_____.
0082	638.4000 Moving Small Sign Supports	4.000 EACH	_____.	_____.
0084	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0086	643.0300 Traffic Control Drums	10,430.000 DAY	_____.	_____.



Proposal Schedule of Items

Page 4 of 5

Proposal ID: 20250114031 Project(s): 1195-05-60, 1195-06-60

Federal ID(s): WISC 2025165, WISC 2025166

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	643.0420 Traffic Control Barricades Type III	210.000 DAY	_____.	_____.
0090	643.0705 Traffic Control Warning Lights Type A	420.000 DAY	_____.	_____.
0092	643.0715 Traffic Control Warning Lights Type C	6,270.000 DAY	_____.	_____.
0094	643.0800 Traffic Control Arrow Boards	210.000 DAY	_____.	_____.
0096	643.0900 Traffic Control Signs	3,750.000 DAY	_____.	_____.
0098	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.
0102	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0104	646.2025 Marking Line Grooved Black Epoxy 6-Inch	1,550.000 LF	_____.	_____.
0106	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	13,950.000 LF	_____.	_____.
0108	646.9000 Marking Removal Line 4-Inch	7,183.000 LF	_____.	_____.
0110	650.5000 Construction Staking Base	135.000 LF	_____.	_____.
0112	650.6501 Construction Staking Structure Layout (structure) 01. B-03-0050	1.000 EACH	_____.	_____.
0114	650.6501 Construction Staking Structure Layout (structure) 02. B-03-0051	1.000 EACH	_____.	_____.
0116	650.8000 Construction Staking Resurfacing Reference	3,520.000 LF	_____.	_____.



Proposal Schedule of Items

Page 5 of 5

Proposal ID: 20250114031 Project(s): 1195-05-60, 1195-06-60

Federal ID(s): WISC 2025165, WISC 2025166

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0118	650.9911 Construction Staking Supplemental Control (project) 01. 1195-05-60	1.000 EACH	_____.	_____.
0120	650.9911 Construction Staking Supplemental Control (project) 02. 1195-06-60	1.000 EACH	_____.	_____.
0122	690.0150 Sawing Asphalt	48.000 LF	_____.	_____.
0124	690.0250 Sawing Concrete	106.000 LF	_____.	_____.
0126	715.0720 Incentive Compressive Strength Concrete Pavement	1,000.000 DOL	1.00000	1,000.00
0128	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0130	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0132	SPV.0090 Special 01. Salvage and Reinstall Guardrail	84.000 LF	_____.	_____.
0134	305.0110 Base Aggregate Dense 3/4-Inch	140.000 TON	_____.	_____.
0136	460.2000 Incentive Density HMA Pavement	660.000 DOL	1.00000	660.00
0138	643.3180 Temporary Marking Line Removable Tape 6-Inch	18,131.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.