



Wisconsin Department of Transportation

January 30, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #26: 1130-65-76, WISC 2025323
Appleton – De Pere
Ballard Rd (CTH E) Intchg
IH 41
Outagamie County

Letting of February 11, 2025

This is Addendum No 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
2.1	Prosecution and Progress
5.1	Utilities
10.2	Notice to Contractors, Geotechnical Exploration Information

Added Special Provisions	
Article No.	Description
12.10	Inlet Marker, Item SPV.0060.2000
18.10	Decorative Silhouette Item SPV.0060.3000

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
460.5224	HMA Pavement 4 LT 58-28 S	TON	1061	83	1144
614.2610	MGS Guardrail Terminal EAT	EACH	1	2	3
531.2036	Drilling Shaft 36-Inch	LF	10	26	36

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0060.2000	Inlet Marker	EACH	0	7	7
SPV.0060.3000	Decorative Silhouette	EACH	0	2	2

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
460.5223	HMA Pavement 3 LT 58-28 S	TON	83	-83	0
531.2030	Drilling Shaft 30-Inch	LF	26	-26	0
614.1200	MGS Guardrail Temporary Terminal EAT	EACH	2	-2	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
3	General notes – Revised HMA type
52	Plan Detail Legend – removed temporary EAT
63	Plan Detail – Revised callout of EAT
68	Plan Detail – Revised callout of EAT
435	MQ Sheet – Revised HMA quantity
440	MQ Sheet – Revised EAT quantity

Added Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
39A	Inlet Marker Detail
197A-197C	Lighting Details
444A	MQ Sheet – Decorative Silhouette
449A	MQ Sheet – Inlet Marker
518A	Standard Sign
894A	Silhouette Detail

Deleted Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was deleted)
31	Referenced structure not part of 1130-65-76 contract

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1130-65-76

January 30, 2025

Special Provisions

2.1 Prosecution and Progress.

Insert the paragraph below after paragraph four:

Prior to the utility facilities being discontinued on the structure, the contractor may partially remove structure B-44-172. Submit removal plans, for approval by engineer, to ensure protection of the utility facilities during construction operations.

*Replace the second sentence under the heading **Interim Completion and Liquidated Damages – SB IH 41 Entrance Ramp from CTH E, NB IH 41 Exit Ramp to CTH E and NB IH 41 Entrance Ramp from CTH E: 90 Calendar Days** with the sentence below:*

Complete the work necessary to reopen all three ramps to traffic within 90 calendar days after closure.

*Replace the first sentence under the heading **Interim Completion and Liquidated Damages – Capitol Drive: Fifty Calendar Days** with the sentence below:*

If the contractor fails to complete the work necessary to reopen Capitol Drive to traffic in fifty calendar days, the department will assess the contractor \$2,185 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM 50 calendar days after closure.

5.1 Utilities.

*Replace the tenth paragraph under **AT&T Wisconsin (COMLN)** with the following::*

From Station 606'ESB'+28 to Station 620'ESB'+40 left AT&T Wisconsin has underground communication lines and facilities attached to Structure B-44-172(west side). Prior to and during construction AT&T Wisconsin will discontinue in place all communication lines and install new underground communication lines jointly with We Energies crossing IH-41. It is anticipated the facilities attached to Structure B-44-172 will be discontinued during construction.

*Replace paragraph six under section titled **Spectrum (COMLN)** with the following:*

Spectrum anticipates starting work described above, prior to construction, 15 days after notification from We Energies of completion of their electric relocation work. Spectrum anticipates 70 working days to complete their work, which will be during construction.

*Insert the following prior to the last paragraph under section titled **We Energies (ELCTY)**:*

We Energies anticipates starting work described above 02/02/2025 and will require 40 working days to complete.

10.2 Notice to Contractor, Geotechnical Exploration Information.

Revise second bullet to:

- Geotechnical Site Investigation Report: R-44-40 & 41

Delete third and fourth bullets:

- Geotechnical Site Investigation Report: OSS Non-Standard Foundations, August 1, 2024.
- Geotechnical Site Investigation Report: OSS Standard Foundations, August 1, 2024.

12.10 Inlet Marker, Item SPV.0060.2000.

A Description

This special provision describes furnishing and installing a Type II W5-53S sign to mark inlet locations adjacent to barrier wall or parapets as shown in the plans, in accordance with standard spec 637, and as hereinafter provided.

Refer to WisDOT Sign Plate Manual for details of W5-53S (Low Inlet Marker).

B Materials

Furnish sheet aluminum conforming to standard spec 637.2.1.3.

Furnish reflective sheeting conforming to standard spec 637.2.2.2.

Furnish stainless steel anchors and washers conforming to standard spec 513.2.1.

C Construction

Manufacture, assemble and install inlet marker in accordance with 637.3 of the standard spec.

Install inlet marker against a clean and flat surface.

D Measurement

The department will measure Inlet Marker as each individual marker acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.2000	Inlet Marker	EACH

Payment is full compensation for providing sign including mounting hardware; and for installing barrier wall inlet marker.

ner41-633 (20241104)

18.10 Decorative Silhouette Item SPV.0060.3000.

A Description

Fabricate, galvanize, paint, deliver, and install decorative silhouette on bridge tubular steel railing screening.

B Materials

B.1 General

All materials shall meet the requirements shown on the plans and applicable provisions of the standard specifications as follows:

- Plate, Bracket, Mounting Hardware: Standard spec 506
- Welding Materials: AWS D 1.5 Bridge Welding Code
- Painting: Standard spec 517.2

Steel preparation includes the chamfering of sharp edges. Flatten all sharp edges by a single pass of a grinder or suitable device along the sharp edge. Condition any thermal cut edges before blast cleaning by shallow grinding or other cleaning to remove any hardened surface layer. Remove all evident steel defects exposed in accordance to AASHTO M 160 prior to blast cleaning.

Complete all welded connections and drill holes to the decorative silhouette as part of the manufacturing process.

Fabricate the decorative silhouette plates as shown in the plans and patterns. Electro-galvanize the decorative silhouette plates in accordance with ASTM A 591-01 (0.08 oz/square foot/surface) and then paint with an approved tie and topcoat. The topcoat shall be AMS color number 27038, Tricorn Black to match the color of the tubular steel railing screening. Electronic files of the decorative silhouette patterns are available from the Wisconsin Department of Transportation, Bryan Learst, 920-366-5639, bryan.learst@dot.wi.gov.

B.2 Painting

Shop coat all steel galvanized surfaces with a department approved paint system. Clean galvanizing surfaces to be painted according to SSP-SP1 to remove chlorides, sulfates, zinc salts, oil, dirt, organic matter and other contaminants. Brush-off blast clean the surface per SSPC-SP7 to create a slight angular surface profile (1.0-1.5 mils suggested) for adhesion. Do not fracture the galvanized finish to remove any dry film thickness during these processes.

After cleaning provide a tie coat from an approved coating system that is specifically intended to be used on a galvanized surface. The tie coat shall etch the galvanized rail and prepare the surface for the topcoat. Apply a topcoat matching AMS color number 27038, Tricorn Black. The tie and topcoats should be of contrasting colors. Use a pre-approved topcoat that is resistant to the effects of the sun and is suitable for use in a marine environment. Paint the decorative silhouette with the tie and topcoats before final installation. Exercise care so as not to damage the painted surface of the decorative silhouette or tubular steel railing screening.

Paint all plates, brackets, bolts, nuts, and washers prior to installation. Repair all paint surfaces damaged during installation.

C Construction

Follow procedures in Standard spec 506.3.

Follow procedures in Standard spec 517.3 for painting requirements.

Follow procedures in Standard spec 506.3.19 for welding requirements.

Provide shop drawings in accordance to the requirements of section 506.3.2 of the standard spec. Shop drawings shall contain material sizes and types, weld sizes and locations, and all necessary details, dimensions, and information to allow fabrication of the decorative silhouette in conformance with the requirements of the contract. Do not begin fabrication prior to shop drawing review and acceptance.

Notify the engineer two days prior to the delivery of the decorative silhouette. The engineer shall inspect the silhouette for damage, defects, or non-conformities. Materials that arrive to the site damaged or in unsatisfactory condition will be rejected.

After the product is unloaded, the installation contractor will signify in writing that the decorative silhouette was received in acceptable condition per the engineer's inspection. Any damage to the decorative silhouette after being accepted by the engineer will be the responsibility of the contractor. No field welding, field cutting, or drilling will be permitted without the approval of the engineer.

Take special care while handling and during construction to minimize the number and size of touch-up spots. Follow the manufacturer's recommendations for damaged area repairs. The engineer must approve the field paint appearance prior to final acceptance.

Locate and field drill holes as required through the tubular steel railing screening. Repair damaged paint and galvanized surfaces in the tubular steel railing prior to installation of the decorative silhouette. Follow procedures in Standard spec 513.3.3 (10) to repair railing galvanizing and paint systems damaged by silhouette installation.

Provide the engineer with the name, address, and phone number of a representative of the decorative silhouette for future coordination.

D Measurement

The department will measure Decorative Silhouette as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.3000	Decorative Silhouette	EACH

Payment is full compensation for supplying shop drawings, furnishing and installation.

ner41-506 (01242025)

Schedule of Items

Attached, dated January 30, 2025, are the revised Schedule of Items Pages 1 – 29.

Plan Sheets


The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 3, 52, 63, 68, 435, 440, 924, and 925.

Added: 39A, 197A – 197C, 444A, 449A, 518A, and 894A. Deleted 31.

END OF ADDENDUM

Addendum No. 01
ID 1130-65-76
Deleted Sheet 31
January 30, 2025





LEGEND

- WALL EXCAVATION - SEE WALL PLANS
- MSE BACKFILL - SEE WALL PLANS
- ROADWAY EMBANKMENT - ROADWAY ITEM
- EXCAVATION COMMON - ROADWAY ITEM

NOTES:
1. REFER TO WALL PLANS AND ROADWAY CROSS SECTIONS FOR ADDITIONAL DETAILS NOT SHOWN HERE.
2. R-44-56 REQUIRES ADDITIONAL BID ITEMS FOR CONSTRUCTION. REFER TO WALL PLANS AND DETAILS FOR ADDITIONAL INFORMATION.

PROJECT NO: 1130-65-76	HWY: IH 41	COUNTY: OUTAGAMIE	CONSTRUCTION DETAILS	SHEET 31	E
FILE NAME: C:\USERS\OSCHARLA\DC\ACDDCS\WISDOT\11306570\11306576\11306576\021001-CD.DWG	LAYOUT NAME: 09	PLOT BY: SCHARLAU, DAVE	PLOT NAME:	PLOT SCALE: 1:30	WISDOT/CADD SHEET 42
PLOT DATE: 10/20/2024 9:12 PM					



DETAIL A - MARKER MOUNTING

Addendum No. 01
ID 1130-65-76
Added Sheet 39A
January 30, 2025

INLET MARKER
NOT TO SCALE

- NOTES:
- 1. STANDARD SIGN W5-53S, SIZE 2M (SIGN PLATE W5-53S, LOW INLET MARKER)
 - 2. 3/8" X 1" STAINLESS STEEL ANCHOR WITH NYLON AND STAINLESS STEEL WASHERS.
 - 3. ANCHORS SHALL HAVE HEXAGONAL HEADS.
 - 4. SEE SIGN PLATE A4-8 FOR ADDITIONAL INFORMATION REGARDING WASHERS.

LEGEND

- AG01

BASE AGGREGATE DENSE 3/4-INCH
- AP02

HMA PAVEMENT 2-INCH
- AP3.5

HMA PAVEMENT 3 1/2-INCH
- AP04

HMA PAVEMENT 4-INCH
- AP84

5-INCH ASPHALTIC SURFACE
- BC09

STEEL THREE BEAM BULLNOSE TERMINAL
- BG10

STEEL THREE BEAM
- BG21

GUARDRAIL MOW STRIP EMULSIFIED ASPHALT
- BG28

CRASH CUSHIONS TEMPORARY
- BG37

MGS GUARDRAIL TEMPORARY TERMINAL EAT
- BG37

MGS GUARDRAIL 3
- BG39

MGS THREE BEAM TRANSITION
- BG40

MGS GUARDRAIL TERMINAL EAT
- CB42

CONCRETE BARRIER TYPE S42 SPECIAL
- CG12

CONCRETE CURB & GUTTER 18-INCH TYPE A
- CG14

CONCRETE CURB & GUTTER 30-INCH TYPE A
- CG20

CONCRETE CURB & GUTTER INTEGRAL 30-INCH TYPE D

CG42

CONCRETE CURB PEDESTRIAN

CG43

CURB RAMP DETECTABLE WARNING FIELD YELLOW

CG46

CURB RAMP DETECTABLE WARNING FIELD RADIAL YELLOW

CG50

CONCRETE CURB & GUTTER 24-INCH TYPE D

CM02

COLORING CONCRETE (SEAPLANE GRAY)

CM04

CONCRETE SIDEWALK 4-INCH

CM06

CONCRETE SIDEWALK 6-INCH

CM12

CONCRETE MEDIAN SLOPED NOSE

CP09

CONCRETE PAVEMENT 9-INCH

CP19

CONCRETE PAVEMENT HES 9-INCH

DR06

CONCRETE DRIVEWAY 6-INCH

DR09

CONCRETE DRIVEWAY 9-INCH

DR20

ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES

PD01

CONCRETE PAVEMENT APPROACH SLAB

PD05

ASPHALTIC FLUME


PD06

CONCRETE SURFACE DRAIN

NOTES: * DENOTES LOCATION OF DEPRESSED CURB HEAD
** DENOTES LOCATION OF REVERSE GUTTER SLOPE

Addendum No. 01
ID 1130-65-76
Revised Sheet 52
January 30, 2025

PROJECT NO: 1130-65-76	HWY: IH 41	COUNTY: OUTAGAMIE	PLAN DETAILS	SHEET 52	E
FILE NAME: C:\USERS\ZONGLO\DCAC\DCOS\WISDOT\11306301\PROJECT FILES\DSGN\11306576\11306576-021201-PD.DWG	1/27/2025 1:28 PM	PLOT DATE:	PLOT BY: BROZOVICH, SARA	PLOT NAME:	PLOT SCALE: 1 IN=40 FT
LAYOUT NAME: -00					WISDOT/CAD05 SHEET 42




Addendum No. 01
ID 1130-65-76
Revised Sheet 63
January 30, 2025

PROJECT NO: 1130-65-76	HWY: IH 41	COUNTY: OUTAGAMIE	PLAN DETAILS	SHEET 63	E
FILE NAME: C:\USERS\ZONGLO\ODAC\DCS\WISDOT\11306301\PROJECT FILES\DSGN\11306576\11306576-021201-PD.DWG	1/27/2025 1:23 PM	PLOT BY: BROZOVICH, SARA	PLOT NAME: 1 IN=40 FT		
LAYOUT NAME: 03-44-02					

WISDOT/CAD05 SHEET 42

Addendum No. 01
ID 1130-65-76
Revised Sheet 68
January 30, 2025



PROJECT NO: 1130-65-76	HWY: IH 41	COUNTY: OUTAGAMIE	PLAN DETAILS	SHEET 68	E
FILE NAME: C:\USERS\ZONG\ODDCAC\DCS\WISDOT\11306576\PROJECT FILES\DSGN\11306576\9SHEETS\11306576-021201-PD.DWG	LAYOUT NAME: 05-ED-01	PLOT DATE: 1/27/2025 1:27 PM	PLOT BY: BROZOVICH, SARA	PLOT SCALE: 1 IN=40 FT	WISDOT/CAD05 SHEET 42

GENERAL NOTES (APPLIES TO THIS CONSTRUCTION DETAIL)


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

ALL INTERNAL ELECTRICAL COMPONENTS WILL BE PRE-WIRED BY THE CABINET FABRICATOR.


ALL CONDUIT ENTRIES SHALL BE SEALED WITH AN APPROPRIATE DUCT SEALING COMPOUND.

ORIENT PHOTOCELL AWAY FROM AMBIENT LIGHT SOURCES AND ONCOMING TRAFFIC HEADLIGHTS.


A COMPLETE LIGHTING OR ELECTRICAL PLAN SHALL BE SECURELY PLACED IN THE DOCUMENT HOLDER ATTACHED TO THE DOOR.



SIDE VIEW



UTILITY METER PEDESTAL 200 AMP PROVIDED BY CONTRACTOR UNDER SEPARATE BID ITEM. MAY, OR MAY NOT BE ATTACHED TO OUTSIDE OF CONTROL CABINET PER PROJECT REQUIREMENTS



Addendum No. 01
ID 1130-65-76
Added Sheet 197A
January 30, 2025

LIGHTING CONTROL CABINET - SCHEMATICS
CB600 659.2230

PROJECT NO: 1130-65-76

HWY: IH 41

COUNTY: OUTAGAMIE

LIGHTING PLANS - CONTROL CABINET SCHEMATICS

SHEET 197A

E

FILE NAME: G:\WIDOTR\USH 41 CORRIDOR LIGHTING\CVL 3D\SHEET\PLAN\CONSTRUCTION DETAILS\1130-65-76 IN BALLARD RD (CTH E) INTERCHANGE\CONTROL CABINET SCHEMATICS - N BALLARD RD (CTH E) INTERCHANGE\CB600.DWG

LAYOUT NAME: CONTROL CABINET

PLOT BY: SARAH ADAMS

PLOT NAME:

PLOT SCALE: XXXXX

WISDOT/CADDS SHEET 42



A COMPLETE LIGHTING OR ELECTRICAL PLAN SHALL BE SECURELY PLACED IN THE DOCUMENT HOLDER ATTACHED TO THE DOOR.



SHEET 3 OF 13

NOTE:

ANCHOR BOLTS/NUTS NOT INCLUDED
WITH COVER SHROUD ITEM.



Addendum No. 01
ID 1130-65-76
Added Sheet 197C
January 30, 2025

ANCHOR BOLT COVER SHROUD
NO SCALE
SPV.0600.0500

ANCHOR BOLT DETAIL

SHEET 4 OF 13

PROJECT NO: 1130-65-76

HWY: IH 41

COUNTY: OUTGAMIE

LIGHTING PLANS - ANCHOR BOLT COVER SHROUD

SHEET

197C

E

FILE NAME: G:\WOODNEUSH-41 CORRIDOR LIGHTING\CIVIL 3D\SHEETS\PLAN\CONSTRUCTION DETAILS\1130-65-76_N BALLARD RD (CTH E) INTERCHANGE\021003_CD_SHROUD - CTH E.DWG

LAYOUT NAME - SHEET - (1)

PLOT DATE: 10/9/2024 1:06 PM

PLOT BY: ISAMAH ADAMS

PLOT NAME:

PLOT SCALE: XXXXXX

WISDOT/CADDS SHEET 42

Addendum No. 01
ID 1130-65-76
Revised Sheet 435
January 30, 2025

CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	GAL	COAT	455.0605 TACK	460.3224 HMA PAVEMENT 4 LT 58-28 S	465.0105 ASPHALTIC SURFACE*	TON	SY
1000										TON			
STAGE 1													
STAGE 1 SUBTOTAL													
STAGE 2													
NB	851+57	-	856+06	25	RT		25			--	140	--	--
SB	852+10	-	856+34	27	LT		24			--	132	--	--
ENB	600+29	-	600+56	VARIES	L7/RT		4			--	22	--	--
ESB	600+68	-	604+29	VARIES	RT		22			--	125	--	--
ESB	603+36	-	603+70	VARIES	LT		2			--	13	--	--
ESB	603+94	-	604+28	52	LT		--			--	--	--	4
EA	856+26	-	863+50	VARIES	LT		--			46	--	--	--
EA	857+26	-	862+44	24	RT		--			65	--	--	--
EB	851+13	-	851+45	29	RT		--			4	--	--	--
EC	843+00	-	851+79	VARIES	LT		--			96	--	--	--
EC	850+38	-	851+79	0	RT		--			8	--	--	--
EC	843+00	-	850+38	0	RT		--			48	--	--	--
ED	295+83	-	298+37	40	LT		--			29	--	--	--
EAT	863+50	-	869+00	VARIES	L7/RT		144			--	804	--	--
EBT	840+00	-	845+87	VARIES	L7/RT		123			--	690	--	--
ECT	829+63	-	843+00	VARIES	L7/RT		186			--	1,043	--	--
EDT	301+50	-	307+95	VARIES	L7/RT		121			--	678	--	--
STAGE 2 SUBTOTAL													
STAGE 3													
ESB	603+51	-	603+59	45	LT		--			--	--	--	1
STAGE 3 SUBTOTAL													
CATEGORY 1000 TOTAL													
											1,144	3,647	5

ASPHALT PAVEMENT ITEMS

1600							485.0120
CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	485.0105 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES
							TON TON
STAGE 3							
	CAP	17+49	-	18+58	18	RT	--
	CAP	18+74	-	19+15	46	RT	2
STAGE 3 SUBTOTAL							2
							2
CATEGORY 1600 TOTAL							2

*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

CONCRETE BARRIER

CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	1000	
							S42 SPECIAL	LF
STAGE 2								
	ENB	611+32	-	611+98	20	RT	62	
	ENB	611+68	-	611+98	28	LT	40	
	ENB	614+18	-	614+28	20	RT	9	
	ESB	614+18	-	614+96	22	LT	74	
	EA	862+44	-	863+50	23	RT	105	
	EB	845+87	-	851+13	VARIES	RT	522	
	EB	845+87	-	851+44	VARIES	LT	562	
	EB	851+44	-	853+80	30	LT	199	
	ED	295+74	-	301+50	VARIES	RT	568	
	ED	294+00	-	295+83	18	RT	202	
	ED	298+37	-	301+50	VARIES	LT	310	
STAGE 2 SUBTOTAL							2,655	
CATEGORY 1000 TOTAL							2,655	

FENCING

CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	616.07006 FENCE CHAIN LINK 6-FT SAFETY		
							LF	LF	LF
1000									
STAGE 1									
	ENB	612+12	-	612+15	VARIES	RT	20	--	--
	ESB	614+00	-	614+01	VARIES	RT	20	--	--
STAGE 1 SUBTOTAL							40		
STAGE 2									
	NB	839+96	-	840+49	VARIES	RT	95	--	--
	NB	888+99	-	871+04	VARIES	RT	242	--	--
	ENB	605+67	-	608+44	VARIES	RT	328	--	--
	ENB	617+64	-	619+63	VARIES	RT	230	--	--
	ESB	618+62	-	620+94	VARIES	LT	239	--	--
	EA	855+94	-	868+99	VARIES	LT	1,331	--	--
	EB	840+49	-	850+83	VARIES	RT	1,009	--	--
	EC	840+17	-	848+88	VARIES	LT	869	--	--
	ED	298+47	-	309+95	VARIES	LT	1,188	--	--
	EBB	610+61	-	612+58	VARIES	LT	350	--	--
	ECC	612+23	-	618+56	VARIES	LT	500	--	--
	EDD	612+00	-	616+93	VARIES	RT	425	--	--
STAGE 2 SUBTOTAL							6,807		
CATEGORY 1000 SUBTOTAL							6,847	--	--
UNDISTRIBUTED							--	1,000	
CATEGORY 1000 TOTAL							6,847	1,000	

BEAM GUARD

CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	EACH	614.0220	614.0230	614.0397	614.2300	614.2500	614.2610
1000	NB	849+36	-	856+03	36	RT	1	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		852+57	-	853+10	VARIES	LT	1	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		853+10	-	854+98	22	LT	187.5	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		854+98	-	855+51	VARIES	LT	1	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		851+98	-	856+65	38	LT	1	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		853+10	-	854+98	22	RT	187.5	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		861+39	-	862+46	24	RT	375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
		CATEGORY 1000 TOTAL					2	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							2	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH
							375	STEEL THRIE BEAM BULLNOSE TERMINAL	GUARDRAIL	MOW STRIP EMULSIFIED ASPHALT	MGS GUARDRAIL 3	MGS THRIE BEAM TRANSITION	MGS GUARDRAIL TERMINAL EAT EACH

Addendum No. 01
ID 1130-65-76
Revised Sheet 440
January 30, 2025

FILE NAME: C:\USERS\WU\THOMAS\PROJECT FILES\11306576\11306576\11306576-030201-IMG-RDWAY.DWG

LAYOUT NAME: 15

1/28/2025 10:28 AM

PLOT DATE: 1/28/2025 10:28 AM

PLOT BY: MUTH, CAMERON

PLOT NAME: 1"=1'

WISDOT/CAD05 SHEET 42

DECORATIVE SILHOUETTES

SPV.0060.3000
DECORATIVE
SILHOUETTE

CATEGORY	LOCATION	STRUCTURE	EACH
1000	CTH E N8	B-44-0325	1
	CTH E S8	B-44-0324	1
PROJECT 1130-65-76 TOTALS			2


Addendum No. 01
ID 1130-65-76
Added Sheet 444A
January 30, 2025

Addendum No. 01
ID 1130-65-76
Added Sheet 449A
January 30, 2025

INLET MARKERS				SPV.0060.2000
CATEGORY	LOCATION	STRUCTURE	INLET MARKER	EACH
1000	CTH E NB	928		1
	CTH E NB	929		1
	RAMP EB	897		1
	RAMP EB	983		1
	RAMP EB	985		1
	RAMP ED	987		1
PROJECT 1130-65-76 TOTALS				7

NOTES

1. Sign is Type II -Type H Reflective
2. Color:
Background - Green
3. Base material shall be .040" aluminum.
Corners shall be rounded.




Addendum No. 01
ID 1130-65-76
Added Sheet 518A
January 30, 2025


SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	4	12	1 1/2																								.33
2M	4	12	1 1/2																								.33
3																											
4																											
5																											

STANDARD SIGN
W5 - 53S
WISCONSIN DEPT OF TRANSPORTATION
APPROVED
<i>Matthew L. Rauch</i> For State Traffic Engineer
DATE 3/27/24
PLATE NO. W5-53S.3

PROJECT NO: 1130-65-76	HWY: IH 41	COUNTY: OUTAGAMIE	PERMANENT SIGNING	SHEET NO: 518A	E
PLOT NAME : C:\CAEFiles\Projects\1130-65-76\1130-65-76.dgn					WISDOT/CADDs SHEET 42
PLOT DATE : 27-MAR 2024 3:28					PLOT BY : mscj9n
PLOT SCALE : 1"=10'-0"					




PANEL 2: FACING SB LANES



PANEL 1: FACING NB LANES

- NOTES:
- PLACE SILHOUETTE IN CENTER OF RAIL PANEL CENTERED OVER THE ROAD NAME PANEL.
 - PLATES, BRACKETS, ANGLES, BARS AND SHIMS SHALL CONFORM TO ASTM A709, GRADE 36.
 - CARRIAGE BOLTS, NUTS AND WASHERS SHALL BE EITHER STAINLESS STEEL OR ASTM 307. IF 307 IS USED, CARRIAGE BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED.
 - ANCHORAGES TO TUBULAR RAILING SHALL BE ACCURATELY PLACED TO PROVIDE CORRECT ALIGNMENT OF SILHOUETTE.
 - THE BID ITEM SHALL BE "DECORATIVE SILHOUETTE" AND SHALL INCLUDE ALL ITEMS SHOWN INCLUDING THE PLATE, BRACKET AND MOUNTING HARDWARE.
 - THE SILHOUETTE PANELS AND ALL MOUNTING HARDWARE SHALL BE PAINTED AMS STD. COLOR NO. 27038, BLACK.
 - PROVIDE 3" DECORATIVE SILHOUETTE INSET PLATE. 5'-0" O.D. WITH HOLES FOR 1/4" DIA. CARRIAGE BOLTS.
 - ELECTRONIC COPIES OF THE CUTTING PATTERN ARE AVAILABLE BY CONTACTING:
BRYAN LEARST, WISDOT
944 VAN DER PERREN WAY, GREEN BAY, WI 54304
PHONE: (920) 366-5639
EMAIL: BRYAN.LEARST@DOT.WI.GOV
 - FIELD DRILL HOLES IN HSS 2 1/2" X 2 1/2" X 3/16" FOR 1/2" DIA. CARRIAGE BOLT, WASHER, AND NUT. PROVIDE 5/8" X 5/8" SQUARE HOLE IN SPACE BAR FOR SQUARE PORTION OF THE BOLT HEAD.



BRACKET DETAIL
(CONCEPT BRACKET DETAIL SHOWN.
DESIGN TO BE PROVIDED BY FABRICATOR.)

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-44-324/325			
DRAWN BY XXX LKCD			
SHEET 2			
RAILING SILHOUETTE DETAILS			894A

DESIGN DATA

CONTRACTOR DESIGNED OVERHEAD SIGN STRUCTURES SHALL BE DESIGNED ACCORDING TO THE AASHTO "LRFD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS", 1ST EDITION AND INTERIM SPECIFICATIONS, AND THE WISDOT BRIDGE MANUAL.

STANDARD FOUNDATIONS DESIGNED ACCORDING TO THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH EDITION.

DEAD LOAD: 3.15% TO TOP SURFACE OF SIGN & SURFACE AREA OF MEMBERS
WIND PRESSURE: 15 PSF (SEE SPECIFICATIONS FOR EXPOSED MEMBERS
(70 YEAR MEAN RECURRENCE INTERVAL))

WIND COMPONENTS	NORMAL	TRANSVERSE
LOAD CASE 1:	1.00	0.00
LOAD CASE 2:	0.75	0.75
LOAD CASE 3:	0.75	0.75

LOAD COMBINATIONS	
STRENGTH I:	1.25 DC + 1.6 LL
EXTREME I (MAX DC):	1.1 DC + 1.0 W + 1.0 ICE
EXTREME II (MIN DC):	0.9 DC + 1.0 W + 1.0 ICE
SERVICE I:	1.0 DC + 1.0 W
FATIGUE:	1.0 NW (NATURAL WIND GUST)
	1.0 TRG (TRUCK INDUCED GUST)
	1.0 GVW (GALLOPING - CANTILEVER ONLY)

MATERIAL PROPERTIES

CONCRETE MASONRY	$f'_c = 3,500$ PSI
HIGH STRENGTH STEEL REINFORCEMENT, GRADE 60	$f_y = 60,000$ PSI
STRUCTURAL ANGLES, PLATES & BARS - ASTM A709 GRADE 36	$f_y = 36,000$ PSI
HIGH STRENGTH BOLTS - ASTM A3125 GRADE A325	$f_u = 92,000$ PSI
ANCHOR RODS - ASTM A1554 GRADE 55	$f_u = 55,000$ PSI
HEAVY HEX NUTS - ASTM A563 GRADE DH OR ASTM A194 GRADE 2H	
WASHERS - ASTM F436	
DTI WASHERS - ASTM F959 TYPE 325	

FOUNDATION DATA

CONTRACTOR FOUNDATIONS ARE SUPPORTED ON DRILLED SHAFTS THAT HAVE BEEN DESIGN FOR 250 KIP COMPRESSION AND 100 KIP TENSION. THE SHAFTS ARE TO BE DRILLED TO 24" DIA. (SEE SPECIFICATIONS FOR DETAILS). THE GROUND WATER TABLE FOR DESIGN IS ASSUMED TO BE AT A UNIT WEIGHT OF 125 PCF. THE GROUND WATER TABLE FOR DESIGN IS ASSUMED TO BE AT A DEPTH OF 10'-0" BELOW THE GROUND SURFACE, ACTUAL WATER LEVEL AT SITE MAY VARY. THE REGION GEOTECHNICAL ENGINEER SHALL VISUALLY INSPECT THE SUBSURFACE SOILS DURING THE DRILLING OF THE HOLE TO CONFIRM THESE PROPERTIES PRIOR TO PLACEMENT OF THE DRILLED SHAFT CONCRETE.

TOTAL ESTIMATED QUANTITIES

BID ITEM NO.	BID ITEM	UNIT	S-44-403
531.2036	DRILLING SHAFT 36 INCH DIA	LF	26
531.5220	FOUNDATION SINGLE-SHAFT TYPE MF-II S-44-403	EA	2
532.5220	MONOTUBE FULL SPAN TYPE MF-II S-44-403	EA	1

ALL ITEMS ARE CATEGORY 6060

STRUCTURE DATA

STRUCTURE ID	SIGN AREA	SIGN DEPTH	FOUNDATION TYPE	TRUSS TYPE
S-44-403	42.5F	4'-0"	TYPE MF-II	TYPE MF-II

TRAFFIC VOLUME

E CAPITOL DRIVE
R.D.S. = 30 MPH

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

ALTERNATE DESIGNS ARE NOT ALLOWED.

COORDINATES ON THIS PLAN ARE REFERENCED TO THE WISCONSIN COUNTY COORDINATE SYSTEM (WCCS). OUTAGAMIE COUNTY ZONE NAD 83 (1987). ALL STATIONS AND ELEVATIONS ARE IN FEET. ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM NAVD 88 (2007).

ALL REINFORCING BARS ARE IN ENGLISH UNITS. THE FIRST DIGIT OF A THREE-DIGIT BAR MARK OR THE FIRST TWO DIGITS OF A FOUR-DIGIT BAR MARK SIGNIFIES THE BAR SIZE.

SIGN BRIDGE ID PLATES SHALL BE CONSIDERED INCIDENTAL TO THE TRUSS OR MONOTUBE BID ITEMS FOR EACH APPLICABLE SIGN STRUCTURE IN THE PLAN SET. LOCATE THE ID PLACQUE ON THE FREEWAY SIDE OF THE SUPPORT COLUMN SO THAT IT CAN BE SEEN FROM THE ROADWAY.

FABRICATE AND INSTALL THE ID PLACQUE IN ACCORDANCE WITH S.D.D. 12.44-3.

UNLESS DETAILED OTHERWISE IN THE PLANS, ALL U.S. BOLTED CONNECTIONS SHALL BE MADE WITH 3/4" DIA. A325 GALVANIZED BOLTS. FIELD CONNECTIONS SHALL BE INSTALLED WITH DTI WASHERS.

WELDED CONNECTIONS CAN BE USED IN LIEU OF BOLTED CONNECTIONS, IF A TRUSS UNIT CAN BE GALVANIZED IN ONE PIECE.

WELD TEST AS PER AWS D11.

SEE SIGN PLATE NO. A4-6, A4-7A & A4-7B OF THE SIGN PLATE MANUAL FOR INSTRUCTIONS ON CENTERING SIGNS VERTICALLY ON THE TRUSS.

SIGNS OR BLANKS SHALL BE INSTALLED ON TRUSS AT TIME OF ERECTION. BLANKS SHALL BE 1/2" THE LENGTH OF THE CANTILEVER SPAN, 2'-0" DEEPER THAN THE C/L TO C/L OF CHORDS, AND SHALL BE CENTERED ON THE BRIDGE. SIGNS SHALL BE AS DESIGNATED ON THE PLANS.

THE INFORMATION SHOWN ON THESE DRAWINGS CONCERNING TYPE AND LOCATION OF UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL INCLUSIVE. THE CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN DETERMINATION OF THE TYPE AND LOCATION OF UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE.

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS PER THE REQUIREMENTS IN THE STANDARD SPECIFICATIONS PRIOR TO FABRICATION OF THE STRUCTURE. CONTRACTOR SHALL SHOW SIGNS ON THE SHOP DRAWINGS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR DRILLING OR EXCAVATING AND MAINTAINING A HOLE TO THE FULL DEPTH OF THE SIGN SUPPORT PRIOR TO THE INSTALLATION OF THE DRILLED SHAFT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STABILITY OF THE EXCAVATED HOLE FOR THE SIGN SUPPORT PRIOR TO FILLING THE HOLE WITH CONCRETE. PERMANENT CASING MADE FROM STEEL OR CORRUGATED METAL PIPE MAY BE USED IN LIEU OF TEMPORARY CASING. TEMPORARY/PERMANENT CASING, IF USED, SHALL BE INCIDENTAL TO THE BID ITEM "DRILLING SHAFT (30-INCH)".


EXISTING UTILITIES SHOWN WILL BE RELOCATED IN ADVANCE OF CONSTRUCTION TO AVOID CONFLICTS WITH STRUCTURE.

LIST OF DRAWINGS:

- GENERAL NOTES & DESIGN DATA
- LAYOUT S-44-403

LIST OF STANDARD DESIGN DRAWINGS


- MONOTUBE & 2-CHORD TRUSS CONNECTIONS 1
- MONOTUBE & 2-CHORD TRUSS CONNECTIONS 2
- MONOTUBE & 2-CHORD TRUSS CONNECTIONS 3
- MONOTUBE & 2-CHORD TRUSS FOUNDATIONS



LOCATION MAP

THESE ARE STANDARD DESIGN PLANS DEVELOPED AND MAINTAINED BY THE WISDOT. THE DESIGNER CERTIFIES THAT THE DESIGN AND PLAN DETAILS CHOSEN ARE CONSISTENT WITH THE GUIDANCE PROVIDED IN THE CURRENT WISDOT BRIDGE MANUAL CHAPTER 39.

01/30/25



STRUCTURE DESIGN CONTACTS:
BRIDGE OFFICE:
AARON BONK (608) 261-0261
CONSULTANT:
STEVE MILLER (414) 272-2426

NO.	DATE	REVISION	BY
1	1/28/25	DRILLED SHAFT FOUNDATION REVISED TO 36" DIA.	TMH

Jacobs

8

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

ACCEPTED: CHIEF STRUCTURES DESIGN ENGINEER DATE

MONOTUBE & 2-CHORD

IN-41 SEGMENT 5 SIGN STRUCTURES

COUNTY: OUTAGAMIE TOWNSHIP: GRAND CHUTE

DESIGN SPEC: AASHTO LRFD BRIDGE DESIGN SPECIFICATION
DESIGNED BY: TMH
CHECKED BY: TMH
EKM BY: EKM

GENERAL NOTES
& DESIGN DATA

SHEET 1 OF 6

924

DATE: 12/19/2024

8



Proposal Schedule of Items

Page 1 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0205 Grubbing	28.000 STA	_____.	_____.
0004	203.0220 Removing Structure (structure) 0001. B-44-172	1.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	34,646.000 SY	_____.	_____.
0008	204.0115 Removing Asphaltic Surface Butt Joints	8.000 SY	_____.	_____.
0010	204.0120 Removing Asphaltic Surface Milling	6,081.000 SY	_____.	_____.
0012	204.0150 Removing Curb & Gutter	124.000 LF	_____.	_____.
0014	204.0155 Removing Concrete Sidewalk	3,994.000 SY	_____.	_____.
0016	204.0165 Removing Guardrail	855.000 LF	_____.	_____.
0018	204.0170 Removing Fence	6,504.000 LF	_____.	_____.
0020	204.0195 Removing Concrete Bases	17.000 EACH	_____.	_____.
0022	204.0210 Removing Manholes	7.000 EACH	_____.	_____.
0024	204.0220 Removing Inlets	48.000 EACH	_____.	_____.
0026	204.0245 Removing Storm Sewer (size) 0001. 12-Inch	476.000 LF	_____.	_____.
0028	204.0245 Removing Storm Sewer (size) 0002. 15-Inch	731.000 LF	_____.	_____.
0030	204.0245 Removing Storm Sewer (size) 0003. 18-Inch	1,126.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	204.0245 Removing Storm Sewer (size) 0004. 24-Inch	1,104.000 LF	_____.	_____.
0034	204.0246 Removing Ancillary Structure (structure) 0001. S-44-033	1.000 EACH	_____.	_____.
0036	204.0246 Removing Ancillary Structure (structure) 0002. S-44-034	1.000 EACH	_____.	_____.
0038	204.0280 Sealing Pipes	2.000 EACH	_____.	_____.
0040	204.9060.S Removing (item description) 0001. Removing Sign (Station 866'EA'+00 66' RT)	1.000 EACH	_____.	_____.
0042	204.9060.S Removing (item description) 0002. Removing Sign (Station 302'ED'+00 69' LT)	1.000 EACH	_____.	_____.
0044	204.9060.S Removing (item description) 0003. Removing Sign Base (Station 21'CAP'+21 38' LT)	1.000 EACH	_____.	_____.
0046	204.9060.S Removing (item description) 0701. Communications Vault	1.000 EACH	_____.	_____.
0048	204.9060.S Removing (item description) 1000. Removing Traffic Signals Ballard Road & Capitol Drive	1.000 EACH	_____.	_____.
0050	205.0100 Excavation Common	61,661.000 CY	_____.	_____.
0052	206.1001 Excavation for Structures Bridges (structure) 0001. B-44-324	1.000 EACH	_____.	_____.
0054	206.1001 Excavation for Structures Bridges (structure) 0002. B-44-325	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0056	209.0200.S Backfill Controlled Low Strength	26.000 CY	_____.	_____.
0058	210.1500 Backfill Structure Type A	1,110.000 TON	_____.	_____.
0060	213.0100 Finishing Roadway (project) 0001. 1130-65-76	1.000 EACH	_____.	_____.
0062	305.0110 Base Aggregate Dense 3/4-Inch	213.000 TON	_____.	_____.
0064	305.0120 Base Aggregate Dense 1 1/4-Inch	30,745.000 TON	_____.	_____.
0066	310.0115 Base Aggregate Open-Graded	115.000 CY	_____.	_____.
0068	312.0110 Select Crushed Material	68,103.000 TON	_____.	_____.
0070	390.0100 Removing Pavement for Base Patching	100.000 CY	_____.	_____.
0072	390.0201 Base Patching Asphaltic	148.000 TON	_____.	_____.
0074	405.0200 Coloring Concrete Custom	456.000 CY	_____.	_____.
0076	415.0090 Concrete Pavement 9-Inch	43,050.000 SY	_____.	_____.
0078	415.0410 Concrete Pavement Approach Slab	342.000 SY	_____.	_____.
0080	415.1090 Concrete Pavement HES 9-Inch	158.000 SY	_____.	_____.
0082	415.4100 Concrete Pavement Joint Filling	34,622.000 SY	_____.	_____.
0084	416.0610 Drilled Tie Bars	402.000 EACH	_____.	_____.
0086	416.0620 Drilled Dowel Bars	1,014.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	455.0605 Tack Coat	1,114.000 GAL	_____.	_____.
0090	460.2000 Incentive Density HMA Pavement	740.000 DOL	1.00000	740.00
0094	460.5224 HMA Pavement 4 LT 58-28 S	1,144.000 TON	_____.	_____.
0096	465.0105 Asphaltic Surface	3,665.000 TON	_____.	_____.
0098	465.0120 Asphaltic Surface Driveways and Field Entrances	2.000 TON	_____.	_____.
0100	465.0315 Asphaltic Flumes	5.000 SY	_____.	_____.
0102	495.1000.S Cold Patch	20.000 TON	_____.	_____.
0104	501.1000.S Ice Hot Weather Concreting	13,883.000 LB	_____.	_____.
0106	502.0100 Concrete Masonry Bridges	570.000 CY	_____.	_____.
0108	502.3200 Protective Surface Treatment	3,082.000 SY	_____.	_____.
0110	502.3210 Pigmented Surface Sealer	565.000 SY	_____.	_____.
0112	503.0146 Prestressed Girder Type I 45W-Inch	2,158.000 LF	_____.	_____.
0114	505.0400 Bar Steel Reinforcement HS Structures	26,790.000 LB	_____.	_____.
0116	505.0600 Bar Steel Reinforcement HS Coated Structures	341,540.000 LB	_____.	_____.
0118	505.0800.S Bar Steel Reinforcement HS Stainless Structures	4,420.000 LB	_____.	_____.



Proposal Schedule of Items

Page 5 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0120	506.2605 Bearing Pads Elastomeric Non-Laminated	24.000 EACH	_____.	_____.
0122	506.4000 Steel Diaphragms (structure) 0001. B-44-324	20.000 EACH	_____.	_____.
0124	506.4000 Steel Diaphragms (structure) 0002. B-44-325	20.000 EACH	_____.	_____.
0126	513.2001 Railing Pipe 0001. R-44-40	131.000 LF	_____.	_____.
0128	513.2001 Railing Pipe 0002. R-44-41	130.000 LF	_____.	_____.
0130	513.4091 Railing Tubular Screening 0001. B-44-324	364.000 LF	_____.	_____.
0132	513.4091 Railing Tubular Screening 0002. B-44-325	360.000 LF	_____.	_____.
0134	516.0500 Rubberized Membrane Waterproofing	66.000 SY	_____.	_____.
0136	517.1010.S Concrete Staining (structure) 1000. B-44-324	8,250.000 SF	_____.	_____.
0138	517.1010.S Concrete Staining (structure) 1010. B-44-325	8,170.000 SF	_____.	_____.
0140	517.1010.S Concrete Staining (structure) 1020. R-44-0040	4,400.000 SF	_____.	_____.
0142	517.1010.S Concrete Staining (structure) 1030. R-44-0041	4,650.000 SF	_____.	_____.
0144	520.8000 Concrete Collars for Pipe	9.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 6 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0146	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	141.000 LF	_____.	_____.
0148	522.0430 Culvert Pipe Reinforced Concrete Class IV 30-Inch	170.000 LF	_____.	_____.
0150	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	13.000 EACH	_____.	_____.
0152	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	7.000 EACH	_____.	_____.
0154	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	7.000 EACH	_____.	_____.
0156	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	2.000 EACH	_____.	_____.
0158	531.1100 Concrete Masonry Ancillary Structures Type NS	4.800 CY	_____.	_____.
0160	531.1140 Steel Reinforcement HS Ancillary Structures Type NS	720.000 LB	_____.	_____.
0162	531.2024 Drilling Shaft 24-Inch	40.000 LF	_____.	_____.
0166	531.2036 Drilling Shaft 36-Inch	36.000 LF	_____.	_____.
0168	531.2042 Drilling Shaft 42-Inch	184.000 LF	_____.	_____.
0170	531.4050 Foundation Camera Pole 50-FT	1.000 EACH	_____.	_____.
0172	531.5220 Foundation Single-Shaft Type MF-II (structure) 6060. S-44-403	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 7 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0174	531.5440 Foundation Single-Shaft Type TF-IV (structure) 6000. S-44-367	2.000 EACH	_____.	_____.
0176	531.5440 Foundation Single-Shaft Type TF-IV (structure) 6020. S-44-373	2.000 EACH	_____.	_____.
0178	531.5440 Foundation Single-Shaft Type TF-IV (structure) 6030. S-44-369	2.000 EACH	_____.	_____.
0180	531.5440 Foundation Single-Shaft Type TF-IV (structure) 6040. S-44-370	2.000 EACH	_____.	_____.
0182	531.8990 Anchor Assemblies Poles on Structures	6.000 EACH	_____.	_____.
0184	532.5220 Monotube Full Span Type II (structure) 6060. S-44-403	1.000 EACH	_____.	_____.
0186	532.5420 Truss Full Span 2-Chord Type II (structure) 6010. S-44-371	1.000 EACH	_____.	_____.
0188	532.5420 Truss Full Span 2-Chord Type II (structure) 6050. S-44-401	1.000 EACH	_____.	_____.
0190	532.5440 Truss Full Span 2-Chord Type IV (structure) 6000. S-44-367	1.000 EACH	_____.	_____.
0192	532.5440 Truss Full Span 2-Chord Type IV (structure) 6020. S-44-373	1.000 EACH	_____.	_____.
0194	532.5440 Truss Full Span 2-Chord Type IV (structure) 6030. S-44-369	1.000 EACH	_____.	_____.
0196	532.5440 Truss Full Span 2-Chord Type IV (structure) 6040. S-44-370	1.000 EACH	_____.	_____.
0198	550.0010 Pre-Boring Unconsolidated Materials	166.000 LF	_____.	_____.



Proposal Schedule of Items

Page 8 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0200	550.0500 Pile Points	112.000 EACH	_____.	_____.
0202	550.1120 Piling Steel HP 12-Inch X 53 Lb	6,640.000 LF	_____.	_____.
0204	601.0405 Concrete Curb & Gutter 18-Inch Type A	344.000 LF	_____.	_____.
0206	601.0409 Concrete Curb & Gutter 30-Inch Type A	9,912.000 LF	_____.	_____.
0208	601.0452 Concrete Curb & Gutter Integral 30-Inch Type D	2,501.000 LF	_____.	_____.
0210	601.0600 Concrete Curb Pedestrian	285.000 LF	_____.	_____.
0212	602.0405 Concrete Sidewalk 4-Inch	65,767.000 SF	_____.	_____.
0214	602.0415 Concrete Sidewalk 6-Inch	2,201.000 SF	_____.	_____.
0216	602.0505 Curb Ramp Detectable Warning Field Yellow	337.000 SF	_____.	_____.
0218	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	151.000 SF	_____.	_____.
0220	602.0810 Concrete Driveway 6-Inch	137.000 SY	_____.	_____.
0222	602.0825 Concrete Driveway 9-Inch	133.000 SY	_____.	_____.
0224	602.3010 Concrete Surface Drains	4.000 CY	_____.	_____.
0226	603.8000 Concrete Barrier Temporary Precast Delivered	3,945.000 LF	_____.	_____.
0228	603.8125 Concrete Barrier Temporary Precast Installed	3,945.000 LF	_____.	_____.



Proposal Schedule of Items

Page 9 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0230	603.8500 Anchoring Concrete Barrier Temporary Precast	1,670.000 LF	_____.	_____.
0232	604.0400 Slope Paving Concrete	184.000 SY	_____.	_____.
0234	606.0200 Riprap Medium	593.000 CY	_____.	_____.
0236	608.0315 Storm Sewer Pipe Reinforced Concrete Class III 15-Inch	2,016.000 LF	_____.	_____.
0238	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	333.000 LF	_____.	_____.
0240	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	1,415.000 LF	_____.	_____.
0242	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	60.000 LF	_____.	_____.
0244	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	802.000 LF	_____.	_____.
0246	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	687.000 LF	_____.	_____.
0248	611.0535 Manhole Covers Type J-Special	8.000 EACH	_____.	_____.
0250	611.0610 Inlet Covers Type BW	6.000 EACH	_____.	_____.
0252	611.0624 Inlet Covers Type H	69.000 EACH	_____.	_____.
0254	611.0642 Inlet Covers Type MS	1.000 EACH	_____.	_____.
0256	611.0666 Inlet Covers Type Z	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 10 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0258	611.2004 Manholes 4-FT Diameter	7.000 EACH	_____.	_____.
0260	611.2005 Manholes 5-FT Diameter	5.000 EACH	_____.	_____.
0262	611.3004 Inlets 4-FT Diameter	88.000 EACH	_____.	_____.
0264	611.3901 Inlets Median 1 Grate	1.000 EACH	_____.	_____.
0266	611.8110 Adjusting Manhole Covers	3.000 EACH	_____.	_____.
0268	612.0106 Pipe Underdrain 6-Inch	3,896.000 LF	_____.	_____.
0270	612.0406 Pipe Underdrain Wrapped 6-Inch	600.000 LF	_____.	_____.
0272	612.0902.S Insulation Board Polystyrene (inch) 0001. 3-Inch	1.000 SY	_____.	_____.
0274	614.0220 Steel Thrie Beam Bullnose Terminal	2.000 EACH	_____.	_____.
0276	614.0230 Steel Thrie Beam	375.000 LF	_____.	_____.
0278	614.0397 Guardrail Mow Strip Emulsified Asphalt	57.000 SY	_____.	_____.
0280	614.0905 Crash Cushions Temporary	8.000 EACH	_____.	_____.
0284	614.2300 MGS Guardrail 3	1,212.500 LF	_____.	_____.
0286	614.2500 MGS Thrie Beam Transition	39.400 LF	_____.	_____.
0288	614.2610 MGS Guardrail Terminal EAT	3.000 EACH	_____.	_____.
0290	616.0206 Fence Chain Link 6-FT	6,847.000 LF	_____.	_____.



Proposal Schedule of Items

Page 11 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0292	616.0700.S Fence Safety	1,000.000 LF	_____.	_____.
0294	618.0100 Maintenance and Repair of Haul Roads (project) 0001. 1130-65-76	1.000 EACH	_____.	_____.
0296	619.1000 Mobilization	1.000 EACH	_____.	_____.
0298	620.0300 Concrete Median Sloped Nose	345.000 SF	_____.	_____.
0300	623.0200 Dust Control Surface Treatment	84,386.000 SY	_____.	_____.
0302	624.0100 Water	422.000 MGAL	_____.	_____.
0304	625.0500 Salvaged Topsoil	131,672.000 SY	_____.	_____.
0306	628.1504 Silt Fence	12,640.000 LF	_____.	_____.
0308	628.1520 Silt Fence Maintenance	28,469.000 LF	_____.	_____.
0310	628.1905 Mobilizations Erosion Control	9.000 EACH	_____.	_____.
0312	628.1910 Mobilizations Emergency Erosion Control	5.000 EACH	_____.	_____.
0314	628.2004 Erosion Mat Class I Type B	112,341.000 SY	_____.	_____.
0316	628.2008 Erosion Mat Urban Class I Type B	11,296.000 SY	_____.	_____.
0318	628.7005 Inlet Protection Type A	102.000 EACH	_____.	_____.
0320	628.7015 Inlet Protection Type C	112.000 EACH	_____.	_____.
0322	628.7020 Inlet Protection Type D	5.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 12 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0324	628.7504 Temporary Ditch Checks	521.000 LF	_____.	_____.
0326	628.7555 Culvert Pipe Checks	39.000 EACH	_____.	_____.
0328	628.7560 Tracking Pads	6.000 EACH	_____.	_____.
0330	629.0210 Fertilizer Type B	40.000 CWT	_____.	_____.
0332	630.0130 Seeding Mixture No. 30	5,265.000 LB	_____.	_____.
0334	630.0500 Seed Water	2,781.000 MGAL	_____.	_____.
0336	632.0101 Trees (species, root, size) 0010. Baldcypress, B&B, 2.5" Cal.	6.000 EACH	_____.	_____.
0338	632.0101 Trees (species, root, size) 0020. Buckeye, 'Early Glow', B&B, 2.5" Cal.	2.000 EACH	_____.	_____.
0340	632.0101 Trees (species, root, size) 0030. Elm, 'Triumph', B&B, 2.5" Cal.	3.000 EACH	_____.	_____.
0342	632.0101 Trees (species, root, size) 0040. Hackberry, B&B, 2.5" Cal.	2.000 EACH	_____.	_____.
0344	632.0101 Trees (species, root, size) 0050. Honeylocust, 'Skyline', B&B, 2.5" Cal.	2.000 EACH	_____.	_____.
0346	632.0101 Trees (species, root, size) 0060. Maple, 'Sienna Glenn', B&B, 2.5" Cal.	1.000 EACH	_____.	_____.
0348	632.0101 Trees (species, root, size) 0070. Oak, Chinkapin, B&B, 2.5" Cal.	3.000 EACH	_____.	_____.
0350	632.0101 Trees (species, root, size) 0080. Oak, Hybrid Swamp x Bur, B&B, 2.5" Cal.	8.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 13 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0352	632.0101 Trees (species, root, size) 0090. Oak, Swamp White, B&B, 2.5" Cal.	12.000 EACH	_____.	_____.
0354	632.0101 Trees (species, root, size) 0100. Hawthorn, 'Winter King' (Shrub Form Tree), B&B, 6' Ht.	20.000 EACH	_____.	_____.
0356	632.0101 Trees (species, root, size) 0110. Serviceberry, 'Autumn Brilliance' (Shrub Form Tree), B&B, 6' Ht.	10.000 EACH	_____.	_____.
0358	632.0101 Trees (species, root, size) 0120. Witchhazel (Shrub Form Tree), B&B, 6' Ht.	4.000 EACH	_____.	_____.
0360	632.0201 Shrubs (species, root, size) 0010. Juniper, 'Broadmoor', Cont., 24" Sprd. / #3	9.000 EACH	_____.	_____.
0362	632.0201 Shrubs (species, root, size) 0020. Juniper, 'Kallay's Compact' Pfitzer, Cont., 24" Sprd. / #3	15.000 EACH	_____.	_____.
0364	632.0201 Shrubs (species, root, size) 0030. Honeysuckle, Dwarf Bush, Cont., 24" Sprd. / #3	27.000 EACH	_____.	_____.
0366	632.0201 Shrubs (species, root, size) 0040. Sumac, Gro-low, Cont., 24" Sprd./#3	16.000 EACH	_____.	_____.
0368	632.9101 Landscape Planting Surveillance and Care Cycles	20.000 EACH	_____.	_____.
0370	633.5200 Markers Culvert End	29.000 EACH	_____.	_____.
0372	634.0614 Posts Wood 4x6-Inch X 14-FT	23.000 EACH	_____.	_____.
0374	634.0616 Posts Wood 4x6-Inch X 16-FT	16.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 14 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0376	634.0618 Posts Wood 4x6-Inch X 18-FT	5.000 EACH	_____.	_____.
0378	635.0200 Sign Supports Structural Steel HS	2,950.000 LB	_____.	_____.
0380	637.1220 Signs Type I Reflective SH	1,882.700 SF	_____.	_____.
0382	637.2210 Signs Type II Reflective H	637.000 SF	_____.	_____.
0384	637.2215 Signs Type II Reflective H Folding	102.880 SF	_____.	_____.
0386	637.2230 Signs Type II Reflective F	103.000 SF	_____.	_____.
0388	638.2101 Moving Signs Type I	10.000 EACH	_____.	_____.
0390	638.2102 Moving Signs Type II	5.000 EACH	_____.	_____.
0392	638.2601 Removing Signs Type I	2.000 EACH	_____.	_____.
0394	638.2602 Removing Signs Type II	57.000 EACH	_____.	_____.
0396	638.3000 Removing Small Sign Supports	51.000 EACH	_____.	_____.
0398	643.0300 Traffic Control Drums	114,915.000 DAY	_____.	_____.
0400	643.0420 Traffic Control Barricades Type III	12,867.000 DAY	_____.	_____.
0402	643.0500 Traffic Control Flexible Tubular Marker Posts	16.000 EACH	_____.	_____.
0404	643.0600 Traffic Control Flexible Tubular Marker Bases	16.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 15 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0406	643.0705 Traffic Control Warning Lights Type A	25,734.000 DAY	_____.	_____.
0408	643.0715 Traffic Control Warning Lights Type C	24,727.000 DAY	_____.	_____.
0410	643.0800 Traffic Control Arrow Boards	1,015.000 DAY	_____.	_____.
0412	643.0900 Traffic Control Signs	117,703.000 DAY	_____.	_____.
0414	643.0910 Traffic Control Covering Signs Type I	29.000 EACH	_____.	_____.
0416	643.0920 Traffic Control Covering Signs Type II	3.000 EACH	_____.	_____.
0418	643.1000 Traffic Control Signs Fixed Message	1,133.000 SF	_____.	_____.
0420	643.1050 Traffic Control Signs PCMS	164.000 DAY	_____.	_____.
0422	643.3165 Temporary Marking Line Paint 6-Inch	1,101.000 LF	_____.	_____.
0424	643.3180 Temporary Marking Line Removable Tape 6-Inch	3,815.000 LF	_____.	_____.
0426	643.3280 Temporary Marking Line Removable Tape 10-Inch	610.000 LF	_____.	_____.
0428	643.3350 Temporary Marking Crosswalk Removable Tape 6-inch	320.000 LF	_____.	_____.
0430	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0432	644.1410 Temporary Pedestrian Surface Asphalt	1,185.000 SF	_____.	_____.
0434	644.1440 Temporary Pedestrian Surface Matting	54.000 SF	_____.	_____.



Proposal Schedule of Items

Page 16 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0436	644.1601 Temporary Pedestrian Curb Ramp	57.000 DAY	_____.	_____.
0438	644.1605 Temporary Pedestrian Detectable Warning Field	99.000 SF	_____.	_____.
0440	644.1810 Temporary Pedestrian Barricade	1,884.000 LF	_____.	_____.
0442	645.0111 Geotextile Type DF Schedule A	1,732.000 SY	_____.	_____.
0444	645.0120 Geotextile Type HR	1,187.000 SY	_____.	_____.
0446	646.2020 Marking Line Epoxy 6-Inch	16,559.000 LF	_____.	_____.
0448	646.2025 Marking Line Grooved Black Epoxy 6-Inch	977.000 LF	_____.	_____.
0450	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	6,949.000 LF	_____.	_____.
0452	646.2050 Marking Line Grooved Permanent Tape 6-Inch	1,370.000 LF	_____.	_____.
0454	646.4020 Marking Line Epoxy 10-Inch	1,151.000 LF	_____.	_____.
0456	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	258.000 LF	_____.	_____.
0458	646.4050 Marking Line Grooved Permanent Tape 10-Inch	7,118.000 LF	_____.	_____.
0460	646.5020 Marking Arrow Epoxy	96.000 EACH	_____.	_____.
0462	646.5120 Marking Word Epoxy	11.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 17 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	646.5220 Marking Symbol Epoxy	38.000 EACH	_____.	_____.
0466	646.6120 Marking Stop Line Epoxy 18-Inch	622.000 LF	_____.	_____.
0468	646.6220 Marking Yield Line Epoxy 18-Inch	6.000 EACH	_____.	_____.
0470	646.7120 Marking Diagonal Epoxy 12-Inch	55.000 LF	_____.	_____.
0472	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,477.000 LF	_____.	_____.
0474	646.8105 Marking Curb Paint	60.000 LF	_____.	_____.
0476	646.8205 Marking Island Nose Paint	6.000 EACH	_____.	_____.
0478	646.8320 Marking Parking Stall Epoxy	4,058.000 LF	_____.	_____.
0480	646.9000 Marking Removal Line 4-Inch	1,810.000 LF	_____.	_____.
0482	646.9100 Marking Removal Line 8-Inch	75.000 LF	_____.	_____.
0484	652.0125 Conduit Rigid Metallic 2-Inch	32.000 LF	_____.	_____.
0486	652.0210 Conduit Rigid Nonmetallic Schedule 40 1-Inch	395.000 LF	_____.	_____.
0488	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	8,966.000 LF	_____.	_____.
0490	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	5,179.000 LF	_____.	_____.
0492	652.0325 Conduit Rigid Nonmetallic Schedule 80 2-Inch	1,090.000 LF	_____.	_____.



Proposal Schedule of Items

Page 18 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0494	652.0335 Conduit Rigid Nonmetallic Schedule 80 3-Inch	2,020.000 LF	_____.	_____.
0496	652.0800 Conduit Loop Detector	3,071.000 LF	_____.	_____.
0498	653.0154 Pull Boxes Non-Conductive 24x36-Inch	5.000 EACH	_____.	_____.
0500	653.0164 Pull Boxes Non-Conductive 24x42-Inch	67.000 EACH	_____.	_____.
0502	653.0222 Junction Boxes 18x12x6-Inch	6.000 EACH	_____.	_____.
0504	653.0905 Removing Pull Boxes	29.000 EACH	_____.	_____.
0506	654.0101 Concrete Bases Type 1	14.000 EACH	_____.	_____.
0508	654.0102 Concrete Bases Type 2	8.000 EACH	_____.	_____.
0510	654.0105 Concrete Bases Type 5	33.000 EACH	_____.	_____.
0512	654.0107 Concrete Bases Type 7	2.000 EACH	_____.	_____.
0514	654.0110 Concrete Bases Type 10	1.000 EACH	_____.	_____.
0516	654.0113 Concrete Bases Type 13	2.000 EACH	_____.	_____.
0518	654.0120 Concrete Bases Type 10-Special	7.000 EACH	_____.	_____.
0520	654.0217 Concrete Control Cabinet Bases Type 9 Special	2.000 EACH	_____.	_____.
0522	654.0230 Concrete Control Cabinet Bases Type L30	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 19 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0524	655.0230 Cable Traffic Signal 5-14 AWG	10,285.000 LF	_____.	_____.
0526	655.0240 Cable Traffic Signal 7-14 AWG	746.000 LF	_____.	_____.
0528	655.0260 Cable Traffic Signal 12-14 AWG	581.000 LF	_____.	_____.
0530	655.0305 Cable Type UF 2-12 AWG Grounded	2,570.000 LF	_____.	_____.
0532	655.0515 Electrical Wire Traffic Signals 10 AWG	5,809.000 LF	_____.	_____.
0534	655.0610 Electrical Wire Lighting 12 AWG	11,483.000 LF	_____.	_____.
0536	655.0625 Electrical Wire Lighting 6 AWG	37,341.000 LF	_____.	_____.
0538	655.0700 Loop Detector Lead In Cable	6,500.000 LF	_____.	_____.
0540	655.0800 Loop Detector Wire	8,972.000 LF	_____.	_____.
0542	655.0900 Traffic Signal EVP Detector Cable	1,075.000 LF	_____.	_____.
0544	656.0201 Electrical Service Meter Breaker Pedestal (location) 0001. S44-2014 (IH 41 SB & CTH E)	1.000 EACH	_____.	_____.
0546	656.0201 Electrical Service Meter Breaker Pedestal (location) 0002. S44-0578 (IH 41 NB & CTH E)	1.000 EACH	_____.	_____.
0548	656.0201 Electrical Service Meter Breaker Pedestal (location) 0003. MB4-1	1.000 EACH	_____.	_____.
0550	656.0401 Electrical Service Main Lugs Only Meter Pedestal (location) 0001. CB600	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 20 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0552	656.0501 Electrical Service Breaker Disconnect Box (location) 0001. CB4-1	1.000 EACH	_____.	_____.
0554	656.0501 Electrical Service Breaker Disconnect Box (location) 0002. CB4-2	1.000 EACH	_____.	_____.
0556	657.0100 Pedestal Bases	17.000 EACH	_____.	_____.
0558	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	44.000 EACH	_____.	_____.
0560	657.0310 Poles Type 3	7.000 EACH	_____.	_____.
0562	657.0315 Poles Type 4	1.000 EACH	_____.	_____.
0564	657.0322 Poles Type 5-Aluminum	32.000 EACH	_____.	_____.
0566	657.0347 Poles Type 9-Special	1.000 EACH	_____.	_____.
0568	657.0350 Poles Type 10	1.000 EACH	_____.	_____.
0570	657.0352 Poles Type 10-Special	6.000 EACH	_____.	_____.
0572	657.0360 Poles Type 13	2.000 EACH	_____.	_____.
0574	657.0420 Traffic Signal Standards Aluminum 13-FT	7.000 EACH	_____.	_____.
0576	657.0425 Traffic Signal Standards Aluminum 15-FT	1.000 EACH	_____.	_____.
0578	657.0430 Traffic Signal Standards Aluminum 10-FT	9.000 EACH	_____.	_____.
0580	657.0530 Monotube Arms 30-FT	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 21 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0582	657.0536 Monotube Arms 35-FT-Special	1.000 EACH	_____.	_____.
0584	657.0546 Monotube Arms 45-FT-Special	6.000 EACH	_____.	_____.
0586	657.0550 Monotube Arms 50-FT	1.000 EACH	_____.	_____.
0588	657.0555 Monotube Arms 55-FT	1.000 EACH	_____.	_____.
0590	657.0609 Luminaire Arms Single Member 4-Inch Clamp 6-FT	1.000 EACH	_____.	_____.
0592	657.0610 Luminaire Arms Single Member 4 1/2- Inch Clamp 6-FT	1.000 EACH	_____.	_____.
0594	657.0709 Luminaire Arms Truss Type 4-Inch Clamp 12-FT	8.000 EACH	_____.	_____.
0596	657.0710 Luminaire Arms Truss Type 4 1/2-Inch Clamp 12-FT	38.000 EACH	_____.	_____.
0598	657.0806 Luminaire Arms Steel 6-FT	1.000 EACH	_____.	_____.
0600	657.0810 Luminaire Arms Steel 10-FT	2.000 EACH	_____.	_____.
0602	657.0812 Luminaire Arms Steel 12-FT	4.000 EACH	_____.	_____.
0604	658.0173 Traffic Signal Face 3S 12-Inch	46.000 EACH	_____.	_____.
0606	658.0174 Traffic Signal Face 4S 12-Inch	3.000 EACH	_____.	_____.
0608	658.0416 Pedestrian Signal Face 16-Inch	18.000 EACH	_____.	_____.
0610	658.0500 Pedestrian Push Buttons	18.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 22 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0612	658.5070 Signal Mounting Hardware (location) 0001. S44-2014 (IH 41 SB & CTH E)	1.000 EACH	_____.	_____.
0614	658.5070 Signal Mounting Hardware (location) 0002. S44-0578 (IH 41 NB & CTH E)	1.000 EACH	_____.	_____.
0616	659.1120 Luminaires Utility LED B	38.000 EACH	_____.	_____.
0618	659.1125 Luminaires Utility LED C	15.000 EACH	_____.	_____.
0620	659.2130 Lighting Control Cabinets 120/240 30-Inch	1.000 EACH	_____.	_____.
0622	659.2230 Lighting Control Cabinets 240/480 30-Inch	1.000 EACH	_____.	_____.
0624	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	88.000 EACH	_____.	_____.
0626	661.0201 Temporary Traffic Signals for Intersections (location) 1000. STH 47 & Ridgeview Drive	1.000 EACH	_____.	_____.
0628	662.1026.S Ramp Closure Gates 26-FT	1.000 EACH	_____.	_____.
0630	662.1032.S Ramp Closure Gates 32-FT	1.000 EACH	_____.	_____.
0632	662.1040.S Ramp Closure Gates 40-FT	2.000 EACH	_____.	_____.
0634	670.0101 Field System Integrator	1.000 EACH	_____.	_____.
0636	670.0201 ITS Documentation	1.000 EACH	_____.	_____.
0638	671.0132 Conduit HDPE 3-Duct 2-Inch	1,899.000 LF	_____.	_____.



Proposal Schedule of Items

Page 23 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0640	671.0300 Fiber Optic Cable Marker	10.000 EACH	_____.	_____.
0642	673.0105 Communication Vault Type 1	3.000 EACH	_____.	_____.
0644	673.0200 Tracer Wire Marker Posts	6.000 EACH	_____.	_____.
0646	673.1225.S Install Pole Mounted Cabinet	2.000 EACH	_____.	_____.
0648	677.0150 Install Camera Pole 50-FT	1.000 EACH	_____.	_____.
0650	677.0200 Install Camera Assembly	2.000 EACH	_____.	_____.
0652	678.0012 Install Fiber Optic Cable Outdoor Plant 12-CT	1,821.000 LF	_____.	_____.
0654	678.0400 Fiber Optic Termination	8.000 EACH	_____.	_____.
0656	678.0501 Communication System Testing	1.000 EACH	_____.	_____.
0658	678.0600 Install Ethernet Switches	3.000 EACH	_____.	_____.
0660	678.0700 Install Wireless Antennas	2.000 EACH	_____.	_____.
0662	690.0150 Sawing Asphalt	256.000 LF	_____.	_____.
0664	690.0250 Sawing Concrete	3,995.000 LF	_____.	_____.
0666	715.0502 Incentive Strength Concrete Structures	3,420.000 DOL	1.00000	3,420.00
0668	715.0603 Incentive Strength Concrete Barrier	1,327.000 DOL	1.00000	1,327.00



Proposal Schedule of Items

Page 24 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0670	715.0720 Incentive Compressive Strength Concrete Pavement	13,065.000 DOL	1.00000	13,065.00
0672	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	4,400.000 HRS	5.00000	22,000.00
0674	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0676	SPV.0035 Special 0100. Roadway Embankment	130,670.000 CY	_____.	_____.
0678	SPV.0035 Special 0800. HPC Masonry Structures	1,281.000 CY	_____.	_____.
0680	SPV.0035 Special 5000. Planting Mixture	173.000 CY	_____.	_____.
0682	SPV.0035 Special 5010. Topsoil Special	214.000 CY	_____.	_____.
0684	SPV.0045 Special 0100. Connected Work Zone Start and End Location Markers	222.000 DAY	_____.	_____.
0686	SPV.0060 Special 0100. Construction Staking Survey Project 1130-65-76	1.000 EACH	_____.	_____.
0688	SPV.0060 Special 0105. Baseline CPM Progress Schedule	1.000 EACH	_____.	_____.
0690	SPV.0060 Special 0110. CPM Progress Schedule and Accepted Revisions	8.000 EACH	_____.	_____.
0692	SPV.0060 Special 0160. Mobilizations Emergency Pavement Repair	4.000 EACH	_____.	_____.
0694	SPV.0060 Special 0165. Emergency Response to Traffic Involving Concrete Barrier Temporary	14.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 25 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0696	SPV.0060 Special 0170. Emergency Response to Traffic Involving Crash Cushion Temporary	18.000 EACH	_____.	_____.
0698	SPV.0060 Special 0205. Cover Plates Left-In-Place	15.000 EACH	_____.	_____.
0700	SPV.0060 Special 0208. Pipe Connection to Existing Structure	3.000 EACH	_____.	_____.
0702	SPV.0060 Special 0500. Anchor Bolt Cover Shroud	2.000 EACH	_____.	_____.
0704	SPV.0060 Special 0600. Remove Traffic Signal S44-2014 (IH 41 SB & CTH E)	1.000 EACH	_____.	_____.
0706	SPV.0060 Special 0601. Remove Traffic Signal S44-0578 (IH 41 NB & CTH E)	1.000 EACH	_____.	_____.
0708	SPV.0060 Special 0602. Salvaging Monotube Poles Type 13 (IH 41 NB & CTH E)	1.000 EACH	_____.	_____.
0710	SPV.0060 Special 0603. Salvaging Monotube Poles Type 13 (IH 41 SB & CTH E)	1.000 EACH	_____.	_____.
0712	SPV.0060 Special 0604. Salvaging Monotube Arms 40-ft (IH 41 NB & CTH E)	1.000 EACH	_____.	_____.
0714	SPV.0060 Special 0605. Salvaging Monotube Arms 40-ft (IH 41 SB & CTH E)	1.000 EACH	_____.	_____.
0716	SPV.0060 Special 0606. Salvaging Monotube Luminaires (IH 41 NB & CTH E)	2.000 EACH	_____.	_____.
0718	SPV.0060 Special 0607. Salvaging Monotube Luminaires (IH 41 SB & CTH E)	2.000 EACH	_____.	_____.
0720	SPV.0060 Special 0608. Salvaging Transformer Bases (IH 41 NB & CTH E)	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 26 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0722	SPV.0060 Special 0609. Salvaging Transformer Bases (IH 41 SB & CTH E)	2.000 EACH	_____.	_____.
0724	SPV.0060 Special 0610. Salvaging 12" Steel Pull Box Rims & Covers (IH 41 NB & CTH E)	2.000 EACH	_____.	_____.
0726	SPV.0060 Special 0611. Salvaging 12" Steel Pull Box Rims & Covers (IH 41 SB & CTH E)	4.000 EACH	_____.	_____.
0728	SPV.0060 Special 0612. Salvaging 24" Steel Pull Box Rims & Covers (IH NB & CTH E)	2.000 EACH	_____.	_____.
0730	SPV.0060 Special 0613. Salvaging 24" Steel Pull Box Rims & Covers (IH 41 SB & CTH E)	3.000 EACH	_____.	_____.
0732	SPV.0060 Special 0614. Salvaging 24" Non-conductive Pull Box Rims & Covers (IH 41 NB & CTH E)	9.000 EACH	_____.	_____.
0734	SPV.0060 Special 0615. Salvaging 24" Non-conductive Pull Box Rims & Covers (IH 41 SB & CTH E)	7.000 EACH	_____.	_____.
0736	SPV.0060 Special 0701. Salvaging Ramp Gate System	4.000 EACH	_____.	_____.
0738	SPV.0060 Special 1000. Concrete Bases Type 1 Special	4.000 EACH	_____.	_____.
0740	SPV.0060 Special 1005. Concrete Bases Type 2 Special	2.000 EACH	_____.	_____.
0742	SPV.0060 Special 1010. Radar Vehicle Detection System Special	1.000 EACH	_____.	_____.
0744	SPV.0060 Special 1015. Remove and Reinstall Emergency Vehicle Preemption System	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 27 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0746	SPV.0060 Special 1020. Remove and Reinstall Radio Communications System	1.000 EACH	_____.	_____.
0748	SPV.0060 Special 1025. Temporary Vehicle Detection System STH 47 & Ridgeview	1.000 EACH	_____.	_____.
0750	SPV.0060 Special 1030. Remove and Reinstall Traffic Signal Standard	1.000 EACH	_____.	_____.
0752	SPV.0060 Special 1200. Reconstructing Sanitary Manhole	1.000 EACH	_____.	_____.
0754	SPV.0060 Special 1202. Adjusting Sanitary Manhole	9.000 EACH	_____.	_____.
0756	SPV.0060 Special 5000. Accent Boulder	48.000 EACH	_____.	_____.
0758	SPV.0060 Special 5010. Perennials, Junegrass, Container, #1	236.000 EACH	_____.	_____.
0760	SPV.0060 Special 5020. Perennials, Prairie Dropseed, (Tara), Container, #1	240.000 EACH	_____.	_____.
0762	SPV.0060 Special 5030. Perennials, Switch Grass, (Shenendoah), Container, #1	27.000 EACH	_____.	_____.
0764	SPV.0060 Special 5040. Perennials, Allium, (Summer Beauty), Container, #1	140.000 EACH	_____.	_____.
0766	SPV.0060 Special 5050. Perennials, Aster, (October Skies), Container, #1	30.000 EACH	_____.	_____.
0768	SPV.0060 Special 5060. Perennials, Black-Eyed Susan, (American Gold Rush), Container, #1	131.000 EACH	_____.	_____.
0770	SPV.0060 Special 5070. Perennials, Butterfly Milkweed, Container, #1	113.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 28 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0772	SPV.0060 Special 5080. Perennials, Dwarf False Indigo, Container, #1	29.000 EACH	_____.	_____.
0774	SPV.0060 Special 5090. Perennials, Spiked Gayfeather, (Kobold), Container, #1	37.000 EACH	_____.	_____.
0776	SPV.0075 Special 0100. Street Sweeping	66.000 HRS	_____.	_____.
0778	SPV.0085 Special 0100. Low Maintenance Seed Mix	424.000 LB	_____.	_____.
0780	SPV.0090 Special 0100. Removal and Salvage of High-Tension Cable Guard and Posts	4,112.000 LF	_____.	_____.
0782	SPV.0090 Special 0115. Concrete Barrier Type S42 Special	2,655.000 LF	_____.	_____.
0784	SPV.0090 Special 0800. Fence Chain Link Polymer Coated 6-FT B-44-325	72.000 LF	_____.	_____.
0786	SPV.0090 Special 0801. Fence Chain Link Polymer Coated 6-FT B-44-324	72.000 LF	_____.	_____.
0788	SPV.0090 Special 0802. Removing Existing Steel Piling	900.000 LF	_____.	_____.
0790	SPV.0090 Special 0900. Fence Chain Link Polymer-Coated 6-FT R-44-40	160.000 LF	_____.	_____.
0792	SPV.0090 Special 0901. Fence Chain Link Polymer-Coated 6-FT R-44-41	166.000 LF	_____.	_____.
0794	SPV.0090 Special 1000. Concrete Curb & Gutter 24-Inch Type D	4.000 LF	_____.	_____.
0796	SPV.0090 Special 1005. Cable Traffic Signal 16-14 AWG	1,469.000 LF	_____.	_____.



Proposal Schedule of Items

Page 29 of 29

Proposal ID: 20250211026 Project(s): 1130-65-76

Federal ID(s): WISC 2025323

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0798	SPV.0090 Special 1010. Tray Cable for Street Lighting 3 Conductor 12 AWG	1,623.000 LF	_____.	_____.
0800	SPV.0090 Special 5000. Metal Edging	994.000 LF	_____.	_____.
0802	SPV.0165 Special 0100. Wall Modular Block Gravity Landscape (Station 21CAP+25 LT)	194.000 SF	_____.	_____.
0804	SPV.0165 Special 0800. Longitudinal Grooving Bridge Deck	24,496.000 SF	_____.	_____.
0806	SPV.0165 Special 0900. Wall Concrete Panel Mechanically Stabilized Earth R-44-40	4,470.000 SF	_____.	_____.
0808	SPV.0165 Special 0901. Wall Concrete Panel Mechanically Stabilized Earth R-44-41	4,805.000 SF	_____.	_____.
0810	SPV.0195 Special 0100. HMA Longitudinal Joint Repair	100.000 TON	_____.	_____.
0812	SPV.0195 Special 0105. HMA Transverse Joint Repair	50.000 TON	_____.	_____.
0814	SPV.0195 Special 5010. Stone Cobbles	157.000 TON	_____.	_____.
0816	SPV.0060 Special 2000. Inlet Markers	7.000 EACH	_____.	_____.
0818	SPV.0060 Special 3000. Decorative Silhouette	2.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.