

# **Wisconsin Department of Transportation**

January 24, 2025

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

#### **NOTICE TO ALL CONTRACTORS:**

Proposal #48: 7050-00-72 7050-00-73

Neillsville - Thorp Neillsville - Thorp

Hunt Street to STH 29 E Rock Creek Bridge to Hunt

STH 73 Street Clark County STH 73

**Clark County** 

## Letting of February 11, 2025

This is Addendum No. 01, which provides for the following:

### **Special Provisions:**

Revised Special Provisions						
Article No.	Description					
3	Prosecution and Progress					
4	Traffic					

Added Special Provisions					
Article No.	Description				
39	Notice to Contractor – Local Utilities				
40	Notice to Contractor – Contamination Beyond Construction Limits				

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

## ADDENDUM NO. 01 7050-00-72/73 January 9, 2025

#### **Special Provisions**

#### 3. Prosecution and Progress.

Replace paragraph one under section titled with the following:

Within the project limits of project 7050-00-73, all work shall be completed by 11:59 PM on Friday, August 29, 2025. If the contractor fails to complete the work specified in the contract for project 7050-00-73 before 12:00 AM on August 30, 2025, the department will assess the contractor \$2,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM on August 30, 2025. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

#### 4. Traffic.

Add the following paragraph:

#### **Private and Commercial Access**

Access to businesses and residences shall be maintained throughout the project. Access may not be closed for work without prior approval from the engineer.

#### 39. Notice to Contractor – Local Utilities.

Lighting systems owned by the City of Greenwood are located within the 7050-00-73 project limits. No impacts are anticipated.

### 40. Notice to Contractor – Contamination Beyond Construction Limits.

The department completed testing for soil and ground water contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present at the following sites:

- 1. Station 91+20 to Station 92+45 from 60 feet LT of centerline to 40 feet RT of centerline.
- 2. Station 97+17 to Station 102+62 from 415 feet LT of centerline to 90 feet RT of centerline.
- 3. Station 102+30 to Station 104+75 from 12 feet LT of centerline to 70 feet RT of centerline.
- 4. Station 105+12 to Station 106+80 from 2 feet RT of centerline to 65 feet RT of centerline.
- Station 114+25 to Station 114+66 from 60 feet LT of centerline to 17 feet LT of centerline.
- 6. Station 116+19 to Station 116+41 from 38 feet LT of centerline to 16 feet LT of centerline.
- 7. Station 116+68 to Station 117+12 from 8 feet LT of centerline to 65 feet RT of centerline.
- 8. Station 120+07 to Station 120+78 from 55 feet LT of centerline to 40 feet RT of centerline.
- 9. Station 127+26 to Station 128+68 from 10 feet RT of centerline to 160 feet RT of centerline.
- 10. Station 250+00 to Station 251+00 from 15 feet RT of centerline to 50 feet RT of centerline.
- 11. Station 312+00 to Station 322+00 from 15 feet LT & RT of centerline to 50 feet LT & RT of centerline.
- 12. Station 421+00 to Station 422+50 from 15 feet LT of centerline to 80 feet LT of centerline.

The contaminated soils at the above sites are expected to be beyond the excavation limits necessary to complete the work under this project. Control construction operations at these locations to ensure that they do not extend beyond the excavation limits indicated in the plans. If contaminated soils are encountered at these sites or elsewhere on the project during excavation, terminate excavation in the area and notify the engineer.

The Hazardous Materials Report is available by contacting: Dan Rambo, (715) 836-5181. stp-107-100 (20230113)

**END OF ADDENDUM**