



Wisconsin Department of Transportation

March 4, 2025

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #13: 2050-08-71, WISC 2025370
C Oak Creek W Rawson Avenue
S. 13th Street to S Howell avenue
CTH BB
Milwaukee County

Letting of March 11, 2025

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

Project ID 2050-08-71

March 4, 2025

Special Provisions

6. Utilities.

*Replace entire section titled **WE Energies – Gas** with the following:*

WE Energies-Gas has buried gas main and service facilities throughout the project area. Adjustments to these underground facilities will be completed by WE Energies-Gas prior to and during construction operations under this contract. Gas main and services not explicitly identified as being relocated have been deemed to be not in conflict and will remain in place as is. Work prior to construction began in September 2024 and is expected to take 80 working days. Work during to construction is anticipated to begin after existing pavement has been removed and is expected to take 10 working days to complete.

It is imperative that the highway contractor contact We Energies before removing any gas facilities, to verify that they have been discontinued and carry no natural gas.

Contact 1-800-261-5325 for gas emergencies and to identify if gas facilities are live and for gas valve box adjustments.

WE Energies- Gas has identified that the existing gas mains potentially contain asbestos Coal-Tar Wrap. Asbestos pipe removal will take place from station 14+00 to station 55+40. Facilities to be removed are as listed below:

Prior to Construction				
	<u>Station</u>	<u>to</u>	<u>Station</u>	<u>Offset</u>
1.	15+56		15+76	4' RT
2.	17+33		17+53	7' RT
3.	19+76		19+96	14' RT
4.	27+90		28+10	34' RT
5.	42+58		42+78	5' RT
6.	45+75		45+95	5' RT
7.	48+33		48+53	5' RT

During Construction, After Pavement Removal				
	<u>Station</u>	<u>to</u>	<u>Station</u>	<u>Offset</u>
1.	29+52		34+78	38' RT

Facilities that were determined to have sufficient clearance from the proposed storm sewer and remained in place are as follows:

Remain In-Place				
	<u>Station</u>	<u>to</u>	<u>Station</u>	<u>Offset</u>
1.	23+38		23+58	25' RT
2.	25+90		26+10	30' RT
3.	35+86		36+06	30' RT
4.	38+88		39+10	15' RT

Contact Kelly Kempken at 414-944-5571, in advance to coordinate any excavation within 5 feet of their facilities. Notify We Energies before the work site is anticipated to be available for asbestos pipe removal.

END OF ADDENDUM

