



## Wisconsin Department of Transportation

---

March 7, 2025

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631

Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #28: 4987-02-75, WISC 2025384**  
**C Green Bay, Country Club Road**  
**Mason St Frontage Road to Indian Hill**  
**Loc Str**  
**Brown County**

### Letting of March 11, 2025

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

| Revised Special Provisions |             |
|----------------------------|-------------|
| Article No.                | Description |
| 37                         | Storm Sewer |

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**4987-02-75**

**March 7, 2025**

**Special Provisions**

**37. Storm Sewer.**

*Replace the entire article language with the following:*

*Supplement standard spec 608.2. as follows:*

Provide tracer wire and access boxes conforming to 417.2 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

Pipe handling holes are permitted only on reinforced concrete storm sewer pipe 21 inches or larger in diameter. One handling hole is permitted on straight lengths of pipe, less than 48 inches in diameter, and two on pipe 48 inches and larger in diameter. After the pipe has been laid, the handling holes shall be promptly plugged with mortar and an approved manufactured plug.

*Replace standard spec 608.2.2.2 (1) with the following:*

Furnish foundation backfill material conforming to 404.2 of City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

*Replace standard spec 608.2.2.3 (1) with the following:*

Furnish trench backfill material conforming to 404.2 of City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

*Replace standard spec 608.3 as follows:*

Construction shall be conforming to the plans, with 404.3 and 415.3 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

Testing shall be conforming to the plans, with 402.3 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

Tracer wire shall be conforming to the plans, with 417.3 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

Surface and Trench Water Control shall be conforming to the plans, with 407.3 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

Televise all new storm sewer pipes and new inlet leads conforming to 403.3 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

*Replace standard spec 608.5.1(3) as follows:*

Additional excavation including undercut to paid for according to 404.4 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition.

*Replace standard spec 608.5.2 as follows:*

Payment is full compensation according to 404.4, 415.4 and 417.4 of the City of Green Bay Standard Specifications & Construction Standards for Public Works Construction, 2024 Edition; for surface and trench water control; for testing and televising of pipe.

**END OF ADDENDUM**