



Wisconsin Department of Transportation

March 4, 2025

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #34: 6991-00-74
Plover - Waupaca
Portage Co Line to Foxfire Drive
STH 54
Waupaca County

Letting of March 11, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
23	Reestablish Section Corner Monuments, SPV.0060.01

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
42	Miscellaneous Quantities (updated monument material)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

6991-00-74

March 4, 2025

Special Provisions

23. Reestablish Section Corner Monuments, Item SPV.0060.01.

Replace the entire article language with the following:

A Description

This special provision describes reestablishing section corner monuments.

B Materials

Provide one of the following survey monuments for each location.

For placement in asphalt or concrete pavement furnish a magnetic survey nail with center point a minimum of 2 ½-inches long for.

For placement in locations outside the pavement area furnish a ¾-inch rebar or 1-inch OD (¾-inch ID) iron pipe with plastic survey marker caps with lettering that reads "Witness Monument".

C Construction

Perform work under the direction and control of a professional land surveyor registered in the state of Wisconsin, following Wisconsin Administrative Code A-E 7.

Preserve existing USPLSS monuments and witness monuments (ties) within the construction limits in their original position until monuments are verified and sufficiently tied off.

C.2 Pre-Construction

Notify the county surveyor and the NCR survey coordinator at least 30 days prior to construction operations starting about all USPLSS monuments within the construction limits that might be disturbed.

Obtain the existing USPLSS Monument Record from the county surveyor. Verify existing monuments and witness monuments are in place and undisturbed.

Replace witness monuments that are missing or that could be disturbed by construction operations. Locate new witness monuments near the USPLSS monument but outside the construction limits.

Temporarily mark the location of all witness monuments to protect them during construction.

C.3 Removals

Remove or abandon existing monuments and monument covers that interfere with construction operations.

C.4 Post-Construction

Verify the location of monuments and witness monuments when construction operations are complete.

Set new monuments and witness monuments where necessary. Recess magnetic survey nails ¼" below the pavement surface for monuments located in pavement. Use iron pipe, or ¾" rebar for monuments not in pavement and for witness monuments. Locate new witness monuments near the USPLSS monument and outside the roadbed. Install plastic caps on witness monuments.

Install marker posts next to all witness monuments if required and supplied by the county surveyor.

Omit setting monuments in the pavement if approved by the department's regional survey coordinator and county surveyor due to traffic or safety concerns.

Submit a monument record.

C.5 Monument Records

Submit a monument record in accordance with [CMM 785.3](#) on department form [DT1291](#), or equivalent form, to the county surveyor at locations where monuments were set. Provide a copy to the engineer and regional survey coordinator.

D Measurement

The department will measure Reestablish Section Corner Monuments by each individual section corner monument acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Reestablish Section Corner Monuments	Each

Payment for the Verify and Reset Public Land Survey Monuments bid item is full compensation for providing all materials; for coordinating with county surveyors; for obtaining existing monument records; for verifying the existing location of monuments and witness monuments; for removing or abandoning existing monuments and monument covers; for resetting monuments; for setting or resetting temporary and permanent witness monuments; and for submitting monument records.

ncr-621-010 (20250224)

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 42.

END OF ADDENDUM

CONCRETE CURB AND GUTTER

STATION TO STATION	DIR	LOCATION	601.0205 CONCRETE GUTTER 24-INCH	601.0411 CONCRETE CURB & GUTTER 30-INCH TYPE D	601.0557 CONCRETE CURB & GUTTER 6-INCH SLOPED 36-INCH TYPE D
			LF	LF	LF
CATEGORY 0010					
254+30 - 254+40	R/L	STH 54	10	---	---
259+15 - 259+25	R/L	STH 54	10	---	---
259+15 - 259+25	LT	STH 54	10	---	---
FOXFIRE SPLITTER ISLAND	RT	STH 54	---	90	---
FOXFIRE CURB RAMP	RT	STH 54	---	---	14
260+04 - 260+20	LT	STH 54	---	---	16
260+62 - 260+76	LT	STH 54	---	---	14
261+10 - 261+24	LT	STH 54	---	---	14
CATEGORY TOTALS			30	90	58
CATEGORY 0020					
CTH 0 NW	LT	STH 54/CTH 0 WIDENING	---	---	60
CTH 0 SW	RT	STH 54/CTH 0 WIDENING	---	---	90
CTH 0 NE	LT	STH 54/CTH 0 WIDENING	---	---	90
CTH 0 SE	RT	STH 54/CTH 0 WIDENING	---	---	60
CATEGORY TOTALS			0	0	300
PROJECT TOTALS			30	90	358

CONCRETE SLIDEWALK

CATEGORY	LOCATION	621. 0100		SPV. 0060. 01
		LANDMARK REFERENCE MONUMENTS	EACH	
	68+48	STH 54	---	1
	94+80	STH 54	---	1
	121+30	STH 54	4	
	147+25	STH 54	---	1
	173+73	STH 54	---	1
	199+71	STH 54	---	1
	225+77	STH 54	---	1
	252+64	STH 54	---	1
	260+12	STH 54	---	

Addendum No. 01
ID 6991-00-74
Revised Sheet 42
March 4, 2025

* SEE BASE COURSE TABLE FOR ADDITIONAL QUANTITIES

CULVERT PIPES

PROJECT NO: 6991-00-74	HWY: STH 54	COUNTY: WAUPACA	MISCELLANEOUS QUANTITIES	SHEET	42	E
ORIGINATOR: WESTWOOD FILE NAME: N:\3001648.00\CIVIL_3D\dwg\6991-00-74\0201.mxd			REV. DATE: March 3, 2025 ORIG. DATE: August 17, 2015	PRINT DATE: March 3, 2025		