



March 27, 2025

Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #09: 1090-03-78
IH 41 Airport Freeway - Noise Barrier
76th St to STH 36
IH 41
Milwaukee County

Letting of April 8, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
7	Utilities

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
201.0105	Clearing	STA	0	74	74

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
12	Removal Plans (Added note, "6. Large Diameter trees have previously been cut down within the project limits but will need to be removed as part of this project. Removing debris, brush and downed trees is incidental to grubbing.")
65	Miscellaneous Quantities (Added Bid Item 201.0105 Clearing)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1090-03-78

March 27, 2025

Special Provisions

3. Prosecution and Progress.

*Replace paragraph four under section titled **Protection of Endangered Bats (Tree Clearing)** with the following:*

The department has contracted with others and will perform the following operations after October 31 and prior to April 1:

- Cutting trees.

*Add the following to the end of the section titled **Protection of Endangered Bats (Tree Clearing)**:*

The contractor is responsible for removing the cut trees within the right-of-way. Tree removal is incidental to the grubbing item.

7. Utilities.

*Replace entire section titled **Spectrum** with the following:*

Spectrum has existing underground fiber optic and overhead communications facilities throughout the project limits. The Spectrum overhead line crossing the freeway and crossing the noise barrier at approximately Station 169+57, 130' RT will be relocated during the project as part of relocation work being done by WE Energies Electric. Spectrum anticipates beginning this work on June 9, 2025, and will work alongside of WE Energies Electric to complete this work.

Schedule of Items

Attached, dated March 27, 2025, are the revised Schedule of Items Page 7.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 12 and 65.

END OF ADDENDUM

GENERAL NOTES:

- 1) ALL ITEMS ASSOCIATED WITH SIGN REMOVALS ARE SHOWN IN THE SIGNING PLANS.
- 2) CLEARING DONE BY OTHERS.
- 3) FOR ADDITIONAL UTILITY INFORMATION SEE EXISTING UTILITY PLAN.
- 4) THE LOCATION OF THE EXISTING UTILITY INSTALLATIONS AS SHOWN ON THE PLANS IS APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN, INCLUDING BUILDING SERVICES AND LATERALS.
- 5) EXISTING FENCE TO REMAIN IN PLACE UNTIL ADJACENT NOISE BARRIER CONSTRUCTION IS COMPLETED EXCEPT AT LOCATIONS NOTED WHERE EXISTING FENCE CONFLICTS WITH PROPOSED NOISE BARRIER ALIGNMENT AS NOTED ON THE REMOVAL PLAN SHEETS. INSTALL SAFETY FENCE WHERE EXISTING FENCE IS REMOVED PRIOR TO WALL CONSTRUCTION AS SHOWN ON THE PLAN DETAIL SHEETS.
- 6) LARGE DIAMETER TREES HAVE PREVIOUSLY BEEN CUT DOWN WITHIN THE PROJECT LIMITS BUT WILL NEED TO BE REMOVED AS PART OF THIS PROJECT. REMOVING DEBRIS, BRUSH AND DOWNED TREES IS INCIDENTAL TO GRUBBING.

REMOVAL LEGEND
CLEARING (WORK DONE BY OTHERS) AND GRUBBING
REMOVING FENCE



Addendum NO. 01
ID 1090-03-78
Revised Sheet 12
March 27, 2025

PROJECT NO: 1090-03-78

HWY: IH 41

COUNTY: MILWAUKEE

REMOVAL PLANS

SHEET 12

E

FILE NAME: C:\VW\WORKDIR\JACOBS-US-VA-PW-02\00193572\10900308-02101-RM.DWG

LAYOUT NAME - 00

PLOT DATE: 3/26/2025 3:49 PM

PLOT BY: GIBSON-MURPHY, MIKI

PLOT NAME: #####

WBSOT/CADDS SHEET 42

CLEARING & GRUBBING

CATEGORY	STAGE	ROADWAY	STATION	TO	STATION	OFFSET	201.0105		201.0205		COMMENTS
							STA	STA	STA	STA	
1000	1	N-40-107/108	125'EW+61	-	149'EW+05	RT	25		25		
			149'EW+05	-	175'EW+35	RT	25		25		
	STAGE 1 SUBTOTAL						50		50		
	2	N-40-109	203'EW+52	-	226'EW+79	LT	24		24		
STAGE 2 SUBTOTAL						24		24			
TOTAL						74		74			

REMOVING CURB & GUTTER

CATEGORY	STAGE	ROADWAY	204.0150 REMOVING CURB & GUTTER		COMMENTS
			LF		
1000	1	<u>N-40-107/108</u>	UNDISTRIBUTED	200	REMOVE CURB & GUTTER IF DAMAGED DURING CONSTRUCTION
		STAGE 1 SUBTOTAL			200
	2	<u>N-40-109</u>	UNDISTRIBUTED	100	REMOVE CURB & GUTTER IF DAMAGED DURING CONSTRUCTION
STAGE 2 SUBTOTAL			100		
TOTAL				300	

Addendum NO. 01
ID 1090-03-78
Revised Sheet 65
March 27, 2025



Proposal Schedule of Items

Page 7 of 7

Proposal ID: 20250408009 Project(s): 1090-03-78

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0186	SPV.0075 Special 01. Pavement Cleanup Project 1090-03-78	120.000 HRS	_____.	_____.
0188	201.0105 Clearing	74.000 STA	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

