



Wisconsin Department of Transportation

March 18, 2025

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #19: 9225-07-60, WISC 2025121
Chelsea - Spirit
Taylor County Line to STH 86
STH 102
Price County**

Letting of April 8, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
17	Reestablish Section Corner Monuments, Item SPV.0060.01

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
PROJECT ID 9225-07-60
March 17, 2025

Special Provisions

17. Reestablish Section Corner Monuments, Item SPV.0060.01.

Replace entire article language with the following:

A Description

This special provision describes reestablishing section corner monuments.

B Materials

Provide one of the following survey monuments for each location.

For placement in asphalt or concrete pavement furnish a magnetic survey nail with center point a minimum of 2 ½-inches long.

For placement in locations outside the pavement area furnish a ¾-inch rebar or 1-inch OD (¾-inch ID) iron pipe with plastic survey marker caps with lettering that reads "Witness Monument".

C Construction

Perform work under the direction and control of a professional land surveyor registered in the state of Wisconsin, following Wisconsin Administrative Code A-E 7.

Preserve existing USPLSS monuments and witness monuments (ties) within the construction limits in their original position until monuments are verified and sufficiently tied off.

C.2 Pre-Construction

Notify the county surveyor and the NCR survey coordinator at least 30 days prior to construction operations starting about all USPLSS monuments within the construction limits that might be disturbed.

Obtain the existing USPLSS Monument Record from the county surveyor. Verify existing monuments and witness monuments are in place and undisturbed.

Replace witness monuments that are missing or that could be disturbed by construction operations. Locate new witness monuments near the USPLSS monument but outside the construction limits.

Temporarily mark the location of all witness monuments to protect them during construction.

C.3 Removals

Remove or abandon existing monuments and monument covers that interfere with construction operations. If needed, backfill where monument was removed using materials and requirements of surface surrounding the existing monument.

C.4 Post-Construction

Verify the location of monuments and witness monuments when construction operations are complete.

Set new monuments and witness monuments where necessary. Recess magnetic survey nails ¼" below the pavement surface for monuments located in pavement. Use iron pipe, or ¾" rebar for monuments not in pavement and for witness monuments. Locate new witness monuments near the USPLSS monument and outside the roadbed. Install plastic caps on witness monuments.

Install marker posts next to all witness monuments if required and supplied by the county surveyor.

Omit setting monuments in the pavement if approved by the department's regional survey coordinator and county surveyor due to traffic or safety concerns.

Submit a monument record in accordance with CMM 785.3 on department form DT1291, or equivalent form, to the county surveyor at locations where monuments were set. Provide a copy to the engineer and regional survey coordinator.

D Measurement

The department will measure Reestablish Section Corner Monuments by each individual section corner monument acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Reestablish Section Corner Monuments	Each

Payment is full compensation for providing survey monuments; all excavation, backfilling, and drilling necessary to place section corner monuments; furnishing a professional land surveyor and all survey work; and preparing and delivering monument records.

ncr-621-010 (20250312)

END OF ADDENDUM

