



Wisconsin Department of Transportation

June 3, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #01: 1200-02-63
Truck Scale Pavement Repair
Dickeyville SWEF – USH 51
STH 11
Grant County

1202-00-75, WISC 2025515
Dubuque - Dickeyville
Mississippi River to CTH HH
USH 61
Grant County

Letting of June 10, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
33	Reprocess and Relay, Item SPV.0180.02

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0180.02	Reprocess and Relay	SY	0	41,961	41,961

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
330.0100	Mill and Relay	SY	41,961	-41,961	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
143	Miscellaneous Quantities (Item change 330.0100 to SPV.0180.02)
144	Miscellaneous Quantities (Item change 330.0100 to SPV.0180.02)
145	Miscellaneous Quantities (Item change 330.0100 to SPV.0180.02)
146	Miscellaneous Quantities (Item change 330.0100 to SPV.0180.02)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
1200-02-63/1202-00-75
June 3, 2025

Special Provisions

33. Reprocess and Relay, Item SPV.0180.02.

A Description

This special provision describes in-place reprocessing of the existing asphaltic pavement full depth utilizing milling or pulverizing and relaying the material to construct a new base. Conform to standard spec 325 for pulverizing and relaying or 330 for milling and relaying and as modified in this special provision.

B (Vacant)

C Construction

Replace standard spec 325.3(1) with the following:

Pulverize the existing asphaltic pavement full depth until 97% or more will pass the 2-inch sieve. Limit incorporation of existing underlying base material to extent possible and mix with the pulverized asphaltic pavement. Add water to the pulverizing head during grinding operations to cool teeth while maintaining the depth showed in the plans. Windrow material as construction operations dictate.

Replace standard spec 330.3(1) with the following:

Mill the existing asphaltic pavement full depth and until 100 percent will pass the 1 1/2-inch sieve. Limit incorporation of existing underlying base material to extent possible and mix with the milled asphaltic pavement. Windrow material as construction operations dictate.

D Measurement

The department will measure Reprocess and Relay by the square yard acceptably completed, measured using the centerline length and width of the of completed base, but limited to the width the plans show or the engineer directs.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.###	Reprocess and Relay	SY

Replace standard spec 325.5(3) with the following:

Payment also includes water for compaction, teeth cooling, and dust control except, if the contract contains the Water bid item, the department will pay separately for compaction, teeth cooling, and dust control water under 624.5.

swr-325-001 (20250528)

Schedule of Items

Attached, dated June 3, 2025, are the revised Schedule of Items Pages 1 – 13.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 143-146.

END OF ADDENDUM

ASPHALT PAVEMENT CONTINUED

SPV 0180.02
(REPROCESS
AND RELAY)
SHOULDERS

CATEGORY	STATION	TO	STATION	LOCATION	SY	204.0105 REMOVING CONCRETE PAVEMENT BUTT JOINTS	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	204.0120 REMOVING ASPHALTIC SURFACE MILLING	211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS	SPV 0180.02 (REPROCESS AND RELAY) SHOULDERS	415.6000.S POUT AND SEAL	TACK COAT GAL	450.5224 LT 58-28 S	450.5224 MT 58-28 S	450.5224 HT 58-28 H	460.7424 SMA 58-28 V	REMARKS
0010	435+64	-	471+32	Mainline RT Shoulder	-	-	-	2379	-	-	3568	-	533	-	-	-	-
0010	459+50	-	460+28	TRAFFIC CROSSING MEDIAN	-	-	-	313	-	-	173	16	70	-	-	-	-
0010	460+28	-	461+28	Mainline LT Shoulder	-	-	-	34	-	-	100	-	8	-	-	-	-
0010	461+28	-	464+82	TRAFFIC CROSSING MEDIAN	-	-	-	724	-	-	446	37	163	-	-	-	-
0010	464+82	-	472+92	Mainline LT Shoulder	-	-	-	270	-	-	810	-	61	-	-	-	-
0010	471+32	-	474+38	TURNLANE/SIDE ROAD RT	-	-	-	556	-	-	306	30	131	-	-	-	-
0010	474+38	-	497+31	Mainline RT Shoulder	-	-	-	7	-	-	2293	-	343	-	-	-	-
0010	472+92	-	474+06	TRAFFIC CROSSING MEDIAN	-	-	-	657	-	-	451	33	148	-	-	-	-
0010	474+06	-	481+11	Mainline LT Shoulder	-	-	-	235	-	-	705	-	53	-	-	-	-
0010	481+11	-	481+82	TRAFFIC CROSSING MEDIAN	-	-	-	286	-	-	157	15	64	-	-	-	-
0010	481+82	-	497+31	Mainline LT Shoulder	-	-	-	517	-	-	1549	-	116	-	-	-	-
0010	100+03A	-	100+63A	Mainline RT Shoulder	-	-	-	10	-	-	-	-	3				

Addendum No. 01
ID 1202-00-75
Revised Sheet 145
June 3, 2025

ASPHALT PAVEMENT CONTINUED

CATEGORY	STATION	TO	STATION	LOCATION	SY	204.0105 REMOVING CONCRETE PAVEMENT BUTT JOINTS	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	204.0120 REMOVING ASPHALTIC SURFACE MILLING	211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDER	SPV.0180.02 SPECIAL (REPROCESS AND RELAY)	LF	TACK COAT GAL	455.0605 HMA PAVEMENT 4 HMA PAVEMENT 4 HMA PAVEMENT 4 MT 58-28 S HT 58-28 S	460.5224	460.6224	460.7424	460.8624	REMARKS
0010	363+77A	-	373+05A	Mainline LT Shoulder	-	-	7	612	-	928	-	-	-	139	-	-	-	-
0010	375+00A	-	410+47A	Mainline LT Shoulder	-	-	14	2351	-	3547	-	-	-	530	-	-	-	-
0010	410+47A	-	421+30A	Mainline RT Shoulder	-	-	8	1175	-	3547	-	-	-	265	-	-	-	-
0010	412+56A	-	421+30A	Mainline LT Shoulder	-	-	7	569	-	864	-	-	-	130	-	-	-	-
0010	412+56A	-	458+80A	Mainline RT Shoulder	-	-	4	1534	-	4614	-	-	-	345	-	-	-	-
0010	421+30A	-	423+22A	Mainline GORE	-	-	-	-	188	-	-	-	-	37	-	-	-	-
0010	429+72A	-	462+89A	Mainline LT Shoulder	-	-	-	2212	-	3317	-	-	-	496	-	-	-	-
0010	459+75A	-	463+22A	Mainline RT Shoulder	-	-	32	116	-	347	-	-	-	26	-	-	-	-
0010	462+89A	-	465+80A	TURNLANE SIDE ROAD LT	-	-	-	565	-	291	-	30	-	134	-	-	-	-
0010	464+14A	-	473+12A	Mainline RT Shoulder	-	-	-	300	-	898	-	-	-	68	-	-	-	-
0010	465+80A	-	486+55A	Mainline LT Shoulder	-	-	7	2043	-	3075	-	-	-	460	-	-	-	



Proposal Schedule of Items

Page 1 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0205 Grubbing	3.000 STA	_____.	_____.
0004	203.0100 Removing Small Pipe Culverts	5.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	28,278.000 SY	_____.	_____.
0008	204.0105 Removing Concrete Pavement Butt Joints	4,793.000 SY	_____.	_____.
0010	204.0110 Removing Asphaltic Surface	508.000 SY	_____.	_____.
0012	204.0115 Removing Asphaltic Surface Butt Joints	3,144.000 SY	_____.	_____.
0014	204.0120 Removing Asphaltic Surface Milling	85,544.000 SY	_____.	_____.
0016	204.0150 Removing Curb & Gutter	855.000 LF	_____.	_____.
0018	204.0155 Removing Concrete Sidewalk	212.000 SY	_____.	_____.
0020	204.0157 Removing Concrete Barrier	1,257.000 LF	_____.	_____.
0022	204.0165 Removing Guardrail	12,836.000 LF	_____.	_____.
0024	204.0190 Removing Surface Drains	13.000 EACH	_____.	_____.
0026	205.0100 Excavation Common	4,359.000 CY	_____.	_____.
0028	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 1202-00-75	1.000 EACH	_____.	_____.
0030	211.0400 Prepare Foundation for Asphaltic Shoulders	180.000 STA	_____.	_____.



Proposal Schedule of Items

Page 2 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	213.0100 Finishing Roadway (project) 01. 1202-00-75	1.000 EACH	_____.	_____.
0034	305.0110 Base Aggregate Dense 3/4-Inch	14,519.000 TON	_____.	_____.
0036	305.0120 Base Aggregate Dense 1 1/4-Inch	6,616.000 TON	_____.	_____.
0040	390.0100 Removing Pavement for Base Patching	980.000 CY	_____.	_____.
0042	390.0305 Base Patching Concrete HES	980.000 CY	_____.	_____.
0044	405.0100 Coloring Concrete WisDOT Red	14.000 CY	_____.	_____.
0046	415.0080 Concrete Pavement 8-Inch	23,784.000 SY	_____.	_____.
0048	415.0090 Concrete Pavement 9-Inch	4,172.000 SY	_____.	_____.
0050	415.0100 Concrete Pavement 10-Inch	230.000 SY	_____.	_____.
0052	415.0110 Concrete Pavement 11-Inch	123.000 SY	_____.	_____.
0054	415.0410 Concrete Pavement Approach Slab	552.000 SY	_____.	_____.
0056	415.2010 Concrete Truck Apron 12-inch	40.000 SY	_____.	_____.
0058	415.6000.S Rout and Seal	106,943.000 LF	_____.	_____.
0060	416.0610 Drilled Tie Bars	5,431.000 EACH	_____.	_____.
0062	416.0620 Drilled Dowel Bars	7,741.000 EACH	_____.	_____.
0064	416.1710 Concrete Pavement Repair	5,897.000 SY	_____.	_____.



Proposal Schedule of Items

Page 3 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	416.1720 Concrete Pavement Replacement	1,077.000 SY	_____.	_____.
0068	455.0605 Tack Coat	17,075.000 GAL	_____.	_____.
0070	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0072	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	1.000 EACH	_____.	_____.
0074	460.0115.S HMA Pavement Test Strip Volumetrics	1.000 EACH	_____.	_____.
0076	460.0120.S HMA Pavement Test Strip Density	1.000 EACH	_____.	_____.
0078	460.2000 Incentive Density HMA Pavement	16,461.000 DOL	1.00000	16,461.00
0080	460.2005 Incentive Density PWL HMA Pavement	10,143.000 DOL	1.00000	10,143.00
0082	460.2007 Incentive Density HMA Pavement Longitudinal Joints	19,030.000 DOL	1.00000	19,030.00
0084	460.2010 Incentive Air Voids HMA Pavement	12,663.000 DOL	1.00000	12,663.00
0086	460.5224 HMA Pavement 4 LT 58-28 S	1,274.000 TON	_____.	_____.
0088	460.6224 HMA Pavement 4 MT 58-28 S	22,876.000 TON	_____.	_____.
0090	460.7424 HMA Pavement 4 HT 58-28 H	15,422.000 TON	_____.	_____.
0092	460.8624 HMA Pavement 4 SMA 58-28 V	12,447.000 TON	_____.	_____.
0094	460.9000.S Material Transfer Vehicle	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	465.0105 Asphaltic Surface	10.000 TON	_____.	_____.
0098	465.0120 Asphaltic Surface Driveways and Field Entrances	4.000 TON	_____.	_____.
0100	465.0125 Asphaltic Surface Temporary	64.000 TON	_____.	_____.
0102	465.0310 Asphaltic Curb	88.000 LF	_____.	_____.
0104	465.0315 Asphaltic Flumes	453.000 SY	_____.	_____.
0106	465.0510 Asphaltic Rumble Strips, Shoulder Divided Roadway	143,844.000 LF	_____.	_____.
0108	502.2000 Compression Joint Sealer Preformed Elastomeric (width) 01. 4-INCH	45.000 LF	_____.	_____.
0110	517.3001.S Structure Overcoating Cleaning and Priming (structure) 01. B-22-61	1.000 EACH	_____.	_____.
0112	517.4001.S Containment and Collection of Waste Materials (structure) 01. B-22-61	1.000 EACH	_____.	_____.
0114	517.6001.S Portable Decontamination Facility	1.000 EACH	_____.	_____.
0116	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	2.000 EACH	_____.	_____.
0118	521.1018 Apron Endwalls for Culvert Pipe Steel 18-Inch	1.000 EACH	_____.	_____.
0120	521.3118 Culvert Pipe Corrugated Steel 18-Inch	12.000 LF	_____.	_____.
0122	522.0118 Culvert Pipe Reinforced Concrete Class III 18-Inch	92.000 LF	_____.	_____.



Proposal Schedule of Items

Page 5 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	1.000 EACH	_____.	_____.
0126	530.0112 Culvert Pipe Corrugated Polyethylene 12-Inch	142.000 LF	_____.	_____.
0128	601.0115 Concrete Curb Type G	80.000 LF	_____.	_____.
0130	601.0120 Concrete Curb Type J	15.000 LF	_____.	_____.
0132	601.0409 Concrete Curb & Gutter 30-Inch Type A	10.000 LF	_____.	_____.
0134	601.0411 Concrete Curb & Gutter 30-Inch Type D	147.000 LF	_____.	_____.
0136	601.0413 Concrete Curb & Gutter 6-Inch Sloped 30-Inch Type G	316.000 LF	_____.	_____.
0138	601.0582 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type T	245.000 LF	_____.	_____.
0140	601.0600 Concrete Curb Pedestrian	72.000 LF	_____.	_____.
0142	602.0410 Concrete Sidewalk 5-Inch	1,530.000 SF	_____.	_____.
0144	602.0505 Curb Ramp Detectable Warning Field Yellow	96.000 SF	_____.	_____.
0146	602.3010 Concrete Surface Drains	81.700 CY	_____.	_____.
0148	603.1142 Concrete Barrier Type S42	1,232.000 LF	_____.	_____.
0150	603.3313 Concrete Barrier Transition Type NJ32DF to S36	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 6 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	603.3535 Concrete Barrier Transition Type S36 to S42	1.000 EACH	_____.	_____.
0154	603.8000 Concrete Barrier Temporary Precast Delivered	863.000 LF	_____.	_____.
0156	603.8125 Concrete Barrier Temporary Precast Installed	1,688.000 LF	_____.	_____.
0158	606.0200 Riprap Medium	15.000 CY	_____.	_____.
0160	611.0610 Inlet Covers Type BW	10.000 EACH	_____.	_____.
0162	611.0651 Inlet Covers Type S	2.000 EACH	_____.	_____.
0164	611.0654 Inlet Covers Type V	3.000 EACH	_____.	_____.
0166	611.3220 Inlets 2x2-FT	2.000 EACH	_____.	_____.
0168	611.3225 Inlets 2x2.5-FT	1.000 EACH	_____.	_____.
0170	611.8115 Adjusting Inlet Covers	5.000 EACH	_____.	_____.
0172	611.9710 Salvaged Inlet Covers	7.000 EACH	_____.	_____.
0174	614.0200 Steel Thrie Beam Structure Approach	82.400 LF	_____.	_____.
0176	614.0220 Steel Thrie Beam Bullnose Terminal	4.000 EACH	_____.	_____.
0178	614.0230 Steel Thrie Beam	325.000 LF	_____.	_____.
0180	614.0305 Steel Plate Beam Guard Class A	1,550.000 LF	_____.	_____.



Proposal Schedule of Items

Page 7 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0182	614.0345 Steel Plate Beam Guard Short Radius	68.750 LF	_____.	_____.
0184	614.0370 Steel Plate Beam Guard Energy Absorbing Terminal	5.000 EACH	_____.	_____.
0186	614.0390 Steel Plate Beam Guard Short Radius Terminal	1.000 EACH	_____.	_____.
0188	614.0800 Crash Cushions Permanent	1.000 EACH	_____.	_____.
0190	614.2300 MGS Guardrail 3	9,112.500 LF	_____.	_____.
0192	614.2500 MGS Thrie Beam Transition	433.400 LF	_____.	_____.
0194	614.2610 MGS Guardrail Terminal EAT	14.000 EACH	_____.	_____.
0196	614.2620 MGS Guardrail Terminal Type 2	11.000 EACH	_____.	_____.
0198	616.0700.S Fence Safety	300.000 LF	_____.	_____.
0200	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1202-00-75	1.000 EACH	_____.	_____.
0202	619.1000 Mobilization	1.000 EACH	_____.	_____.
0204	620.0100 Concrete Corrugated Median	417.000 SF	_____.	_____.
0206	620.0300 Concrete Median Sloped Nose	145.000 SF	_____.	_____.
0208	624.0100 Water	323.000 MGAL	_____.	_____.
0210	625.0500 Salvaged Topsoil	11,815.000 SY	_____.	_____.



Proposal Schedule of Items

Page 8 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0212	628.1504 Silt Fence	12,503.000 LF	_____.	_____.
0214	628.1520 Silt Fence Maintenance	12,503.000 LF	_____.	_____.
0216	628.1905 Mobilizations Erosion Control	5.000 EACH	_____.	_____.
0218	628.1910 Mobilizations Emergency Erosion Control	5.000 EACH	_____.	_____.
0220	628.2002 Erosion Mat Class I Type A	11,528.000 SY	_____.	_____.
0222	628.2006 Erosion Mat Urban Class I Type A	287.000 SY	_____.	_____.
0224	628.7005 Inlet Protection Type A	3.000 EACH	_____.	_____.
0226	628.7010 Inlet Protection Type B	14.000 EACH	_____.	_____.
0228	628.7015 Inlet Protection Type C	12.000 EACH	_____.	_____.
0230	628.7504 Temporary Ditch Checks	480.000 LF	_____.	_____.
0232	628.7555 Culvert Pipe Checks	13.000 EACH	_____.	_____.
0234	628.7570 Rock Bags	477.000 EACH	_____.	_____.
0236	629.0210 Fertilizer Type B	17.400 CWT	_____.	_____.
0238	630.0130 Seeding Mixture No. 30	900.100 LB	_____.	_____.
0240	630.0140 Seeding Mixture No. 40	30.100 LB	_____.	_____.
0242	630.0200 Seeding Temporary	560.200 LB	_____.	_____.



Proposal Schedule of Items

Page 9 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0244	630.0500 Seed Water	1,326.800 MGAL	_____.	_____.
0246	633.1000 Delineators Barrier Wall	12.000 EACH	_____.	_____.
0248	633.5200 Markers Culvert End	4.000 EACH	_____.	_____.
0250	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0252	643.0300 Traffic Control Drums	88,755.000 DAY	_____.	_____.
0254	643.0370.S Digital Speed Reduction System (DSRS)	356.000 DAY	_____.	_____.
0256	643.0420 Traffic Control Barricades Type III	5,077.000 DAY	_____.	_____.
0258	643.0500 Traffic Control Flexible Tubular Marker Posts	154.000 EACH	_____.	_____.
0260	643.0600 Traffic Control Flexible Tubular Marker Bases	154.000 EACH	_____.	_____.
0262	643.0705 Traffic Control Warning Lights Type A	10,216.000 DAY	_____.	_____.
0264	643.0715 Traffic Control Warning Lights Type C	24,465.000 DAY	_____.	_____.
0266	643.0800 Traffic Control Arrow Boards	263.000 DAY	_____.	_____.
0268	643.0900 Traffic Control Signs	26,639.000 DAY	_____.	_____.
0270	643.0910 Traffic Control Covering Signs Type I	5.000 EACH	_____.	_____.
0272	643.0920 Traffic Control Covering Signs Type II	54.000 EACH	_____.	_____



Proposal Schedule of Items

Page 10 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0274	643.1050 Traffic Control Signs PCMS	135.000 DAY	_____.	_____.
0276	643.3165 Temporary Marking Line Paint 6-Inch	34,772.000 LF	_____.	_____.
0278	643.3505 Temporary Marking Arrow Paint	16.000 EACH	_____.	_____.
0280	643.3805 Temporary Marking Stop Line Paint 18-Inch	39.000 LF	_____.	_____.
0282	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0284	645.0120 Geotextile Type HR	65.500 SY	_____.	_____.
0286	646.2020 Marking Line Epoxy 6-Inch	15,385.000 LF	_____.	_____.
0288	646.2025 Marking Line Grooved Black Epoxy 6-Inch	21,383.000 LF	_____.	_____.
0290	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	210,780.000 LF	_____.	_____.
0292	646.4020 Marking Line Epoxy 10-Inch	1,133.000 LF	_____.	_____.
0294	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	15,868.000 LF	_____.	_____.
0296	646.5020 Marking Arrow Epoxy	44.000 EACH	_____.	_____.
0298	646.5120 Marking Word			



Proposal Schedule of Items

Page 11 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0304	646.7120 Marking Diagonal Epoxy 12-Inch	100.000 LF	_____.	_____.
0306	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	72.000 LF	_____.	_____.
0308	646.7520 Marking Crosswalk Epoxy Block Style 24-Inch	48.000 LF	_____.	_____.
0310	646.8320 Marking Parking Stall Epoxy	2,537.000 LF	_____.	_____.
0312	646.9000 Marking Removal Line 4-Inch	62.000 LF	_____.	_____.
0314	646.9002 Marking Removal Line 6-Inch	5,224.000 LF	_____.	_____.
0316	646.9200 Marking Removal Line Wide	13.000 LF	_____.	_____.
0318	650.5000 Construction Staking Base	504.000 LF	_____.	_____.
0320	650.5500 Construction Staking Curb Gutter and Curb & Gutter	512.000 LF	_____.	_____.
0322	650.6000 Construction Staking Pipe Culverts	4.000 EACH	_____.	_____.
0324	650.7000 Construction Staking Concrete Pavement	14,099.000 LF	_____.	_____.
0326	650.7500 Construction Staking Concrete Barrier	1,257.000 LF	_____.	_____.



Proposal Schedule of Items

Page 12 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0332	650.9911 Construction Staking Supplemental Control (project) 01. 1202-00-75	1.000 EACH	_____.	_____.
0334	650.9911 Construction Staking Supplemental Control (project) 02. 1200-02-63	1.000 EACH	_____.	_____.
0336	661.0101 Temporary Traffic Signals for Bridges (structure) 01. 53+00V	1.000 EACH	_____.	_____.
0338	690.0250 Sawing Concrete	71,631.000 LF	_____.	_____.
0340	715.0603 Incentive Strength Concrete Barrier	615.000 DOL	1.00000	615.00
0342	715.0720 Incentive Compressive Strength Concrete Pavement	8,125.000 DOL	1.00000	8,125.00
0344	740.0440 Incentive IRI Ride	27,808.000 DOL	1.00000	27,808.00
0346	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
0348	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	6,480.000 HRS	5.00000	32,400.00
0350	SPV.0060 Special 01. Cleaning and Painting Bearings			



Proposal Schedule of Items

Page 13 of 13

Proposal ID: 20250610001 Project(s): 1200-02-63, 1202-00-75

Federal ID(s): N/A, WISC 2025515

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0358	SPV.0180	123.000		
	Special 01. Scale Approach Pavement Reinforcement	SY	_____.	_____.
0360	SPV.0180	41,961.000		
	Special 02. Reprocess and Relay	SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.