



Wisconsin Department of Transportation

October 6, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #10: 1053-07-86
Abbotsford-Wausau
STH 97 to Pheasant Falls Road, WB
STH 29
Marathon County

1053-07-87, WISC 2026025
Abbotsford-Wausau
Pheasant Falls to Purple Martin, WB
STH 29
Marathon County

Letting of October 14, 2025

This is Addendum No. 02, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
27	Coring of Existing Concrete Pavement

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0060.03	Coring of Existing Concrete Pavement	EA	0	60	60

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
184	Miscellaneous Quantities (Added table for Coring of Existing Concrete Pavement)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

1053-07-86/87

October 6, 2025

Special Provisions

27. Coring of Existing Concrete Pavement, Item SPV.0060.03

A Description

This special provision describes coring of existing concrete pavement prior to removal.

B Materials

Furnish coring equipment capable of extracting intact core-samples with a minimum diameter of 6 inches. Use a water-cooled diamond core drill or other engineer approved method to minimize damage to the core samples.

C Construction

C.1 Coring Locations

The department will determine and designate coring locations. The contractor shall notify the engineer at least two working days before performing coring operations.

C.2 Core Extraction

Perform coring in accordance with AASHTO T24/ASTM C42 to preserve the integrity of the pavement and underlying base materials. Extract full-depth cores to include only the pavement. Clearly mark each core with its location and orientation.

C.3 Core Handling, Packaging, and Delivery

Securely package the cores for transport in approved containers to prevent physical damage. Store and transport cores in compliance with AASHTO T24 requirements. Project staff will take possession immediately after coring.

D Measurement

The department will measure Coring of Existing Concrete Pavement as each complete core acceptably extracted and packaged.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Coring of Existing Concrete Pavement	EACH

Payment is full compensation for coring, core handling and secure packaging.

Schedule of Items

Attached, dated October 6, 2025, are the revised Schedule of Items Page 11.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 184.

END OF ADDENDUM

WISDOT/CADDs SHEET 42

CORING EXISTING CONCRETE PAVEMENT		
CATEGORY	LOCATION	SPV.0060.03 EACH
0010	UNDISTRIBUTED	60

REESTABLISH SECTION CORNER MONUMENTS				
CATEGORY	STATION	OFFSET	SPV.0060.01 EACH	COMMENTS
0010	MAINLINE	9708+99 WB	15' LT	1 REESTABLISH SECTION CORNER MONUMENT.
		9744+57 WB	19' LT	1 REESTABLISH SECTION CORNER MONUMENT.
		9770+79 WB	4' RT	1 REESTABLISH SECTION CORNER MONUMENT.
		9797+26 WB	3' LT	1 REESTABLISH SECTION CORNER MONUMENT.
		9823+62 WB	29' LT	1 REESTABLISH SECTION CORNER MONUMENT.
		9849+92 WB	20' LT	1 REESTABLISH SECTION CORNER MONUMENT.
	STH 97	1025+60	10' LT	1 REESTABLISH 4 WITNESS MONUMENTS.
		TOTAL	7	



Proposal Schedule of Items

Page 11 of 11

Proposal ID: 20251014010 Project(s): 1053-07-86, 1053-07-87

Federal ID(s): N/A, WISC 2026025

SECTION: 0001

Roadway Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0300	SPV.0045 Special 01. Connected Work Zone Notification System	688.000 DAY	_____.	_____.
0302	SPV.0060 Special 01. Reestablish Section Corner Monuments	7.000 EACH	_____.	_____.
0304	SPV.0060 Special 02. Locate and Clean Existing Underdrain Outfalls	132.000 EACH	_____.	_____.
0306	SPV.0180 Special 01. Unbonded Concrete Overlay 7-inch	41,650.000 SY	_____.	_____.
0308	SPV.0180 Special 02. HP Concrete Pavement 8-Inch	16,490.000 SY	_____.	_____.
0310	SPV.0180 Special 03. HP Concrete Pavement 10-Inch	131,830.000 SY	_____.	_____.
0312	204.9180.S Removing (item description) 01. Buried Concrete Pavement	10,700.000 SY	_____.	_____.
0314	SPV.0060 Special 03. Coring of Existing Concrete Pavement	60.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.