



Wisconsin Department of Transportation

January 6, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #35: 9423-00-70
STH 86 – CTH E
Spirit River Bridge, B-35-0162
CTH O
Lincoln County

Letting of January 13, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
26	Infill Riprap – B-35-162, Item SPV.0195.01

Deleted Special Provisions	
Article No.	Description
25	Infill Riprap – B-35-162, Item SPV.0180.01

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0195	01. Infill Riprap – B-35-162	TON	0	66	66

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
SPV.0180	01. Infill Riprap – B-35-162	SY	208	-208	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
33	Structure Plan (Infill Riprap – B-35-0162 unit changed from SY to TON)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

9423-00-70

January 6, 2026

Special Provisions

25. Deleted

26. Infill Riprap – B-35-162, Item SPV.0195.01.

A Description

This special provision describes infilling riprap voids.

B Materials

Furnish clean, coarse aggregate that has 0 to 10 percent passing through a No. 10 sieve and remaining voids are no larger than 1.5-Inches. Do not use crushed concrete or reclaimed asphalt.

C Construction

Place after riprap has been completed. Fill in voids of riprap with materials as specified in Section B so that no void larger than 1.5-Inches remains. Fill to the top of riprap. At abutments, fill riprap voids above the waterline.

D Measurement

The department will measure Infill Riprap – “Location” by the TON acceptably completed, measured as the area of the heavy riprap being infilled as the contract designates or the engineer establishes.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0195.01	Infill Riprap – B-35-162	TON

Payment for Infill Riprap – “Location” is full compensation for providing, placing, and shaping the material.

ncr-606-005 (20251121)

Schedule of Items

Attached, dated January 6, 2026, are the revised Schedule of Items Page 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 33

END OF ADDENDUM



Proposal Schedule of Items

Page 1 of 5

Proposal ID: 20260113035 Project(s): 9423-00-70

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 01. B-35-003	1.000 EACH	_____.	_____.
0004	205.0100 Excavation Common	276.000 CY	_____.	_____.
0006	206.1001 Excavation for Structures Bridges (structure) 01. B-35-162	1.000 EACH	_____.	_____.
0008	210.1500 Backfill Structure Type A	300.000 TON	_____.	_____.
0010	213.0100 Finishing Roadway (project) 01. 9423-00-70	1.000 EACH	_____.	_____.
0012	305.0110 Base Aggregate Dense 3/4-Inch	98.000 TON	_____.	_____.
0014	305.0120 Base Aggregate Dense 1 1/4-Inch	710.000 TON	_____.	_____.
0016	450.4000 HMA Cold Weather Paving	50.000 TON	_____.	_____.
0018	455.0605 Tack Coat	50.000 GAL	_____.	_____.
0020	465.0105 Asphaltic Surface	200.000 TON	_____.	_____.
0022	465.0315 Asphaltic Flumes	10.000 SY	_____.	_____.
0024	502.0100 Concrete Masonry Bridges	408.000 CY	_____.	_____.
0026	502.3200 Protective Surface Treatment	422.000 SY	_____.	_____.
0028	502.3210 Pigmented Surface Sealer	150.000 SY	_____.	_____.
0030	505.0400 Bar Steel Reinforcement HS Structures	22,280.000 LB	_____.	_____.

