



Wisconsin Department of Transportation

January 6, 2026

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631

Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #056: 1090-39-70, WISC 2026103
IH 43 Rock Freeway
STH 83 to STH 164
IH 43
Waukesha County

Letting of January 13, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
1541-1579	Earthwork Data Sheets (not legible in advertised plan set)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1090-39-70

January 6, 2026

Special Provisions

3. Prosecution and Progress

*Replace the section titled **Interim Completion and Liquidated Damages – IH 43 NB: November 16, 2026** with the following:*

Interim Completion and Liquidated Damages – IH 43 NB: November 2, 2026

Complete construction operations on IH 43 northbound to the stage necessary to reopen all lanes of traffic by November 2, 2026. Do not reopen until completing the following work: IH 43 northbound lanes, shoulders, and ramps; temporary pavement marking; signing; permanent or temporary restoration; and crossover closures.

If the contractor fails to complete the work necessary to reopen IH 43 to all lanes of traffic by November 2, 2026, the department will assess the contractor \$3,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM on November 3, 2026. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

*Replace the section titled **Interim Completion and Liquidated Damages – Complete Stage 5, IH 43 SB and STH 164: November 19, 2027** with the following:*

Interim Completion and Liquidated Damages – Complete Stage 5, IH 43 SB and STH 164: November 5, 2027

Complete construction operations on IH 43 southbound and STH 164 to the stage necessary to reopen all lanes of traffic by November 5, 2027. Do not reopen until completing the following work: IH 43 southbound lanes, shoulders, and ramps; STH 164 lanes, shoulders, and traffic signals; permanent or cold weather pavement marking; signing; permanent or temporary restoration; and crossover closures.

If the contractor fails to complete the work necessary to reopen IH 43 and STH 164 to all lanes of traffic by November 5, 2027, the department will assess the contractor \$3,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM on November 6, 2027. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

*Under the section titled **Schedule of Operations** and the first subsection titled **Fall and Winter Work Restrictions**, replace paragraph 1 with the following:*

Complete construction operations on IH 43 and STH 164 to the stage necessary to reopen to all lanes of traffic by November 2, 2026, unless otherwise approved by the engineer. Do not reopen until the work that has been started is complete and all materials, equipment, and temporary traffic control devices are removed from the IH 43 right-of-way. Work on retaining wall R-67-172 may continue with southbound shoulder closures on STH 164.

*Under the section titled **Schedule of Operations** and the second subsection titled **Fall and Winter Work Restrictions**, replace paragraph 1 with the following:*

Complete construction operations on IH 43 and STH 164 to the stage necessary to reopen to all lanes of traffic by November 5, 2027, unless otherwise approved by the engineer. Do not reopen until the work that has been started is complete and all materials, equipment, and temporary traffic control devices are removed from the IH 43 and STH 164 right-of-way.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 1541 - 1579.

END OF ADDENDUM

PROJECT NO:	1090-39-70	HWY:	IH 43	COUNTY:	WAUKESHA	EARTHWORK DATA	SHEET	1542	
FILE NAME: N:\PROJECTS\109039000\GHEITSPLAN\090101_ELV_1H43.DWG						DATE: 10/27/2025	TIME: 11:46 AM	PLT BY: ABU,AWA,WINNER J	PLT NAME: 1" = 1'

FH 43 NB - BEGIN PROJECT TO FOX RIVER (CONTINUE)											
STATION	REAL STATION	DISTANCE	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGE/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGE/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4	
145+00.00	145000.00	100	96.50	45.33	6.95	360	168	26	21742	1045	11517
146+00.00	146000.00	100	96.18	45.33	18.75	357	168	48	22099	1093	11658
147+00.00	147000.00	100	98.25	45.33	2.87	360	168	40	22459	1133	11810
148+00.00	148000.00	100	90.14	45.33	8.08	349	168	20	22808	1153	11971
149+00.00	149000.00	100	87.46	45.33	11.03	329	168	35	23137	1188	12097
150+00.00	150000.00	100	88.56	45.33	7.03	326	168	33	23463	1221	12222
151+00.00	151000.00	100	88.54	45.33	10.44	328	168	32	23791	1253	12350
152+00.00	152000.00	100	92.04	45.33	13.49	334	168	44	24125	1297	12472
153+00.00	153000.00	100	93.50	45.33	11.60	344	168	46	24469	1343	12602
154+00.00	154000.00	100	85.33	45.33	11.91	331	168	44	24800	1387	12721
155+00.00	155000.00	100	85.56	45.33	15.04	316	168	50	25116	1437	12819
156+00.00	156000.00	100	79.97	45.33	22.03	307	168	69	25423	1506	12889
157+00.00	157000.00	100	79.95	45.33	14.04	296	168	67	25719	1573	12950
158+00.00	158000.00	100	81.71	45.33	13.20	299	168	50	26018	1623	13031
159+00.00	159000.00	100	84.88	45.33	7.22	308	168	38	26326	1661	13133
160+00.00	160000.00	100	82.64	45.33	14.50	310	168	40	26636	1701	13235
161+00.00	161000.00	100	85.69	45.33	5.89	312	168	38	26948	1739	13341
162+00.00	162000.00	100	88.15	45.33	14.63	322	168	38	27270	1777	13457
163+00.00	163000.00	100	88.06	45.33	5.37	326	168	37	27596	1814	13578
164+00.00	164000.00	100	92.78	45.33	17.61	335	168	43	27931	1857	13702
165+00.00	165000.00	100	95.40	45.33	3.36	348	168	39	28279	1896	13843
166+00.00	166000.00	100	88.98	45.33	14.35	341	168	33	28620	1929	13983
167+00.00	167000.00	100	90.75	45.33	13.20	333	168	51	28953	1980	14097
168+00.00	168000.00	100	100.58	45.33	13.97	354	168	50	29307	2030	14233
169+00.00	169000.00	100	102.22	45.33	11.69	376	168	48	29683	2078	14393
170+00.00	170000.00	100	102.40	45.33	3.80	379	168	29	30062	2107	14575
171+00.00	171000.00	100	95.15	45.33	6.43	366	168	19	30428	2126	14754
172+00.00	172000.00	100	92.34	45.33	11.61	347	168	33	30775	2159	14900
173+00.00	173000.00	100	92.97	45.33	11.03	343	168	42	31118	2201	15033
174+00.00	174000.00	100	93.64	45.33	16.14	346	168	50	31464	2251	15161
175+00.00	175000.00	100	96.08	45.33	9.55	351	168	48	31815	2299	15296
176+00.00	176000.00	100	93.41	45.33	7.71	351	168	32	32166	2331	15447
177+00.00	177000.00	100	97.65	45.33	6.75	354	168	27	32520	2358	15606
178+00.00	178000.00	100	95.08	45.33	5.58	357	168	23	32877	2381	15772
179+00.00	179000.00	100	99.23	45.33	3.64	360	168	17	33237	2398	15947
180+00.00	180000.00	100	120.48	45.33	4.00	407	168	14	33644	2412	16172
181+00.00	181000.00	100	128.15	45.33	3.42	460	168	14	34104	2426	16450
182+00.00	182000.00	100	128.00	45.33	3.13	474	168	12	34578	2438	16744
183+00.00	183000.00	100	144.19	45.33	5.87	504	168	17	35082	2455	17063
184+00.00	184000.00	100	159.23	45.33	8.39	562	168	26	35644	2481	17431
185+00.00	185000.00	100	153.14	45.33	1.51	578	168	18	36222	2499	17823
186+00.00	186000.00	100	142.24	45.33	0.00	547	168	18	36769	2502	18199
187+00.00	187000.00	100	147.83	45.33	0.00	537	168	0	37306	2506	18568
188+00.00	188000.00	100	147.54	45.33	0.00	500	168	0	37836	2502	18952

IH-43 NB - EDGEWOOD AVE TO OKDALE DR

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORINATE
						NOTE 1	NOTE 2	NOTE 3		1.00	NOTE 4
220+73.70	22073.70	0.00	153.25	45.33	0.00	0	0	0	0	0	0
221+00.00	22100.00	26.30	161.36	45.33	0.00	153	44	0	153	0	109
222+00.00	22200.00	100.00	152.47	45.33	3.27	581	168	6	734	6	516
223+00.00	22300.00	100.00	137.07	45.33	3.14	536	168	12	1270	18	872
224+00.00	22400.00	100.00	131.45	45.33	5.79	497	168	17	1767	35	1184
225+00.00	22500.00	100.00	122.22	45.33	8.33	470	168	26	2237	61	1460
226+00.00	22600.00	100.00	113.84	45.33	8.36	437	168	31	2674	92	1698
227+00.00	22700.00	100.00	114.98	45.33	10.25	424	168	34	3098	126	1920
228+00.00	22800.00	100.00	111.80	45.33	9.99	420	168	37	3518	163	2135
229+00.00	22900.00	100.00	112.64	45.33	5.97	416	168	30	3934	193	2353
230+00.00	23000.00	100.00	106.15	45.33	6.70	405	168	23	4339	216	2567
231+00.00	23100.00	100.00	112.56	45.33	3.51	405	168	19	4744	235	2785
232+00.00	23200.00	100.00	114.32	45.33	1.08	420	168	9	5164	244	3028
233+00.00	23300.00	100.00	116.28	45.33	3.20	427	168	8	5591	252	3279
234+00.00	23400.00	100.00	116.54	45.33	3.24	431	168	13	6022	265	3529
235+00.00	23500.00	100.00	115.14	45.33	4.74	429	168	16	6451	281	3774
236+00.00	23600.00	100.00	111.53	45.33	5.95	420	168	20	6871	301	4006
237+00.00	23700.00	100.00	106.91	45.33	4.99	405	168	20	7276	321	4223
238+00.00	23800.00	100.00	99.46	45.33	4.97	382	168	18	7658	339	4419
239+00.00	23900.00	100.00	105.23	45.33	2.39	379	168	14	8037	353	4616
240+00.00	24000.00	100.00	109.92	45.33	1.21	398	168	7	8435	360	4839
241+00.00	24100.00	100.00	79.62	45.33	2.19	351	168	6	8786	366	5016
242+00.00	24200.00	100.00	117.61	45.33	3.21	365	168	10	9151	376	5203
243+00.00	24300.00	100.00	118.10	45.33	1.80	437	168	9	9588	385	5463
244+00.00	24400.00	100.00	113.28	45.33	2.27	428	168	8	10016	393	5715
245+00.00	24500.00	100.00	105.83	45.33	5.04	406	168	14	10422	407	5939
246+00.00	24600.00	100.00	93.43	45.33	5.27	369	168	19	10791	426	6121
247+00.00	24700.00	100.00	90.79	45.33	7.50	341	168	24	11132	450	6370
248+00.00	24800.00	100.00	91.71	45.33	9.23	338	168	31	11470	481	6409
249+00.00	24900.00	100.00	93.96	45.33	6.34	344	168	29	11814	510	6556
250+00.00	25000.00	100.00	96.96	45.33	4.19	354	168	20	12168	530	6722
251+00.00	25100.00	100.00	91.87	45.33	9.36	350	168	25	12518	555	6879
252+00.00	25200.00	100.00	91.28	45.33	10.21	339	168	36	12857	591	7014
253+00.00	25300.00	100.00	95.04	45.33	6.39	345	168	31	13202	622	7160
254+00.00	25400.00	100.00	94.97	45.33	10.90	352	168	32	13554	654	7312
255+00.00	25500.00	100.00	96.70	45.33	7.81	355	168	35	13909	689	7464
256+00.00	25600.00	100.00	97.07	45.33	9.70	359	168	32	14268	721	7623
257+00.00	25700.00	100.00	103.42	45.33	4.29	371	168	26	14639	747	7800
258+00.00	25800.00	100.00	111.26	45.33	2.31	398	168	12	15037	759	8018
259+00.00	25900.00	100.00	109.57	45.33	0.92	409	168	6	15446	765	8253
260+00.00	26000.00	100.00	112.77	45.33	0.00	412	168	2	15858	767	8495
261+00.00	26100.00	100.00	107.70	45.33	1.11	408	168	2	16266	769	8733
262+00.00	26200.00	100.00	102.94	45.33	3.56	390	168	9	16656	778	8946
263+00.00	26300.00	100.00	116.94	45.33	2.90	407	168	12	17063	790	9173
264+00.00	26400.00	100.00	109.38	45.33	4.48	419	168	14	17482	804	9410
265+00.00	26500.00	100.00	103.28	45.33	2.75	394	168	13	17876	817	9623
266+00.00	26600.00	100.00	95.27	45.33	5.63	368	168	16	18244	833	9807
267+00.00	26700.00	100.00	87.01	45.33	11.34	338	168	31	18582	864	9946
268+00.00	26800.00	100.00	85.63	45.33	9.03	320	168	38	18902	902	10060
269+00.00	26900.00	100.00	87.12	45.33	9.97	320	168	35	19222	937	10177
270+00.00	27000.00	100.00	93.75	45.33	12.76	335	168	42	19557	979	10302
271+00.00	27100.00	100.00	112.88	45.33	9.06	383	168	40	19940	1019	10477
272+00.00	27200.00	100.00	118.53	45.33	7.74	429	168	31	20369	1050	10707
273+00.00	27300.00	100.00	140.03	45.33	9.65	479	168	32	20848	1082	10986
274+00.00	27400.00	100.00	166.36	45.33	3.26	567	168	24	21415	1106	11361
275+00.00	27500.00	100.00	177.96	45.33	0.00	638	168	6	22053	1112	11825
276+00.00	27600.00	100.00	157.67	45.33	0.00	622	168	0	22675	1112	12275
276+72.07	27672.07	72.07	150.89	45.33	0.10	412	121	0	23087	1112	12570

Addendum No. 01
ID 1090-39-70
Revised Sheet 1544
January 6, 2026

PROJECT NO: 1090-39-70

HWY: IH 43

COUNTY: WAUKESHA

EARTHWORK DATA

SHEET 1544

E

FILE NAME: N:\PROJ\CD\10903900\DWG\10903900\10903900-1544.DWG

LAYOUT NAME: 04

PLOT DATE: 10/27/2025 11:46 AM

PLOT BY: ABU AJWA, MUTHIER J

PLOT NAME:

PLOT SCALE: 1" = 1'

WISDOT/CADSW SHEET 49

9

IH 43 NB - HILO DR TO EVERGREEN DR (CONTINUE)

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	EXPANDED FILL
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 4
393+00.00	39300.00	100	134.89	45.33	0.40	494	168	4	14733
394+00.00	39400.00	100	116.66	45.33	0.09	466	168	1	15030
395+00.00	39500.00	100	126.45	45.33	0.00	450	168	0	15312
396+00.00	39600.00	100	135.51	45.33	0.53	485	168	1	15628
397+00.00	39700.00	100	138.53	45.33	0.58	507	168	2	15965
398+00.00	39800.00	100	142.72	45.33	0.56	521	168	2	16316
399+00.00	39900.00	100	132.39	45.33	5.14	509	168	11	16646
400+00.00	40000.00	100	123.77	45.33	0.10	474	168	10	16942
401+00.00	40100.00	100	136.39	45.33	0.00	482	168	0	17256
402+00.00	40200.00	100	151.52	45.33	0.00	533	168	0	17621
403+00.00	40300.00	100	152.11	45.33	0.00	533	168	0	17777

Addendum No. 01
ID 1090-39-70
Revised Sheet 1547
January 6, 2026

[illegible]

9

PLOT SCALE: 1" = 1'

WISDOT/CADD SHEET 49

9

WISDOT/CADD SHEET 49

9

SHEET 1553 E

PLOT SCALE: 1" = 1'

ER J

10/27/2025 11:50 AM

PLC

43.DWG

90101-EV

SHEETSPI

0601\1090

21

FILE N

1

IH 43 SB - EDGEWOOD AVE TO OAKDALE DR												
STATION	REAL STATION	DISTANCE	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)		
			CUT	SAVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SAVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORINATE	
						NOTE 1	NOTE 2	NOTE 3		NOTE 1	1.00	NOTE 4
218+79.82	21879.82	0.00	158.68	41.09	0.00	0	0	0		0	0	0
219+00.00	21900.00	20.18	168.44	41.09	0.00	122	31	0		122	0	91
220+00.00	22000.00	100.00	178.86	41.09	0.00	643	152	0		765	0	582
221+00.00	22100.00	100.00	174.54	41.09	3.49	654	152	6		1419	6	1078
222+00.00	22200.00	100.00	130.56	41.09	5.86	602	152	17		2021	23	1511
223+00.00	22300.00	100.00	145.39	41.09	8.40	548	152	26		2569	49	1881
224+00.00	22400.00	100.00	149.19	41.09	5.39	546	152	56		3115	75	2249
225+00.00	22500.00	100.00	155.96	41.09	2.14	565	152	14		3680	88	2648
226+00.00	22600.00	100.00	151.85	41.09	2.40	570	152	8		4250	97	3058
227+00.00	22700.00	100.00	143.31	41.09	2.59	547	152	12		4797	106	3444
228+00.00	22800.00	100.00	143.46	41.09	3.79	531	152	12		5328	118	3811
229+00.00	22900.00	100.00	125.20	41.09	1.60	498	152	10		5826	128	4147
230+00.00	23000.00	100.00	106.24	41.09	1.25	429	152	5		6255	133	4419
231+00.00	23100.00	100.00	108.77	41.09	1.58	398	152	5		6653	138	4660
232+00.00	23200.00	100.00	106.83	41.09	3.02	399	152	9		7052	147	4898
233+00.00	23300.00	100.00	109.30	41.09	3.47	400	152	12		7452	159	5134
234+00.00	23400.00	100.00	111.44	41.09	3.94	409	152	15		7861	173	5377
235+00.00	23500.00	100.00	112.30	41.09	2.01	414	152	11		8275	184	5628
236+00.00	23600.00	100.00	108.37	41.09	1.72	409	152	8		8684	191	5878
237+00.00	23700.00	100.00	106.61	41.09	2.38	398	152	7		9082	199	6116
238+00.00	23800.00	100.00	99.93	41.09	1.56	382	152	206		9464	206	6339
239+00.00	23900.00	100.00	105.62	41.09	1.87	381	152	12		9845	218	6556
240+00.00	24000.00	100.00	108.05	41.09	3.66	396	152	16		10241	234	6784
241+00.00	24100.00	100.00	113.37	41.09	4.85	410	152	16		10651	250	7036
242+00.00	24200.00	100.00	114.06	41.09	3.85	421	152	16		11072	266	7279
243+00.00	24300.00	100.00	111.60	41.09	2.49	418	152	12		11480	278	7533
244+00.00	24400.00	100.00	108.66	41.09	2.77	408	152	10		11898	288	7779
245+00.00	24500.00	100.00	109.74	41.09	1.25	404	152	3		12302	295	8024
246+00.00	24600.00	100.00	104.37	41.09	0.40	396	152	3		12698	298	8265
247+00.00	24700.00	100.00	105.38	41.09	0.18	388	152	1		13086	299	8500
248+00.00	24800.00	100.00	105.06	41.09	0.94	390	152	2		13476	301	8736
249+00.00	24900.00	100.00	106.66	41.09	2.22	392	152	6		13868	307	8970
250+00.00	25000.00	100.00	103.37	41.09	4.98	389	152	13		14257	320	9194
251+00.00	25100.00	100.00	103.00	41.09	2.51	382	152	14		14639	334	9410
252+00.00	25200.00	100.00	101.83	41.09	1.91	379	152	8		15018	342	9629
253+00.00	25300.00	100.00	96.96	41.09	2.94	368	152	9		15386	351	9836
254+00.00	25400.00	100.00	94.68	41.09	4.34	355	152	13		15741	364	10026
255+00.00	25500.00	100.00	94.69	41.09	2.76	351	152	13		16092	377	10212
256+00.00	25600.00	100.00	108.45	41.09	2.02	376	152	3		16468	386	10427
257+00.00	25700.00	100.00	115.70	41.09	0.57	415	152	5		16883	391	10685
258+00.00	25800.00	100.00	118.87	41.09	1.34	434	152	4		17317	395	10963
259+00.00	25900.00	100.00	118.99	41.09	4.16	440	152	10		17757	405	11241
260+00.00	26000.00	100.00	113.78	41.09	5.74	431	152	18		18188	423	11502
261+00.00	26100.00	100.00	108.95	41.09	4.11	412	152	18		18600	441	11744
262+00.00	26200.00	100.00	106.08	41.09	3.50	398	152	14		18998	455	11976
263+00.00	26300.00	100.00	108.59	41.09	10.17	398	152	25		19396	480	12197
264+00.00	26400.00	100.00	111.28	41.09	11.15	407	152	39		19803	519	12413
265+00.00	26500.00	100.00	109.06	41.09	3.23	408	152	27		20211	546	12642
266+00.00	26600.00	100.00	106.09	41.09	7.82	398	152	20		20609	566	12868
267+00.00	26700.00	100.00	105.30	41.09	3.85	391	152	22		21000	588	13085
268+00.00	26800.00	100.00	105.01	41.09	2.89	389	152	12		21389	600	13310
269+00.00	26900.00	100.00	98.10	41.09	7.12	376	152	15		21765	619	13515
270+00.00	27000.00	100.00	97.16	41.09	6.94	362	152	26		22127	645	13699
271+00.00	27100.00	100.00	97.99	41.09	5.93	361	152	24		22488	669	13894
272+00.00	27200.00	100.00	109.70	41.09	9.01	385	152	28		22873	697	14089
273+00.00	27300.00	100.00	115.68	41.09	6.25	417	152	28		23290	725	14326
274+00.00	27400.00	100.00	128.50	41.09	4.39	452	152	20		23742	745	14606
275+00.00	27500.00	100.00	141.62	41.09	11.42	500	152	29		24242	774	14925
276+00.00	27600.00	100.00	152.43	41.09	3.51	545	152	28		24787	802	15290
277+00.00	27700.00	100.00	153.34	41.09	1.76	566	152	3		25353	811	15695
277+37.53	27737.53	37.53	146.34	41.09	9.22	708	152	7		25551	818	15839

IH 43 SB - HILO DR TO EVERGREEN DR (CONTINUE)

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4
394+00.00	39400.00	100	111.42	41.09	2.16	410	152	7	25249	593
395+00.00	39500.00	100	112.36	41.09	2.61	414	152	9	25663	602
396+00.00	39600.00	100	120.97	41.09	1.44	432	152	8	26095	610
397+00.00	39700.00	100	127.40	41.09	0.30	460	152	3	26555	613
398+00.00	39800.00	100	123.33	41.09	4.19	464	152	8	27019	621
399+00.00	39900.00	100	131.14	41.09	1.48	471	152	10	27490	631
400+00.00	40000.00	100	136.59	41.09	14.21	496	152	29	27986	660
401+00.00	40100.00	100	151.24	41.09	5.51	533	152	37	28519	697
402+00.00	40200.00	100	150.31	41.09	7.99	558	152	25	29077	722
402+67.97	40267.97	67.97	147.83	41.09	16.61	375	103	31	29452	753

Addendum No. 01
ID 1090-39-70
Revised Sheet 1556
January 6, 2026

9

9

PROJECT NO: 1090-39-70

HWY: IH 43

COUNTY: WAUKESHA

EARTHWORK DATA

SHEET 1556

E

FILE NAME: N:\PDS\CD\10903900\SHETS\PLAN\090101-EW_IH43.DWG

LAYOUT NAME: 15

PLOT DATE: 10/27/2025 11:53 AM

PLOT BY: ABU AJWA, MUNTHEER J

PLOT SCALE: 1" = 1'

WISDOT/CADSW SHEET 49

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			EXPANDED FILL	CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL			FILL
458+87.84	45887.84	0.00	159.79	46.76	0.99	0	0	0	NOTE 1	NOTE 4
459+00.00	45900.00	12.16	165.90	46.76	0.00	73	21	73	0	52
460+00.00	46000.00	100	155.74	46.76	0.27	596	173	0	475	0
461+00.00	46100.00	100	152.11	46.76	0.00	570	0.00	1239	0	872
462+00.00	46200.00	100	154.03	46.76	0.00	567	173	0	1806	0
463+00.00	46300.00	100	143.75	46.76	4.88	551	173	9	2357	1635
464+00.00	46400.00	100	134.50	46.76	0.75	515	173	19	2872	1967
465+00.00	46500.00	100	133.37	46.76	0.00	496	173	1	3368	2289
466+00.00	46600.00	100	99.41	46.76	0.00	431	0	3799	20	2547
467+00.00	46700.00	100	87.95	46.76	0.29	347	173	1	4146	21
468+00.00	46800.00	100	81.44	46.76	1.24	314	173	3	4460	24
469+00.00	46900.00	100	125.97	46.76	9.51	384	173	20	4844	44
470+00.00	47000.00	100	129.70	46.76	3.38	474	173	24	5317	68
471+00.00	47100.00	100	126.18	46.76	4.38	474	173	14	5791	82
472+00.00	47200.00	100	127.39	46.76	4.13	470	173	16	6261	98
473+00.00	47300.00	100	131.95	46.76	4.13	480	173	15	6741	113
474+00.00	47400.00	100	135.91	46.76	1.52	496	173	10	7237	123
475+00.00	47500.00	100	132.43	46.76	2.27	497	173	7	7734	130
476+00.00	47600.00	100	130.86	46.76	6.77	488	173	7	8222	147
477+00.00	47700.00	100	126.56	46.76	5.20	477	173	22	8699	167
477+29.29	47729.29	29.29	0.00	46.76	0.00	69	51	3	8768	172
477+29.29	47729.29									5410

9

PROJECT NO:	1090-39-70	Hwy:	IH 43	COUNTY:	WAUKESHA	EARTHWORK DATA	SHEET	1558
FILE NAME :						PLOT DATE :	PLOT SCALE :	WISDOT/CADDS SHEET #91
N:\P\103D\109039070\SHEETS\PLAN\090101_EW_IH43.DWG						10/27/2022 11:53 AM	1" = 1'	
LAYOUT NAME :						PLOT BY:		
LAYOUT NAME - 18						ABULAWA, M(INTERJ)		

9

	PROJECT NO:	1090-39-70	HWM: IH 43	COUNTY: WAUKESHA	EARTHWORK DATA	SHEET 1559	E			
FILE NAME: N:\PDS\CD\I060B00\SHEETS\LAN\090101_EW_IH43.DWG										
					PLOT DATE:	10/27/2025 11:51 AM	PLOT BY:	RABU AWA MUNIRERJ	PLOT SCALE:	1" = 1'
WSOCT/CADD SHEET #49										

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SAVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SAVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4	
101+75.70	10175.70	0.00	87.92	26.76	0.00	0	0	0	0	0	
102+00.00	10200.00	24.33	87.15	26.76	0.00	79	24	0	79	0	55
103+00.00	10300.00	100	97.65	26.76	0.07	342	99	0	421	0	298
104+00.00	10400.00	100	80.41	26.76	1.62	330	99	3	751	3	526
105+00.00	10500.00	100	74.90	26.76	2.92	288	99	8	1039	11	707
106+00.00	10600.00	100	79.84	26.76	1.30	287	99	8	1326	19	887
107+00.00	10700.00	100	77.15	26.76	0.90	294	99	4	1620	23	1078
108+00.00	10800.00	100	77.52	26.76	4.82	290	99	11	1910	34	1258
109+00.00	10900.00	100	83.70	26.76	1.43	278	99	12	2188	46	1425
110+00.00	11000.00	100	65.92	26.76	5.57	259	99	13	2752	59	1782
111+00.00	11100.00	100	52.84	26.76	6.87	270	99	17	2974	82	1978
112+00.00	11200.00	100	52.33	26.76	4.96	28	99	3	3071	85	1889
112+14.51	11214.51	14.51	52.33	26.76	4.96	28	99	3	3071	85	1889

STH 164 NB

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	1.00	NOTE 4
1456+00.00	145600.00	0.00	69.64	15.34	0.00	0	0	0	0	0	0
1456+50.00	145650.00	50.00	72.22	15.52	0.00	131	29	0	131	0	102
1457+00.00	145700.00	50.00	75.84	15.89	0.00	137	29	0	268	0	210
1457+50.00	145750.00	50.00	76.48	18.11	0.01	141	31	0	409	0	320
1458+00.00	145800.00	50.00	77.00	18.69	1.69	142	34	2	551	2	426
1458+50.00	145850.00	50.00	80.53	20.52	1.54	146	36	3	697	5	533
1459+00.00	145900.00	50.00	80.73	21.10	8.29	149	39	9	846	14	634
1459+50.00	145950.00	50.00	84.84	21.11	19.78	153	39	26	999	40	722
1460+00.00	146000.00	50.00	86.98	21.15	18.41	159	39	35	1158	75	807
1460+50.00	146050.00	50.00	87.85	21.04	5.20	162	39	22	1320	97	908
1461+00.00	146100.00	50.00	82.30	21.38	13.75	158	39	18	1478	115	1009
1461+50.00	146150.00	50.00	79.93	23.33	0.00	150	41	13	1628	128	1105
1462+00.00	146200.00	50.00	66.03	25.43	12.09	135	45	11	1763	139	1184
1462+50.00	146250.00	50.00	67.04	21.34	75.57	123	43	81	1886	220	1183
1463+00.00	146300.00	50.00	66.75	21.16	82.27	124	39	146	2010	366	1122
1463+50.00	146350.00	50.00	66.99	21.29	106.47	124	39	175	2134	541	1032
1464+00.00	146400.00	50.00	65.53	21.07	105.03	123	39	196	2257	737	920
1464+50.00	146450.00	50.00	65.03	21.08	89.01	121	39	180	2378	917	822
1465+00.00	146500.00	50.00	85.57	21.41	17.89	139	39	99	2517	1016	823
1465+50.00	146550.00	50.00	108.27	16.88	10.12	179	35	26	2696	1042	941
1466+00.00	146600.00	50.00	104.54	10.81	9.48	197	26	18	2893	1060	1094
1466+50.00	146650.00	50.00	83.62	3.02	14.60	174	13	22	3067	1082	1233
1467+00.00	146700.00	50.00	62.28	0.00	21.67	135	3	34	3202	1116	1331
1467+50.00	146750.00	50.00	16.59	0.00	83.29	73	0	97	3275	1213	1307
1468+00.00	146800.00	50.00	5.97	0.00	121.36	21	0	189	3296	1402	1139
1468+15.61	146815.61	15.61	0.05	0.00	69.44	2	0	55	3298	1457	1086
1468+50.00	146850.00	34.39	8.05	0.00	54.20	5	0	79	3303	1536	1012
1469+00.00	146900.00	50.00	34.71	0.00	76.21	40	0	121	3343	1657	931
1469+50.00	146950.00	50.00	148.27	60.95	0.00	169	56	71	3512	1728	973
1469+89.51	146989.51	39.51	135.77	32.71	11.50	208	69	8	3720	1736	1104
1470+00.00	147000.00	10.49	138.72	31.94	17.61	53	13	6	3773	1742	1138
1470+34.59	147034.59	34.59	98.79	22.17	0.00	152	35	11	3925	1753	1244
1470+71.16	147071.16	36.57	151.86	34.86	0.00	170	39	0	4095	1753	1375
1470+94.74	147094.74	23.58	164.71	34.25	2.13	138	30	1	4233	1754	1482
1471+00.00	147100.00	5.26	183.50	34.10	5.85	34	7	1	4267	1755	1508
1471+50.00	147150.00	50.00	190.52	32.26	0.86	346	61	6	4613	1761	1787
1472+00.00	147200.00	50.00	214.15	31.43	0.00	375	59	1	4988	1762	2102
1472+50.00	147250.00	50.00	173.16	25.74	0.00	359	53	0	5347	1762	2408
1473+00.00	147300.00	50.00	173.73	21.61	0.00	321	44	0	5668	1762	2685
1473+50.00	147350.00	50.00	166.64	20.90	0.00	315	39	0	5983	1762	2961
1474+00.00	147400.00	50.00	185.36	21.00	0.00	326	39	0	6309	1762	3248
1474+50.00	147450.00	50.00	165.37	21.71	0.00	325	40	0	6634	1762	3533
1474+63.49	147463.49	13.49	149.87	21.96	0.00	79	11	0	6713	1762	3601
1474+75.78	147475.78	12.29	128.26	21.55	6.68	63	12	2	6776	1764	3652
1474+98.91	147498.91	23.13	118.96	22.55	0.00	106	19	3	6882	1767	3736
1475+35.14	147535.14	36.23	177.21	35.07	9.38	199	39	6	7081	1773	3890
1475+56.35	147556.35	21.21	105.94	35.10	0.03	111	28	4	7192	1777	3969
1476+01.25	147601.25	44.90	135.09	35.96	9.18	200	59	8	7392	1785	4102
1476+50.00	147650.00	48.75	139.67	61.97	1.24	248	88	9	7640	1794	4253
1477+00.00	147700.00	50.00	83.26	23.56	19.04	206	79	19	7846	1813	4361

Addendum No. 01
ID 1090-39-70
Revised Sheet 1560
January 6, 2026

PROJECT NO: 1090-39-70

HWY: IH 43

COUNTY: WAUKESHA

EARTHWORK DATA

SHEET 1560

E

FILE NAME: N:\PROJ\CD\10903900\01\DWG\STH164.DWG

LAYOUT NAME: 01

PLOT DATE: 10/27/2025 11:52 AM

PLOT BY: ABU AJWA, MUNTHE J

PLOT SCALE: 1" = 1'

WISDOT/CADDS SHEET 49

Addendum No. 01
ID 1090-39-70
Revised Sheet 1561
January 6, 2026

STATION	REAL STATION	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
		DISTANCE	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
					NOTE 1	NOTE 2	NOTE 3		NOTE 1	1.00	NOTE 4
1477+50.00	147750.00	50.00	354.84	0.00	0.59	406	22	18	8252	1831	4727
1478+00.00	147800.00	50.00	233.17	0.00	7.08	544	0	7	8796	5264	5264
1478+50.00	147850.00	50.00	115.94	0.00	20.41	323	0	25	9119	1863	5562
1479+00.00	147900.00	50.00	88.94	0.00	33.80	190	0	50	9309	1913	5702
1479+50.00	147950.00	50.00	115.43	0.00	41.69	189	0	70	9498	1983	5821
1480+00.00	148000.00	50.00	131.36	0.00	39.12	229	0	75	9727	2058	5975
1480+50.00	148050.00	50.00	164.65	0.00	40.31	274	0	74	10001	2132	6175
1481+00.00	148100.00	50.00	162.26	0.00	42.66	303	0	77	10304	2209	6401
1481+50.00	148150.00	50.00	166.74	0.00	40.00	305	0	77	10609	2286	6629
1482+00.00	148200.00	50.00	172.54	0.00	37.74	314	0	72	10923	2358	6871
1482+50.00	148250.00	50.00	176.48	0.00	28.81	323	0	62	11246	2420	7132
1482+70.28	148270.28	20.28	172.37	0.00	47.30	131	0	29	11377	2449	7234
1483+00.00	148300.00	29.72	208.45	0.00	45.76	210	0	51	11587	2500	7393
1483+50.00	148350.00	50.00	234.08	0.00	7.03	410	0	49	11987	2549	7754
1483+71.17	148371.17	21.17	107.24	0.00	0.00	134	0	3	12131	2552	7885

9

9

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CU) (UNADJUSTED)		CUT	EXPANDED FILL	CUMULATIVE VOL (CU)				
			SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL							
			CUT				NOTE 1	NOTE 2	NOTE 3	CUT	NOTE 1	EXPANDED FILL	NOTE 4
1474+64.99	147464.99	14.99	188.94	34.83	0.00	113	19		1	8927	4322	3053	
1474+88.59	147488.59	23.60	179.57	0.29	0.29	0	161	31	0	9088	4322	3183	
1475+25.18	147525.18	36.59	97.47	23.10	0.03	188	40	0	0	9276	4322	3331	
1475+40.18	147540.18	15.00	138.94	23.23	7.39	66	13	2	2	9342	4324	3382	
1475+85.08	147585.08	44.90	150.65	26.70	36.16	241	36		36	9583	4360	3545	
1476+00.00	147600.00	14.92	154.40	26.86	31.82	84	15	19		9667	4379	3595	
1476+50.00	147650.00	50.00	192.38	0.00	0.00	321	97	29	321	9988	4408	3790	
1477+00.00	147700.00	50.00	77.56	0.00	40.29	230	76	4	37	10218	4445	3907	
1477+50.00	147750.00	50.00	4.85	2.89	40.29	162	40	462	40	10380	4485	4025	
1477+60.31	147760.31	10.31	119.02	0.00	2.94	39	1		1	10419	4486	4063	
1478+00.00	147800.00	39.69	394.43	0.00	8.59	352	0	0	8	10771	4494	4407	
1478+50.00	147850.00	50.00	264.43	0.00	6.23	410	14	0	14	11381	4508	5003	
1479+00.00	147900.00	50.00	205.57	0.00	4.04	435	0	0	10	11816	4518	5428	
1479+50.00	147950.00	50.00	167.51	0.00	2.40	345	0	6	6	12161	4524	5767	
1480+00.00	148000.00	50.00	135.21	0.00	2.06	280	0	4	4	12441	4528	6043	
1480+50.00	148050.00	50.00	118.16	0.00	1.72	235	0	0	4	12676	4532	6274	
1481+00.00	148100.00	50.00	105.32	0.00	5.73	207	0	0	7	12883	4539	6474	
1481+50.00	148150.00	50.00	104.04	0.00	22.32	194	0	0	26	13077	4565	6642	
1482+00.00	148200.00	50.00	108.33	0.00	32.10	197	0	0	50	13274	4615	6789	
1482+50.00	148250.00	50.00	104.80	0.00	47.95	197	0	0	74	13471	4689	6912	
1483+00.00	148300.00	50.00	103.33	0.00	46.50	193	0	0	87	13664	4776	7018	
1483+50.00	148350.00	50.00	122.72	0.00	0.47	209	0	0	0	13834	4819	7184	
1484+00.00	148400.00	50.00	139.14	0.00	0.00	61	0	0	0	13924	4819	7245	

FILE NAME:	N:\POS\CDU\09080600\CHETSPJAN\090801-EDW_5TH.GDWG
PROJECT NO:	1090-39-70
HWM:	IH 43
COUNTY:	WAUKESHA
EARTHWORK DATA	
SHEET	1564
PLOT DATE:	10/27/2025 11:54 AM
PLOT BY:	ABU AWAL MONTHER J
PLOT SCALE:	1" = 1'
WS0707CA0DS SHEET 49	

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4
453+00.00	45300.00	0.00	0.00	0.00	121.86	0	0	0	0	0
453+50.00	45350.00	50.00	0.00	0.00	110.41	0	0	215	0	215
454+00.00	45400.00	50.00	0.00	0.00	93.86	0	0	189	0	404
454+50.00	45450.00	50.00	0.00	0.00	60.53	0	0	143	0	547
455+00.00	45500.00	50.00	1.69	2	40.37	2	0	640	5	-638
455+50.00	45550.00	50.00	1.56	3	38.15	3	0	93	5	-708
456+00.00	45600.00	50.00	0.28	2	35.82	2	0	68	7	-774
456+50.00	45650.00	50.00	1.61	2	46.12	2	0	76	9	-848
457+00.00	45700.00	50.00	9.36	10	59.28	10	0	95	19	-936
457+50.00	45750.00	50.00	36.37	43	36.95	43	0	98	51	-983

PROJECT NO:	1090-39-70	HWY:	IH 43	COUNTY:	WAUKESHA	EARTHWORK DATA	SHEET	1565	E
FILE NAME: N:\POS\CAD\10903970\SHEETS\LAYOUT\1090101_EW_5TH104.DWG									
PLOT DATE: 10/27/2022 11:54 AM									
PLOT BY: ABUAWA, MUNTHEB J									
PLOT NAME: 1" = 1'									
LAYOUT NAME: 06									
WSDOT/CADD SHEET 49									

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL. (CY) (UNADJUSTED)			CUMULATIVE VOL. (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 4
454+50.27	45450.27	0.00	185.59	20.20		0	0		0	0	0
455+00.00	45500.00	49.73	187.48	14.07		344	32	678	344	678	344
455+50.00	45550.00	50.00	170.85	0.00		332	13	624	676	1302	671
456+00.00	45600.00	50.00	281.53	0.00		419	0	495	1095	1797	747
456+50.00	45650.00	50.00	390.02	0.00		622	0	272	1717	2069	397
457+00.00	45700.00	50.00	411.69	0.00		742	0	82	2459	2151	263
457+12.42	45712.42	12.42	144.92	0.00		144	0	3	2603	2154	404
457+25.51	45725.51	11.09	77.28	0.00		64	0	2663	2154	2154	454

PROJECT NO:	1090-39-70	HWY:	IH 43	COUNTY:	WAUKESHA	EARTHWORK DATA	SHEET	1566	E
FILE NAME:		N:\PROJECTS\10903900\SHEETS\10903901\EW_5TH164.DWG		PLOT DATE:		10/27/2025 11:54 AM	PLOT BY:		ABU, AWA, MUNTHEER J
LAYOUT NAME:		-07		PLOT SCALE:		1" = 1'	WORKSHEET SHEET 49		

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) [UNADJUSTED]			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	EXPANDED FILL	MASS ORDINATE
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4
457+00.00	45700.00	0.00	699.41	0.00	1.03	0	0	0	0	0
457+50.00	45750.00	50.00	294.21	0.00	4.29	920	0	5	920	915
458+00.00	45800.00	50.00	385.86	0.00	13.22	630	0	16	1550	1529
458+50.00	45850.00	50.00	474.64	0.00	23.25	797	0	34	2347	2292
459+00.00	45900.00	50.00	489.14	0.00	23.64	892	0	43	3239	3141
459+50.00	45950.00	50.00	458.79	0.00	15.72	36	0	36	4117	3983
460+00.00	46000.00	50.00	398.70	0.00	5.27	794	0	19	4911	4758
460+50.00	46050.00	50.00	364.77	0.00	1.20	607	0	6	5618	5459
461+00.00	46100.00	50.00	191.58	0.00	0.00	515	0	1	6133	5973
461+50.00	46150.00	50.00	117.01	0.00	0.00	286	0	0	6419	6259
462+00.00	46200.00	50.00	53.63	0.00	1.81	157	0	2	6576	6414

FILE NAME:	N:\PROJECTS\0993900\SHEETS\PLAN\090101\EW_5TH.DWG	
PROJECT NO:	1090-39-70	HWY: IH 43
COUNTY:	WAUKESHA	EARTHWORK DATA
PLOT DATE: 10/27/2025 11:54 AM PLOT BY: ABU AWMA, MUNTHE J PLOT NAME:	PLOT SCALE: 1" = 1' WSDOT/CADDIS SHEET 491	
SHEET 1567		E

STH 164 RAMP D1			AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
STATION	REAL STATION	DISTANCE	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	1.00	NOTE 4
457+42.35	45742.35	0.00	148.80	0.00	0.00	0	0	0	0	0	0
457+75.12	45775.12	32.77	87.64	0.00	5.36	143	0	3	143	3	140
458+00.00	45800.00	24.88	76.20	0.00	15.33	75	0	10	218	205	205
458+50.00	45850.00	50.00	62.38	0.00	54.13	64	0	64	346	77	269
459+00.00	45900.00	50.00	12.20	0.00	210.51	69	0	245	415	322	93
459+50.00	45950.00	50.00	37.01	0.00	339.41	46	0	509	461	831	-370
460+00.00	46000.00	50.00	103.48	0.00	430.97	130	16	713	591	1544	-969
460+50.00	46050.00	50.00	17.22	0.00	475.41	167	32	839	758	2383	-1673
461+00.00	46100.00	50.00	109.07	0.00	410.06	172	34	920	930	3203	-2355
461+50.00	46150.00	50.00	138.25	0.00	348.90	229	37	703	1159	3906	-2866
462+00.00	46200.00	50.00	172.34	0.00	278.22	287	37	526	1446	526	3192

Addendum No. 01
ID 1090-39-70
Revised Sheet 1568
January 6, 2026

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) [UNADJUSTED]				CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 4
0+99.38	99.38	0.00	43.54	0.00	0.13	0	0	0	0	0
1+27.61	127.61	28.23	43.98	0.00	3.21	45	0	2	45	45
1+50.00	150.00	22.39	62.90	0.00	0.00	44	0	1	89	86
1+63.43	163.43	13.43	63.91	0.00	0.52	32	0	0	121	118
1+76.71	176.71	13.28	39.18	0.00	7.77	25	0	2	146	141
2+73.30	273.30	96.59	26.39	0.00	5.56	117	0	24	263	234
3+00.00	300.00	26.70	51.60	0.00	14.30	39	0	10	302	263
3+13.92	313.92	13.92	37.22	0.00	54.73	23	0	18	325	268
3+27.09	327.09	13.17	36.64	0.00	19.46	18	0	18	343	268
3+50.00	350.00	22.91	34.77	0.00	0.01	30	0	8	373	290
3+77.69	377.69	27.69	43.47	0.00	0.00	40	0	0	413	330
3+97.53	397.53	19.84	38.00	0.00	0.00	30	0	0	443	360

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) [UNADJUSTED]				CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 6
17+28.10	1728.10	0.00	14.22	10.00	0.00	0	0	0	0	0
17+50.00	1750.00	21.90	24.53	10.00	0.32	16	8	0	16	8
18+00.00	1800.00	50.00	16.08	10.00	0.62	38	19	1	54	26
18+50.00	1850.00	50.00	27.24	10.00	0.00	40	19	1	94	46
18+53.20	1853.20	3.20	24.63	10.00	0.00	3	1	0	97	48
21+37.75	2137.75	0.00	21.70	10.00	0.00	0	0	0	97	48
21+50.00	2150.00	12.25	22.27	10.00	1.56	10	5	0	107	53
22+00.00	2200.00	50.00	15.92	10.00	0.67	35	19	2	142	67
22+50.00	2250.00	50.00	14.41	10.00	2.89	28	19	3	170	73
22+91.68	2291.68	41.68	11.94	10.00	0.02	20	15	2	190	76

Addendum No. 01
ID 1090-39-70
Revised Sheet 1569
January 6, 2026

BIG BEND PARK & RIDE

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORINATE	NOTE 4
11+00.72	1100.72	0.00	69.33	0.00	0.00	0	0	0	0	0	0	0
11+50.00	1150.00	49.28	81.36	0.00	0.00	138	0	0	138	0	138	138
12+00.00	1200.00	50.00	80.65	0.00	0.00	150	0	0	288	0	288	288
12+33.47	1233.47	33.47	67.47	0.00	0.00	92	0	0	380	0	380	380
12+50.00	1250.00	16.53	54.50	0.00	0.00	37	0	0	417	0	417	417
12+68.47	1268.47	18.47	44.15	0.00	3.00	34	0	1	451	1	450	450
13+00.00	1300.00	31.53	39.91	12.75	4.87	49	7	5	500	6	487	487
13+32.25	1332.25	32.25	39.93	12.75	4.22	48	15	5	548	11	515	515
13+50.00	1350.00	17.75	39.91	12.75	3.77	26	8	3	574	14	530	530
13+82.25	1382.25	32.25	39.86	12.75	5.22	48	15	5	622	19	558	558
14+00.00	1400.00	17.75	39.90	12.75	3.76	26	8	3	648	22	573	573
14+50.00	1450.00	50.00	50.06	0.00	6.63	83	12	10	731	32	634	634
14+58.47	1458.47	8.47	69.89	0.00	6.59	19	0	2	750	34	651	651
14+93.34	1493.34	34.87	146.61	0.00	7.29	140	0	9	890	43	782	782
15+23.28	1523.28	29.94	119.05	0.00	0.00	147	0	4	1037	47	925	925
15+50.00	1550.00	26.72	80.80	0.00	0.00	99	0	0	1136	47	1024	1024
15+91.49	1591.49	41.49	0.85	0.00	0.00	63	0	0	1199	47	1087	1087

STH 164 DRY PONDS

LOCATION	INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)			
	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	NOTE 3	CUT	EXPANDED FILL	MASS ORINATE	NOTE 4
DRY POND 1	1,791	262	272	1,791	1,791	272	1,257	1,257
DRY POND 2	1,232	179	632	1,232	1,232	632	421	421
DRY POND 3	1,128	97	294	1,128	1,128	294	737	737
DRY POND 4	2,328	237	532	2,328	2,328	532	1,559	1,559
DRY POND 5	2138	126	38	2,138	2,138	38	1,974	1,974
DRY POND 6	3,204	498	155	3,204	3,204	155	2,551	2,551

NOTES:

- 1 - CUT
- 2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- 3 - FILL
- 4 - MASS ORINATE
- CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
- THIS DOES NOT SHOW UP IN CROSS SECTIONS
- INCLUDES EXISTING HMA PAVEMENT, RUBBLIZED AND INTACT REINFORCED CONCRETE PAVEMENT, ASPHALT STABILIZED BASE COURSE AND ASPHALTIC SHOULDERS
- DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
- MASS ORINATE DOES NOT INCLUDE EBS

PROJECT NO: 1090-39-70

HWY: IH 43

COUNTY: WAUKESHA

EARTHWORK DATA

SHEET 1569

E

FILE NAME: N:\PROJ\CD\10903900\SHETS\PLAN\0101-EW_STH164.DWG

LAYOUT NAME: 1D

PLOT DATE: 10/27/2025 11:58 AM

PLOT BY: ABU/AMA, MUNTHEP J

PLOT SCALE: 1" = 1'

WISDOT/CADD SHEET 49

Division 1 - IH43 SOUTH CROSSOVER

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)			
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDINATE	NOTE 8
			SALVAGED/UNUSABLE PAVEMENT MATERIAL		SALVAGED/UNUSABLE PAVEMENT MATERIAL		NOTE 1		NOTE 3	
			NOTE 1		NOTE 2		NOTE 4		NOTE 5	
79+59.651	7959.65	0.00	19.54	0.00	1.68	0	0	0	0	0
79+96.618	7996.62	36.97	20.32	3.44	1.69	27	2	27	2	23
80+46.618	8046.62	50.00	17.82	3.42	1.74	35	6	62	5	49
80+96.618	8096.62	50.00	16.61	3.45	0.54	32	6	2	94	73
81+50.723	8150.72	54.10	33.49	7.23	0.30	50	11	1	144	8
81+96.618	8196.62	45.90	34.07	7.31	0.54	57	12	1	201	9
82+46.618	8246.62	50.00	33.30	7.47	0.44	62	14	1	263	10
82+96.618	8296.62	50.00	44.40	7.42	2.96	72	14	3	335	13
83+46.618	8346.62	50.00	36.81	7.32	1.43	75	14	4	410	17
83+96.618	8396.62	50.00	43.33	7.33	19.49	74	14	19	484	36
84+46.618	8446.62	50.00	53.18	7.29	34.12	89	14	50	573	86
84+96.618	8496.62	50.00	56.38	7.31	45.39	101	14	74	674	160
85+47.018	8547.02	50.40	50.15	7.33	57.25	99	14	96	773	256
85+96.618	8596.62	49.60	23.74	0.00	73.56	68	7	120	841	376
86+46.618	8646.62	50.00	11.63	0.00	67.47	33	0	131	874	507
86+96.618	8696.62	50.00	7.66	0.00	51.84	18	0	110	892	617
87+46.618	8746.62	50.00	6.94	0.00	57.58	14	0	101	906	718
87+96.618	8796.62	50.00	6.19	0.00	75.84	12	0	124	918	842
88+46.618	8846.62	50.00	4.47	0.00	62.97	10	0	129	928	971
88+96.618	8896.62	50.00	4.54	0.00	56.36	8	0	110	936	1081
89+46.618	8946.62	50.00	6.94	0.00	57.53	11	0	105	947	1186
89+96.618	8996.62	50.00	17.95	0.00	59.51	23	0	108	970	1294
90+46.618	9046.62	50.00	33.90	3.76	56.54	48	3	107	1018	1401
90+96.618	9096.62	50.00	49.14	7.52	49.57	77	10	98	1095	1499
91+46.618	9146.62	50.00	47.78	7.54	32.15	90	14	76	1185	1575
91+96.618	9196.62	50.00	45.64	7.56	19.58	87	14	48	1272	1623
92+46.618	9246.62	50.00	39.10	7.58	10.95	78	14	28	1350	1651
92+96.618	9296.62	50.00	36.80	7.59	10.35	70	14	20	1420	1671
93+46.618	9346.62	50.00	37.43	12.94	7.14	69	19	16	1489	1687
93+96.618	9396.62	50.00	36.16	12.23	8.77	68	23	15	1557	1702
94+46.618	9446.62	50.00	32.59	12.01	10.88	64	22	18	1621	1720
94+96.618	9496.62	50.00	31.23	11.68	14.39	59	22	23	1680	1743
95+46.618	9546.62	50.00	33.67	11.40	15.1	60	21	15	1740	1758
95+96.618	9596.62	50.00	36.02	10.87	14.87	65	21	15	1805	1773
96+46.618	9646.62	50.00	39.31	10.31	14.73	70	20	27	1875	1800
96+96.618	9696.62	50.00	39.57	10.11	15.40	73	19	28	1948	1828
97+46.618	9746.62	50.00	39.52	9.90	5.89	73	19	20	2021	1848
97+96.618	9796.62	50.00	18.19	4.38	4.26	53	13	9	2074	1857
98+46.618	9846.62	50.00	20.89	4.38	5.79	36	8	9	2110	1866
98+96.618	9896.62	50.00	20.86	4.37	8.77	39	8	13	2149	1879
99+46.618	9946.62	50.00	21.52	4.36	7.05	39	8	15	2188	1894
99+96.614	9996.61	50.00	22.85	4.34	1.16	41	8	8	2229	1902
100+35.496	10035.50	38.88	21.32	4.37	0.00	32	6	1	2261	1903

Notes:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDINATE	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

CROSSOVERS - STAGE 1B SOUTH

Division 2 - IH43 CENTRAL CROSSOVER

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDNATE
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	1.00	NOTE 8
117+96.54	11796.54	0.00	27.12	7.94	1.68	0	0	0	0	0	0
118+46.54	11846.54	50.00	28.31	7.87	0.14	51	15	2	51	2	34
118+96.54	11896.54	50.00	29.70	7.81	0.01	54	15	0	105	2	73
119+46.54	11946.54	50.00	28.80	7.75	0.61	54	14	1	159	3	112
119+96.54	11996.54	50.00	29.01	7.70	1.11	54	14	2	213	5	150
120+46.54	12046.54	50.00	30.90	7.64	2.50	55	14	3	268	8	188
120+96.54	12096.54	50.00	34.79	7.56	2.65	61	14	5	329	13	230
121+46.54	12146.54	50.00	38.28	7.34	2.01	68	14	4	397	17	280
121+96.54	12196.54	50.00	40.94	7.11	2.77	73	13	4	470	21	336
122+46.54	12246.54	50.00	45.36	6.92	7.06	80	13	9	550	30	394
122+96.54	12296.54	50.00	45.23	3.75	10.78	84	10	17	634	47	451
123+46.54	12346.54	50.00	40.50	3.78	19.29	79	7	28	713	75	495
123+96.54	12396.54	50.00	36.59	3.75	20.73	71	7	37	784	112	522
124+46.54	12446.54	50.00	27.02	0.00	22.85	59	3	40	843	152	538
124+96.54	12496.54	50.00	25.76	1.35	16.86	49	1	37	892	189	549
125+46.54	12546.54	50.00	17.99	1.53	5.61	41	3	21	933	210	566
125+96.54	12596.54	50.00	24.30	3.55	9.81	39	5	14	972	224	586
126+46.54	12646.54	50.00	46.01	11.56	0.99	65	14	10	1037	234	627
126+96.54	12696.54	50.00	5.63	2.75	37.22	48	13	35	1085	269	627
127+46.54	12746.54	50.00	4.03	1.37	46.76	9	4	78	1094	347	554
127+96.54	12796.54	50.00	6.21	0.00	44.40	9	1	84	1103	431	478
128+46.54	12846.54	50.00	12.37	0.00	42.86	17	0	81	1120	512	414
128+96.54	12896.54	50.00	21.58	3.75	44.18	31	3	81	1151	593	361
129+46.54	12946.54	50.00	25.19	3.75	51.40	43	7	88	1194	681	309
129+96.54	12996.54	50.00	28.00	3.75	46.15	49	7	90	1243	771	261
130+46.54	13046.54	50.00	31.06	3.75	42.78	55	7	82	1298	853	227
130+96.54	13096.54	50.00	35.28	5.67	33.22	61	9	70	1359	923	209
131+46.54	13146.54	50.00	36.50	6.82	23.26	66	12	52	1425	975	211
131+96.54	13196.54	50.00	32.17	7.55	21.49	64	13	41	1489	1016	221
132+46.54	13246.54	50.00	32.38	7.54	27.36	60	14	45	1549	1061	222
132+96.54	13296.54	50.00	30.05	7.50	25.09	58	14	49	1607	1110	217
133+46.54	13346.54	50.00	33.57	7.48	17.43	59	14	39	1666	1149	223
133+96.54	13396.54	50.00	36.02	7.49	16.11	64	14	31	1730	1180	242
134+46.54	13446.54	50.00	37.16	7.50	17.01	68	14	31	1798	1211	265
134+96.54	13496.54	50.00	37.59	7.51	17.24	69	14	32	1867	1243	288
135+46.54	13546.54	50.00	37.92	7.50	18.58	70	14	33	1937	1276	311
135+96.54	13596.54	50.00	32.20	10.10	18.23	65	16	34	2002	1310	326
136+46.54	13646.54	50.00	37.73	7.51	8.22	65	16	24	2067	1334	351
136+96.54	13696.54	50.00	34.32	7.61	5.77	67	14	13	2134	1347	391
137+46.54	13746.54	50.00	34.16	7.51	0.27	63	14	6	2197	1353	434
137+96.54	13796.54	50.00	37.49	7.52	0.06	66	14	0	2263	1353	486
138+46.54	13846.54	50.00	26.12	3.75	0.00	59	10	0	2322	1353	535
138+96.54	13896.54	50.00	25.52	3.75	0.00	48	7	0	2370	1353	576
139+46.54	13946.54	50.00	22.62	3.74	0.00	45	7	0	2415	1353	614
139+96.54	13996.54	50.00	23.00	3.69	0.00	42	7	0	2457	1353	649
140+46.54	14046.54	50.00	20.72	3.64	0.01	40	7	0	2497	1353	682
140+96.54	14096.54	50.00	17.20	3.59	0.00	35	7	0	2532	1353	710

Notes:
1 - CUT
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL
3 - FILL
8 - MASS ORDINATE

CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
THIS DOES NOT SHOW UP IN CROSS SECTIONS
DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

Addendum No. 01
ID 1090-39-70
Revised Sheet 1571
January 6, 2026

CROSSOVERS - STAGE 1B CENTRAL

Division 3 - IH43 NORTH CROSSOVER

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 1	NOTE 8
489+41.489	48941.49	0.00	15.05	4.60	0.00	0	0	0	0	0	0
489+96.495	48996.49	55.01	15.61	4.60	1.27	31	9	4.60	1	31	21
490+46.5	49046.50	50.01	14.97	4.57	2.68	28	8	4	59	5	37
490+96.505	49096.51	50.01	38.73	8.13	0.57	50	12	3	109	8	72
491+46.511	49146.51	50.01	35.94	8.26	0.14	69	15	1	178	9	125
491+96.516	49196.52	50.01	36.08	8.38	0.65	67	15	1	245	10	176
492+46.522	49246.52	50.01	35.58	8.19	1.43	66	15	2	311	12	225
492+96.525	49296.53	50.00	34.86	7.88	0.40	65	15	2	376	14	273
493+46.525	49346.53	50.00	33.76	7.85	0.74	64	15	1	440	15	321
493+96.525	49396.53	50.00	32.74	8.00	0.80	62	15	1	502	16	367
494+46.525	49446.53	50.00	32.58	8.14	4.81	60	15	5	562	21	407
494+96.525	49496.53	50.00	34.13	7.79	8.91	62	15	13	624	34	441
495+46.525	49546.53	50.00	38.78	7.45	15.08	68	14	22	692	56	473
495+96.525	49596.53	50.00	42.11	7.21	21.48	75	14	34	767	90	500
496+46.525	49646.53	50.00	44.60	7.19	39.43	80	13	56	847	146	511
496+96.525	49696.53	50.00	48.14	7.37	55.49	86	13	88	933	234	496
497+46.525	49746.53	50.00	49.21	7.56	58.99	90	14	106	1023	340	466
497+96.525	49796.53	50.00	46.57	3.75	58.81	89	10	109	1112	449	436
498+46.525	49846.53	50.00	33.07	3.75	54.84	74	7	105	1186	554	398
498+96.525	49896.53	50.00	23.27	0.00	44.69	52	3	92	1238	646	355
499+46.525	49946.53	50.00	13.11	0.00	34.97	34	0	74	1272	720	315
499+96.525	49996.53	50.00	7.02	0.00	52.37	19	0	81	1291	801	253
500+46.525	50046.53	50.00	6.21	0.00	61.67	12	0	106	1303	907	159
500+96.525	50096.53	50.00	6.83	0.00	63.75	12	0	116	1315	1023	55
501+46.525	50146.53	50.00	6.89	0.00	56.73	13	0	112	1328	1135	-44
501+96.525	50196.53	50.00	8.86	0.00	42.27	15	0	92	1343	1227	-121
502+46.525	50246.53	50.00	16.27	0.00	37.47	23	0	74	1366	1301	-172
502+96.525	50296.53	50.00	27.83	0.00	51.57	41	0	82	1407	1383	-213
503+46.525	50346.53	50.00	46.49	3.89	63.33	69	4	106	1476	1489	-254
503+96.525	50396.53	50.00	55.06	8.34	54.33	94	11	109	1570	1598	-280
504+46.525	50446.53	50.00	57.32	9.09	36.01	104	16	84	1674	1682	-276
504+96.525	50496.53	50.00	54.68	9.83	12.00	104	18	44	1778	1726	-234
505+46.525	50546.53	50.00	23.20	4.28	6.29	72	13	17	1850	1743	-192
505+96.525	50596.53	50.00	20.14	4.43	3.60	40	8	9	1890	1752	-169
506+46.525	50646.53	50.00	17.93	4.51	0.30	35	8	4	1925	1756	-146

Notes:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDINATE	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

CROSSOVERS - STAGE 1B NORTH

Addendum No. 01
ID 1090-39-70
Revised Sheet 1572
January 6, 2026

9

Addendum No. 01
ID 1090-39-70
Revised Sheet 1573
January 6, 2026

Division 1 - IH43 SOUTH CROSSOVER REMOVAL											
STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) [UNADJUSTED]			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	MASS ORDNATE		
			NOTE 1		NOTE 2	NOTE 3		NOTE 1	NOTE 8		
			1.00			1.00		1.00			
90+46.618	9046.62	0.00	67.82	0.00	0.00	0	0	0	0		
90+96.618	9096.62	50.00	43.32	5.93	0.00	103	12	0	91		
91+46.618	9146.62	50.00	24.68	3.85	0.48	63	9	0	145		
91+96.618	9196.62	50.00	12.33	1.62	0.57	34	5	1	173		
92+46.618	9246.62	50.00	2.03	2.03	0.43	13	3	1	182		
92+96.618	9296.62	50.00	2.99	0.83	0.50	5	3	1	183		
93+46.618	9346.62	50.00	2.26	1.47	1.21	5	2	2	184		
93+96.618	9396.62	50.00	7.59	2.78	0.09	9	4	1	188		
94+46.618	9446.62	50.00	11.02	11.02	0.03	17	13	0	192		
94+96.618	9496.62	50.00	12.45	12.45	0.00	22	22	0	192		
95+46.618	9546.62	50.00	5.39	2.29	1.19	17	14	1	194		
95+96.618	9596.62	50.00	13.60	2.29	1.26	18	4	2	206		
96+21.618	9621.62	25.00	12.13	2.15	1.98	12	2	1	215		
96+46.618	9646.62	25.00	11.18	1.80	2.78	11	2	2	222		
96+96.618	9696.62	50.00	11.26	1.04	1.63	21	3	4	236		
97+46.618	9746.62	50.00	5.66	0.09	6.82	16	1	8	243		
97+89.280	9789.28	42.66	1.81	0.09	3.33	6	0	8	241		
97+96.618	9796.62	7.34	1.65	0.00	3.68	1	0	1	241		
98+46.618	9846.62	50.00	1.13	0.00	5.69	3	0	9	235		
98+96.618	9896.62	50.00	2.21	0.00	4.13	3	0	9	229		
99+46.618	9946.62	50.00	0.85	0.00	7.69	3	0	11	221		
99+96.614	9996.61	50.00	0.00	0.00	10.65	1	0	17	205		
100+36.122	10036.12	39.51	0.00	0.00	13.77	0	0	18	187		

Notes:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDNATE	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

SOUTH CROSSOVER REMOVAL

9

Addendum No. 01
ID 1090-39-70
Revised Sheet 1573
January 6, 2026

Notes:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDNATE	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

SOUTH CROSSOVER REMOVAL

Division 1 - IH43 SOUTH CROSSOVER ADJUSTED STAGE 4B

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 8
88+83.618	8883.62	0.00	31.16	10.16	0.00	0	0	0	0	0
89+46.618	8946.62	63.00	30.80	10.45	0.00	72	24	0	72	48
89+96.618	8996.62	50.00	31.39	10.71	0.00	58	20	0	130	86
90+46.618	9046.62	50.00	30.17	7.25	0.00	57	17	0	187	126
90+91.393	9091.39	44.77	34.42	8.86	0.00	54	13	0	241	167
91+46.618	9146.62	55.23	32.03	7.96	0.00	68	17	0	309	218
91+96.618	9196.62	50.00	30.12	7.22	0.00	58	14	0	367	262
92+46.618	9246.62	50.00	22.61	6.64	2.05	49	13	2	416	296
92+96.618	9296.62	50.00	20.93	5.70	1.18	40	11	3	456	322
93+46.618	9346.62	50.00	19.30	6.65	1.35	37	11	2	493	346
93+96.618	9396.62	50.00	21.10	5.83	1.03	37	12	2	530	369
94+46.618	9446.62	50.00	19.45	5.29	0.86	38	10	2	568	395
94+96.618	9496.62	50.00	18.93	4.82	0.67	36	9	1	604	421
95+46.618	9546.62	50.00	17.97	4.55	0.46	34	9	1	638	445

Division 2 - IH43 CENTRAL CROSSOVER ADJUSTED STAGE 4A

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
			NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 8
117+93.267	11793.27	0.00	8.66	1.68	0.46	0	0	0	0	0
117+96.54	11796.54	3.27	10.08	1.68	1.28	1	0	1	0	1
118+46.54	11846.54	50.00	9.60	1.67	0.83	18	3	2	19	14
118+96.54	11896.54	50.00	9.39	1.67	0.81	18	3	2	37	27
119+46.54	11946.54	50.00	9.20	1.67	1.16	17	3	2	54	39
119+96.54	11996.54	50.00	9.67	1.67	1.50	17	3	2	71	51
120+46.54	12046.54	50.00	10.36	1.92	1.76	19	3	3	90	64
120+96.54	12096.54	50.00	11.55	2.69	1.79	20	4	3	110	77
121+46.54	12146.54	50.00	13.02	3.47	1.49	23	6	3	133	91
121+96.54	12196.54	50.00	13.98	4.41	1.07	25	7	2	158	107
122+46.54	12246.54	50.00	16.40	5.52	1.44	28	9	2	186	124
122+96.54	12296.54	50.00	16.52	6.65	1.52	30	11	3	216	140
123+46.54	12346.54	50.00	20.29	7.47	2.44	34	13	4	250	157
123+96.54	12396.54	50.00	24.13	8.40	1.20	41	15	3	291	180
124+18.001	12418.00	21.46	26.09	8.79	0.80	20	7	1	311	192
124+46.54	12446.54	28.54	20.66	6.90	0.46	25	8	1	336	208
124+96.54	12496.54	50.00	29.05	7.96	0.00	46	14	0	382	240
125+46.54	12546.54	50.00	30.44	10.09	0.00	55	17	0	437	278
125+96.54	12596.54	50.00	28.05	9.23	0.00	54	18	0	491	314
126+46.54	12646.54	50.00	27.29	8.38	0.00	51	16	0	542	349

Addendum No. 01
ID 1090-39-70
Revised Sheet 1575
January 6, 2026

Notes:	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
1 - CUT	THIS DOES NOT SHOW UP IN CROSS SECTIONS
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
3 - FILL	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]
8 - MASS ORDINATE	

CROSSOVERS - STAGE 4

PROJECT NO: 1090-39-70	HWY: IH 43	COUNTY: WAUKESHA	EARTHWORK DATA	SHEET 1575	E
FILE NAME: X:\M\2023\2023043\DESIGN\TRANSPORTATION\DESIGN\QUANTITIES\REPORTS\040\AD\EA\THWORK DATA\SHEETS.DWG	LAYOUT NAME: 06	PLOT DATE: 1/9/2026 3:40 PM	PLOT BY: STEUCK BOB	PLOT SCALE: 1"=1'	WBS07/CADDS SHEET 49

Division 1 - IH43 FOX RIVER

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 8
184+71.662	18471.66	0.00	15.71	0.00	0.00	0	0	0	0	0
185+85.018	18585.02	113.36	18.79	0.63	7.14	72	1	15	72	15
185+97.453	18597.45	12.44	17.27	0.60	8.65	8	0	4	80	19
186+09.946	18609.95	12.49	14.28	0.57	8.23	7	0	4	87	23
186+34.945	18634.95	25.00	14.31	0.86	7.27	13	1	7	100	30
186+73.811	18673.81	38.87	8.88	1.10	34.42	17	1	30	117	60
189+56.676	18956.68	0.00	18.88	0.00	0.15	0	0	0	117	60
189+69.6	18969.60	12.92	14.78	0.00	0.64	8	0	0	125	60
189+94.58	18994.58	24.98	13.77	0.00	0.42	13	0	0	138	60
190+07.052	19007.05	12.47	12.66	0.00	0.82	6	0	0	144	60
190+19.559	19019.56	12.51	12.69	0.00	1.91	6	0	1	150	61
192+47.197	19247.20	227.64	14.32	0.00	0.01	114	0	8	264	69

Division 2 - IH43 EDGEWOOD AVE

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 8
214+26.278	21426.28	0.00	17.62	2.82	0.01	0	0	0	0	0
215+50.542	21550.54	124.26	21.60	2.82	0.19	90	13	0	90	0
215+63.08	21563.08	12.54	22.02	2.99	1.17	10	1	0	100	0
215+75.524	21575.52	12.44	20.78	2.83	1.45	10	1	1	110	1
216+00.507	21600.51	24.98	17.44	10.26	1.68	18	6	1	128	2
216+29.951	21629.95	29.44	15.03	0.00	8.03	18	6	5	146	7
219+83.886	21983.89	0.00	26.93	0.00	0.35	0	0	0	146	7
220+22.643	22022.64	38.76	20.48	0.00	2.13	34	0	2	180	9
220+47.631	22047.63	24.99	18.61	0.00	3.32	18	0	3	198	12
220+60.136	22060.14	12.50	17.32	0.00	5.01	8	0	2	206	14
220+72.619	22072.62	12.48	18.47	0.00	5.56	8	0	2	214	16
221+96.353	22196.35	123.73	16.34	0.00	1.12	80	0	15	294	31

Division 3 - IH43 OAKDALE DRIVE

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL
						NOTE 1	NOTE 2	NOTE 3	NOTE 1	NOTE 8
275+34.594	27534.59	0.00	15.48	0.00	0.00	0	0	0	0	0
276+47.641	27647.64	113.05	20.01	3.45	0.41	74	7	1	74	1
276+60.16	27660.16	12.52	18.89	3.72	0.10	9	2	0	83	1
276+72.628	27672.63	12.47	18.53	3.93	0.03	9	2	0	92	1
276+97.625	27697.63	25.00	19.34	4.51	0.08	18	4	0	110	1
277+35.883	27735.88	38.26	19.42	5.45	0.97	27	7	1	137	2
278+60.418	27860.42	0.00	20.32	0.00	0.71	0	0	0	137	2
279+00.415	27900.41	40.00	25.47	0.00	0.00	34	0	1	171	3
279+25.407	27925.41	24.99	18.22	0.00	3.22	20	0	1	191	4
279+37.888	27937.89	12.48	19.17	0.00	4.16	9	0	2	200	6
279+50.39	27950.39	12.50	19.28	0.00	6.65	9	0	3	209	9
280+60.933	28060.93	110.54	32.00	0.00	0.02	105	0	14	314	23

Notes:
1 - CUT
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL
3 - FILL
8 - MASS ORDINATE

CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
THIS DOES NOT SHOW UP IN CROSS SECTIONS
DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

Addendum No. 01
ID 1090-39-70
Revised Sheet 1576
January 6, 2026

PROJECT NO: 1090-39-70

HWY: IH 43

COUNTY: WAUKESHA

TEMPORARY END PROTECTION

EARTHWORK DATA

PLOT NAME:

1"=1'

SHEET 1576

WISDOT/CADDS SHEET 49

Addendum No. 01
ID 1090-39-70
Revised Sheet 1578
January 6, 2026

DIVISION 1 - STH 164

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDNATE

Notes:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDNATE	[CUT - SALVAGED PAVT - (FILL * FILL FACTOR)]

STH 164 TEMPORARY WIDENING

9

9

DIVISION 1 - ILL 43 NB TEMPORARY ENTRANCE RAMP CONNECTION - STA 1164