

JANUARY 2026

ORDER OF SHEETS

Section No. 1 Title
 Section No. 2 Typical Sections and Details
 Section No. 3 Estimate of Quantities
 Section No. 3 Miscellaneous Quantities
 Section No. 4 Right of Way Plat
 Section No. 5 Plan and Profile
 Section No. 6 Standard Detail Drawings
 Section No. 7 Sign Plates
 Section No. 8 Structure Plans
 Section No. 9 Computer Earthwork Data
 Section No. 9 Cross Sections

TOTAL SHEETS = 106



DESIGN DESIGNATION

A.A.D.T.	2026	= 660
A.A.D.T.	2046	= 890
D.H.V.		= 106
D.D.		= 50/50
T.		= 15%
DESIGN SPEED		= 45 MPH
ESALS		= 360,000

CONVENTIONAL SYMBOLS

PLAN	PROFILE
CORPORATE LIMITS	GRADE LINE
PROPERTY LINE	ORIGINAL GROUND
LOT LINE	MARSH OR ROCK PROFILE (To be noted as such)
LIMITED HIGHWAY EASEMENT	SPECIAL DITCH
EXISTING RIGHT OF WAY	GRADE ELEVATION
PROPOSED OR NEW R/W LINE	CULVERT (Profile View)
SLOPE INTERCEPT	UTILITIES
REFERENCE LINE	ELECTRIC
EXISTING CULVERT	FIBER OPTIC
PROPOSED CULVERT (Box or Pipe)	GAS
COMBUSTIBLE FLUIDS	SANITARY SEWER
MARSH AREA	STORM SEWER
WOODED OR SHRUB AREA	TELEPHONE
	WATER
	UTILITY PEDESTAL
	POWER POLE
	TELEPHONE POLE

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION


PLAN OF PROPOSED IMPROVEMENT

CTH N - T CLIFTON

INDIAN CREEK BRIDGE B-41-0335

CTH A
MONROE COUNTY

STATE PROJECT NUMBER
5116-00-71



STATE PROJECT

5116-00-71

FEDERAL PROJECT

WISC 2026129

1

ACCEPTED FOR
 MONROE COUNTY

Date 08/21/25 (Signature and Title of Official)

ORIGINAL PLANS PREPARED BY

Mead & Hunt



DATE: 8/13/2025 (Professional Engineer Signature)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

PREPARED BY
 Surveyor MEAD & HUNT
 Designer MEAD & HUNT
 Project Manager DELLA KOENIG, PE
 Regional Examiner
 Regional Supervisor KYLE HEMP, PE

APPROVED FOR THE DEPARTMENT
 DATE: (Signature) Digitally signed by Della Koenig P.E. Date: 2025-08-21 15:51:42-05'00'

E

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

CONTRACTOR WILL BE RESPONSIBLE FOR RESHAPING AND SEEDING ANY PREVIOUSLY GRASSED AREAS WHICH ARE DISTURBED BY OPERATIONS, OUTSIDE OF THE NORMAL CONSTRUCTION LIMITS.

HMA PAVEMENT WEIGHT CALCULATIONS ARE BASED ON 112 LBS/SY/IN.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.

RIGHT OF WAY INFORMATION SHOWN ON THE PLANS IS APPROXIMATE.

THE CONTRACTOR IS TO WORK WITH UTMOST CARE AND PROTECT ALL SURVEY MARKERS. REMOVAL OF ANY SURVEY MARKER IS TO BE WITH THE APPROVAL OF THE ENGINEER.

WHEN THE QUANTITY OF THE ITEMS OF BASE AGGREGATE, SUBBASE OR HMA PAVEMENT IS MEASURED FOR PAYMENT BY THE TON OR CUBIC YARD, THE DEPTH OR THICKNESS OF THE LAYERS SHOWN ON THE PLAN IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

EROSION CONTROL FEATURES AS SHOWN IN THE PLANS ARE AT APPROXIMATE LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE CONTRACTOR'S EROSION CONTROL IMPLEMENTATION PLAN (ECIP) AND APPROVED BY THE ENGINEER. MAINTAIN EROSION CONTROL MEASURES UNTIL SUCH A TIME AS THE ENGINEER DETERMINES THE MEASURE IS NO LONGER NECESSARY.

THE EXACT LOCATION AND WIDTH OF DRIVEWAYS SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

SAWCUTS, AS SHOWN ON THE PLANS, ARE SUGGESTED LOCATIONS AND MAY BE ADJUSTED AT THE DISCRETION OF THE ENGINEER TO BETTER SUIT FIELD CONDITIONS.

PRIOR TO PLACEMENT OF BEAM GUARD THE SHOULDERS SHALL BE IN PLACE, SHAPED AND COMPACTED.

CONTRACTOR SHALL MAINTAIN ACCESS TO ALL DRIVEWAYS AT ALL TIMES EXCEPT WHEN PAVING OR PIPE LAYING OPERATIONS REQUIRE THE DRIVEWAY TO BE CLOSED. ACCESS TO DRIVEWAYS SHALL BE RE-ESTABLISHED IMMEDIATELY AFTER OPERATIONS ARE COMPLETED. ACCESS SHALL BE PROVIDED DURING ALL NON-WORKING HOURS.

TRAFFIC CONTROL DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.

DO NOT DRIVE OR STORE EQUIPMENT, OR STORE CONSTRUCTION MATERIALS IN ENVIRONMENTALLY SENSITIVE AREAS, WETLANDS OR WATERWAYS.

RUNOFF COEFFICIENT TABLE

LAND USE:	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)		SLOPE RANGE (PERCENT)
0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	
ROW CROPS:	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIPTURF:	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPETURF:			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT:												.70 - .95
CONCRETE:												.80 - .95
BRICK:												.70 - .80
DRIVES, WALKS:												.75 - .85
ROOFS:												.75 - .95
GRAVEL ROADS, SHOULDERS:												.40 - .60

TOTAL PROJECT AREA = 1.44 ACRES

TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.75 ACRES

DESIGN PROJECT MANAGER

DELLA KOENIG, PE
SOUTHWEST REGION
2101 WRIGHT STREET
MADISON, WI 53704
PHONE: (608) 246-7963
EMAIL: Della.Koenig@dot.wi.gov

WISCONSIN DNR LIAISON

KAREN KALVELAGE
DNR WEST CENTRAL REGION
3550 MORMON COULEE ROAD
LA CROSSE, WI 54601-6768
PHONE: (608) 406-7880
EMAIL: Karen.Kalvelage@Wisconsin.Gov

COUNTY HIGHWAY COMMISSIONER

DAVID OHNSTAD, PE
MONROE COUNTY
803 WASHINGTON STREET
SPARTA, WI 54656
PHONE: (608) 269-8740
EMAIL: David.Ohnstad@co.monroe.wi.us

UTILITIES CONTACTS

LEMONWEIR VALLEY TELEPHONE COMPANY	OAKDALE ELECTRIC COOPERATIVE
COMMUNICATION LINE	ELECTRICITY
BEN GRILLEY	MATT RIGGS
127 US HWY 12	489 OAKWOOD ST
P.O. BOX 267	TOMAH, WI 54660
CAMP DOUGLAS, WI 54618	PHONE: (608) 372-8828
PHONE: (608) 427-6515	mriggs@oakdalerec.com
Ben.Grilly@getlynxx.com	

ORDER OF SECTION 2 DETAIL SHEETS

GENERAL NOTES
TYPICAL SECTIONS
CONSTRUCTION DETAILS



Mead & Hunt



DESIGN CONTACT


JAY WHEATON, PE
MEAD & HUNT, INC
750 NORTH THIRD STREET
LA CROSSE, WI 54601
PHONE: (608) 386-0212
EMAIL: Jay.Wheaton@meadhunt.com

STANDARD ABBREVIATIONS

ABUT	ABUTMENT	LT	LEFT
AC	ACRE	LHF	LEFT HAND FORWARD
AGG	AGGREGATE	L	LENGTH OF CURVE
AH	AHEAD	LF	LINEAR FOOT
∠	ANGLE	LC	LONG CHORD OF CURVE
AADT	ANNUAL AVERAGE DAILY TRAFFIC	LS	LUMP SUM
AEW	APRON ENDWALL	MGAL	ONE THOUSAND GALLONS
ASPH	ASPHALTIC	MH	MANHOLE
BK	BACK	ML OR M/L	MATCH LINE
BC	BACK OF CURB	NOM	NOMINAL
BAD	BASE AGGREGATE DENSE	NC	NORMAL CROWN
BL OR B/L	BASE LINE	NB	NORTHBOUND
BM	BENCH MARK	NO	NUMBER
CB	CATCH BASIN	OD	OUTSIDE DIAMETER
CL OR C/L	CENTER LINE	PAVT	PAVEMENT
Δ	CENTRAL ANGLE OR DELTA	PLE	PERMANENT LIMITED EASEMENT
CE	COMMERCIAL ENTRANCE	PC	POINT OF CURVATURE
CONC	CONCRETE	PI	POINT OF INTERSECTION
CSW	CONCRETE SIDEWALK	PT	POINT OF TANGENCY
CONST	CONSTRUCTION	PCC	PORTLAND CEMENT CONCRETE
CP	CONTROL POINT	LB	POUND
CO	COUNTY	PSI	POUNDS PER SQUARE INCH
CTH	COUNTY TRUCK HIGHWAY	PE	PRIVATE ENTRANCE
CY	CUBIC YARD	PROJ	PROJECT
CP	CULVERT PIPE	PL	PROPERTY LINE
CPCA	CULVERT PIPE CORRUGATED ALUMINUM	PRW	PROPOSED RIGHT OF WAY
CPCPE	CULVERT PIPE CORRUGATED POLYETHYLENE	R	RADIUS
CPCPP	CULVERT PIPE CORRUGATED POLYPROPYLENE	RL OR R/L	REFERENCE LINE
CPCS	CULVERT PIPE CORRUGATED STEEL	REQD	REQUIRED
CPCSAC	CULVERT PIPE CORRUGATED STEEL ALUMINUM COATED	RT	RIGHT
CPCSPC	CULVERT PIPE CORRUGATED STEEL POLYMER COATED	RHF	RIGHT HAND FORWARD
CPRC	CULVERT PIPE REINFORCED CONCRETE	R/W	RIGHT OF WAY
CPRCHE	CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL	RD	ROAD
CPS	CULVERT PIPE SALVAGED	RDWY	ROADWAY
CPT	CULVERT PIPE TEMPORARY	SHLDR	SHOULDER
C & G	CURB AND GUTTER	SW	SIDEWALK
D	DEGREE OF CURVE	SB	SOUTHBOUND
DHV	DESIGN HOUR VOLUME	SPECS	SPECIFICATIONS
DIA	DIAMETER	SF	SQUARE FEET
DD	DIRECTIONAL DISTRIBUTION	SY	SQUARE YARD
DE	DRAINAGE EASEMENT	SDD	STANDARD DETAIL DRAWINGS
DWY	DRIVEWAY	STH	STATE TRUNK HIGHWAY
EA	EACH	STA	STATION
EB	EASTBOUND	SSPC	STORM SEWER PIPE COMPOSITE
EL OR ELEV	ELEVATION	SSCP	STORM SEWER PIPE CORRUGATED POLYETHYLENE
EMB	EMBANKMENT	SSCPP	STORM SEWER PIPE CORRUGATED POLYPROPYLENE
EW	ENDWALL	SSPNRC	STORM SEWER PIPE NON-REINFORCED CONCRETE
EAT	ENERGY ABSORBING TERMINAL	SSPRC	STORM SEWER PIPE REINFORCED CONCRETE
ESALS	EQUIVALENT SINGLE AXLE LOADS	SSPRC	STORM SEWER PIPE REINFORCED CONCRETE
EXC	EXCAVATION	SSPRCHE	STORM SEWER PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL
EBS	EXCAVATION BELOW SUBGRADE	SE	SUPERELEVATION
EXIST	EXISTING	SL OR S/L	SURVEY LINE
FERT	FERTILIZER	TEMP	TEMPORARY
FE	FIELD ENTRANCE	TI	TEMPORARY INTEREST
FL OR F/L	FLOW LINE	TLE	TEMPORARY LIMITED EASEMENT
FT	FOOT	TC	TOP OF CURB
FTMS	FREE TRAFFIC MANAGEMENT SYSTEM	TL OR T/L	TRANSIT LINE
HES	HIGH EARLY STRENGTH	T	TRUCKS (PERCENT OF)
HE	HIGHWAY EASEMENT	TYP	TYPICAL
CWT	HUNDRED WEIGHT	USH	UNITED STATES HIGHWAY
IN DIA	INCH DIAMETER	VAR	VARIABLE
INL	INLET	VC	VERTICAL CURVE
ID	INSIDE DIAMETER	VPC	VERTICAL POINT OF CURVATURE
INTERS	INTERSECTION	VPI	VERTICAL POINT OF INTERSECTION
IH	INTERSTATE HIGHWAY	VPT	VERTICAL POINT OF TANGENCY
INV	INVERT	W	WEST
JT	JOINT	WB	WESTBOUND








2

2



LEGE

The legend consists of five entries, each with a symbol followed by a text label. The symbols are: a series of vertical double hash marks for 'EROSION MAT URBAN CLASS I, TYPE'; a solid horizontal line with circular dots for 'SILT FENCE'; a dashed horizontal line with circular dots for 'RIP RAP HEAVY'; a dashed horizontal line with square markers for 'SLOPE INTERCEPT'; a double-headed arrow with horizontal dashes for 'TURBIDITY BARRIER'; and a wavy line for 'SURFACE WATER FLOW'.

PROJECT NO: 5116-00-71

HWY: CTH

COUNTY: MONROE

EROSION CONTROL

SHEET

8

FILE NAME : X:\1323000\240176.01\TECH\CAD\51160001\Sheets\022001_EC.DWG
LAYOUT NAME - 01

PLOT DATE : 8/22/2025 8:39 AM


PLOT BY : JEFF BRE


PLOT NAME

PLOT SCALE : 1 IN:50 FT

Page 10

7





Estimate Of Quantities

5116-00-71

Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	3.000	3.000
0004	201.0205	Grubbing	STA	3.000	3.000
0006	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. B-41-923	EACH	1.000	1.000
0008	204.0115	Removing Asphaltic Surface Butt Joints	SY	26.000	26.000
0010	204.0120	Removing Asphaltic Surface Milling	SY	400.000	400.000
0012	204.0165	Removing Guardrail	LF	170.000	170.000
0014	205.0100	Excavation Common	CY	487.000	487.000
0016	206.1001	Excavation for Structures Bridges (structure) 01. B-41-335	EACH	1.000	1.000
0018	208.0100	Borrow	CY	152.000	152.000
0020	210.1500	Backfill Structure Type A	TON	344.000	344.000
0022	213.0100	Finishing Roadway (project) 01. 5116-00-71	EACH	1.000	1.000
0024	305.0110	Base Aggregate Dense 3/4-Inch	TON	290.000	290.000
0026	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	1,280.000	1,280.000
0028	455.0605	Tack Coat	GAL	98.000	98.000
0030	465.0105	Asphaltic Surface	TON	410.000	410.000
0032	502.0100	Concrete Masonry Bridges	CY	156.000	156.000
0034	502.3200	Protective Surface Treatment	SY	219.000	219.000
0036	505.0400	Bar Steel Reinforcement HS Structures	LB	4,900.000	4,900.000
0038	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	24,970.000	24,970.000
0040	513.4061	Railing Tubular Type M	LF	90.000	90.000
0042	516.0500	Rubberized Membrane Waterproofing	SY	14.000	14.000
0044	550.1100	Piling Steel HP 10-Inch X 42 Lb	LF	490.000	490.000
0046	606.0300	Riprap Heavy	CY	80.000	80.000
0048	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	182.000	182.000
0050	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0052	614.2300	MGS Guardrail 3	LF	200.000	200.000
0054	614.2500	MGS Thrie Beam Transition	LF	157.600	157.600
0056	614.2610	MGS Guardrail Terminal EAT	EACH	4.000	4.000
0058	618.0100	Maintenance and Repair of Haul Roads (project) 01. 5116-00-71	EACH	1.000	1.000
0060	619.1000	Mobilization	EACH	1.000	1.000
0062	624.0100	Water	MGAL	32.000	32.000
0064	625.0500	Salvaged Topsoil	SY	1,570.000	1,570.000
0066	627.0200	Mulching	SY	170.000	170.000
0068	628.1504	Silt Fence	LF	1,135.000	1,135.000
0070	628.1520	Silt Fence Maintenance	LF	1,135.000	1,135.000
0072	628.1905	Mobilizations Erosion Control	EACH	5.000	5.000
0074	628.1910	Mobilizations Emergency Erosion Control	EACH	2.000	2.000
0076	628.2008	Erosion Mat Urban Class I Type B	SY	1,570.000	1,570.000
0078	628.6005	Turbidity Barriers	SY	250.000	250.000
0080	629.0210	Fertilizer Type B	CWT	1.300	1.300
0082	630.0120	Seeding Mixture No. 20	LB	56.000	56.000
0084	630.0200	Seeding Temporary	LB	61.000	61.000
0086	630.0500	Seed Water	MGAL	50.000	50.000
0088	638.2602	Removing Signs Type II	EACH	4.000	4.000
0090	638.3000	Removing Small Sign Supports	EACH	4.000	4.000
0092	642.5001	Field Office Type B	EACH	1.000	1.000
0094	643.0420	Traffic Control Barricades Type III	DAY	1,296.000	1,296.000
0096	643.0705	Traffic Control Warning Lights Type A	DAY	2,592.000	2,592.000
0098	643.0900	Traffic Control Signs	DAY	1,310.000	1,310.000

Estimate Of Quantities

5116-00-71

Line	Item	Item Description	Unit	Total	Qty
0100	643.5000	Traffic Control	EACH	1.000	1.000
0102	645.0111	Geotextile Type DF Schedule A	SY	108.000	108.000
0104	645.0120	Geotextile Type HR	SY	203.000	203.000
0106	646.1020	Marking Line Epoxy 4-Inch	LF	996.000	996.000
0108	650.4500	Construction Staking Subgrade	LF	585.000	585.000
0110	650.5000	Construction Staking Base	LF	585.000	585.000
0112	650.6501	Construction Staking Structure Layout (structure) 01. B-41-335	EACH	1.000	1.000
0114	650.9911	Construction Staking Supplemental Control (project) 01. 5116-00-71	EACH	1.000	1.000
0116	650.9920	Construction Staking Slope Stakes	LF	585.000	585.000
0118	690.0150	Sawing Asphalt	LF	390.000	390.000
0120	715.0502	Incentive Strength Concrete Structures	DOL	924.000	924.000
0122	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. 10+00	EACH	1.000	1.000
0124	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	300.000	300.000
0126	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	300.000	300.000
0128	SPV.0090	Special 01. Removing Existing Timber Piling	LF	192.000	192.000
0130	SPV.0090	Special 02. Flashing Stainless Steel	LF	38.000	38.000

DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION (1)	SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL (2)	UNEXPANDED FILL	EXPANDED FILL	MASS ORDINATE +/- (3)	208.0100 BORROW
			CUT				FACTOR		
MONROE CTH A	6+89.66 - 13+18.36	M/L	487	96	391	434	1.25	-152	152
	TOTAL COMMON EXC		487						

3

3

NOTES:

1 - CUT (SALVAGE/UNUSABLE PAVEMENT MATERIAL INCLUDED)
 2 - AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
 3 - THE MASS ORDINATE + OF - QUANTITIES CALCULATE FOR THE DIVISION. PLUS QUANTITIES INDICATES AN EXCESS OF MATERIAL. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

NO MARSH OR EBS IS ANTICIPATED.

		REMOVING ASPHALTIC SURFACE			
STATION	TO	STATION	LOCATION	SY	SY
7+52	-	7+57	M/L	13	-
7+57	-	8+75	M/L	-	290
12+00	-	12+45	M/L	-	110
12+45	-	12+50	M/L	13	-
		ITEM TOTALS		26	400

CLEARING & GRUBBING					
STATION	TO	STATION	LOCATION	STA	STA
8+00	-	11+00	M/L, LT	3	3
		ITEM TOTALS		3	3

REMOVING GUARDRAIL

REMOVING GUARDRAIL					
STATION	TO	STATION	LOCATION	LF	REMOVING GUARDRAIL
9+40	-	9+84	M/L, LT	44	
9+43	-	9+84	M/L, RT	41	
10+17	-	10+62	M/L, LT	45	
10+17	-	10+57	M/L, RT	40	
		ITEM TOTALS		170	

BASE AGGREGATE DENSE					
STATION	TO	STATION	LOCATION	TON	TON
6+89.7	-	9+79.7	M/L	140	590
10+25.3	-	13+18.4	M/L, LT & RT	140	690
12+15.0		FE, LT		10	-
		ITEM TOTALS		290	1,280
					32

ASPHALT ITEMS					
STATION	TO	STATION	LOCATION	TON	GAL
7+52.0	-	9+79.7	M/L	95	-
7+52.0	-	9+79.7	M/L	95	38
10+25.3	-	12+50.0	M/L	125	-
10+25.3	-	12+50.0	M/L	95	60
		ITEM TOTALS		410	98

SILT FENCE					
STATION	TO	STATION	LOCATION	LF	LF
6+90	-	9+80	M/L, LT & RT	575	575
10+25	-	13+18	M/L, LT & RT	560	560
		ITEM TOTALS		1135	1135

EROSION CONTROL SUMMARY					
STATION	TO	STATION	LOCATION	EACH	EACH
628.1504	628.1520	628.1905	628.1910	MOBILIZATIONS	MOBILIZATIONS
SILT	SILT	EROSION	EROSION	EMERGENCY	EMERGENCY
FENCE	FENCE	CONTROL	CONTROL	EROSION	EROSION
Maintenance					
		UNDISTRIBUTED	VARIOUS	5	2
		ITEM TOTALS		5	2

TURBIDITY BARRIERS					
STATION	TO	STATION	LOCATION	SY	REMARKS
9+91				120	LOWER LAYER
10+09				130	UPPER LAYER
		ITEM TOTALS		250	

LANDSCAPING ITEMS

			628.2008	630.0120							
		625.0500	629.0210	URBAN	SEEDING	630.0500					
		SALVAGED	TOPSOIL	MULCHING	FERTILIZER	CLASS I	TYPE B	MIXTURE	NO. 20	TEMPORARY	SEED WATER
STATION	TO	STATION	LOCATION	SY	SY	CWT	SY	LB	LB	MGAL	
6+89.7	-	9+79.7	M/L, LT & RT	800	-	0.6	800	28	28	23	
10+25.3	-	13+18.4	M/L, LT & RT	770	-	0.6	770	28	28	23	
BORROW SITE				-	-	170	0.1	-	5	4	
ITEM TOTALS				1570	170	1.3	1570	56	61	50	

SIGNING

				638.3000	
			638.2602		
			REMOVING	SMALL	
			SIGNS	SIGN	
			TYPE II	SUPPORTS	
STATION	LOCATION	SIGN MESSAGE	EACH	EACH	
8+82	M/L, LT & RT	TIGER STRIPES	2	2	
10+19	M/L, LT & RT	TIGER STRIPES	2	2	
ITEM TOTALS				4	4

TRAFFIC CONTROL SUMMARY

		643.0705									
		643.0420	TRAFFIC	643.0900		643.5000					
		TRAFFIC	CONTROL	TRAFFIC	WARNING	TRAFFIC	CONTROL	TRAFFIC	CONTROL	TRAFFIC	CONTROL
		BARRICADES	LIGHTS	TYPE III	TYPE A	SIGNS	CONTROL	TYPE III	TYPE A	TYPE III	TYPE A
LOCATION	DURATION	QTY*	DAY	QTY*	DAY	QTY*	DAY	EACH	REMARKS		
CTH A/MONROE	7	-	-	-	-	2	14	1	ADVANCED WARNING		
CTH A TRAFFIC CONTROL	72	18	1,296	36	2,592	18	1,296	-			
ITEM TOTALS		1,296		2,592		1,310		1			

* FOR INFORMATION ONLY

MGS GUARDRAIL

				614.2610	
		614.2300	614.2500		
		MGS GUARDRAIL	MGS THRIE BEAM		
		3		TRANSITION	TERMINAL EAT
STATION	TO	STATION	LOCATION	LF	LF EACH
8+38.8	-	8+91.7	M/L, LT	-	- 1
8+38.8	-	8+91.7	M/L, RT	-	- 1
8+91.7	-	9+41.9	M/L, LT	50.0	-
8+91.7	-	9+41.9	M/L, RT	50.0	-
9+41.9	-	9+81.3	M/L, LT	-	39.4
9+41.9	-	9+81.3	M/L, RT	-	39.4
10+20.7	-	10+59.8	M/L, LT	-	39.4
10+20.7	-	10+60.5	M/L, RT	-	39.4
10+59.8	-	11+08.8	M/L, LT	50.0	-
10+60.5	-	11+11.5	M/L, RT	50.0	-
11+08.8	-	11+60.7	M/L, LT	-	- 1
11+11.5	-	11+65.9	M/L, RT	-	- 1
ITEM TOTALS				200	157.6 4

RIPRAP AND GEOTEXTILE

		645.0111									
		606.0300	RIPRAP	GEOTEXTILE	TYPE DF	645.0120		GEOTEXTILE	TYPE HR		
CATEGORY	STATION	CY	SY	SY							
0030	WEST ABUTMENT	2	4	6							
0030	EAST ABUTMENT	3	4	7							
TOTALS		5	8	13							

***MONROE COUNTY PORTION OF PROPOSED BRIDGE CONSTRUCTION

PAVEMENT MARKING ITEMS

				646.1020	
		646.1020			
		MARKING LINE			
STATION	TO	STATION	LOCATION	LF	REMARKS
7+52	-	12+50	M/L	996	DOUBLE SOLID YELLOW CENTER LINE
ITEM TOTALS				996	


NOTE: ALL ITEMS AND QUANTITIES ON THIS SHEET ARE FOR ENGINEER ESTIMATE CATEGORY 0010, UNLESS OTHERWISE NOTED.

3
STAKING ITEMS

CATEGORY	STATION	TO STATION	LOCATION	650.4500		650.5000		650.6501		650.9911		650.9920	
				CONSTRUCTION	STAKING	CONSTRUCTION	STAKING	STRUCTURE	STAKING	SUPPLEMENTAL	STAKING	CONSTRUCTION	STAKING
				STAKING	SUBGRADE	STAKING	BASE	LAYOUT	CONTROL	5116-00-71	STAKING	CONSTRUCTION	STAKES
0010	PROJECT			-	-	-	-	-	-	1	-	-	-
0010	6+89	-	9+80	M/L	291	291	-	-	-	-	291	-	-
0010	10+25	-	13+19	M/L	294	294	-	-	-	-	294	-	-
0020	10+01			M/L	-	-	-	1	-	-	-	-	-
	ITEM TOTALS				585	585	1	1	1	585			


3
SAWING

STATION	LOCATION	690.0150	
		LF	SAWING
7+52	-	8+75	M/L, LT & RT
		8+75	M/L
12+00	-	12+50	M/L, LT & RT
		12+00	M/L
	ITEM TOTALS	390	



Standard Detail Drawing List


08D21-01	DRIVEWAYS WITHOUT CURB & GUTTER
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
12A03-10	NAME PLATE (STRUCTURES)
13C19-03	HMA LONGITUDINAL JOINTS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15C02-09A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-09B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C04-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 M.P.H. OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC
15C06-12	SIGNING & MARKING FOR TWO LANE BRIDGES
15C08-23A	PERMANENT LONGITUDINAL PAVEMENT MARKINGS
15C11-10B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS



PLAN VIEW
(UNPAVED SHOULDER ON HIGHWAY)

PLAN VIEW
(PAVED SHOULDER ON HIGHWAY)

RURAL DRIVEWAY INTERSECTION DETAIL
(NO CURB AND GUTTER OR SIDEWALK)




IN CUT

IN FILL

TYPICAL CROSS SECTION FOR
PRIVATE DRIVE OR FIELD ENTRANCE
AGGREGATE SURFACE

** SLOPE CAN VARY WITH
SPEED. SEE 11-45-30.6.2

POSTED SPEED MPH	MAX. SLOPE
<35	4:1
≥ 35 TO < 60	6:1
≥ 60	10:1



IN CUT


IN FILL

TYPICAL CROSS SECTION FOR
PRIVATE DRIVE OR FIELD ENTRANCE
ASPHALTIC SURFACE


DRIVEWAYS WITHOUT
CURB AND GUTTER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
December 2017 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVE
FHWA UNIT SUPERVISOR 17



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SILT FENCE AT MEDIAN SURFACE DRAINS


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.


- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1/8" X 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL



SILT FENCE




TWIST METHOD




HOOK METHOD

JOINING TWO LENGTHS OF SILT FENCE^⑤




SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)


SILT FENCE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED	/S/ Beth Cannon
4-29-05	DATE
CHIEF ROADWAY DEVELOP 18	
FHWA	




SECTION B - B

**TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6**


SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION
TURBIDITY BARRIER PLACEMENT DETAILS


PLAN VIEW




PLAN VIEW

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW



SECTION C - C

**TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES**
TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
6/4/02 /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA 19

GENERAL NOTES

NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.


THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.





TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

6




NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES

S.D.D. 12 A 3-10




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)


NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED	
3/26/10	/S/ Scot Beck
DATE	CHIEF STRUCTURAL DEVELOP 20
FHWA	



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY $0.1"$ AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO $2"$ FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)

HMA LONGITUDINAL JOINTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2020 /S/ Steven Hefel
DATE
FHWA

HMA PAVEMENT ENGIN 21

① WOOD OR STEEL POSTS (W6X9 OR W6X8.5) MAY BE USED. DO NOT INTERMIX WOOD AND STEEL POSTS. INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.

② USE WOOD OR APPROVED PLASTIC BLOCKOUTS. WOOD BLOCKOUTS MAY BE CONSTRUCTED OUT OF TWO OR MORE WOOD BLOCKOUTS. SEE ALTERNATE WOOD BLOCKOUT DETAIL. DIMENSIONS OF APPROVED PLASTIC BLOCKOUTS MAY VARY.


③ IF ROCK IS ENCOUNTERED DURING EXCAVATION, PROVIDE A HOLE 12 INCHES IN DIAMETER EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE APPROXIMATELY 2 1/2 INCHES OF GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE. CUT THE POSTS TO LENGTH AND INSTALL. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT. BACKFILL IS TO BE FREE OF LARGE ROCKS.

④ WHEN THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING (K).


⑤ FOR NEW MGS INSTALLATION TOP OF W-BEAM RAIL TOLERANCE IS ± 1 ". FOR EXISTING MGS INSTALLATION TOP OF W-BEAM IS BETWEEN 27 $\frac{3}{4}$ " TO 32".

⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.


⑦ TOTAL POST LENGTH FOR TYPE K IS 7' - 0".
TOTAL POST LENGTH FOR OTHER MGS TYPES IS 6' - 0".




END VIEW
LOCATED ALONG A ROADWAY SHOULDER
STANDARD INSTALLATION




END VIEW
LOCATED ALONG A CURBED ROADWAY




END VIEW
MGS LONGER POST AT HALFPOST
SPACING W BEAM (K)




END VIEW
SETTING STEEL OR WOOD POST IN ROCK




STEEL POST & HOLE
PUNCHING DETAIL
(W 6 X 9) ①




WOOD POST
(6" X 8") NOMINAL ①



PLAN VIEW
WOOD POST,
BLOCKOUT & BEAM




PLAN VIEW
STEEL POST,
PLASTIC BLOCKOUT & BEAM




WOOD OR PLASTIC
BLOCKOUT ②

MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




FRONT VIEW
POST SPACING STANDARD INSTALLATION



**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**



**FRONT VIEW
QUARTER POST SPACING (QS)**




FRONT VIEW
MID-SPAN BEAM SPLICE


GENERAL NOTES

POST BOLTS ARE A $\frac{3}{8}$ " DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT
REQUIRES $\frac{3}{8}$ " DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND $\frac{3}{8}$ "
DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS
ARE BEING USED.


GUARD RAIL SPLICE BOLTS ARE A $\frac{3}{8}$ " DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES $\frac{5}{8}$ " DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAII




ONE SIDED REFLECTOR DETAIL AND TYPICAL INSTALLATION



DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.




DETAIL FOR 36" BLOCKOUT DEPTH

NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.


DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.

NOTE:
1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF $\frac{3}{16}$ ".
2. IF THE BOLT EXTENDS MORE THAN $\frac{1}{4}$ " FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"




ALTERNATE BOLT HEAD




POST BOLT, SPLICE BOLT AND RECESS NUT



PLAN VIEW BEAM LAPPING DETAIL



POST DRIVING FOR CONTINUOUS UNDERGROUND OBSTRUCTION




SIDE VIEW

PLAN VIEW


ALTERNATE WOOD BLOCKOUT DETAIL

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL) (407)

400 MAX SPAN 12' - 6"
 401 2' MIN.
 402 MGS GUARDRAIL 3
 403 NESTING BEAM GUARD
 404 ASYMMETRIC TRANSITION
 405 SOIL WELL DRAINED AND COMPACTED
 406 SEE OTHER DRAWINGS IN THIS SDD
 407 SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
 408 SEE SDD 14B44
 409 SEE SDD 14B45
 410 SEE SDD 14B47
 411 MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2021 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVE
FHWA UNIT SUPERVISOR 25

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE (HPL) AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
- (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED.
- (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W-BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
- (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF-TAPPING SCREWS. ONE SCREW PER CORNER.
- (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.

DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.


SEE SDD 14B42 FOR MORE INFORMATION.

* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.


DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.

SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.


THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.




DETAIL "A" (E)




SECTION C - C
TYPICAL AT POST NOS. 3 - 9




PLAN




ELEVATION



SECTION B - B
TYPICAL AT POST NO. 2*



SECTION A - A
TYPICAL AT POST NO. 1*




DETAIL "B" (E)

MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2



GENERIC GROUND STRUT ^{⑨ (E)}




FRONT VIEW









SECTION A - A



GENERIC ANCHOR CABLE BOX ^{⑨ (E)}



BEARING PLATE ^{⑯ (E)}

UPPER POST NO. 1 ^① ^(E)LOWER POST NO. 1 ^② ^(E)WOOD CRT POST
POSTS NUMBER 3-9 ^③ ^(E)UPPER POST NO. 2 ^⑮ ^(E)LOWER POST NO. 2 ^⑯ ^(E)WOOD BLOCKOUT ^④


REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2

REFLECTIVE SHEETING DETAIL ^(E)


FRONT VIEW



SIDE VIEW

E.A.T. MARKER POST ^⑯

SIDE VIEW




TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
7/2018 */S/ Rodney Taylor*
DATE ROADWAY STANDARDS DEVE
FHWA UNIT SUPERVISOR 28



TWO WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED



ONE WAY TRAFFIC

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES

IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2½", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY


① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.

⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


GENERAL NOTES

- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (4) TOLERANCE FOR TOP OF W-BEAM RAIL IS $\pm 1"$.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42




SECTION A-A
POSTS 1-5

6





SECTION D-D
POSTS 12-17

S.D.D. 14 B 45-5b



SPICE DETAIL

SECTION B-B
POST 6



SECTION C-C
POSTS 7-11






PLATE WASHER DETAIL



**THRIE BEAM
TERMINAL CONNECTOR**




**SECTION THRU THRIE
BEAM RAIL ELEMENT**

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

S.D.D. 14 B 45-5b


6





W-BEAM TO THRIE BEAM TRANSITION SECTION






6'-3" THRIE BEAM SECTION



12'-6" THRIE BEAM SECTION



SIDE VIEW
TOP VIEW
ALTERNATE WOOD BLOCKOUT DETAIL



GENERAL NOTES

STEEL POSTS ARE W6X9 OR W6X8.5.

BOLT HOLES FOR POST ARE ON FRONT AND SIDE OF POST.


(3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

(5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.

(13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



FRONT VIEW


THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS



FRONT VIEW

W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS

(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)




SECTION E-E


GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".



SECTION F-F



DRILL HOLE LOCATION

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018
DATE
/S/ Rodney Taylor
FHWA

ROADWAY STANDARDS UNIT SUPERVISOR
32
INT

GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PARAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.



SECTION G-G

⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE) WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER 7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET (4 REQ'D.)


THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET

(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



FRONT VIEW



SECTION H-H


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS UNIT SUPERVISOR
FHWA 33


GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



FRONT VIEW


W BEAM CONNECTION TO PARAPETS WITH SLOPED ENDS (USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)



DRILL HOLE LOCATION AND PATTERN
FOR THRIE BEAM CONNECTION


6

- ⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(5 REQ'D.)



FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPETS WITH SLOPED ENDS



SECTION I-I


S.D.D. 14 B 45-5f

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS UNIT SUPERVISOR
FHWA 34 ENT


S.D.D. 14 B 45-5f



BACK-UP PLATE DETAIL




SECTION J-J




**BACK-UP PLATE MOUNTING
ONTO BRIDGE RAILING**

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING HOLES THROUGH THE PAPRPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




FRONT VIEW
**TRI-BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**TRI-BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K


**MIDWEST GUARDRAIL SYSTEM
TRI-BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018
/S/ Rodney Taylor 35
DATE
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES

④ TOLERANCE FOR TOP OF W-BEAM RAIL IS $\pm 1"$.




FRONT VIEW




PLAN VIEW

BACK-UP PLATE DETAIL, TYPE "M"




FRONT VIEW


ANCHOR PLATE DETAIL, TYPE "M"




SECTION M-M



ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW




PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS UNIT SUPERVISOR
FHWA 36 ENT



WELDING INSTRUCTION

(VIEWED FROM BACK SIDE OF PLATE)



10

11

TYPICAL

PLATE AND STIFFENER IDENTIFICATION

(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 9/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 1/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 7/16" x 10 3/16" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 1/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 7/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 9/16" x 6" x 3 5/8" x 5 7/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 1/32"	1/4"
S10	1		1 7/8" x 9 7/16" x 3 5/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 1/32"	1/4"

SINGLE SLOPE CONNECTION PLATE

GENERAL NOTES

COVER PLATE PANELS ARE $\frac{3}{16}$ " THICK.

ALL STIFFENERS ARE $\frac{1}{4}$ " THICK.

CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.


FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.

ALL HOLE DIAMETERS SHALL BE 1".

FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

(10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND $\frac{3}{16}$ " FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.

(11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
 $\frac{3}{16}$ " FILLET WELD BY 1" LONG SPACED AT 2".



MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS 137
FHWA UNIT SUPERVISOR


GENERAL NOTES

CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.



- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER




SINGLE SLOPE CONNECTION PLATE PLACEMENT



MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DI
FHWA UNIT SUPERVIS 38 JT




ELEVATION OF DETAIL AT NY3 END POST

THRIE BEAM RAIL ATTACHMENT

GENERAL NOTES

(4) TOLERANCE FOR TOP OF BEAM IS ± 1 ".

(12) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREAD LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.




ELEVATION OF DETAIL AT NY4 END POST

THRIE BEAM RAIL ATTACHMENT

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS C 39
FHWA UNIT SUPERVISOR




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

GENERAL NOTES

(4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.

(12) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

APPROVED
 7/2018 /S/ Rodney Taylor
 DATE ROADWAY STANDARDS C 40
 FHWA UNIT SUPERVISOR NT








DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR


WORK ZONE LESS THAN $\frac{1}{2}$ MILE FROM DETOUR ROUTE (1000 FEET IF URBAN)

LEGEND

- SIGN ON PERMANENT SUPPORT
- + TYPE III BARRICADE
- || TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)



SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750



DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR

BARRICADES AND SIGNS FOR MAINLINE CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidke
DATE
FHWA
WORK ZONE ENGINEER 41

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:

R11 - 2 SHALL BE 48" X 30"

R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"

M4 - 9 SHALL BE 30" X 24"

M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)


M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)

M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)

M05 - 1 AND M06 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)

D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.


R1 - 1 SHALL BE 36" X 36"



DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW

6

6



DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW

SEE SDD 15C2 - SHEET "a" FOR LEGEND

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

BARRICADES AND SIGNS FOR VARIOUS CLOSURES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023
DATE
FHWA

/S/ Andrew Heidke
WORK ZONE ENGINEER 42


GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS.
 THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.
 ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.
 SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.
 IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.
 * OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS
 ** PLACE AN ADDITIONAL W20-1A "ROAD WORK AHEAD" SIGN IF WORK AREA WITHIN THE PROJECT IS SEPARATED BY MORE THAN 2 MILES FROM PREVIOUS WORK AREA.



LEGEND

- Ⓐ SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC
- ▨ WORK AREA




TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45MPH OR GREATER


TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 MPH OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
July 2018 /S/ Andrew Heidke
DATE
FHWA
WORK ZONE ENGINEER 43

**SITUATION 1**

WARRANTING CRITERIA:
BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.

**SITUATION 2**

WARRANTING CRITERIA:
1. BRIDGE WIDTH IS AT LEAST 24 FEET AND
2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THE DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.

ON BRIDGE ONLY PROJECTS, PLACE 300 FEET OF EDGELINE.

OMIT EDGELINES ON ROADWAYS WITHOUT EXISTING EDGELINES.

① OMIT ON ONE-WAY TRAVELED WAYS.

LEGEND

Ⓐ SIGN ON PERMANENT SUPPORT

→ DIRECTION OF TRAFFIC


DISTANCE TABLE

POSTED OR 85TH PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	700'

**SIGNING AND MARKING
FOR TWO LANE BRIDGES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Jeannie Silver
DATE
FHWA
Statewide Pavement Marking Engineer



TWO WAY TRAFFIC

PERMANENT PAVEMENT MARKING



ONE WAY TRAFFIC

GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.


* CONFIRM MARKING LINE WIDTH WITH THE MISCELLANEOUS QUANTITIES

- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.


LEGEND

- "T" MARKING
- SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC

PERMANENT LONGITUDINAL PAVEMENT MARKINGS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2023 DATE FHWA	/S/ Jeannie Silver Statewide Pavement Marking Engineer


**DRUM**

BALLAST WIDTHS
RANGE FROM 24"-36"


**42" CONE**

DO NOT USE IN TAPERS
 $\frac{1}{2}$ SPACING OF DRUMS


BALLAST WIDTHS
RANGE FROM 14"-20"

**VERTICAL PANEL**

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.

**TYPE II BARRICADE**

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.

**TYPE III BARRICADE**

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.
















CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
November 2022 /S/ Andrew Heidtke
DATE
FHWA

WORK ZONE ENGINEER 46

TYPICAL ASSEMBLIES




(Typical Vertical J-Assembly
See Note 10 and 11)



JH-1

JH-1



PROJECT NO:

FILE NAME : C:\CAEfiles\Projects\tr_stdplate_A21S.dgn

PLOT DATE : 7-JUN 2023 9:14

PLOT BY : mscj9h


PLOT NAME :

SHEET NO: 47


E

WISDOT/CADD'S SHEET 42

URBAN AREA




RURAL AREA (See Note 2)



GENERAL NOTES

1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.
3. The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±) 3". The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±) 3".
4. For expressways and freeways, mounting height is 7'-3" (±) 3" or 6'-3" (±) 3" depending upon existence of a sub-sign.
5. Minimum mounting height for signs mounted on traffic signal poles is 5'-3" (±) 3".
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (±) 3" or as directed by the Engineer.

2' Min - 4' Max (See Note 5)




White Edgeline Location

White Edgeline Location

7

7

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.



White Edgeline Location

Outside Edge of Gravel

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

TYPICAL INSTALLATION
OF PERMANENT TYPE II
SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew P. Rauch*
for State Traffic Engineer

DATE 12/6/23 PLATE NO. A4-3.23


PROJECT NO:

HWY:

COUNTY:

SHEET NO: 48


E



NOTES: 1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
 2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
 3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.


ELEVATION VIEW

DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



PLAN VIEW

FOR NEW CONCRETE/ASPHALT INSTALLATIONS

SIGN POST
BOX-OUTS
A4-3B

WISCONSIN DEPT OF TRANSPORTATION

APPROVED
Matthew P Rauch
for State Traffic Engineer
DATE 1/27/14 PLATF 49 A4-3B.1


PROJECT NO:

HWY:


COUNTY:

SHEET NO:

E



SIGN SHALL BE MOUNTED TO PROJECT
ABOVE THE TOP OF THE POST



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation :B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)

MACHINE BOLTS - $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts

WOOD POSTS (4" x 6")

LAG SCREWS - $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)
 $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)

SQUARE STEEL POSTS (2" x 2")

MACHINE BOLTS - $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)

RIVETS - $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL

O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH

WASHERS (ALL POSTS) -

1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL

1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON

* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.


ATTACHMENT OF SIGNS TO POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer


DATE 4/1/2020 PLATE NO. A4-8.9

**TELESCOPIC TUBING ANCHORS
TWO PIECE SYSTEM**





DETAIL OF TUBULAR STEEL SIGN POST

(IN Poured CONCRETE OR ASPHALT)



DETAIL OF TUBULAR STEEL SIGN POST

(IN LOCATIONS OTHER THAN Poured CONCRETE OR ASPHALT)



Area of Sign Installation (Sq. Ft.)	Number of Required Posts
9 or less	1
Greater than 9 less than or equal to 18	2
Greater than 18 less than or equal to 27	3

Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

**TUBULAR STEEL
SIGN POST**

A4-9

WISCONSIN DEPT OF TRANSPORTATION

APPROVED
Matthew P. Rauch

for State Traffic Engineer

DATE 2/05/15 PLATI 52 14-9.9



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E



SIDE VIEW

GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two $1\frac{1}{2}$ " diameter holes drilled perpendicular to the roadway centerline.

4 X 6 WOOD POST
MODIFICATIONS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Cheska J. Sprey
for State Traffic Engineer

DATE 3/27/97

PLATE NO. A4-11.2


PROJECT NO:

HWY:

COUNTY:

SHEET NO: 53





E



GENERAL NOTES

- ALL SIGNS OVER 60" IN WIDTH SHALL HAVE A 3" RADIUS ON THE OUTSIDE CORNERS OF THE ALUMINUM BLANK.
- MOUNTING HOLES SHALL BE $\frac{7}{16}$ " DIAMETER.
- SEE CHART FOR HOLE SPACING REQUIREMENTS
- FOR SIGN PANELS WITH DIMENSION (H) 36" AND OVER, DIMENSION E SHALL BE 6"
- FOR SIGN PANELS WITH DIMENSION (H) UNDER 36", DIMENSION E SHALL BE 4"
- SIGN STRINGER MATERIAL SHALL CONSIST OF STEEL CHANNEL POST SECTIONS, WEIGHING 1.12 LBS/FT IN ACCORDANCE WITH SECTION 633.2.1 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION.
- SEE SIGN PLATE A4-8 FOR SIGN STRINGER BOLTING REQUIREMENTS.

SIGN WIDTH	STRINGER WIDTH	POSTS	HOLE SPACING	MOUNTING HOLES
78"	72"	2	16"	15" 31" 47" 63"
84"	72"	2	17"	16 $\frac{1}{2}$ " 33 $\frac{1}{2}$ " 50 $\frac{1}{2}$ " 67 $\frac{1}{2}$ "
90"	72"	2	18"	18" 36" 54" 72"
96"	90"	2	19"	19 $\frac{1}{2}$ " 38 $\frac{1}{2}$ " 57 $\frac{1}{2}$ " 76 $\frac{1}{2}$ "
102"	90"	2	20"	21" 41" 61" 81"
108"	90"	2	21"	22 $\frac{1}{2}$ " 43 $\frac{1}{2}$ " 64 $\frac{1}{2}$ " 85 $\frac{1}{2}$ "
114"	108"	3	15"	12" 27" 42" 57" 72" 87" 102"
120"	108"	3	16"	12" 28" 44" 60" 76" 92" 108"
126"	108"	3	17"	12" 29" 46" 63" 80" 97" 114"
132"	126"	3	18"	12" 30" 48" 66" 84" 102" 120"
138"	126"	3	19"	12" 31" 50" 69" 88" 107" 126"
144"	126"	3	20"	12" 32" 52" 72" 92" 112" 132"






BANDING


GENERAL NOTES

1. Any sign over 3 feet in width shall use the V-Block banding method. See A5-10 standard plate.
2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
3. Banding and assembly bracket shall be stainless steel. All bands shall be $\frac{3}{4}$ " in width and 0.025" thickness.
4. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM designation: B 633, Type III, SC 3

SINGLE SIGN




WASHER PLACEMENT



WASHERS (ALL POSTS) -
 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL
 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON
 FOR ALL TYPE H SIGNS

"J" ASSEMBLY





STANDARD SIGN SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

 for State Traffic Engineer
 DATE 6/10/19 PLATE NO. A5-9.4



GENERAL NOTES

1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WisDOT STANDARD SPECIFICATIONS
2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, $3/4$ " WIDTH AND 0.025" THICKNESS
3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORMALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3
6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
7. STEEL WASHERS SHALL BE $1\frac{1}{4}$ " O.D. X $3\frac{3}{8}$ " I.D. X $\frac{1}{16}$ "
8. NYLON WASHERS SHALL BE $1\frac{1}{4}$ " O.D. X $3\frac{3}{8}$ " I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN

＊ LAG BOLTS SHALL BE $3/8$ " X $2\frac{1}{2}$ "

7

7


BLOCK BANDING DETAIL
(V-BLOCK OPTION)

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 4/19/2022 PLATE NO. A5-10.3

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - Green
Message - White
3. Message Series - C



D11-10

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	18	1 1/2		1/2	3	1 3/4	2 1/2	7 5/8	7 1/8	5 1/8	5 1/2	5 7/8	2	1 1/4	9 1/8	5	2 1/8								3.0	
2M	24	18	1 1/2		1/2	3	1 3/4	2 1/2	7 5/8	7 1/8	5 1/8	5 1/2	5 7/8	2	1 1/4	9 1/8	5	2 1/8								3.0	
3																											
4																											
5																											


STANDARD SIGN	
D11-10	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	Matthew P. Rauch for State Traffic Engineer
DATE 1/25/2023 PLATE NO. D11-10.6	

PROJECT NO:

SHEET NO: 57 E

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



G20-2A

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	18	1 1/2	3/8	1/2	4	3 3/4	2 1/2	4 1/8	4 1/8	11 1/8	2	1	12 1/8												4.5	
2	48	24	1 7/8	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2												8.0	
2M	48	24	1 7/8	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2												8.0	
3	48	24	1 7/8	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2												8.0	
4	48	24	1 7/8	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2												8.0	
5	48	24	1 7/8	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2												8.0	

PROJECT NO:





HWY:

COUNTY:

STANDARD SIGN
G20-2A
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 1/26/2023 PLATE NO. G20-2A.10

SHEET NO:

E



NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White & Black
Message - Black
3. Message Series - see Note 4
4. Message Series E for 1 letter.
Message Series D for 2 letters unless message is too big then Series C.
Message Series C for 3 letters unless message is too big then Series B.
5. Substitute appropriate letters & optically center to achieve proper balance.

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24		1 1/2			10	3	5 1/8	4 1/8	9 1/4	9 5/8	2	11 1/2	10 1/8	9 3/8	2 1/4		6 5/8								4.0	
2M	24		1 1/2			10	3	5 1/8	4 1/8	9 1/4	9 5/8	2	11 1/2	10 1/8	9 3/8	2 1/4		6 5/8								4.0	
3	36		2 1/4			16	4	7 5/8	5 5/8	12 1/4	12 7/8	3	17 1/8	15 1/4	14	3 3/8		10								9.0	
4	36		2 1/4			16	4	7 5/8	5 5/8	12 1/4	12 7/8	3	17 1/8	15 1/4	14	3 3/8		10								9.0	
5	36		2 1/4			16	4	7 5/8	5 5/8	12 1/4	12 7/8	3	17 1/8	15 1/4	14	3 3/8		10								9.0	

PROJECT NO:



HWY:

COUNTY:

CTH MARKER
M1-5A FOR ASSEMBLIES
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 11/8/2022 PLATE NO. M1-5A.9

SHEET NO:

E



NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - D except 3 number signs Series C

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	24		1 1/2			12	5 1/2	6 1/2	10 1/4	2 1/2	8 7/8	11 1/2	1	1 7/8	11 1/4	21 7/8										4.0	
2M	24		1 1/2			12	5 1/2	6 1/2	10 1/4	2 1/2	8 7/8	11 1/2	1	1 7/8	11 1/4	21 7/8										4.0	
3	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33										9.0	
4	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33										9.0	
5	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 7/8	16 7/8	33										9.0	

PROJECT NO.:

HWY.:

COUNTY:

STATE ROUTE MARKER
M1-6 FOR ASSEMBLIES


WISCONSIN DEPT OF TRANSPORTATION

APPROVED


Matthew R. Rauch
for State Traffic Engineer
DATE 11/8/2022 PLATE NO. M1-6.11

SHEET NO. 60


E




M3-1
MM3-1
MP3-1




MB3-1
MK3-1
MN3-1




M3-2
MM3-2
MP3-2




MB3-2
MK3-2
MN3-2




M3-3
MM3-3
MP3-3



MB3-3
MK3-3
MN3-3



M3-4
MM3-4
MP3-4



MB3-4
MK3-4
MN3-4

NOTES

1. All Signs Type II - Type H Reflective
2. Color:
Background - See note 5
Message - See note 5
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. M3-1 thru M3-4 Background - White
 Message - Black
 MB3-1 thru MB3-4 Background - Blue
 Message - White
 MK3-1 thru MK3-4 Background - Green
 Message - White
 MM3-1 thru MM3-4 Background - White
 Message - Green
 MN3-1 thru MN3-4 Background - Brown
 Message - White
 MP3-1 thru MP3-4 Background - White
 Message - Blue
6. Note the first letter of each direction is larger than the remainder of the message.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	12	1 1/2	3/8	3/8	6	7	2 1/4	2 3/4	10 1/4	7 7/8	8 3/8	10 1/4	9 3/4	8 3/4											2.00	
2M	24	12	1 1/2	3/8	3/8	6	7	2 1/4	2 3/4	10 1/4	7 7/8	8 3/8	10 1/4	9 3/4	8 3/4											2.00	
3	36	18	1 1/2	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13											4.5	
4	36	18	1 1/2	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13											4.5	
5	36	18	1 1/2	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8	12	12 1/8	14	14 1/8	13											4.5	

PROJECT NO:





HWY:

COUNTY:

STANDARD SIGNS
M3-1 THRU M3-4
SERIES
WISCONSIN DEPT OF TRANSPORTATION
APPROVED <i>Matthew P. Rauch</i> for State Traffic Engineer
DATE 2/8/2023 PLATE NO. M3-1.15


SHEET NO: 61

E



NOTES

1. Signs are Type II - Type H Reflective except as shown
2. Color:
 - Background - See note 4
 - Message - See note 4
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. M6-1 and M6-2 Background - White
Message - Black
- MB6-1 and MB6-2 Background - Blue
Message - White
- MK6-1 and MK6-2 Background - Green
Message - White
- MM6-1 and MM6-2 Background - White
Message - Green
- MN6-1 and MN6-2 Background - Brown
Message - White
- M06-1 and M06-2 Background - Orange - Type F Reflective
Message - Black
- MP6-1 and MP6-2 Background - White
Message - Blue
- MR6-1 and MR6-2 Background - Brown
Message - Yellow



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	21		1 1/2	3/8	3/8		7 1/2	7 1/8	5 5/8	5	4 1/4	5 1/4	3	2 5/8	1/2							1/2				3.06	
2M	21		1 1/2	3/8	3/8		7 1/2	7 1/8	5 5/8	5	4 1/4	5 1/4	3	2 5/8	1/2							1/2				3.06	
3	30		1 7/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	
4	30		1 7/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	
5	30		1 7/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN
M6-1 & M6-2
SERIES





WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 2/13/2023 PLATE NO. M6-1.16


SHEET NO: 62

E



NOTES

1. Signs are Type II - Type H Reflective except as shown
2. Color:
Background - See Note 4
Message - See Note 4
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. M6-4 and M6-6 Background - White
Message - Black
MB6-4 and MB6-6 Background - Blue
Message - White
MK6-4 and MK6-6 Background - Green
Message - White
MM6-4 and MM6-6 Background - White
Message - Green
MN6-4 and MN6-6 Background - Brown
Message - White
M06-4 and M06-6 Background - Orange - Type F Reflective
Message - Black
MP6-4 and MP6-6 Background - White
Message - Blue
MR6-4 and MR6-6 Background - Brown
Message - Yellow
5. M6-6R same as M6-6L except arrow points ahead and right.



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	21		1 1/2	3/8	3/8		7 1/2	8 3/4	4 1/4			5 1/4	3	2 5/8	1/2							1/2				3.06	
2M	21		1 1/2	3/8	3/8		7 1/2	8 3/4	4 1/4			5 1/4	3	2 5/8	1/2							1/2				3.06	
3	30		1 7/8	1/2	5/8		10 3/4	12 1/2	6 3/4			7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	
4	30		1 7/8	1/2	5/8		10 3/4	12 1/2	6 3/4			7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	
5	30		1 7/8	1/2	5/8		10 3/4	12 1/2	6 3/4			7 1/2	4 1/4	3 3/4	3/4							1/2				6.25	

PROJECT NO:


HWY:

COUNTY:


STANDARD SIGN
M6-4 & M6-6
SERIES
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Paul*
for State Traffic Engineer
DATE 2/13/2023 PLATE NO. M6-4.11

SHEET NO: 63

E



M7-1



M7-2

M7-3

M7-4

M7-5

M7-6

M7-7

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - Green
Message - White

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	12	9	1 1/2	3/8		1 5/8	4 3/8	3	3 1/4	3 3/4	1 3/8	3 7/8	3 1/8	3 3/8	2 7/8	2 1/2	5	2 1/2	2 1/4	4 1/4	1 1/4	4 1/2				.75	
2M	12	9	1 1/2	3/8		1 5/8	4 3/8	3	3 1/4	3 3/4	1 3/8	3 7/8	3 1/8	3 3/8	2 7/8	2 1/2	5	2 1/2	2 1/4	4 1/4	1 1/4	4 1/2				.75	
3																											
4																											
5																											

PROJECT NO:

HWY:

COUNTY:

FILE NAME : C:\CAEfiles\Projects\tr_stdplate\M71.dgn

PLOT DATE : 21-NOV 2022 11:01

PLOT BY : dotc4c

PLOT NAME :

PLOT SCALE :

WISDOT/CADD5 SHEET 42

STANDARD SIGN
M7 SERIES


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Ranch*
for State Traffic Engineer

DATE 11/21/2022 PLATE NO. M7-1.2

SHEET NO: 64

E



NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Red
Message - White
3. Message Series - C

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	30				5/8	10	12 1/2	45°		12 3/4																5.18	
2S	30				5/8	10	12 1/2	45°		12 3/4																5.18	
2M	36				3/4	12	15	45°		15 3/8																7.46	
3	36				3/4	12	15	45°		15 3/8																7.46	
4	48				1	16	20	45°		20 1/2																13.25	
5	48				1	16	20	45°		20 1/2																13.25	
6	18				3/8	6	7 3/4	45°		7 3/4																1.86	
7	12				1/4	4	5	45°		5 1/8																0.78	

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN
R1-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED
Matthew R Rauch
for State Traffic Engineer


DATE 11/12/15 PLATE NO. R1-1.13

SHEET NO: 65

E

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - E
4. Substitute appropriate numerals and optically adjust spacing to achieve proper balance.



R2-1

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	18	24	1 1/2	3/8	1/2	3	8	3	2	2	3	7 1/4	5 1/2												3.0		
2S	24	30	1 1/2	3/8	1/2	4	10	3	2 1/4	3 3/8	3 3/8	9 5/8	7 3/8												5.0		
2M	30	36	1 7/8	1/2	5/8	5	12	5	2 1/2	2 1/2	4	12	9 1/4												7.5		
3	36	48	1 7/8	1/2	5/8	6	14	6	5	5	6	14 3/8	11												12.0		
4	36	48	1 7/8	1/2	5/8	6	14	6	5	5	6	14 3/8	11												12.0		
5	48	60	3	3/4	1	8	20	6	4 1/2	6 3/4	6 3/4	19 1/4	14 5/8												20.0		

PROJECT NO:

HWY:

COUNTY:


STANDARD SIGN	
R2-1	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew P Rauch</i> State Traffic Engineer
DATE	2/1/23
PLATE NO.	R2-1.14

SHEET NO: 66

E

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R11-2B

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	30	1 7/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8															10.0	
2M	48	30	1 7/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8															10.0	
3	48	30	1 7/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8															10.0	
4	48	30	1 7/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8															10.0	
5	48	30	1 7/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8															10.0	

PROJECT NO:

FILE NAME : C:\CAEfiles\Projects\tr_stdplate\R112B.dgn

PLOT DATE : 5-FEB 2024 2:20

PLOT BY : mscj9h

STANDARD SIGN	
R11-2B	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> for State Traffic Engineer
DATE	2/5/24
PLATE NO.	R11-2B.3


SHEET NO: 67

E


WISDOT/CADD'S SHEET 42

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Substitute appropriate numerals to nearest quarter mile and optically adjust spacing to achieve proper balance.



** See Note 5



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	18	1 1/2	3/8	3/8	4	3	2	11 1/4	3	1 1/8	15 3/8	2	3 3/4	8 1/4	5/8		1 3/8	13 1/4	8 3/8	7/8	10 1/2	7 1/8			4.5	
2S	60	30	1 7/8	1/2	5/8	6	5	3 1/2	16 7/8	5	1 3/8	23 1/4	3	6 1/4	13 5/8	1 1/8		1 7/8	22 1/8	14	1 1/2	17 1/2	11 7/8			12.5	
2M	60	30	1 7/8	1/2	5/8	6	5	3 1/2	16 7/8	5	1 3/8	23 1/4	3	6 1/4	13 5/8	1 1/8		1 7/8	22 1/8	14	1 1/2	17 1/2	11 7/8			12.5	
3																											
4																											
5																											

PROJECT NO:

HWY:

COUNTY:


STANDARD SIGN	
R11-3	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> for State Traffic Engineer
DATE	2/5/24
PLATE NO.	R11-3.10

SHEET NO: 68

E

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R11-4

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	60	30	1 7/8	1/2	5/8	6	5	4	2 1/2	16 1/8		7/8	23 3/8	3 1/4	3	16 3/4	5 1/4	2 1/4	24 1/4							12.5	
2M	60	30	1 7/8	1/2	5/8	6	5	4	2 1/2	16 1/8		7/8	23 3/8	3 1/4	3	16 3/4	5 1/4	2 1/4	24 1/4							12.5	
3																											
4																											
5																											


PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN
R11 - 4
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R. Rauch*
for State Traffic Engineer
DATE 2/5/24 PLATE NO. R11-4.4

SHEET NO: 69 E



W1-4R

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	24		1 1/2	3/8	1/2	3 1/2	2 5/8	8 1/4	5 1/4	11 1/4	7	1 1/8	4	3	5/8	1/4	1 1/2	5								4.0	
2S	30		1 7/8	1/2	5/8	4 3/8	3 1/4	10 1/4	6 1/2	14	8 3/4	1 3/8	5	3 5/8	3/4	3/8	1 7/8	6 1/4								6.25	
2M	36		2 1/4	5/8	3/4	5 1/4	4	12 3/8	7 7/8	16 7/8	10 1/2	1 5/8	6	4 1/2	1	1/2	2 1/4	7 1/2								9.0	
3	36		2 1/4	5/8	3/4	5 1/4	4	12 3/8	7 7/8	16 7/8	10 1/2	1 5/8	6	4 1/2	1	1/2	2 1/4	7 1/2								9.0	
4	36		2 1/4	5/8	3/4	5 1/4	4	12 3/8	7 7/8	16 7/8	10 1/2	1 5/8	6	4 1/2	1	1/2	2 1/4	7 1/2								9.0	
5	48		3	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10								16.0	

STANDARD SIGN

W1-4

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 3/23/2023 PLATE NO. W1-4.12

PROJECT NO:

HWY:


COUNTY:

SHEET NO:

E

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
 - Background - Yellow
 - Message - Black



STANDARD SIGN

W1 - 6

WISCONSIN DEPT OF TRANSPORTATION

COVED *m-111* 0 0 1

Mather R Rauch

For State Traffic Engineer


DATE 4/13/2023 PLATE NO. W1-6.9

PROJECT NO:

HWY

COUNTY:

SHEET NO:



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. W2-2L same as W2-2R but is rotated 180° when mounted.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	24		1 1/2	3/8	1/2	20	2	4	10	8															4.0		
2S	30		1 7/8	1/2	5/8	25	2 1/2	5	12 1/2	10															6.25		
2M	30		1 7/8	1/2	5/8	25	2 1/2	5	12 1/2	10															6.25		
3	36		2 1/4	5/8	3/4	30	3	6	15	12															9.0		
4	48		3	3/4	1	40	4	8	20	16															16.0		
5																											

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN

W2-2 L&R

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R Rauch*

for State Traffic Engineer

DATE 8/16/2023 PLATE NO. W2-2.8

SHEET NO: 72

E



7

W3-1

NOTES


1. Sign is Type II - Type F Reflective

2. Color:

Background - Yellow

Arrow & Border - Black

Stop Symbol - White Border on Red Background



ARROW DETAIL

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	30		1 7/8	1/2	5/8	6 1/4	11 1/4	2 7/8	15 3/4	1/2	1/2	16	8	1 1/4	5											6.25	
2S	36		2 1/4	5/8	3/4	7 1/2	13 1/2	3 1/2	19	5/8	5/8	19 1/4	9 3/4	1 5/8	6											9.0	
2M	36		2 1/4	5/8	3/4	7 1/2	13 1/2	3 1/2	19	5/8	5/8	19 1/4	9 3/4	1 5/8	6											9.0	
3	36		2 1/4	5/8	3/4	7 1/2	13 1/2	3 1/2	19	5/8	5/8	19 1/4	9 3/4	1 5/8	6											9.0	
4	48		3	3/4	1	10	17 7/8	4 1/2	25 1/8	3/4	7/8	25 5/8	13	2	8											16.0	
5	48		3	3/4	1	10	17 7/8	4 1/2	25 1/8	3/4	7/8	25 5/8	13	2	8											16.0	

PROJECT NO:

FILE NAME : C:\CAEfiles\Project\tr_stdplate\W31.dgn

PLOT DATE : 17-AUG 2023 2:30



PLOT BY : dotc4c

STANDARD SIGN
W3-1
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew P Rauch*
for State Traffic Engineer
DATE 8/17/2023 PLATE NO. W3-1.13

SHEET NO: 73

E

WISDOT/CADDS SHEET 42



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Alternate colors of stripes as shown.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4															3.0	
2M	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4															3.0	
3	18	54	1 1/2			6	5 1/2	8 1/2	45°	6	6 9/16															6.75	
4																											
5																											

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN

W5-52L & W5-52R


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*

for State Traffic Engineer

DATE 3/4/2024 PLATE NO. W5-52.10

SHEET NO: 74 E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
 - Background - Yellow
 - Message - Black

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	30		1 1/8	1/2	5/8	5 3/8	5 1/4	13 5/8	12 5/8																6.25		
2S	36		2 1/4	5/8	3/4	6 1/2	6 3/8	16 3/8	15 1/8																9.0		
2M	36		2 1/4	5/8	3/4	6 1/2	6 3/8	16 3/8	15 1/8																9.0		
3	36		2 1/4	5/8	3/4	6 1/2	6 3/8	16 3/8	15 1/8																9.0		
4	48		3	3/4	1	8 5/8	8 1/2	21 7/8	20 1/8																16.0		
5																											

STANDARD SIGN
W11-14
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 3/27/24 PLATE NO. W11-14.2


PROJECT NO:

HWY:

COUNTY:

SHEET NO: 75

E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Message Series - C

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	24		1 1/2	3/8	1/2	4	2 3/8	3 3/4	10 3/4																	4.0	
2S	30		1 7/8	1/2	5/8	5	3	4 5/8	13 3/8																	6.25	
2M	36		2 1/4	5/8	3/4	6	3 1/2	5 5/8	16																	9.0	
3	36		2 1/4	5/8	3/4	6	3 1/2	5 5/8	16																	9.0	
4	48		3	3/4	1	8	5	7 3/8	21 1/4																	16.0	
5																											

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN

W11-50


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer

DATE 11/21/2023 PLATE NO. W11-50.5


SHEET NO: 76

E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - See note 5
4. The top line is series E, the numerals are series C, and the bottom line is series D.
5. Substitute appropriate numerals and adjust spacing as required.



ARROW DETAIL

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48		3	3/4	1	6	12	11 3/8	9 5/8	11 1/2	16	13	12	15 5/8	8	9 1/4	1 1/4	10 5/8								16.0	
2M	48		3	3/4	1	6	12	11 3/8	9 5/8	11 1/2	16	13	12	15 5/8	8	9 1/4	1 1/4	10 5/8								16.0	
3																											
4																											
5																											

PROJECT NO:


HWY:

COUNTY:

STANDARD SIGN	
W12-52	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R Rauch</i> for State Traffic Engineer
DATE	3/10/2024
PLATE NO.	W12-52.8

SHEET NO: 77

E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Message Series - D

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	24		1 1/2	3/8	1/2	5	1	2	8 1/4	8 5/8	5 5/8	6 1/4														4.0	
2S	30		1 7/8	1/2	5/8	6	1 1/2	2 1/2	9 3/4	10 1/4	6 3/4	7 1/2														6.25	
2M	30		1 7/8	1/2	5/8	6	1 1/2	2 1/2	9 3/4	10 1/4	6 3/4	7 1/2														6.25	
3	36		2 1/4	5/8	3/4	7	2	3	11 3/8	12	7 7/8	8 3/4														9.0	
4																											
5																											

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN

W14-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Matthew R Rauch

for State Traffic Engineer


DATE 1/8/2024 PLATE NO. W14-1.8

SHEET NO:

E

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Message Series - Lines 1 and 2 are Series D.
Line 3 is series C.
4. Corners and borders shall be rounded on all base materials for this sign.



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	36	2 1/4	5/8	7/8	5	2	8 1/2	3	8	26 3/4	12 3/4														5.56	
2M																											
3																											
4																											
5																											

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN
W14-3

WISCONSIN DEPT OF TRANSPORTATION









APPROVED *Matthew P Rauch*
for State Traffic Engineer
DATE 3/21/17 PLATE NO. W14-3.10

SHEET NO: 79

E

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.





SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		$2\frac{1}{4}$	$\frac{5}{8}$	$\frac{3}{4}$	5	$2\frac{5}{8}$	$3\frac{1}{4}$	$10\frac{1}{8}$	7	$7\frac{5}{8}$	$8\frac{7}{8}$	$1\frac{1}{8}$	$4\frac{1}{2}$	$3\frac{1}{2}$	9	$3\frac{1}{4}$	$2\frac{1}{2}$	$2\frac{1}{4}$	$5\frac{5}{8}$	9	$1\frac{3}{8}$	8	$1\frac{3}{4}$	$10\frac{3}{4}$	6	9.0
2S	48		3	$\frac{3}{4}$	1	8	$3\frac{3}{4}$	$5\frac{1}{8}$	$15\frac{3}{8}$	$11\frac{1}{8}$	$12\frac{1}{8}$	$14\frac{3}{8}$	$1\frac{5}{8}$	$6\frac{7}{8}$	$5\frac{3}{8}$	$13\frac{7}{8}$	$4\frac{3}{8}$	$3\frac{7}{8}$	3	$8\frac{5}{8}$	$13\frac{3}{4}$	$2\frac{1}{8}$	$11\frac{7}{8}$	$2\frac{3}{4}$	$16\frac{3}{8}$	9	16.0
2M	48		3	$\frac{3}{4}$	1	8	$3\frac{3}{4}$	$5\frac{1}{8}$	$15\frac{3}{8}$	$11\frac{1}{8}$	$12\frac{1}{8}$	$14\frac{3}{8}$	$1\frac{5}{8}$	$6\frac{7}{8}$	$5\frac{3}{8}$	$13\frac{7}{8}$	$4\frac{3}{8}$	$3\frac{7}{8}$	3	$8\frac{5}{8}$	$13\frac{3}{4}$	$2\frac{1}{8}$	$11\frac{7}{8}$	$2\frac{3}{4}$	$16\frac{3}{8}$	9	16.0
3	48		3	$\frac{3}{4}$	1	8	$3\frac{3}{4}$	$5\frac{1}{8}$	$15\frac{3}{8}$	$11\frac{1}{8}$	$12\frac{1}{8}$	$14\frac{3}{8}$	$1\frac{5}{8}$	$6\frac{7}{8}$	$5\frac{3}{8}$	$13\frac{7}{8}$	$4\frac{3}{8}$	$3\frac{7}{8}$	3	$8\frac{5}{8}$	$13\frac{3}{4}$	$2\frac{1}{8}$	$11\frac{7}{8}$	$2\frac{3}{4}$	$16\frac{3}{8}$	9	16.0
4	48		3	$\frac{3}{4}$	1	8	$3\frac{3}{4}$	$5\frac{1}{8}$	$15\frac{3}{8}$	$11\frac{1}{8}$	$12\frac{1}{8}$	$14\frac{3}{8}$	$1\frac{5}{8}$	$6\frac{7}{8}$	$5\frac{3}{8}$	$13\frac{7}{8}$	$4\frac{3}{8}$	$3\frac{7}{8}$	3	$8\frac{5}{8}$	$13\frac{3}{4}$	$2\frac{1}{8}$	$11\frac{7}{8}$	$2\frac{3}{4}$	$16\frac{3}{8}$	9	16.0
5	48		3	$\frac{3}{4}$	1	8	$3\frac{3}{4}$	$5\frac{1}{8}$	$15\frac{3}{8}$	$11\frac{1}{8}$	$12\frac{1}{8}$	$14\frac{3}{8}$	$1\frac{5}{8}$	$6\frac{7}{8}$	$5\frac{3}{8}$	$13\frac{7}{8}$	$4\frac{3}{8}$	$3\frac{7}{8}$	3	$8\frac{5}{8}$	$13\frac{3}{4}$	$2\frac{1}{8}$	$11\frac{7}{8}$	$2\frac{3}{4}$	$16\frac{3}{8}$	9	16.0

PROJECT NO:

STANDARD SIGN
W20-1A, B, C, D, E, F, G & H
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R. Rauch*
for State Traffic Engineer
DATE 1/10/2024 PLATE NO. W20-1.12

SHEET NO:

E




NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - see note 5
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Lines 1 and 2 are Series D.
Line 3 is Series D for AHEAD and Series C for all other distances.

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		$2\frac{1}{4}$	$\frac{5}{8}$	$\frac{3}{4}$	5	$3\frac{3}{8}$	$3\frac{1}{2}$	$1\frac{1}{8}$	4	$8\frac{3}{8}$	$8\frac{7}{8}$	$12\frac{1}{2}$	11	9	6	$10\frac{1}{8}$	$2\frac{1}{2}$	$1\frac{7}{8}$	$5\frac{5}{8}$	8	$1\frac{3}{8}$	$4\frac{1}{2}$	$3\frac{1}{2}$	$10\frac{3}{4}$	$1\frac{3}{4}$	9.0
2S	48		3	$\frac{3}{4}$	1	7	$4\frac{1}{2}$	$4\frac{3}{4}$	$1\frac{1}{2}$	$5\frac{1}{4}$	$11\frac{3}{4}$	$12\frac{1}{2}$	$17\frac{1}{4}$	$14\frac{5}{8}$	12	8	$13\frac{1}{2}$	$3\frac{3}{8}$	$2\frac{5}{8}$	$7\frac{1}{2}$	$10\frac{5}{8}$	$1\frac{7}{8}$	6	$4\frac{5}{8}$	$14\frac{3}{8}$	$2\frac{3}{8}$	16.0
2M	48		3	$\frac{3}{4}$	1	7	$4\frac{1}{2}$	$4\frac{3}{4}$	$1\frac{1}{2}$	$5\frac{1}{4}$	$11\frac{3}{4}$	$12\frac{1}{2}$	$17\frac{1}{4}$	$14\frac{5}{8}$	12	8	$13\frac{1}{2}$	$3\frac{3}{8}$	$2\frac{5}{8}$	$7\frac{1}{2}$	$10\frac{5}{8}$	$1\frac{7}{8}$	6	$4\frac{5}{8}$	$14\frac{3}{8}$	$2\frac{3}{8}$	16.0
3	48		3	$\frac{3}{4}$	1	7	$4\frac{1}{2}$	$4\frac{3}{4}$	$1\frac{1}{2}$	$5\frac{1}{4}$	$11\frac{3}{4}$	$12\frac{1}{2}$	$17\frac{1}{4}$	$14\frac{5}{8}$	12	8	$13\frac{1}{2}$	$3\frac{3}{8}$	$2\frac{5}{8}$	$7\frac{1}{2}$	$10\frac{5}{8}$	$1\frac{7}{8}$	6	$4\frac{5}{8}$	$14\frac{3}{8}$	$2\frac{3}{8}$	16.0
4	48		3	$\frac{3}{4}$	1	7	$4\frac{1}{2}$	$4\frac{3}{4}$	$1\frac{1}{2}$	$5\frac{1}{4}$	$11\frac{3}{4}$	$12\frac{1}{2}$	$17\frac{1}{4}$	$14\frac{5}{8}$	12	8	$13\frac{1}{2}$	$3\frac{3}{8}$	$2\frac{5}{8}$	$7\frac{1}{2}$	$10\frac{5}{8}$	$1\frac{7}{8}$	6	$4\frac{5}{8}$	$14\frac{3}{8}$	$2\frac{3}{8}$	16.0
5	48		3	$\frac{3}{4}$	1	7	$4\frac{1}{2}$	$4\frac{3}{4}$	$1\frac{1}{2}$	$5\frac{1}{4}$	$11\frac{3}{4}$	$12\frac{1}{2}$	$17\frac{1}{4}$	$14\frac{5}{8}$	12	8	$13\frac{1}{2}$	$3\frac{3}{8}$	$2\frac{5}{8}$	$7\frac{1}{2}$	$10\frac{5}{8}$	$1\frac{7}{8}$	6	$4\frac{5}{8}$	$14\frac{3}{8}$	$2\frac{3}{8}$	16.0

STANDARD SIGN
W20-3A, B, C, D, F & G
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 1/10/2024 PLATE NO. W20-3.8



W21-5

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - C

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		$2\frac{1}{4}$	$\frac{5}{8}$	$\frac{3}{4}$	6	$3\frac{1}{2}$	16	9																	9.0	
2S	48		3	$\frac{3}{4}$	1	8	5	$21\frac{3}{8}$	$11\frac{1}{4}$																	16.0	
2M	48		3	$\frac{3}{4}$	1	8	5	$21\frac{3}{8}$	$11\frac{1}{4}$																	16.0	
3	48		3	$\frac{3}{4}$	1	8	5	$21\frac{3}{8}$	$11\frac{1}{4}$																	16.0	
4	48		3	$\frac{3}{4}$	1	8	5	$21\frac{3}{8}$	$11\frac{1}{4}$																	16.0	
5	48		3	$\frac{3}{4}$	1	8	5	$21\frac{3}{8}$	$11\frac{1}{4}$																	16.0	

PROJECT NO:


HWY:

COUNTY:


STANDARD SIGN
W21-5
WISCONSIN DEPT OF TRANSPORTATION
APPROVED *Matthew R Rauch*
For State Traffic Engineer
DATE 1/11/2024 PLATE NO. W21-5.7

SHEET NO: 82

E



W057-52



* See note 5

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	24	1 1/2	3/8	1/2	6	4 1/2	3	4 3/4	14 5/8	10 5/8	11 3/8	2	12												6.0	
2S	48	36	2 1/4	1/2	5/8	8	7	6	6 3/8	19 1/2	14	15	2 3/4	16 3/8											12.0		
2M	48	36	2 1/4	1/2	5/8	8	7	6	6 3/8	19 1/2	14	15	2 3/4	16 3/8											12.0		
3	48	36	2 1/4	1/2	5/8	8	7	6	6 3/8	19 1/2	14	15	2 3/4	16 3/8											12.0		
4	48	36	2 1/4	1/2	5/8	8	7	6	6 3/8	19 1/2	14	15	2 3/4	16 3/8											12.0		
5	48	36	2 1/4	1/2	5/8	8	7	6	6 3/8	19 1/2	14	15	2 3/4	16 3/8											12.0		

PROJECT NO:

HWY:

COUNTY:

STANDARD SIGN

W057-52

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew P. Rauch*
for State Traffic Engineer

DATE 2/1/2024 PLATE NO. W057-52.3

SHEET NO: 83

E

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BEVEL EXPOSED EDGES OF CONCRETE $\frac{3}{4}$ " UNLESS OTHERWISE NOTED.

THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES B-41-335" SHALL BE THE EXISTING GROUNDLINE.

AT THE BACK FACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL TYPE A.

EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.

THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.


THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH HEAVY RIPRAP AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON SHEET 1 AND THE ABUTMENT DETAILS.

AT ABUTMENTS, CONCRETE POURED UNDER WATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS.


SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.

PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO ENTIRE EXPOSED TOP OF SLAB, INCLUDING THE SLAB EDGE AND 1'-0" UNDER THE SLAB, THE TOP AND EXTERIOR EXPOSED FACE OF WINGS AND FRONT FACE OF ABUTMENT TO 1'-0" PAST THE EDGE OF SLAB.

AS BUILT PILE LOCATIONS ARE UNKNOWN. ESTIMATED 3 PILING AT 16'-0" LONG AT ALL WINGS. USE "REMOVING EXISTING TIMBER PILING" WHERE CONFLICTS OR AS DIRECTED BY ENGINEER.



CROSS SECTION THRU ROADWAY

LOOKING UPSTATION
(PILE NOT SHOWN FOR CLARITY)



ABUTMENT BACKFILL DIAGRAM

L = ABUTMENT BODY LENGTH AT BACKFACE (FT)
H = AVERAGE ABUTMENT FILL HEIGHT (FT)
H1 = WING 1 HEIGHT AT TIP (FT)
H2 = WING 2 HEIGHT AT TIP (FT)
W = WING LENGTH (FT)
EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
 $V_{CF} = (L)(3.0')(H) + (L)(0.5)(1.5H)(H) + (3')(0.5)(H1+H2+H+H)(W)$
 $V_{CY} = V_{CF}(EF)/27$
 $V_{TON} = V_{CY}(2.0)$


TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	SUPER	WEST ABUT.	EAST ABUT.	TOTALS
203.0260	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS B-41-923	EACH	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES B-41-335	EACH	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	---	172	172	344
502.0100	CONCRETE MASONRY BRIDGES	CY	95.8	30.2	30.2	156
502.3200	PROTECTIVE SURFACE TREATMENT	SY	185	17	17	219
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	---	2450	2450	4900
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	21930	1520	1520	24970
513.4061	RAILING TUBULAR TYPE M	LF	90	---	---	90
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	---	7	7	14
550.1100	PILING STEEL HP 10-INCH X 42 LB	LF	---	245	245	490
606.0300	RIPRAP HEAVY	CY	---	34	46	80
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	---	91	91	182
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4	---	---	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	---	54	54	108
645.0120	GEOTEXTILE TYPE HR	SY	---	91	112	203
SPV.0090.01	REMOVING EXISTING TIMBER PILING	LF	---	96	96	192
SPV.0090.02	FLASHING STAINLESS STEEL	LF	38	---	---	38
NON-BID ITEMS		SIZE	---	---	---	$\frac{1}{2}$, $\frac{3}{4}$
FILLER						

PROFILE GRADE LINE



PROTECTIVE SURFACE TREATMENT DETAILS




TYPICAL SECTION THRU ABUTMENT

▲ BACKFILL PAY LIMITS. BACKFILL BEYOND PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.

■ PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.

BENCH MARK

NO.	STATION	DESCRIPTION	ELEV.
BM 1	10+58.78, 49.61' RT	SPIKE IN UTILITY POLE	976.17



RODENT SHIELD DETAIL

* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".


THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALLY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

NO.	DATE	REVISION	BY
			STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

STRUCTURE B-41-335


DRAWN BY	PLANS CK'D	MJB

SHEET 2	85




BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
B-1	NOV 11, 2024	226323	509011
B-2	NOV 11, 2024	226473	508949
BORINGS COMPLETED BY: AMERICAN ENGINEERING TESTING			
REPORT COMPLETED BY: AMERICAN ENGINEERING TESTING			
ALL COORDINATES REFERENCED TO WCCS NAD 83(2011) MONROE COUNTY			

BORINGS COMPLETED BY: AMERICAN ENGINEERING TESTING
REPORT COMPLETED BY: AMERICAN ENGINEERING TESTING
ALL COORDINATES REFERENCED TO WCCS NAD 83(2011) MONROE COUNTY



MATERIAL SYMBOLS

LEGEND OF BORING



⁽¹⁾ UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)

⁽²⁾ UNLESS OTHERWISE, SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

- ▼ AT TIME OF DRILLING
- ▼ END OF DRILLING
- ▼ AFTER DRILLING

ABBREVIATIONS

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.

NO. DATE REVISION BY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

STRUCTURE B-41-335


	DRAWN	PLANS	
	T.D.		M.D.

SUBSURFACE EXPLORATION

SHEET 3


86

1




ELEVATION


LOOKING DOWNSTATION



PLAN



PILE PLAN



SECTION THRU BODY

- (A01) CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6.
- (A06) SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 35' LONG WITH A REQUIRED DRIVING RESISTANCE OF 140TONS PER PILE.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A17) $\frac{1}{2}$ " FILLER: SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF $\frac{1}{2}$ " FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD $\frac{3}{8}$ " BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A22) A506 BARS SPACED @ 1'-0" CNTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)
 - ALTERNATE THE POSITION OF THE 90° AND 180° HOOKS AT EACH VERTICAL LAYER OF TIES.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-41-335			
		DRAWN BY	PLANS CK'D
		JLA	RCP
WEST ABUTMENT		SHEET 4 87	

BILL OF BARS


NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
A501		80	6'-0"	X		ABUT BODY STIRRUPS
A502		34	8'-1"	X		ABUT BODY STIRRUPS - TOP U-BAR
A503		9	39'-3"			ABUT BODY HORIZ. - F.F.
A804		18	25'-7"	X		ABUT BODY HORIZ. - B.F.
A405		33	3'-0"	X		ABUT BODY TIE BARS
A506	X	33	2'-0"			ABUT BODY DOWEL BARS
A407	X	28	10'-2"	X		WING 1 STIRRUPS
A508	X	6	10'-5"	X		WING CORNER STIRRUPS
A509	X	18	11'-9"	X		WING LOWER HORIZ - F.F.
A810	X	18	13'-3"	X		WING LOWER HORIZ. - B.F.
A411	X	4	10'-1"			WING UPPER HORIZ.
A412	X	4	7'-6"			WING UPPER HORIZ.
A413	X	4	5'-0"			WING UPPER HORIZ.
A414	X	4	9'-8"	X		WING TOP HORIZ.
A415	X	4	8'-3"	X		WING 1 UPPER HORIZ. CORNER
A416	X	4	8'-3"	X		WING 2 UPPER HORIZ. CORNER
A417	X	28	10'-10"	X		WING 2 STIRRUPS


WING 1 ELEVATION



WING 1 PLAN




WING 1 PLA




'HP' PILE DETAILS

WING 2 ELEVATION






WING 2 PLAN



SECTION THRU WING 1

SECTION A-A



- (A01) OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE $\frac{3}{4}$ " "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- (A06) SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 35' LONG WITH A REQUIRED DRIVING RESISTANCE OF 140TONS PER PILE.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A19) 18" RUBBERIZED MEMBRANE WATERPROOFING, ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES"

NO.	DATE	REVISION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


STRUCTURE B-41-335

DRAWN BY JLA PLANS CK'D E

WEST APARTMENT SHEET 5


WEST ABUTMENT DETAILS

 INDICATES WING NUMBER




ELEVATION


LOOKING UPSTATION



PLAN



PILE PLAN



SECTION THRU BODY

- (A01)** CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6.
- (A06)** SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 35' LONG WITH A REQUIRED DRIVING RESISTANCE OF 140TONS PER PILE.
- (A15)** PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A17)** $\frac{1}{2}$ " FILLER: SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF $\frac{1}{2}$ " FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD $\frac{1}{8}$ " BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19)** 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A22)** B506 BARS SPACED @ 1'-0" CNTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)



ALTERNATE THE POSITION OF THE 90° AND 180° HOOKS AT EACH VERTICAL LAYER OF TIES

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-41-335			
		DRAWN BY	PLANS CK'D
		JLA	RCP
EAST ABUTMENT		SHEET 6 89	


BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.


BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
B501		80	6'-0"	X		ABUT BODY STIRRUPS
B502		34	8'-1"	X		ABUT BODY STIRRUPS - TOP U-BAR
B503		9	39'-3"			ABUT BODY HORIZ. - F.F.
B804		18	25'-7"	X		ABUT BODY HORIZ. - B.F.
B405		33	3'-0"	X		ABUT BODY TIE BARS
B506	X	33	2'-0"			ABUT BODY DOWEL BARS
B407	X	28	10'-2"	X		WING 4 STIRRUPS
B508	X	6	10'-5"	X		WING CORNER STIRRUPS
B509	X	18	11'-9"	X		WING LOWER HORIZ - F.F.
B810	X	18	13'-3"	X		WING LOWER HORIZ. - B.F.
B411	X	4	10'-1"			WING UPPER HORIZ.
B412	X	4	7'-6"			WING UPPER HORIZ.
B413	X	4	5'-0"			WING UPPER HORIZ.
B414	X	4	9'-8"	X		WING TOP HORIZ.
B415	X	4	8'-3"	X		WING 3 UPPER HORIZ. CORNER
B416	X	4	8'-3"	X		WING 4 UPPER HORIZ. CORNER
B417	X	28	10'-10"	X		WING 3 STIRRUPS




WING 3 ELEVATION



WING 3 PLAN









WING 3 PLAN



'HP' PILE DETAILS


SECTION THRU WING 3

SECTION A-A




- (A01) OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE $\frac{3}{4}$ " "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- (A06) SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 35' LONG WITH A REQUIRED DRIVING RESISTANCE OF 140TONS PER PILE.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A19) 18" RUBBERIZED MEMBRANE WATERPROOFING ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES".


NO.	DATE	REVISION		BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION				
STRUCTURE B-41-335				
EAST ABUTMENT DETAILS		DRAWN BY	PLANS CK'D	RCP
		SHEET 7		90
SCALE 1"				



CROSS SECTION THRU ROADWAY



PLAN




LONGITUDINAL SECTION

**DIMENSIONS ARE GIVEN PARALLEL TO € ROADWAY
UNLESS OTHERWISE NOTED**

① MEASURED NORMAL TO THE € OF ABUTMENT.
DIMENSIONS ARE TYPICAL FOR BOTH ABUTMENTS.

(A22) A506, B506 BARS SPACED @ 1'-0" CNTRS. MAY BE
PLACED AFTER CONCRETE IS POURED BUT BEFORE
INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO
CONC.)

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-41-335			
SUPERSTRUCTURE		DRAWN BY	PLANS CK'D
SCALE		JLA	RCP
SHEET 8		91	




CAMBER AND SLAB THICKNESS DIAGRAM

CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTIONS. CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT.

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE FOLLOW THIS PROCEDURE:

LESS	TOP OF SLAB ELEVATION AT FINAL GRADE
PLUS	SLAB THICKNESS
PLUS	CAMBER
EQUALS	FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
	TOP OF SLAB FALSEWORK ELEVATION




BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
S1001	X	83	42'-2"			SLAB BOTTOM LONGITUDINAL
S602	X	49	34'-2"			SLAB BOTTOM TRANSVERSE
S503	X	43	34'-2"			SLAB TOP TRANSVERSE
S504	X	24	42'-2"			SLAB TOP LONGITUDINAL
S505	X	70	7'-3"	X		ABUTMENT DIAPHRAGM STIRRUPS
S506	X	4	34'-2"			ABUTMENT DIAPHRAGM LONGITUDINAL
S607	X	48	6'-0"			SLAB TOP LONGIT. UNDER RAIL POSTS
S608	X	16	4'-8"	X		SLAB TOP LONGIT. UNDER RAIL END POSTS
S609	X	32	11'-5"	X		SLAB TOP HOOKS UNDER RAIL POSTS

TOP OF SLAB ELEVATIONS

LOCATION	C/L BRG. W. ABUT.	1/10 PT.	2/10 PT.	3/10 PT.	4/10 PT.	5/10 PT.	6/10 PT.	7/10 PT.	8/10 PT.	9/10 PT.	C/L BRG. E. ABUT.
N. EDGE OF DECK	979.17	979.19	979.20	979.22	979.24	979.26	979.28	979.29	979.31	979.33	979.35
CROWN OR R/L	978.82	978.84	978.86	978.88	978.89	978.91	978.93	978.95	978.97	978.98	979.00
S. EDGE OF DECK	978.48	978.50	978.51	978.53	978.55	978.57	978.59	978.60	978.62	978.64	978.66



SURFACE TREATMENT AND FLASHING DETAIL

STAINLESS STEEL FLASHING NOTES

THE BID ITEM "FLASHING STAINLESS STEEL" SHALL INCLUDE PROVIDING AND INSTALLING THE STAINLESS STEEL FLASHING, SILICONE CAULK, $\frac{3}{16}$ " CONCRETE SCREWS AND CLEANING THE EDGE OF DECK PRIOR TO ATTACHMENT OF THE FLASHING.

FLASHING TO BE INSTALLED AFTER PROTECTIVE SURFACE TREATMENT APPLICATION.

CONCRETE SCREWS SHALL BE 410 STAINLESS STEEL.

EXTEND FLASHING TO THE F.F. OF ABUTMENT WINGS.

TOP OF FLASHING SHALL BEGIN APPROXIMATELY 1-INCH BELOW TOP OF SLAB SURFACE.

THE FLASHING IS TO BE A CONSTANT HEIGHT BASED ON THE THINNEST SLAB DEPTH OVER THE ENTIRE BRIDGE LENGTH.

PROVIDE 2" MINIMUM FLASHING OVERLAP, FASTEN WITH $\frac{3}{16}$ " X 2" (MIN.) CONCRETE SCREWS.

CAULK SHALL BE NON-STAINING, GRAY NON-BITUMINOUS JOINT SEALER.

SURVEY TOP OF SLAB ELEVATIONS

LOCATION	ABUTMENT	5/10 PT.	ABUTMENT
N. GUTTER			
CROWN OR R/L			
S. GUTTER			

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF SLAB ELEVATIONS AT THE C/L OF ABUTMENTS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR R/L. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.


NOTES

FILL IN THE TABLE OF "SURVEY TOP OF SLAB ELEVATIONS" FOR EACH SPAN ON AS BUILT PLANS.

TOP TRANSVERSE BARS IN SLAB SHALL BE SUPPORTED BY INDIVIDUAL BAR CHAIRS AT APPROXIMATELY 3'-0" CENTERS EACH WAY. BOTTOM LONGITUDINAL BARS SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS AT APPROXIMATELY 4'-0" CENTERS.

ALL SLAB THICKNESS DIMENSIONS ARE MINIMUM. ANY TOLERANCES NECESSARY TO CORRECT CONSTRUCTION DISCREPANCIES ARE TO BE PLUS (+).

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-41-335			
DRAWN BY	JLA	PLANS CK'D	RCP
SUPERSTRUCTURE DETAILS		SHEET 9	92
SCALE =			



DIVISION - MONROE CTH A

STATION	REAL STATION	DISTANCE	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
									NOTE 1	1.00	
6+89.70	689.70	0.00	13.24	0.00	0.06	0	0	0	0	0	0
7+00.00	700.00	10.30	12.97	0.00	0.92	5	0	0	5	0	5
7+25.00	725.00	25.00	12.82	0.00	3.43	12	0	2	17	3	15
7+50.00	750.00	25.00	13.18	0.75	5.58	12	0	4	29	8	22
7+58.84	758.84	8.84	15.66	0.75	7.36	5	0	2	34	10	24
7+75.00	775.00	16.16	16.28	0.75	13.17	10	0	6	44	18	27
8+00.00	800.00	25.00	16.98	0.75	21.94	15	1	16	59	38	21
8+25.00	825.00	25.00	17.46	0.75	35.66	16	1	27	75	71	2
8+37.50	837.50	12.50	17.94	0.75	43.57	8	0	18	83	94	-13
8+50.00	850.00	12.50	18.43	0.75	32.91	8	0	18	91	116	-27
8+63.76	863.76	13.76	18.15	0.75	24.99	9	0	15	100	135	-37
8+75.00	875.00	11.24	45.04	9.00	11.80	13	2	8	113	145	-36
8+88.74	888.74	13.74	44.48	9.00	5.17	23	5	4	136	150	-23
9+00.00	900.00	11.26	41.36	9.00	7.84	18	4	3	154	154	-13
9+25.00	925.00	25.00	34.29	9.00	9.22	35	8	8	189	164	4
9+50.00	950.00	25.00	27.58	9.00	31.32	29	8	19	218	188	2
9+73.39	973.39	23.39	20.67	9.00	75.25	21	8	46	239	245	-43
10+28.61	1028.61	55.22	17.35	9.00	44.34				239	245	-43
10+50.00	1050.00	21.39	17.78	9.00	27.21	14	7	28	253	280	-71
10+75.00	1075.00	25.00	20.03	9.00	22.77	18	8	23	271	309	-90
11+00.00	1100.00	25.00	23.68	9.00	27.44	20	8	23	291	338	-107
11+11.89	1111.89	11.89	26.09	9.00	26.88	11	4	12	302	353	-115
11+14.67	1114.67	2.78	26.65	9.00	27.58	3	1	3	305	356	-116
11+25.00	1125.00	10.33	28.93	9.00	33.88	11	3	12	316	371	-123
11+36.31	1136.31	11.31	31.48	9.00	40.27	13	4	16	329	391	-134
11+40.24	1140.24	3.93	32.24	9.00	42.96	5	1	6	334	399	-138
11+50.00	1150.00	9.76	34.01	9.00	41.30	12	3	15	346	418	-148
11+60.70	1160.70	10.70	35.38	9.00	43.99	14	4	17	360	439	-159
11+65.85	1165.85	5.15	36.08	9.00	42.86	7	2	8	367	449	-164
11+75.00	1175.00	9.15	37.25	9.00	36.68	12	3	13	379	465	-171
12+00.00	1200.00	25.00	39.52	9.00	21.10	36	8	27	415	499	-177
12+15.00	1215.00	15.00	15.81	0.75	13.39	15	3	10	430	511	-177
12+25.00	1225.00	10.00	16.01	0.75	11.64	6	0	5	436	518	-178
12+38.95	1238.95	13.95	15.07	0.75	10.41	8	0	6	444	525	-177
12+50.00	1250.00	11.05	15.11	0.75	8.39	6	0	4	450	530	-176
12+75.00	1275.00	25.00	14.32	0.00	4.38	14	0	6	464	538	-170
13+00.00	1300.00	25.00	14.70	0.00	1.53	13	0	3	477	541	-160
13+18.34	1318.34	18.34	14.52	0.00	0.63	10	0	1	487	543	-152
					487		96	434			


NOTES:

- 1 - CUT (SALVAGE/UNUSABLE PAVEMENT MATERIAL INCLUDED)
- 2 - SALVAGE/UNUSABLE PAVEMENT MATERIAL. (THIS DOES NOT SHOW UP IN THE CROSSE SECTIONS)
- 3 - FILL (DOES NOT INCLUDE UNUSABLE PAVEMENT VOLUME)
- 4 - THE MASS ORDINATE + OR - QUANTITIES CALCULATED. PLUS QUANTITIES AS EXCESS MATERIAL. MINUS A SHORTAGE OF MATERIAL

NO MARSH OR EBS IS ANTICIPATED.

9

9



BEGIN CONSTRUCTION
STA 6+89.66

PROJECT NO: 5116-00-71

HWY: CTH A

COUNTY: MONROE

CROSS SECTIONS: MAINLINE

SHEET

FILE NAME : X:\1323000\240176.01\TECH\CAD\51160001\Sheets\090201_XS.DWG
LAYOUT NAME - 01


PLOT DATE : 8/22/2025 9:34 AM


PLOT BY : JEFF BRE


PLOT NAME


PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT.


— 95 —


























PROJECT NO: 5116-00-71

HWY: CTH A

COUNTY: MONROE

CROSS SECTIONS: MAINLINE

SHEET

E

FILE NAME : X:\1323000\240176.01\TECH\CAD\51160001\Sheets\090201_XS.DWG
LAYOUT NAME - 11


PLOT DATE : 8/22/2025 9:37 AM

PLOT BY : JEFF BRE

PLOT NAME

PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT.

1/ISDOT/CADD SHEET 4



Wisconsin Department of Transportation

Dedicated people creating transportation solutions
through innovation and exceptional service.

<http://www.dot.wisconsin.gov>