

JANUARY 2026

ORDER OF SHEETS

Section No. 1 Title
 Section No. 2 Typical Sections and Details
 Section No. 3 Estimate of Quantities
 Section No. 3 Miscellaneous Quantities
 Section No. 4 Right of Way Plat
 Section No. 5 Plan and Profile
 Section No. 6 Standard Detail Drawings
 Section No. 7 Sign Plates
 Section No. 8 Structure Plans
 Section No. 9 Computer Earthwork Data
 Section No. 0 Cross Sections

TOTAL SHEETS = 72



N

DESIGN DESIGNATION

A.A.D.T. (2026) = 4,960
 A.A.D.T. (2046) = 6,630
 D.H.V. =
 D.D. = 50/50
 T. = 11%
 DESIGN SPEED = 55 MPH
 ESALS = 1,140,000

CONVENTIONAL SYMBOLS

| PLAN | PROFILE |
|-----------------------------------|--|
| CORPORATE LIMITS | GRADE LINE |
| PROPERTY LINE | ORIGINAL GROUND |
| LOT LINE | MARSH OR ROCK PROFILE (To be noted as such) |
| LIMITED HIGHWAY EASEMENT | SPECIAL DITCH |
| EXISTING RIGHT OF WAY | GRADE ELEVATION |
| PROPOSED OR NEW R/W LINE | CULVERT (Profile View) |
| SLOPE INTERCEPT | |
| REFERENCE LINE | ELECTRIC |
| EXISTING CULVERT | FIBER OPTIC |
| PROPOSED CULVERT (Box or Pipe) | GAS |
| COMBUSTIBLE FLUIDS | SANITARY SEWER |
| MARSH AREA | STORM SEWER |
| WOODED OR SHRUB AREA | TELEPHONE |
| | WATER |
| | UTILITY PEDESTAL |
| | POWER POLE |
| | TELEPHONE POLE |

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


STATE HIGHWAY REHABILITATION-MAINTENANCE PROJECT

FOUNTAIN CITY - ALMA

WAUMANDEE CREEK BRIDGE B-06-0059

STH 35
BUFFALO COUNTY

STATE PROJECT NUMBER
7160-00-72



HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), BUFFALO COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES.

ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 18.

| STATE PROJECT | FEDERAL PROJECT | |
|---------------|-----------------|----------|
| | PROJECT | CONTRACT |
| 7160-00-72 | WISC 2026160 | 1 |
| | | |
| | | |
| | | |

ORIGINAL PLANS PREPARED BY
AYRES



08/01/2025

(Date) (Signature)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY
 Surveyor AYRES ASSOCIATES INC
 Designer AYRES ASSOCIATES INC
 Project Manager KYLE MCLEAN, PE
 Regional Examiner NW REGION
 Regional Supervisor NICHOLAS PITSCHE, PE

APPROVED FOR THE DEPARTMENT
 DATE: 08/01/2025 (Signature)

UTILITIES CONTACTS

BRIGHTSPEED OF CENTRAL WISCONSIN, LLC XCEL ENERGY
 COMMUNICATION LINE ELECTRICITY TRANSMISSION
 ATTN: TOM MURRAY ATTN: JOSH TOMLINSON
 1905 WARD AVENUE 414 NICOLLET MALL
 LA CROSSE, WI 54601 MINNEAPOLIS, MN 55401
 PHONE: 608-780-0895 PHONE: 715-355-9126
 EMAIL: tom.l.murray@brightspeed.com EMAIL: JOSHUA.TOMLINSON@XCELENERGY.COM

COCHRANE COOPERATIVE TELEPHONE CO
 COMMUNICATION LINE
 ATTN: MATT BIESTERVELD
 103 W 5TH ST
 COCHRANE, WI 54622-0189
 PHONE: 608-248-2323
 EMAIL: M.BISTERVELD@COCHRANETEL.COM

WISCONSIN DNR LIAISON

AMY LESIK
 WDNR NORTHERN REGION
 1300 WEST CLAIREMONT AVENUE
 EAU CLAIRE, WI 54701-6127
 PHONE: 715-495-1903
 EMAIL: Amy.Lesik@wisconsin.gov

DESIGN PROJECT MANAGER

KYLE MCLEAN
 WISDOT NW REGION
 718 WEST CLAIREMONT AVENUE
 EAU CLAIRE, WI 54701
 PHONE: 715-225-9442
 EMAIL: Kyle.McLean@dot.wi.gov

DESIGN PROJECT LEADER

ARLEN BEAUDETTE
 AYRES
 3433 OAKWOOD HILLS PARKWAY
 EAU CLAIRE, WI 54701
 PHONE: 715-834-3161
 EMAIL: beaudettea@AyresAssociates.com

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

CONTRACTOR WILL BE RESPONSIBLE FOR RESHAPING AND SEEDING ANY PREVIOUSLY GRASSED AREAS WHICH ARE DISTURBED BY OPERATIONS, OUTSIDE OF THE NORMAL CONSTRUCTION LIMITS.

HMA PAVEMENT WEIGHT CALCULATIONS ARE BASED ON 112 LBS/SY/IN.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.

RIGHT OF WAY INFORMATION SHOWN ON THE PLANS IS APPROXIMATE.

THE CONTRACTOR IS TO WORK WITH UTMOST CARE AND PROTECT ALL SURVEY MARKERS. REMOVAL OF ANY SURVEY MARKER IS TO BE WITH THE APPROVAL OF THE ENGINEER.

WHEN THE QUANTITY OF THE ITEMS OF BASE AGGREGATE, SUBBASE OR HMA PAVEMENT IS MEASURED FOR PAYMENT BY THE TON OR CUBIC YARD, THE DEPTH OR THICKNESS OF THE LAYERS SHOWN ON THE PLAN IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

EROSION CONTROL FEATURES AS SHOWN IN THE PLANS ARE AT APPROXIMATE LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE CONTRACTOR'S EROSION CONTROL IMPLEMENTATION PLAN (ECIP) AND APPROVED BY THE ENGINEER. MAINTAIN EROSION CONTROL MEASURES UNTIL SUCH A TIME AS THE ENGINEER DETERMINES THE MEASURE IS NO LONGER NECESSARY.

CURVE DATA IS BASED ON THE RADIUS DEFINITION.

PAVEMENT REMOVAL WILL BE TO THE NEAREST JOINT OR A SAWED EDGE WILL BE REQUIRED AS DIRECTED BY THE ENGINEER.

PRIOR TO PLACING THE NEW BASE AGGREGATE DENSE COURSE OR PAVED SHOULDERS EXISTING UNCOMPACTED SHOULDER MATERIAL SHALL BE REMOVED OR DEPOSITED ON THE OUTER PORTION OF THE EXISTING SHOULDER OR AS DIRECTED BY THE ENGINEER.

SAWCUTS, AS SHOWN ON THE PLANS, ARE SUGGESTED LOCATIONS AND MAY BE ADJUSTED AT THE DISCRETION OF THE ENGINEER TO BETTER SUIT FIELD CONDITIONS.

PRIOR TO PLACEMENT OF BEAM GUARD THE SHOULDERS SHALL BE IN PLACE, SHAPED AND COMPACTED.

TRAFFIC CONTROL DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.

DO NOT DRIVE OR STORE EQUIPMENT, OR STORE CONSTRUCTION MATERIALS IN ENVIRONMENTALLY SENSITIVE AREAS, WETLANDS OR WATERWAYS.

RUNOFF COEFFICIENT TABLE

| LAND USE: | HYDROLOGIC SOIL GROUP | | | | | | | | | | | |
|--------------------------|-----------------------|----------|-----------------------|-----------------------|----------|-----------------------|-----------------------|----------|-----------------------|-----------------------|----------|-----------------------|
| | A | | | B | | | C | | | D | | |
| | SLOPE RANGE (PERCENT) | | SLOPE RANGE (PERCENT) | SLOPE RANGE (PERCENT) | | SLOPE RANGE (PERCENT) | SLOPE RANGE (PERCENT) | | SLOPE RANGE (PERCENT) | SLOPE RANGE (PERCENT) | | SLOPE RANGE (PERCENT) |
| 0-2 | 2-6 | 6 & OVER | 0-2 | 2-6 | 6 & OVER | 0-2 | 2-6 | 6 & OVER | 0-2 | 2-6 | 6 & OVER | |
| ROW CROPS: | .08 | .16 | .22 | .12 | .20 | .27 | .15 | .24 | .33 | .19 | .28 | .38 |
| | .22 | .30 | .38 | .26 | .34 | .44 | .30 | .37 | .50 | .34 | .41 | .56 |
| MEDIAN STRIPTURF: | .19 | .20 | .24 | .19 | .22 | .26 | .20 | .23 | .30 | .20 | .25 | .30 |
| | .24 | .26 | .30 | .25 | .28 | .33 | .26 | .30 | .37 | .27 | .32 | .40 |
| SIDE SLOPETURF: | | | .25 | | | .27 | | | .28 | | | .30 |
| | | | .32 | | | .34 | | | .36 | | | .38 |
| PAVEMENT: | | | | | | | | | | | | |
| ASPHALT: | | | | | | | | | | | | .70 - .95 |
| CONCRETE: | | | | | | | | | | | | .80 - .95 |
| BRICK: | | | | | | | | | | | | .70 - .80 |
| DRIVES, WALKS: | | | | | | | | | | | | .75 - .85 |
| ROOFS: | | | | | | | | | | | | .75 - .95 |
| GRAVEL ROADS, SHOULDERS: | | | | | | | | | | | | .40 - .60 |

TOTAL PROJECT AREA = 0.938 ACRES

TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.330 ACRES

PROJECT NO: 7160-00-72

HWY: STH 35

COUNTY: BUFFALO



GENERAL NOTES

SHEET

E

2

2




| BENCH MARKS | | | |
|-------------|---------|--------|-----------------------------|
| NO. | STATION | ELEV. | DESCRIPTION |
| 50 | 598+00 | 661.10 | 120D SPIKE IN PPOL, 43' LT. |
| 51 | 595+50 | 671.58 | WISDOT CAP, 21' RT. |

BP: 594+09.51
Y = 244004.81
X = 590116.41

CP #1 (PK NAIL IN SHLDR OF ROAD)
Y = 244052.32
X = 590096.75



BEGIN PROJECT
STA 595+04.75
Y = 244063.11
X = 590041.11




CURVE DATA

PI STA = 596+41.55
Y = 244149.886
X = 589935.317
DELTA = 9°15'41" LT
D = 2°00'00"
T = 232.04'
L = 463.07'
R = 2864.79'
PC STA = 594+09.51
Y = 244004.812
X = 590116.415
PT STA = 598+72.58
Y = 244263.923
X = 589733.232
DB = N51°18'09"W
DA = N60°33'50"W

ALIGNMENT CONTROLS



ALIGNMENT TIES




ASPHALTIC SURFACE MILLING AND PAVEMENT WEDGE DETAIL

STA 595+04.75 - STA 595+28.55
STA 597+66.69 - STA 597+691.67

2

2



APPROACH SLAB DETAIL


NOTES: ELEVATIONS WILL BE FIELD VERIFIED BY THE ENGINEER

ADJUSTING STEEL PLATE BEAM GUARD AND REPLACING GUARDRAIL POSTS AND BLOCKS WILL TAKE PLACE AT EACH QUADRANT OF THE STRUCTURE. REPLACE ALL POSTS REQUIRED FOR THRIF BEAM STRUCTURE APPROACH

| | | | | | |
|--|--------------------------------|-------------------------|----------------------|-------------------------|----------------------|
| PROJECT NO: 7160-00-72 | HWY: STH 35 | COUNTY: BUFFALO | CONSTRUCTION DETAILS | SHEET | E |
| FILE NAME : I:\42\42-1328.00 - BUFFALO CO, STH 35 OVERLAY\C3D\Sheets\021002-CD.DWG | PLOT DATE : 11/25/2025 8:47 AM | PLOT BY : KUSCHEL, LEVI | PLOT NAME : | PLOT SCALE : 1 IN:40 FT | WISDOT\CADDS SHEET 4 |


2

2






LEGEND

—●— SILT FENCE




SILT FENCE END DETAIL
(TURNAROUNDS - TO REDIRECT AMPHIBIANS AND REPTILES AWAY FROM CONSTRUCTION ZONE)





INFORMATION SHOWN ON THIS SHEET IS SCHEMATIC,
DETAIL PROVIDED IS NOT SURVEY QUALITY AND
LOCATIONS SHOULD BE FIELD VERIFIED BY THE ENGINEER



Estimate Of Quantities

7160-00-72

| Line | Item | Item Description | Unit | Total | Qty |
|------|------------|---|------|-----------|-----------|
| 0002 | 203.0211.S | Abatement of Asbestos Containing Material (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0004 | 203.0260 | Removing Structure Over Waterway Minimal Debris (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0006 | 203.0335 | Debris Containment Over Waterway (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0008 | 204.0115 | Removing Asphaltic Surface Butt Joints | SY | 17.000 | 17.000 |
| 0010 | 204.0120 | Removing Asphaltic Surface Milling | SY | 175.000 | 175.000 |
| 0012 | 204.0150 | Removing Curb & Gutter | LF | 21.000 | 21.000 |
| 0014 | 204.0190 | Removing Surface Drains | EACH | 1.000 | 1.000 |
| 0016 | 205.0100 | Excavation Common | CY | 110.000 | 110.000 |
| 0018 | 206.1001 | Excavation for Structures Bridges (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0020 | 210.1500 | Backfill Structure Type A | TON | 70.000 | 70.000 |
| 0022 | 213.0100 | Finishing Roadway (project) 01. 7160-00-72 | EACH | 1.000 | 1.000 |
| 0024 | 305.0110 | Base Aggregate Dense 3/4-Inch | TON | 7.000 | 7.000 |
| 0026 | 305.0120 | Base Aggregate Dense 1 1/4-Inch | TON | 125.000 | 125.000 |
| 0028 | 415.0120 | Concrete Pavement 12-Inch | SY | 74.000 | 74.000 |
| 0030 | 415.0410 | Concrete Pavement Approach Slab | SY | 111.000 | 111.000 |
| 0032 | 455.0605 | Tack Coat | GAL | 15.000 | 15.000 |
| 0034 | 465.0105 | Asphaltic Surface | TON | 40.000 | 40.000 |
| 0036 | 502.0100 | Concrete Masonry Bridges | CY | 9.000 | 9.000 |
| 0038 | 502.3200 | Protective Surface Treatment | SY | 865.000 | 865.000 |
| 0040 | 502.3210 | Pigmented Surface Sealer | SY | 11.000 | 11.000 |
| 0042 | 505.0600 | Bar Steel Reinforcement HS Coated Structures | LB | 1,460.000 | 1,460.000 |
| 0044 | 505.0905 | Bar Couplers No. 5 | EACH | 20.000 | 20.000 |
| 0046 | 509.0301 | Preparation Decks Type 1 | SY | 100.000 | 100.000 |
| 0048 | 509.0302 | Preparation Decks Type 2 | SY | 40.000 | 40.000 |
| 0050 | 509.0500 | Cleaning Decks | SY | 865.000 | 865.000 |
| 0052 | 509.1500 | Concrete Surface Repair | SF | 50.000 | 50.000 |
| 0054 | 509.2000 | Full-Depth Deck Repair | SY | 2.000 | 2.000 |
| 0056 | 509.2500 | Concrete Masonry Overlay Decks | CY | 62.000 | 62.000 |
| 0058 | 516.0500 | Rubberized Membrane Waterproofing | SY | 18.000 | 18.000 |
| 0060 | 601.0584 | Concrete Curb & Gutter 4-Inch Sloped 30-Inch Type TBT | LF | 26.000 | 26.000 |
| 0062 | 602.3010 | Concrete Surface Drains | CY | 1.000 | 1.000 |
| 0064 | 603.8000 | Concrete Barrier Temporary Precast Delivered | LF | 500.000 | 500.000 |
| 0066 | 603.8125 | Concrete Barrier Temporary Precast Installed | LF | 970.000 | 970.000 |
| 0068 | 606.0200 | Riprap Medium | CY | 2.000 | 2.000 |
| 0070 | 614.0150 | Anchor Assemblies for Steel Plate Beam Guard | EACH | 2.000 | 2.000 |
| 0072 | 614.0400 | Adjusting Steel Plate Beam Guard | LF | 136.000 | 136.000 |
| 0074 | 614.0905 | Crash Cushions Temporary | EACH | 4.000 | 4.000 |
| 0076 | 614.0950 | Replacing Guardrail Posts and Blocks | EACH | 36.000 | 36.000 |
| 0078 | 618.0100 | Maintenance and Repair of Haul Roads (project) 01. 7160-00-72 | EACH | 1.000 | 1.000 |
| 0080 | 619.1000 | Mobilization | EACH | 1.000 | 1.000 |
| 0082 | 624.0100 | Water | MGAL | 2.000 | 2.000 |
| 0084 | 628.1504 | Silt Fence | LF | 470.000 | 470.000 |
| 0086 | 628.1520 | Silt Fence Maintenance | LF | 940.000 | 940.000 |
| 0088 | 628.1905 | Mobilizations Erosion Control | EACH | 4.000 | 4.000 |
| 0090 | 628.1910 | Mobilizations Emergency Erosion Control | EACH | 4.000 | 4.000 |
| 0092 | 642.5001 | Field Office Type B | EACH | 1.000 | 1.000 |
| 0094 | 643.0300 | Traffic Control Drums | DAY | 3,509.000 | 3,509.000 |
| 0096 | 643.0420 | Traffic Control Barricades Type III | DAY | 130.000 | 130.000 |
| 0098 | 643.0715 | Traffic Control Warning Lights Type C | DAY | 2,363.000 | 2,363.000 |

Estimate Of Quantities

7160-00-72

| Line | Item | Item Description | Unit | Total | Qty |
|------|------------|---|------|-----------|-----------|
| 0100 | 643.0900 | Traffic Control Signs | DAY | 3,900.000 | 3,900.000 |
| 0102 | 643.1050 | Traffic Control Signs PCMS | DAY | 14.000 | 14.000 |
| 0104 | 643.3165 | Temporary Marking Line Paint 6-Inch | LF | 5,353.000 | 5,353.000 |
| 0106 | 643.3850 | Temporary Marking Stop Line Removable Tape 18-Inch | LF | 105.000 | 105.000 |
| 0108 | 643.5000 | Traffic Control | EACH | 1.000 | 1.000 |
| 0110 | 645.0130 | Geotextile Type R | SY | 6.000 | 6.000 |
| 0112 | 646.2020 | Marking Line Epoxy 6-Inch | LF | 936.000 | 936.000 |
| 0114 | 650.4500 | Construction Staking Subgrade | LF | 90.000 | 90.000 |
| 0116 | 650.5000 | Construction Staking Base | LF | 41.000 | 41.000 |
| 0118 | 650.5500 | Construction Staking Curb Gutter and Curb & Gutter | LF | 26.000 | 26.000 |
| 0120 | 650.6501 | Construction Staking Structure Layout (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0122 | 650.9911 | Construction Staking Supplemental Control (project) 01. 7160-00-72 | EACH | 1.000 | 1.000 |
| 0124 | 650.9920 | Construction Staking Slope Stakes | LF | 90.000 | 90.000 |
| 0126 | 661.0101 | Temporary Traffic Signals for Bridges (structure) 01. B-06-0059 | EACH | 1.000 | 1.000 |
| 0128 | 690.0150 | Sawing Asphalt | LF | 110.000 | 110.000 |
| 0130 | 715.0502 | Incentive Strength Concrete Structures | DOL | 500.000 | 500.000 |
| 0132 | 999.2000.S | Installing and Maintaining Bird Deterrent System (station) 01. 596+49 | EACH | 1.000 | 1.000 |
| 0134 | ASP.1T0A | On-the-Job Training Apprentice at \$5.00/HR | HRS | 300.000 | 300.000 |
| 0136 | ASP.1T0G | On-the-Job Training Graduate at \$5.00/HR | HRS | 300.000 | 300.000 |

REMOVING ITEMS

| | | 204.0115 | 204.0120 | 204.0150 | 204.0190 | 205.0100 | | |
|----------------------------------|----|----------------------------------|----------------------------|-------------------------------|-------------------------------|----------------------------|----------|------------|
| REMOVING ASPHALTIC SURFACE | | REMOVING ASPHALTIC SURFACE | REMOVING BUTT JOINTS | REMOVING CURB & MILLING | REMOVING SURFACE GUTTER | EXCAVATION COMMON CY | | |
| STATION | TO | STATION | LOCATION | SY | SY | LF | EACh | CY |
| 595+04.75 | - | 595+25.36 | STH 35, LT | -- | -- | 21 | 1 | - |
| 595+04.75 | - | 595+28.55 | STH 35 | 8 | 80 | -- | -- | - |
| 595+28.55 | - | 595+49.75 | STH 35 | -- | -- | -- | -- | 60 |
| 597+46.67 | - | 597+66.69 | STH 35 | -- | -- | -- | -- | 50 |
| 597+66.69 | - | 597+91.67 | STH 35 | 9 | 95 | -- | -- | - |
| TOTAL 0010 | | | | 17 | 175 | 21 | 1 | 110 |

FINISHING ROADWAY

213.0100.01
FINISHING ROADWAY
(PROJECT) (01. 7160-00-72)

PROJECT EACH

| STATION | TO | STATION | LOCATION | LF | CY | TYPE TBT | CONCRETE SURFACE DRAINS | RIPRAP MEDIUM | GEOTEXTILE TYPE R |
|-------------------|----|-----------|------------|-----------|----------|----------|----------------------------|------------------|----------------------|
| 595+04.75 | - | 595+25.36 | STH 35, LT | 26 | -- | -- | -- | -- | -- |
| 595+15.58 | - | 595+15.58 | STH 35, LT | -- | 1 | 2 | 6 | | |
| TOTAL 0010 | | | | 26 | 1 | 2 | 6 | | |

BASE AGGREGATE DENSE

| | | 305.011 | 305.0120 | |
|-------------------|---|-----------|----------|------------|
| STATION | | LOCATION | TON | TON |
| 595+04.75 | - | 595+49.75 | STH 35 | 4 |
| 595+28.55 | - | 595+49.75 | STH 35 | -- |
| 597+46.67 | - | 597+66.69 | STH 35 | 65 |
| 597+46.67 | - | 597+91.67 | STH 35 | -- |
| TOTAL 0010 | | | 7 | 125 |

CONCRETE PAVEMENT

| STATION | TO | STATION | LOCATION | SY | SY |
|-------------------|----|-----------|----------|-----------|------------|
| 595+28.55 | - | 595+49.75 | STH 35 | 38 | 57 |
| 597+46.67 | - | 597+66.69 | STH 36 | 36 | 54 |
| TOTAL 0010 | | | | 74 | 111 |

ASPHALTIC SURFACE

| STATION | TO | STATION | LOCATION | GAL | TON |
|-------------------|----|-----------|----------|-----------|-----------|
| 595+04.75 | - | 595+28.55 | STH 35 | 7 | 20 |
| 597+66.69 | - | 597+91.67 | STH 35 | 8 | 20 |
| TOTAL 0010 | | | | 15 | 40 |

ADJUSTING GUARDRAIL

| <u>CONCRETE BARRIER TEMPORARY PRECAST</u> | | | | | |
|---|-------|---|------------|---|--|
| 603.8000 CONCRETE BARRIER TEMPORARY PRECAST DELIVERED | | 603.8125 CONCRETE BARRIER TEMPORARY PRECAST INSTALLED | | 614.0905 CRASH CUSHIONS TEMPORARY EACH | |
| LOCATION | STAGE | LF | LF | BACK WIDTH | OBJECT MARKING PATTERN |
| NB SHOULDER | 1 | 500 | 500 | 2 | 1 OM-3L (W05-58L) 1 OM-3R (W05-58R) |
| SB SHOULDER | 2 | -- | 470 | 2 | 1 OM-3L (W05-58L) 1 OM-3R (W05-58R) |
| TOTAL 0010 | | 500 | 970 | 4 | |

CRASH CUSHION TEMPORARY MISCELLANEOUS QUANTITIES

| LEVEL | CRASH TEST | TRAFFIC DIRECTION | TRAFFIC LOCATION | CRASH SUCION SHIELDS |
|-------|--|----------------------|----------------------------|---|
| 2 FT | 1 OM-3L (W05-58L) 1 OM-3R (W05-58R) | TL-2 | BIDIRECTIONAL LT AND RT | CONCRETE BARRIER PRECAST ALONG BRIDGE WORK ZONE |
| 2 FT | 1 OM-3L (W05-58L) 1 OM-3R (W05-58R) | TL-2 | BIDIRECTIONAL LT AND RT | CONCRETE BARRIER PRECAST ALONG BRIDGE WORK ZONE |

| STATION | TO | STATION | LOCATION | LF | EACH |
|-------------------|----|---------|------------|------------|-----------|
| 594+97 | - | 595+28 | STH 35, LT | 27 | 9 |
| 594+97 | - | 595+47 | STH 35, RT | 44 | 9 |
| 597+47 | - | 597+97 | STH 35, LT | 44 | 9 |
| 597+71 | - | 597+97 | STH 35, RT | 21 | 9 |
| TOTAL 0010 | | | | 136 | 36 |

ALL ITEMS ON THIS SHEET
ARE CATEGORY 0010
UNLESS OTHERWISE NOTED

MAINTENANCE AND REPAIR OF HAUL ROADS

| | | |
|---|---------|----------|
| 618.0100.01 MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) (01. 7160-00-72) | PROJECT | EACH |
| 7160-00-72 | | 1 |
| TOTAL 0010 | | 1 |

MOBILIZATION

| | | |
|--------------------------|----------|----------|
| 619.1000 MOBILIZATION | LOCATION | EACH |
| PROJECT LIMITS | | 1 |
| TOTAL 0010 | | 1 |

WATER

| | | |
|-------------------|----------|----------|
| 624.0100 WATER | LOCATION | MGAL |
| COMPACTION | | 2 |
| TOTAL 0010 | | 2 |

EROSION CONTROL ITEMS

| STATION | TO | STATION | LOCATION | 628.1504 SILT FENCE | 628.1520 SILT FENCE | MAINTENANCE |
|---------|----|---------------|-------------------|---------------------------|------------------------|-------------|
| | | | | LF | LF | |
| 595+00 | - | 595+70 | STH 35 | 200 | 400 | |
| 597+30 | - | 598+00 | STH 35 | 175 | 350 | |
| | | UNDISTRIBUTED | | 95 | 190 | |
| | | | TOTAL 0010 | 470 | 940 | |

MOBILIZATIONS EROSION CONTROL

| | | | | | |
|---|----------|----------|--|----------|------|
| 628.1905 MOBILIZATIONS EROSION CONTROL | LOCATION | EACH | 628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL | LOCATION | EACH |
| PROJECT LIMITS | | 4 | | 4 | |
| TOTAL 0010 | | 4 | | 4 | |

FIELD OFFICE TYPE B

| | | |
|------------------------------------|----------|----------|
| 642.5001 FIELD OFFICE TYPE B | LOCATION | EACH |
| PROJECT LIMITS | | 1 |
| TOTAL 0010 | | 1 |

TRAFFIC CONTROL

| STAGE | DURATION | | TRAFFIC CONTROL CONTROL | TRAFFIC CONTROL BARRICADES | TRAFFIC CONTROL WARNING | TRAFFIC CONTROL TYPE III | TRAFFIC CONTROL LIGHTS | TRAFFIC CONTROL TYPE C | TRAFFIC CONTROL SIGNS | TRAFFIC CONTROL SIGNS | TRAFFIC CONTROL PCMS | TRAFFIC CONTROL TRAFFIC (STRUCTURE) (01. B-06-0059) | TRAFFIC CONTROL FOR BRIDGES (STRUCTURE) (01. B-06-0059) | LOCATION | COLOR/DESCRIPTION | STAGE | LF | LF |
|------------------------------|----------|--------------|-------------------------------|----------------------------------|-------------------------------|--------------------------------|------------------------------|------------------------------|-----------------------------|-----------------------------|----------------------------|---|---|---------------------------|---------------------------------------|--------------|------------|-----------|
| | STAGE | DAYS | EACH | | | | | | | | | | | | | | | |
| | DRUMS | DAY | EACH | DAY | EACH | DAY | EACH | DAY | EACH | DAY | EACH | EACH | EACH | WIS 35 | WHITE/EDGELINE | 1 | 1318 | 23 |
| 7 DAYS PRIOR TO CONSTRUCTION | 7 | 10 | 70 | -- | -- | -- | -- | -- | 2 | 14 | -- | -- | -- | WIS 35 | YELLOW/CENTERLINE | 1 | 1400 | - |
| STAGE 1 | 33 | 47 | 1551 | 2 | 66 | 27 | 891 | 60 | 1,980 | -- | -- | -- | 0.5 | WAUMANDEE CREEK RD | STOP LINE | 1 | - | 35 |
| STAGE 2 | 32 | 59 | 1888 | 2 | 64 | 46 | 1,472 | 60 | 1,920 | -- | -- | -- | 0.5 | WIS 35 | WHITE/EDGELINE | 2 | 1163 | 22 |
| UNDISTRIBUTED | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | 1 | -- | WIS 35 | YELLOW/CENTERLINE | 2 | 1400 | - |
| TOTAL 0010 | | 3,509 | | 130 | | 2,363 | | 3,900 | | 14 | | 1 | | WAUMANDEE CREEK RD | STOP LINE & WHITE/EDGELINE | 2 | 72 | 25 |
| | | | | | | | | | | | | | | TOTAL 0010 | | 5,353 | 105 | |

TEMPORARY MARKING LINE REMOVABLE TAPE

| 643.3165 TEMPORARY | TEMPORARY | | | |
|-----------------------|----------------------------|-------|--------------|------------|
| MARKING | MARKING | | | |
| LINE PAINT | STOP LINE | | | |
| 6-INCH | REMOVABLE | | | |
| TAPE 18-INCH | | | | |
| LOCATION | COLOR/DESCRIPTION | STAGE | LF | LF |
| WIS 35 | WHITE/EDGELINE | 1 | 1318 | 23 |
| WIS 35 | YELLOW/CENTERLINE | 1 | 1400 | - |
| WAUMANDEE CREEK RD | STOP LINE | 1 | - | 35 |
| WIS 35 | WHITE/EDGELINE | 2 | 1163 | 22 |
| WIS 35 | YELLOW/CENTERLINE | 2 | 1400 | - |
| WAUMANDEE CREEK RD | STOP LINE & WHITE/EDGELINE | 2 | 72 | 25 |
| TOTAL 0010 | | | 5,353 | 105 |

ALL ITEMS ON THIS SHEET
ARE CATEGORY 0010
UNLESS OTHERWISE NOTED

3

3

MARKING LINE EPOXY 6-INCH

| | | | | | 646.2020 |
|-------------------|----|-----------|----------|------------------------------------|--------------|
| | | | | | MARKING LINE |
| STATION | TO | STATION | LOCATION | COLOR/DESCRIPTION | LF |
| 595+04.75 | - | 597+91.67 | STH 35 | YELLOW SOLID AND DASHED CENTERLINE | 362 |
| 595+04.75 | - | 597+91.67 | STH 35 | WHITE EDGELINE | 574 |
| TOTAL 0010 | | | | 936 | |

CONSTRUCTION STAKING

| | | | | | 650.4500 | 650.5000 | 650.5500 | 650.9920 |
|-------------------|----|-----------|------------|-----------|------------------|--------------------------|--------------|---------------|
| | | | | | CONSTRUCTION | STAKING CURB | CONSTRUCTION | CONSTRUCTION |
| | | | | | STAKING SUBGRADE | GUTTER AND CURB & GUTTER | STAKING BASE | STAKING SLOPE |
| STATION | TO | STATION | LOCATION | LF | LF | LF | LF | LF |
| 595+04.75 | - | 595+25.36 | STH 35, LT | -- | -- | 26 | -- | -- |
| 595+04.75 | - | 595+49.75 | STH 35 | 45 | 21 | -- | 45 | |
| 597+46.67 | - | 597+91.67 | STH 35 | 45 | 20 | -- | 45 | |
| TOTAL 0010 | | | | 90 | 41 | 26 | 90 | |

CONSTRUCTION STAKING STRUCTURE LAYOUT

| 650.6501.01 | | | |
|--------------------|---------|-----------|------|
| CONSTRUCTION | | | |
| STAKING STRUCTURE | | | |
| LAYOUT (STRUCTURE) | | | |
| CATEGORY | STATION | LOCATION | EACH |
| 0020 | 596+49 | B-06-0059 | 1 |
| TOTAL 0020 | | | |
| | | 1 | |

CONSTRUCTION STAKING SUPPLEMENTAL CONTROL

| 650.9911.01 | | | |
|----------------------------|--|----------|--|
| CONSTRUCTION STAKING | | | |
| SUPPLEMENTAL CONTROL | | | |
| (PROJECT) (01. 7160-00-72) | | | |
| PROJECT | | EACH | |
| 7160-0072 | | 1 | |
| TOTAL 0010 | | | |
| | | 1 | |


SAWING ASPHALT

| 690.0150 | | |
|-------------------|----------|------------|
| SAWING | | |
| ASPHALT | | |
| STATION | LOCATION | LF |
| 595+28.55 | STH 35 | 70 |
| 597+66.69 | STH 35 | 40 |
| TOTAL 0010 | | 110 |

INSTALLING AND MAINTAINING BIRD DETERRENT SYSTEM


| 999.2000.S.01 | | | |
|-------------------|-----------|----------|--|
| INSTALLING AND | | | |
| MAINTAINING BIRD | | | |
| DETERRENT SYSTEM | | | |
| STATION | LOCATION | EACH | |
| 596+49 | B-06-0059 | 1 | |
| TOTAL 0010 | | | |
| | | 1 | |

ALL ITEMS ON THIS SHEET
ARE CATEGORY 0010
UNLESS OTHERWISE NOTED




Standard Detail Drawing List


| | |
|-----------|--|
| 08D01-24A | CONCRETE CURB & GUTTER |
| 08D01-24B | CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS |
| 08D02-08A | CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES |
| 08D02-08B | CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES |
| 08D02-08C | CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES |
| 08D04-07 | CONCRETE SURFACE DRAINS & ASPHALTIC FLUMES |
| 08E09-06 | SILT FENCE |
| 09G02-05A | BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION |
| 09G02-05B | BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION |
| 09G02-05C | BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION |
| 12A03-10 | NAME PLATE (STRUCTURES) |
| 13B02-09A | CONCRETE PAVEMENT APPROACH SLAB |
| 14B07-16A | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16B | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16C | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16D | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16E | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16F | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16G | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16H | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16I | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16J | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16K | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16L | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16M | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B07-16N | CONCRETE BARRIER TEMPORARY PRECAST, 12'-6" |
| 14B08-02A | CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS |
| 14B08-02B | CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS |
| 14B08-02C | CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS |
| 14B08-02D | CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS |
| 14B08-02E | CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS |
| 14B20-12A | STEEL THRIE BEAM STRUCTURE APPROACH |
| 14B20-12B | STEEL THRIE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS |
| 15C02-09F | ADVANCED WIDTH RESTRICTION SIGNING |
| 15C04-05 | TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 M.P.H. OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC |
| 15D33-09 | TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS |





TYPES A (1) & D



6" SLOPED CURB TYPES G (1) & J




4" SLOPED CURB TYPES G (1) & J

TYPES K (1) & L
(OPTIONAL CURB SHAPE)


TYPES K (1) & L

CONCRETE CURB AND GUTTER 30"




TYPES A (1) & D

CONCRETE CURB AND GUTTER 18"




6" SLOPED CURB TYPES A (1) & D




4" SLOPED CURB TYPES A (1) & D

CONCRETE CURB AND GUTTER 36"

4" SLOPED CURB TYPES R (1) & T
CONCRETE CURB AND GUTTER 30"

| | |
|------------|-----|
| TBT & TBTT | X |
| 30" | 22" |
| 36" | 28" |




TYPES TBT & TBTT (1)



CONCRETE CURB AND GUTTER

PAVEMENT THICKNESS
AND MAXIMUM CONCRETE
PANEL WIDTH TABLE

| PAVEMENT THICKNESS | MAXIMUM PANEL WIDTH |
|--------------------|---------------------|
| LESS THAN 10" | 12' |
| 10" & ABOVE | 15' |

PARTIAL SECTION OF PAVEMENT
WITH INTEGRAL CURB AND GUTTER

* BIKE LANE IS NOT SHOWN

REVERSE SLOPE GUTTER
(TYPICAL FOR ALL CURB & GUTTER TYPES) (6)

3" SLOPED CURB TYPES R (1) & T

CONCRETE CURB AND GUTTER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES



DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ SLOPE TO BE REVERSE SLOPE MATCHING THE SLOPE OF THE PAVEMENT AND THE CIRCULATORY ROADWAY








**END SECTION CURB AND GUTTER****GENERAL NOTES**

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑩ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.
- ⑪ PLACE 1" THICK EXPANSION JOINT MATERIAL BETWEEN VERTICAL FACE CURB TYPES EXTENDING FROM THE TOP OF CURB TO 1 INCH BELOW THE ADJOINING CONCRETE SURFACE. RIGID CONCRETE STRUCTURES INCLUDE RAISED CONCRETE MEDIANIS, CONCRETE SAFETY ISLANDS, SPLITTER ISLANDS, OR LOCATIONS IDENTIFIED ON THE PLANS.

**TYPES A (1) & D****CONCRETE CURB****EXPANSION JOINT DETAIL FOR VERTICAL CURB ABUTTING A RIGID STRUCTURE (11)****PLAN VIEW****SECTION A - A****TIE BARS DRILLED INTO EXISTING PAVEMENT****TYPICAL TIE BAR LOCATION****DRIVEWAY ENTRANCE CURB**

(WHEN DIRECTED BY THE ENGINEER)

| |
|---|
| CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS |
|---|

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2025
/S/ Rodney Taylor
DATE
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.


- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2'-0" TIE BARS SPACED AT 3'- 0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSID EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C -C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)

**THRIE BEAM TRANSITION (MGS)
(SEE SDD 14B45)**



PLAN VIEW


**THRIE BEAM TRANSITION (MGS)
(SEE SDD 14B45)**




ELEVATION VIEW

CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SECTION A - A




SECTION G - G



SECTION H - H



SECTION I - I

PLAN VIEW
PERPENDICULAR FLUME


GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.


- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2'-0" TIE BARS SPACED AT 3'-0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.

- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH AS REQUIRED.
- ⑮ GEOTEXTILE TYPE HR.


PLAN VIEW
SKEWED FLUME

**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION





**CURB AND GUTTER TRANSITION SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**




**CURB AND GUTTER END SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**




**CURB AND GUTTER FLOW LINE DEPRESSION
AT FLUMES CONCRETE CURB AND GUTTER
4-INCH SLOPED 36 INCH TYPE TBT OR TBTT**




**SECTION C - C
JOINT DETAIL FOR BRIDGE WITH STRUCTURAL
APPROACH SLAB AND CONCRETE APPROACH SLAB**




**SECTION C - C
JOINT DETAIL FOR BRIDGE APPROACH
WITH CONCRETE SHOULDERS**



SECTION D - D



SECTION E - E



SECTION F - F

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.



- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2'-0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2'-0" TIE BARS SPACED AT 3'-0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45).
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH IS REQUIRED.
- ⑮ GEOTEXTILE TYPE HR.
- ⑯ MINIMUM REINFORCEMENT SHALL BE 6" X 6" - W4.0 X W4.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑰ MSG THRIE BEAM TRANSITION POST 1. SEE SDD 14B45 FOR ADDITIONAL CONSTRUCTION DETAILS AND ACCEPTABLE MATERIALS.
- ⑱ MAINTAIN WIDTH, THICKNESS AND CROSS SLOPE OF ADJACENT TYPE TBT OR TBTT CURB. SEE NOTE 6 FOR TIE BAR SPACING.
- ⑲ ALIGN FACE OF POST BLOCK WITH FLOW LINE.
- ⑳ MAINTAIN FLOW LINE AT EDGE OF PAVEMENT/FACE OF BEAM GUARD AS APPLICABLE.
- ㉑ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING HMA PAVEMENTS.

CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER





NOTE: TAPER CURB ENDS TO GUTTER IN 1' - 0"

ASPHALTIC FLUME**PLAN VIEW
CURB OPENING
FOR FLUME****PLAN VIEW
CONCRETE SURFACE DRAIN****GENERAL NOTES**

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

4" X 4" - W3.0 X W3.0 CONCRETE REINFORCEMENT SHALL BE IN ACCORDANCE WITH AASHTO SPECIFICATION M55.

- ① JOINTS SHALL BE $\frac{1}{8}$ " TO $\frac{1}{4}$ " WIDE BY $\frac{1}{2}$ " DEEP AND SPACED AT UNIFORM INTERVALS OF APPROXIMATELY 4 FEET.
- ② GEOTEXTILE TYPE "R" SHALL UNDERLAY THE FULL LENGTH AND WIDTH OF THE CONCRETE SURFACE DRAIN AND RIPRAP.
- ③ CONCRETE SURFACE DRAIN WITHOUT CURB AND GUTTER MAY BE USED ON BACKSLOPES WHEN SPECIFIED.
- ④ ANGLE OF FLUME IN RELATION TO BACK OF CURB TO BE CONSTRUCTED PER THE PLAN DETAILS OR AS DIRECTED BY THE ENGINEER. ANGLE OF FLUME MAY BE OTHER THAN 90 DEGREES AS SHOWN.


**SECTION A - A****SECTION B - B****SECTION C - C**

MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE, SPACING 12" C-C


SECTION D - D**CONCRETE SURFACE
DRAINS AND
ASPHALTIC FLUMES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
May 2023 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER




PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SILT FENCE AT MEDIAN SURFACE DRAINS



SILT FENCE



TWIST METHOD




JOINING TWO LENGTHS OF SILT FENCE^⑤


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1/8" X 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL



SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)


| | |
|--|--|
| SILT FENCE | |
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | |
| APPROVED 4-29-05 DATE | /S/ Beth Cannestra CHIEF ROADWAY DEVELOPMENT ENGINEER FHWA |



TYPICAL BRIDGE TEMPORARY TRAFFIC SIGNAL LOCATION

LEGEND

- WOOD POLE (NON-BREAKAWAY)
- WOOD POST (BREAKAWAY)
- - - SIGNAL CABLE
- SIGNAL CABLE W/MESSENGER



DIRECTION OF TRAFFIC

LED TRAFFIC SIGNAL WITH BACKPLATE

3-12'

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

POLE MOUNTED TRAFFIC SIGNAL CONTROL CABINET MAY BE MOUNTED ON THE SERVICE POLE IF THE ELECTRICAL UTILITY ALLOWS THE INSTALLATION.

WHEN UTILITY POLES ARE USED TO SPAN THE TEMPORARY OVERHEAD CABLE, WRITTEN PERMISSION MUST BE OBTAINED FROM THE OWNER OF THE POLES AND GIVEN TO THE PROJECT MANAGER. ALL PERTINENT UTILITY AND CODE CLEARANCES SHALL BE MAINTAINED.

WOOD POLES (NON-BREAKAWAY) SHALL BE NO CLOSER TO EDGE OF PAVEMENT THAN OFFSET DISTANCE CHART ALLOWS OR 4 FEET BEHIND PROTECTIVE BARRIER (BEAM GUARD, ETC.).

WOOD POSTS (BREAKAWAY) SHALL BE NO CLOSER THAN 2 FEET OUTSIDE OF SHOULDER.

VERTICAL CLEARANCE ETC. PER NEC.


TRAFFIC SIGNAL FACES SHALL BE TYPICALLY PLACED 12 FEET FROM EDGE OF PAVEMENT.

EACH TRAFFIC SIGNAL SHALL HAVE A BACKPLATE.


SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.

6


6



TYPICAL DROP TO TRAFFIC SIGNAL FACE



POLE MOUNT CABINET INSTALLATION



GROUND MOUNT CABINET INSTALLATION

| MINIMUM POLE LENGTHS | CLASS | POLE BURIAL DEPTHS |
|----------------------|-------|--------------------|
| 25' | V | 5' |
| 30' | V | 6' |
| 35' | IV | 7' |
| 40' | IV | 8' |
| 45' | IV | 9' |

| OFFSET DISTANCES FOR TEMPORARY NON-BREAKAWAY POLES | |
|--|------------------|
| SPEED LIMIT | OFFSET DISTANCE* |
| GREATER THAN 45 MPH | 18 FT |
| 45 MPH OR LESS | 12 FT |
| 45 MPH OR LESS W/CURBS | 2 FT |

* NOTE: OFFSET MEASURED FROM OUTER EDGE OF OUTSIDE THRU LANE.


BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018
/S/ Ahmet Demirbilek
DATE
ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA

SDD09G02 - 05a

SDD09G02 - 05a



GENERAL NOTES


USE 3/4" DRILL IN WOOD POLE TO PROVIDE FOR 5/8" BOLTS.


TYPICAL DEAD-ENDINGS OR GUYING

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2015 /S/ Ahmet Demerbilek
DATE FHWA
ROADWAY STANDARDS DEVELOPMENT
ENGINEER





TRAILER MOUNTED TRAFFIC SIGNAL



TRAILER MOUNTED TRAFFIC SIGNAL

TYPICAL TRAILER MOUNTED TRAFFIC SIGNAL LOCATION

GENERAL NOTES

DETAIL OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.


LEGEND

- POST MOUNTED SIGN
- TEMPORARY PRECAST CONCRETE BARRIER
- TRAILER MOUNTED TRAFFIC SIGNAL
- REMOVE PAVEMENT MARKINGS
- DIRECTION OF TRAFFIC

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2015 /S/ Ahmet Demerbilek
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER



TYPICAL NAME PLATE


NUMBERING DESIGNATION MULTI-UNIT STRUCTURES

GENERAL NOTES

NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.


THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.



SECTION A-A

ALTERNATE LUG




ALTERNATE LUG


(FOR ATTACHMENT TO PRECAST STRUCTURES)

NAME PLATE
(STRUCTURES)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



SKEWED APPROACH (PAVEMENT MORE THAN TWO LANES)




**SKEWS > 20°
(PAVEMENT WIDTH ≤ 30')**




**SKEWS $\leq 20^\circ$
(PAVEMENT WIDTH $\leq 30'$)**


APPROACH SLAB AND ADJACENT PAVEMENT



SECTION A - A
REINFORCEMENT POSITIONING DETAIL



**SECTION B - B
BEND DETAIL
BOTTOM REINFORCEMENT**



**SECTION C - C
TRANSITION DETAIL
APPROACH SLAB TO ADJACENT PAVEMENT**

GENERAL NOTES

THE CONTRACTOR MAY SPLIC NO. 6 BARS IN THE APPROACH SLAB FOR SKEWED STRUCTURES ONLY. STAGGER SPLICES WITH A MAXIMUM OF ONE SPLIC PER BAR. THE LENGTH OF LAP IS 20 INCHES.


TACK WELD DOWEL BARS TO THE BASKETS ON ALTERNATE ENDS.

- ① THE CONTRACTOR MAY USE NO. 4 BARS SPACED AT 2' - 0" C - C IN BOTH THE LONGITUDINAL AND TRANSVERSE DIRECTIONS FOR TOP REINFORCEMENT AS AN ALTERNATIVE TO THE WELDED WIRE FABRIC.
- ② THE CONTRACTOR MAY OMIT THE BARS BETWEEN REINFORCED SLABS WHERE SLAB REINFORCEMENT BARS EXTEND ACROSS THE CENTERLINE OR REFERENCE LINE.
- ③ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING AN HMA PAVEMENT.
- ④ USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ⑤ PLACE EXPANSION CAP ON THE END OF THE DOWEL THAT IS NOT TACK WELDED TO THE BASKET. DO NOT FORCE DOWEL BAR PAST THE DOWEL STOP.
- ⑥ EXTEND EXPANSION JOINT THROUGH ANY ADJACENT TIED CONCRETE.

(A) STANDARD CONTRACTION JOINT NORMAL TO C OR R.


(B) STANDARD LONGITUDINAL JOINT WITH TIE BARS.

(C) 1 1/2" EXPANSION JOINT WITH DOWEL BARS NORMAL TO C OR R.



SECTION D - D

CONTRACTION JOINT




EXPANSION JOINT DETAIL


CONCRETE PAVEMENT APPROACH SLAB

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
ember 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR




CROSS SECTION





PROFILE VIEW



ANCHOR BLOCK DETAIL



TEMPORARY BARRIER



PROFILE VIEW

TEMPORARY BARRIER REINFORCEMENT

GENERAL NOTES

PLACE BARRIER ON PAVED SURFACE. BEFORE PLACEMENT OF TEMPORARY BARRIER, REMOVE ALL LOOSE MATERIAL FROM PAVED SURFACE.

LOOP BARS C1, C2 AND C3 ARE NOT FOR PLACEMENT OR MOVEMENT OF BARRIER.

100 PERMANENTLY FORM INTO ONE END OF BARRIER THE FOLLOWING INFORMATION:
A. TYPE OF BARRIER: WI-CBTP
B. MANUFACTURER
C. DATE OF MANUFACTURE (MONTH AND YEAR)

101 1" OPTIONAL CHAMFER

102 SEE LIFTING SLOT DETAIL

103 SEE ANCHOR BLOCK DETAIL

103 SEE ANCHOR BLOCK DETAIL


(104) 1 3/4" MIN. CLEAR COVER

105 2" MIN. CLEAR COVER

106 1" MIN. CLEAR COVER

107 ± $\frac{1}{8}$ " MEASURED FROM FACE OF CONCRETE BARRIER TO OUTSIDE OF LOOP BAR (TYP.)







108 USE DELINEATORS CONFORMING TO SECTION 633 OF THE STANDARD SPECIFICATIONS. CONTRACTOR MAY USE ALTERNATE SHAPES AND HOUSING. INSTALL DELINEATORS ACCORDING TO MANUFACTURERS INSTRUCTION. INSTALL YELLOW REFLECTORS WHEN BARRIER IS LOCATED LEFT OF TRAFFIC AND WHITE WHEN BARRIER IS LOCATED RIGHT OF TRAFFIC. SPACE DELINEATORS A MAXIMUM OF 25 FEET APART, PROVIDE TOP MOUNTED DELINEATORS IN ADDITION TO SIDE MOUNTED DELINEATORS ON BARRIER INSTALLATIONS LOCATED ON A CURVED ALIGNMENT LONGER THAN 200 FEET AND ON BARRIERS USED TO SEPARATE OPPISING TRAFFIC.



LIFTING SLOT DETAIL (TYP.)



CONCRETE BARRIER TEMPORARY PRECAST, 12' - 6"

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**C BAR DETAILS****B5 BAR DETAIL****B4 BAR DETAIL****PROFILE VIEW
LOOP BAR ASSEMBLY****C BAR DETAILS**

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


**CONNECTOR PIN ASSEMBLY****CONNECTING TEMPORARY BARRIER SECTIONS****GENERAL NOTES**

- (300) SET WITH 3 5/8" WOOD BLOCK.
- (301) HOLE IS OPTIONAL.
- (302) CONNECTOR PIN ASSEMBLY.
- (303) CONCRETE PAVEMENT, APPROACH SLAB, OR DECK.
- (304) CONCRETE DECK.
- (305) DO NOT USE ON CONCRETE BRIDGE DECK WITH ASPHALT OVERLAY OR CONCRETE PAVEMENT WITH ASPHALT OVERLAY.
- (306) MINIMUM OF 2" OF ASPHALT.
- (307) ASPHALT ANCHOR PIN ASSEMBLY
- (308) IF DRILLING A PILOT HOLE, THE MAX. DIA. OF THE HOLE IS 3/4"
- (309) WHEN THERE IS ASPHALT OVERLAYING CONCRETE PAVEMENT, A 1 5/8" DIA. PILOT HOLE CAN BE DRILLED INTO THE OVERLAY AND CONCRETE. IF NEEDED DRILL A 3/4" PILOT HOLE IN BASE COURSE.


**ASPHALT ANCHOR PIN ASSEMBLY****ASPHALT ANCHOR INSTALLATION THROUGH ASPHALT PAVEMENT****ASPHALT ANCHOR INSTALLATION THROUGH ASPHALT OVERLAY ON TOP OF CONCRETE PAVEMENT****SIDE VIEW
THROUGH BOLT ANCHOR INSTALLATION****SIDE VIEW
ADHESIVE ANCHOR INSTALLATION**

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PLAN VIEW
TRANSITION FROM FREE STANDING TO ANCHORED BARRIER




CROSS SECTION
FREE STANDING BARRIER




CROSS SECTION
**ANCHORED BARRIER FOR OBJECTS ABOVE
THE GRADE LINE AND NEAR THE BARRIER**



CROSS SECTION
ANCHORED BARRIER NEAR VERTICAL DROP OFF



CROSS SECTION
ANCHORED BARRIER NEAR A SLOPE



PROFILE VIEW
ANCHORED BARRIER NEAR EXPANSION JOINT (400)

GENERAL NOTES


- (400) NO SINGLE CONCRETE BARRIER SECTION SHALL BE ANCHORED TO BOTH THE BRIDGE DECK AND THE APPROACH SLAB. ALL ANCHOR BOLT LOCATIONS SHALL BE ANCHORED TO THE DECK IN ACCORDANCE WITH THE DETAIL. NO MORE THAN ONE ANCHOR BOLT SHALL BE ELIMINATED FROM A BARRIER SECTION WHEN SPANNING AN EXPANSION JOINT.
- (401) CONCRETE DECK
- (402) CONCRETE DECK OR APPROACH SLAB.
- (403) EXPANSION JOINT
- (404) ADHESIVE ANCHOR SHOWN. SEE ANCHOR DETAILS.
- (405) ANCHORED TEMPORARY BARRIER
- (406) TRANSITION FROM ANCHORED TEMPORARY BARRIER TO FREE STANDING
- (407) FREE STANDING BARRIER
- (408) REMOVE ALL ANCHORS WHEN NO LONGER NEEDED. FILL CONCRETE PAVEMENTS, DECKS AND APPROACH SLABS WITH NON-SHRINK COMMERCIAL GROUT FROM THE APPROVED PRODUCT LIST. FILL ASPHALT PAVEMENTS WITH ASTM D6690 TYPE II RUBBERIZED CRACK FILLER.
- (409) TRAFFIC SIDE
- (410) NON-TRAFFIC SIDE
- (411) ANCHOR LOCATION. SEE ANCHORING DETAILS.
- (412) WORK AREA
- (413) AREA FREE OF OBJECTS AND WORKERS
- (414) GRADE LINE
- (415) EXTENDED GRADE LINE
- (416) ANCHORED TEMPORARY BARRIER. SEE BOLT THROUGH DECK, REMOVABLE ADHESIVE ANCHOR, OR AN ASPHALT ANCHOR ROD DETAILS FOR MORE INFORMATION. ASPHALT ANCHOR ROD SHOWN.
- (417) WHEN OBJECTS EXTEND ABOVE THE GRADE. A MINIMUM OF 1 FOOT IS REQUIRED FROM BACK OF BARRIER TO OBJECT.
- (418) OBJECTS ARE NOT TO BE PLACED ON, MOUNTED TO, OR ALLOWED TO LEAN AGAINST THE BARRIER WITHOUT WRITTEN PERMISSION OF THE PROJECT ENGINEER.
- (419) DEPTHS OF 3 FEET OR MORE.
- (420) Y = 6.5'
- (421) OFFSET FROM BACK OF BARRIER EDGE:
CONCRETE PAVEMENT 0.5'
ASPHALT 0.5'
- (422) POSTED SPEED (MPH):
45 OR GREATER 4.0'
40 OR LOWER 2.0'

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES


- (500) EXISTING RIGID BARRIERS (VARIES)
- (501) TEMPORARY BARRIER
- (502) SEE OTHER DETAIL ON HOW TO ANCHOR TEMPORARY BARRIER (BARRIER ASPHALT ANCHOR SHOWN).
- (503) ANCHORS ARE REQUIRED ON BOTH SIDE OF THE TEMPORARY BARRIER.
- (504) NESTED RAILS ARE REQUIRED ON BOTH SIDES OF THE TEMPORARY BARRIER FOR ALL INSTALLATIONS.
- (505) TRAFFIC TRAVELS FROM PERMANENT BARRIER TO TEMPORARY BARRIER.
- (506) TRAFFIC TRAVELS FROM TEMPORARY BARRIER TO PERMANENT BARRIER.
- (507) VERTICAL BARRIER
- (508) SAFETY SHAPE BARRIER
- (509) SINGLE SLOPE BARRIER
- (510) CAP END PLATE PLACED FLUSH WITH UPSTREAM END OF RIGID BARRIER.
- (511) BENT THRIE BEAM TO FIT.
- (512) THRIE BEAM PIECES ARE OFFSET 15 $\frac{1}{4}$ " TO PREVENT INTERFERENCE FROM THE ANCHORS ON OPPONDING SIDES.
- (513) TWO (2) P1, P2 AND P3 ARE REQUIRED
- (514) FIVE (5) N1, N2 AND N3 ARE REQUIRED
- (515) TWO (2) R1, R2 AND R3 ARE REQUIRED
- (516) CUT WOOD BLOCK TO FIT.
- (517) SEE THRIE BEAM RAIL TERMINAL CONNECTOR DETAIL ASSEMBLY.
- (518) CAP ASSEMBLY
- (519) 4" MAX. GAP BETWEEN TEMPORARY BARRIER AND RIGID BARRIER.
- (520) ALL TWELVE SPLICE HOLES REQUIRE M1 AND M2




PROFILE VIEW




PLAN VIEW
TRANSITION TO RIGID BARRIER




PLAN DETAIL VIEW
TRANSITION TO RIGID BARRIER




FRONT DETAIL VIEW
TRANSITION TO RIGID BARRIER




CROSS SECTION
TEMPORARY BARRIER
PLACEMENT SINGLE SLOPE




CROSS SECTION
TEMPORARY BARRIER
PLACEMENT SAFETY SHAPE



CROSS SECTION
TEMPORARY BARRIER
PLACEMENT VERTICAL




BACK DETAIL VIEW
TRANSITION TO RIGID BARRIER








517) DETAIL PLAN VIEW
THRIE BEAM RAIL TERMINAL CONNECTOR ASSEMBLY

CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION








GENERAL NOTES

STITCH WELD GUSSET PLATES AND END PLATES ON THREE SIDES
STITCH WELD TWO SIDE PLATES TO TOP PLATE, END PLATE AND GUSSETS.
SIDE PLATES, TOP PLATE, END PLATE AND GUSSETS ARE 12 GAUGE ASTM A36
GALVANIZED STEEL.

(700) SIDE PLATES (T3 AND T4) NOT SHOWN FOR CLARITY.




| GUSSET DIMENSIONS | | | | |
|-------------------|-----------|----------|----------|---------|
| GUSSET NO. | A | B | C | D |
| T5 | 22 13/16" | 5 1/16" | 2 5/16" | 8 1/16" |
| T6 | 21" | 5 7/8" | 2 3/16" | 8 1/16" |
| T7 | 19 3/16" | 6 1/16" | 1 15/16" | 8 1/16" |
| T8 | 17 3/8" | 6 1/4" | 1 13/16" | 8 1/16" |
| T9 | 15 5/16" | 6 7/16" | 1 1/16" | 8 1/16" |
| T10 | 13 3/4" | 6 5/8" | 1 7/16" | 8 1/16" |
| T11 | 11 15/16" | 6 13/16" | 1 1/4" | 8 1/16" |
| T12 | 10 1/8" | 7" | 1 1/16" | 8 1/16" |
| T13 | 8 5/16" | 7 3/16" | 7/8" | 8 1/16" |
| T14 | 6 1/2" | 7 3/8" | 1 1/16" | 8 1/16" |
| T15 | 4 1/16" | 7 3/16" | 1/2" | 8" |
| T16 | 2 7/8" | 7 3/4" | 1/4" | 8" |


CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


6

SDD 14B07-16h






**PLAN VIEW
GAP WITHIN SPACING**




**PLAN VIEW
TEMPORARY BARRIER GAP OVER 4" TO 1' MAX.** ⁹⁰⁴

GENERAL NOTES


- 900 SEE OTHER DETAILS FOR TEMPORARY GAP HARDWARE (TYP.)
- 901 TEMPORARY BARRIER GAP
- 902 GAP STIFFENER ASSEMBLY CENTERED IN THE GAP.
- 903 GAP STIFFENER ASSEMBLY IS OFFSET 18 3/4" FROM CENTER
- 904 MINIMUM NUMBER OF GAP STIFFENERS SHOWN FOR THE GAP RANGE SHOWN.
- 905 MINIMUM OF 8 CONTINUOUS FREE STANDING TEMPORARY BARRIERS



**PLAN VIEW
TEMPORARY BARRIER GAP OVER 1' TO 4' MAX.** ⁹⁰⁴




**PLAN VIEW
TEMPORARY BARRIER GAP OVER 4' TO 7' MAX.** ⁹⁰⁴




**PLAN VIEW
TEMPORARY BARRIER GAP OVER 7' TO 12.5' MAX.** ⁹⁰⁴

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PROFILE VIEW **SIDE VIEW**
STIFFENER ASSEMBLY
CENTER PANEL U1




FLAT PATTERN **SIDE VIEW**
STIFFENER ASSEMBLY
SIDE PANEL U2




PROFILE VIEW **SIDE VIEW**
STIFFENER ASSEMBLY
BOTTOM PANEL U3





SECTION A - A




SECTION B - B



PLAN VIEW




SIDE VIEW



ISOMETRIC

GAP STIFFENER ASSEMBLY




PLAN VIEW

SIDE
VIEW

ELEVATION VIEW
W1 TOE PLATE


CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION




ELEVATION VIEW

THRIE BEAM TERMINAL CONNECTOR



ELEVATION VIEW

ADDITIONAL THRIE BEAM TERMINAL CONNECTOR HOLE DETAIL



SLOTTED THRIE BEAM RAIL K1






PLATE WASHER DETAIL G2, H3


SECTION THROUGH
BEAM K1

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION





FRONT ELEVATION




END SECTION

DETAILS OF BARRIER TAPER SECTION


SIDE ELEVATION
(FOR CONNECTION TO LEFT END OF BARRIER)

GENERAL NOTES


(1200) SEE LIFTING SLOT DETAIL. LOCATION OF LIFTING SLOTS DETERMINED BY CONTRACTOR.

SIDE ELEVATION
LOOP BAR ASSEMBLY INVERTED FOR OPPOSITE END
(FOR CONNECTION TO RIGHT END OF BARRIER)


FLARE AT BARRIER END



PLAN VIEW



B12




BENT BAR DETAIL

| BAR | A | B |
|-----|-------------|--------|
| B6 | 10" | 1" |
| B7 | 1' - 1" | 1 1/4" |
| B8 | 1' - 5" | 1 5/8" |
| B9 | 1' - 8" | 1 7/8" |
| B10 | 2' - 0 1/2" | 2 3/8" |
| B11 | 2' - 3" | 2 3/4" |

B BARS

2 OF EACH SIZE REQUIRED
FOR STIRRUP ASSEMBLY



**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS - CONCRETE BARRIER PRECAST

| PART | DESCRIPTION | MATERIALS SPECIFICATIONS | NOTES |
|------|--------------------------------------|---|-------------------------|
| A1 | PRECAST TEMPORARY BARRIER - CONCRETE | MIN. = f_c 5000 PSI | |
| B1 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #5 REBAR, LENGTH 12'-2" |
| B2 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 12'-2" |
| B3 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #5 REBAR, LENGTH 12'-2" |
| B4 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 6'-0" |
| B5 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #6 REBAR, LENGTH 2'-11" |
| B6 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 1'-11" |
| B7 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 2'-2" |
| B8 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 2'-6" |
| B9 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 2'-9" |
| B10 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 3'-2" |
| B11 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 3'-4" |
| B12 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 12'-0" |
| B13 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #4 REBAR, LENGTH 7'-9" |
| B14 | REBAR | STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR | #5 REBAR, LENGTH 11'-9" |
| C1 | LOOP BAR | ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED | 3/4" DIA. |
| C2 | LOOP BAR | ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED | 3/4" DIA. |
| C3 | LOOP BAR | ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED | 3/4" DIA. |
| D1 | CONNECTION PIN - ROD | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | 1 1/4" DIA. |
| D2 | CONNECTION PIN - TOP PLATE | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | |
| G1 | BOLT THROUGH ANCHOR - THREADED ROD | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A OR SAE J429 GRADE 2 UNC | 1 1/8" DIA. |
| G2 | BOLT THROUGH ANCHOR - WASHER, SQUARE | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | |
| G3 | BOLT THROUGH ANCHOR - NUT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | |
| H1 | ADHESIVE ANCHOR - ADHESIVE | ICC-ES-AC308 5 1/4" EMBEDMENT WITH A MIN. BOND STRENGTH OF 1,650 PSI. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS. | |
| H2 | ADHESIVE ANCHOR - THREADED ROD | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A / SAE J429 GRADE 2 UNC | 1 1/8" DIA. |
| H3 | ADHESIVE ANCHOR - WASHER, SQUARE | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | |
| H4 | ADHESIVE ANCHOR - NUT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | |
| J1 | ASPHALT ANCHOR PIN - ROD | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | 1 1/2" DIA. |
| J2 | ASPHALT ANCHOR PIN - STOP PLATE | ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI | |
| K1 | THRIE BEAM RAIL | AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER | 12 GAUGE |
| L1 | THRIE BEAM RAIL - TERMINAL | AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER | 12 GAUGE |

| PART | DESCRIPTION | MATERIALS SPECIFICATIONS | NOTES |
|------|--|--|---------------------|
| M1 | SPICE BOLT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 UNC AASHTO M180 HEAD ASTM A307 GRADE B OR SAE J429 GRADE 2 OR ASTM F1554 GRADE 36 | 5/8" DIA. |
| M2 | SPICE BOLT - NUT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | |
| N1 | THRIE BEAM RAIL TERMINAL - MECHANICAL ANCHOR | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | 3/4" DIA. LENGTH 6" |
| N2 | THRIE BEAM RAIL TERMINAL - WASHER | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1 | |
| N3 | THRIE BEAM RAIL TERMINAL - MECHANICAL OR ADHESIVE ANCHOR | MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 17.9 KIPS AND ULTIMATE SHEAR LOAD 21.96 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS. | |
| P1 | THRIE BEAM RAIL CONNECTION 1-BOLT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | 3/4" DIA. |
| P2 | THRIE BEAM RAIL CONNECTION 1-WASHER | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1 | |
| P3 | THRIE BEAM RAIL CONNECTION 1-MECHANICAL OR ADHESIVE ANCHOR | MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 9.48 KIPS AND ULTIMATE SHEAR LOAD 10.48 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS. | |
| Q1 | BLOCK WOOD | SEE STANDARD SPEC. 614 | |
| R1 | CAP - BOLT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | 5/8" DIA. |
| R2 | CAP - BOLT - WASHER | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1 | |
| R3 | CAP - BOLT - MECHANICAL ANCHOR | MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS ULTIMATE TENSILE LOAD 12.14 KIPS AND ULTIMATE SHEAR LOAD 17.5 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS. | 12 GAUGE |
| S1 | CAP 42-INCH TOP PLATE | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S2 | CAP 42-INCH END PLATE | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S3 | CAP 42-INCH SIDE PLATE | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S4 | CAP 42-INCH GUSSET 1 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S5 | CAP 42-INCH GUSSET 2 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S6 | CAP 42-INCH GUSSET 3 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| S7 | CAP 42-INCH GUSSET 4 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS - CONCRETE BARRIER PRECAST


| PART | DESCRIPTION | MATERIALS SPECIFICATIONS | NOTES |
|------|-----------------------------------|---|----------|
| T1 | CAP 56-INCH TOP PLATE | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T2 | CAP 56-INCH END PLATE | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T3 | CAP 56-INCH SIDE PLATE 1 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T4 | CAP 56-INCH SIDE PLATE 2 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T5 | CAP 56-INCH GUSSET 1 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T6 | CAP 56-INCH GUSSET 2 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T7 | CAP 56-INCH GUSSET 3 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T8 | CAP 42-INCH GUSSET 4 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T9 | CAP 42-INCH GUSSET 5 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T10 | CAP 42-INCH GUSSET 6 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T11 | CAP 42-INCH GUSSET 7 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T12 | CAP 42-INCH GUSSET 8 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T13 | CAP 42-INCH GUSSET 9 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T14 | CAP 42-INCH GUSSET 10 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T15 | CAP 42-INCH GUSSET 11 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| T16 | CAP 42-INCH GUSSET 12 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | 12 GAUGE |
| U1 | GAP STIFFENER | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | |
| U2 | GAP STIFFENER - CONNECTOR PLATE 1 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | |
| U3 | GAP STIFFENER - CONNECTOR PLATE 2 | AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | |


| PART | DESCRIPTION | MATERIALS SPECIFICATIONS | NOTES |
|------|--|--|---------|
| V1 | THRIE BEAM RAIL TERMINAL MECHANICAL OR ADHESIVE ANCHOR | MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS ULTIMATE TENSILE LOAD 24.0 KIPS AND ULTIMATE SHEAR LOAD 21.5 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS. | ¾" DIA. |
| V2 | GAP STIFFENER - BOLT - NUT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 50 TYPE 1 / ASTM B695 CLASS 50 TYPE 1 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291/ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | |
| W1 | TOE PLATE | AASHTO M111/ASTM A123 ASTM A36 MIN STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI | |
| X1 | TOE PLATE - CONNECTION BOLT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 UNC HEAVY HEX HEAD OR AASTHO M180 HEAD, ASTM F3125 GRADE A325 TYPE 1 HEAVY HEX HEAD OR SAE J429 GRADE 5 HEAVY HEX HEAD / ASTM A449 TYPE 1 HEAVY HEX HEAD. BOLTS MAY BE FULLY THREADED. PROVIDE ENOUGH THREADING FOR PROPER TIGHTENING OF BOLT. | ¾" DIA. |
| X2 | TOE PLATE - CONNECTION BOLT - WASHER | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1 (HARDEN WASHER ONLY) | |
| X3 | TOE PLATE - CONNECTION BOLT - NUT | HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5 | |

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2023 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA





**CRASH CUSHION/SAND BARREL ARRAY AND TEMPORARY BARRIER
INSTALLATION FOR TRAFFIC ON ONE SIDE - FLARED INSTALLATION**




**TRANSITION FROM FREE STANDING TEMPORARY BARRIER
TO ANCHORED BARRIER**

LEGEND


| | |
|--|--|
| DIRECTION OF TRAVEL | |
| CRASH CUSHION OR SAND BARREL ARRAY | |
| SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS | |
| SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS | |
| 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER | |
| PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET | |
| FREE STANDING TEMPORARY BARRIER | |

**CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




TEMPORARY BARRIER OVERLAP - ONE-WAY TRAFFIC



TEMPORARY BARRIER OVERLAP - TWO-WAY TRAFFIC



ENDING TEMPORARY BARRIER
DOWNSTREAM - UNANCHORED




ENDING TEMPORARY BARRIER
DOWNSTREAM - ANCHORED

LEGEND

DIRECTION OF TRAVEL



CRASH CUSHION OR
SAND BARREL ARRAY




SEE FREE STANDING TRANSITION
TO TIED-DOWN SYSTEM DETAILS




SEE BI-DIRECTIONAL TRANSITION
TO TIED-DOWN SYSTEM DETAILS




3 PINS PLACED ON
TRAFFIC SIDE OF BARRIER



PERMANENT CONCRETE BARRIER
OR CONCRETE PARAPET




FREE STANDING TEMPORARY
BARRIER




CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



CONNECTING TEMPORARY BARRIER TO PERMANENT CONCRETE BARRIER-TRAFFIC ON ONE SIDE



CONNECTING TEMPORARY BARRIER TO PERMANENT CONCRETE BARRIER-TRAFFIC ON BOTH SIDES

LEGEND

DIRECTION OF TRAVEL



CRASH CUSHION OR SAND BARREL ARRAY



SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS



SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS





3 PINS PLACED ON TRAFFIC SIDE OF BARRIER




PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET



FREE STANDING TEMPORARY BARRIER



OVERLAPPING TEMPORARY BARRIER AND PERMANENT BARRIER - ONE WAY TRAFFIC



OVERLAPPING TEMPORARY BARRIER AND PERMANENT BARRIER - TWO WAY TRAFFIC

CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

LEGEND

| | |
|---|--|
| DIRECTION OF TRAVEL | |
| CRASH CUSHION OR SAND BARREL ARRAY | |
| SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS | |
| SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS | |
| 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER | |
| PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET | |
| FREE STANDING TEMPORARY BARRIER | |

DIMENSION C TABLE

| AVAILABLE DEFLECTION DISTANCE | MINIMUM LENGTH OF BARRIER BEYOND HAZARD FT |
|--|--|
| GREATER THAN 8' | 12.5 |
| LESS THAN OR EQUAL TO 8' BUT GREATER THAN 4' | 50 |
| LESS THAN OR EQUAL TO 4' | 100 |



CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June, 2015 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER





PLATE WASHER DETAIL



GENERAL NOTES

BOLT THE THRIE BEAM TO ALL POSTS AND BLOCKOUTS. DRILL OR PUNCH BOLT HOLES IN THE BEAM IF THE POST SPACING IS LESS THAN 6'-3".


DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.

IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B15 FOR MORE DETAILS.

- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② MINIMUM EMBEDMENT SHALL BE 4'- 0".
- ③ POST BOLTS ARE $\frac{3}{8}$ " DIAMETER ASTM A307 BUTTON HEAD BOLT. A POST BOLT REQUIRES A $\frac{5}{8}$ " DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX AND A $\frac{3}{8}$ " DIAMETER F844 FLAT WASHER. LENGTH OF POST BOLT MAY VARY.
- ④ ALL WOOD POSTS MUST BE 6" X 8" AND AT LEAST 7'-0" LONG.




SECTION THRU BEAM RAIL ELEMENT




STEEL THRIE BEAM STRUCTURE APPROACH

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2022 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER



THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS



W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGE)


GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

BOLTS, NUTS AND WASHERS SHALL CONFORM TO ASTM A325, A449 AND GALVANIZED PER STANDARD SPECIFICATIONS 614.

- ① DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ② BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM TERMINAL CONNECTOR. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/8" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ③ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ④ W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POST WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.


DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.




STEEL THRIE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2022 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER



WIDTH RESTRICTION SIGNING



WIDTH RESTRICTION SIGNING 2 LANE HIGHWAY

LEGEND

© SIGN ON PERMANENT SUPPORT

GENERAL NOTES

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE
ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

WIDTH ON SIGN TO BE APPROXIMATELY ONE FOOT LESS THAN AVAILABLE WIDTH.

* PLACE 500 FEET AFTER THE W20 - 1A AND 500 FEET BEFORE ADDITIONAL SIGNS FOR ROADWAYS WITH A PRE - CONSTRUCTION SPEED LIMIT OF 45 MPH OR MORE. FOR 35-40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25-30 MPH, USE 200 FOOT TYPICAL SPACING.

**** SIGN SHALL BE VISIBLE FROM ROADWAY.**

*** ADDITIONAL SIGNS NEEDED IF THERE IS AN ON RAMP BETWEEN SIGNS.



WIDTH ON SIGN TO BE APPROX. 1 - FOOT LESS THAN AVAILABLE WIDTH


ADVANCED WIDTH RESTRICTION SIGNING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PROVED
ay 2023 _____ /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER


GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS.
 THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.
 ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.
 SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.
 IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.
 * OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS
 ** PLACE AN ADDITIONAL W20-1A "ROAD WORK AHEAD" SIGN IF WORK AREA WITHIN THE PROJECT IS SEPARATED BY MORE THAN 2 MILES FROM PREVIOUS WORK AREA.



LEGEND

- Ⓐ SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC
- ▨ WORK AREA



TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45MPH OR GREATER

TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 MPH OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
July 2018 /S/ Andrew Heidtke
DATE
FHWA
WORK ZONE ENGINEER

LEGEND

- ⊕ TYPE III BARRICADE WITH ATTACHED SIGN
- ◎ SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- ◇ ◇ FLAGS, 16" X 16" MIN. (ORANGE)
- ××× REMOVING PAVEMENT MARKING
- DIRECTION OF TRAFFIC
- ☒☒ ASPHALTIC PAVEMENT WIDENING
- CONCRETE BARRIER TEMPORARY PRECAST
- ██ TEMPORARY SIGNAL. SEE SDD 09G02 FOR EXACT PLACEMENT

WIDTH ON SIGN TO BE APPROX. 1-FOOT LESS THAN AVAILABLE WIDTH. (OMIT IF AVAILABLE WIDTH IS MORE THAN 16 FEET)




**TRAFFIC CONTROL,
ONE LANE ROAD
WITH TEMPORARY SIGNALS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Andrew Heidke
DATE
FHWA
WORK ZONE ENGINEER

URBAN AREA




RURAL AREA (See Note 2)



GENERAL NOTES

1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.
3. The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (\pm) 3". The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (\pm) 3".
4. For expressways and freeways, mounting height is 7'-3" (\pm) 3" or 6'-3" (\pm) 3" depending upon existence of a sub-sign.
5. Minimum mounting height for signs mounted on traffic signal poles is 5'-3" (\pm) 3".
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (\pm) 3" or as directed by the Engineer.

2' Min - 4' Max (See Note 5)



White Edgeline Location



7

7

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

POST EMBEDMENT DEPTH

| Area of Sign Installation (Sq. Ft.) | D (Min) |
|-------------------------------------|---------|
| 20 or Less | 4' |
| Greater than 20 | 5' |

TYPICAL INSTALLATION
OF PERMANENT TYPE II
SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew P. Rauch*
for State Traffic Engineer

DATE 12/6/23 PLATE NO. A4-3.23


PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E




ELEVATION VIEW

DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT


NOTES:

1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



PLAN VIEW

FOR NEW CONCRETE/ASPHALT INSTALLATIONS



**SIGN POST
BOX-OUTS
A4-3B**

WISCONSIN DEPT OF TRANSPORTATION




APPROVED
Matthew P Rauch
for State Traffic Engineer
DATE 1/27/14 PLATE NO. A4-3B.1

GENERAL NOTES

1. For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
2. See tables below for required number of posts.
3. For expressways and freeways, mounting height is 7'-3" (\pm 3") or 6'-3" (\pm 3") depending upon existence of sub-sign.
4. The (\pm) tolerance for mounting height is 3 inches.
5. J-Assemblies are considered to be one sign for mounting height.
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (\pm 3") or as directed by the engineer.
8. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (\pm 3"). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4"-3" (\pm 3").



RURAL AREA (See Note 3)



* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

*** See A4-3 sign plate for signs 4' or less in width and less than 20 S.F. in area.

SIGN SHAPE OTHER THAN DIAMOND (TWO POSTS REQUIRED)

| L | E |
|------------------|-----|
| Greater than 48" | 12" |
| Less than 60" | |
| 60" to 108" | L/5 |

SIGN SHAPE OTHER THAN DIAMOND (THREE POSTS REQUIRED)

| L | E |
|---------------------------|-----|
| Greater than 108" to 144" | 12" |

POST EMBEDMENT DEPTH

| Area of Sign Installation (Sq. Ft.) | D (Min) |
|---------------------------------------|-----------|
| 20 or Less | 4' |
| Greater than 20 | 5' |

TYPICAL INSTALLATION OF TYPE II SIGNS ON MULTIPLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Matthew R Rauch
for State Traffic Engineer

DATE 12/6/23 PLATE NO. A4-4.16


PROJECT NO:

HWY:


COUNTY:

SHEET NO:

E



SIGN SHALL BE MOUNTED TO PROJECT
ABOVE THE TOP OF THE POST



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation :B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)

MACHINE BOLTS - $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts

WOOD POSTS (4" x 6")

LAG SCREWS - $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)
 $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)

SQUARE STEEL POSTS (2" x 2")

MACHINE BOLTS - $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)

RIVETS - $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL

O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH

WASHERS (ALL POSTS) -

1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL

1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON

* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.


ATTACHMENT OF SIGNS TO POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer


DATE 4/1/2020 PLATE NO. A4-8.9

**TELESCOPIC TUBING ANCHORS
TWO PIECE SYSTEM**




DETAIL OF TUBULAR STEEL SIGN POST

(IN Poured CONCRETE OR ASPHALT)



DETAIL OF TUBULAR STEEL SIGN POST

(IN LOCATIONS OTHER THAN Poured CONCRETE OR ASPHALT)



| Area of Sign Installation (Sq. Ft.) | Number of Required Posts |
|--|--------------------------|
| 9 or less | 1 |
| Greater than 9 less than or equal to 18 | 2 |
| Greater than 18 less than or equal to 27 | 3 |

Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

**TUBULAR STEEL
SIGN POST**

A4 - 9

WISCONSIN DEPT OF TRANSPORTATION

APPROVED
Matthew P. Rauch

for State Traffic Engineer

DATE 2/05/15 PLATE NO. A4-9.9



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E



SIDE VIEW

GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two $1\frac{1}{2}$ " diameter holes drilled perpendicular to the roadway centerline.

4 X 6 WOOD POST
MODIFICATIONS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Cheska J. Sprey
for State Traffic Engineer

DATE 3/27/97

PLATE NO. A4-11.2

PROJECT NO:

HWY:

COUNTY:

SHEET NO:




E

GENERAL NOTES


1. Any sign over 3 feet in width shall use the V-Block banding method. See A5-10 standard plate.
2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
3. Banding and assembly bracket shall be stainless steel. All bands shall be $\frac{3}{4}$ " in width and 0.025" thickness.
4. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM designation: B 633, Type III, SC 3

BANDING

SINGLE SIGN




WASHER PLACEMENT



WASHERS (ALL POSTS) -
 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL
 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON
 FOR ALL TYPE H SIGNS

"J" ASSEMBLY





STANDARD SIGN SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

 for State Traffic Engineer
 DATE 6/10/19 PLATE NO. A5-9.4



GENERAL NOTES

1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WisDOT STANDARD SPECIFICATIONS
2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, $3/4$ " WIDTH AND 0.025" THICKNESS
3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORMALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3
6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
7. STEEL WASHERS SHALL BE $1\frac{1}{4}$ " O.D. X $3\frac{3}{8}$ " I.D. X $\frac{1}{16}$ "
8. NYLON WASHERS SHALL BE $1\frac{1}{4}$ " O.D. X $3\frac{3}{8}$ " I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN

＊ LAG BOLTS SHALL BE $3/8$ " X $2\frac{1}{2}$ "


7

7

BLOCK BANDING DETAIL
(V-BLOCK OPTION)

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer
DATE 4/19/2022 PLATE NO. A5-10.3



NOTES

1. Sign is Type II - Type H Reflective
2. Color:
 - Background - White
 - Message - Black
3. Message Series - Line 1 is Series E.
Lines 2 and 3 are Series D.

7

7

R10-11B

STANDARD SIGN
R10-11B

WISCONSIN DEPT. OF TRANSPORTATION

Matthew R Rauch
for State Taxicab Franchise

DATE 1/31/24 PLATE NO. R10-11B.5


PROJECT NO:

HW

COUNTY:


SHEET NO:

E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - See note 5
4. The top line is series E, the numerals are series C, and the bottom line is series D.
5. Substitute appropriate numerals and adjust spacing as required.



ARROW DETAIL

| SIZE | A | B | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q | R | S | T | U | V | W | X | Y | Z | Area sq. ft. |
|------|----|---|---|-----|---|---|----|--------|-------|--------|----|----|----|--------|---|-------|-------|--------|---|---|---|---|---|---|---|------|--------------|
| 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2S | 48 | | 3 | 3/4 | 1 | 6 | 12 | 11 3/8 | 9 5/8 | 11 1/2 | 16 | 13 | 12 | 15 5/8 | 8 | 9 1/4 | 1 1/4 | 10 5/8 | | | | | | | | 16.0 | |
| 2M | 48 | | 3 | 3/4 | 1 | 6 | 12 | 11 3/8 | 9 5/8 | 11 1/2 | 16 | 13 | 12 | 15 5/8 | 8 | 9 1/4 | 1 1/4 | 10 5/8 | | | | | | | | 16.0 | |
| 3 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | |
|---|--|
| STANDARD SIGN | |
| W12-52 | |
| WISCONSIN DEPT OF TRANSPORTATION | |
| APPROVED <i>Matthew R Rauch</i> for State Traffic Engineer | |
| DATE 3/10/2024 PLATE NO. W12-52.8 | |


PROJECT NO:


HWY:

COUNTY:

SHEET NO:


E






TYPICAL SECTION THRU BRIDGE

(LOOKING WEST)



TYPICAL SECTION THRU BRIDGE - STAGE 1

(LOOKING WEST)



TYPICAL SECTION THRU BRIDGE - STAGE 2

(LOOKING WEST)


| NO. | DATE | REVISION | BY |
|--|--------------|----------|---------|
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE B-6-59 | | | |
| DRAWN BY CLP PLANS CK'D AEB | | | |
| TYPICAL SECTIONS | SHEET 2 OF 8 | | |
| | | | SCALE = |

TOTAL ESTIMATED QUANTITIES

| BID ITEM NUMBER | BID ITEMS | UNIT | SUPER. | E. ABUT. | W. ABUT. | TOTALS |
|-----------------|--|------|--------|----------|----------|------------|
| 203.0211.S | ABATEMENT OF ASBESTOS CONTAINING MATERIAL B-6-59 | EACH | 1 | ---- | ---- | 1 |
| 203.0220 | REMOVING STRUCTURE B-6-59 | EACH | 1 | ---- | ---- | 1 |
| 203.0335 | DEBRIS CONTAINMENT FOR WATERWAY B-6-59 | EACH | ---- | ---- | ---- | 1 |
| 206.1001 | EXCAVATION FOR STRUCTURES BRIDGES B-6-59 | EACH | ---- | ---- | ---- | 1 |
| 210.1500 | BACKFILL STRUCTURE TYPE A | TON | ---- | 35 | 35 | 70 |
| 502.0100 | CONCRETE MASONRY BRIDGES | CY | ---- | 4 | 5 | 9 |
| 502.3200 | PROTECTIVE SURFACE TREATMENT | SY | 865 | ---- | ---- | 865 |
| 502.3210 | PIGMENTED SURFACE SEALER | SY | ---- | 6 | 5 | 11 |
| 502.4205 | ADHESIVE ANCHORS NO. 5 BARS | EACH | ---- | 11 | 9 | 20 |
| 505.0600 | BAR STEEL REINFORCEMENT HS COATED STRUCTURES | LB | ---- | 760 | 700 | 1,460 |
| 509.0301 | PREPARATION DECKS TYPE 1 | SY | 100 | ---- | ---- | 100 |
| 509.0302 | PREPARATION DECKS TYPE 2 | SY | 40 | ---- | ---- | 40 |
| 509.0500 | CLEANING DECKS | SY | 865 | ---- | ---- | 865 |
| 509.1500 | CONCRETE SURFACE REPAIR | SF | 50 | ---- | ---- | 50 |
| 509.2000 | FULL-DEPTH DECK REPAIR | SY | 2 | ---- | ---- | 2 |
| 509.2500 | CONCRETE MASONRY OVERLAY DECKS | CY | 62 | ---- | ---- | 62 |
| 516.0500 | RUBBERIZED MEMBRANE WATERPROOFING | SY | ---- | 9 | 9 | 18 |
| 614.0150 | ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD | EACH | 2 | ---- | ---- | 2 |
| | NON-BID ITEMS | | | | | |
| | FILLER | SIZE | ---- | ---- | ---- | 1/2", 3/4" |



△ BID ITEM ALSO INCLUDES CONCRETE FOR:
 "PREPARATION DECKS TYPE 1"
 "PREPARATION DECKS TYPE 2"
 "FULL-DEPTH DECK REPAIR"

* AS DIRECTED BY FIELD ENGINEER



PROFILE GRADE LINE

| BENCH MARKS | | | |
|-------------|---------|--------|-----------------------------|
| NO. | STATION | ELEV. | DESCRIPTION |
| 50 | 598+00 | 661.10 | 120D SPIKE IN PPOL, 45' LT. |
| 51 | 595+50 | 671.58 | WISDOT CAP, 24' RT. |



TYPICAL SECTION AT WING

△ BACKFILL PAY LIMITS. BACKFILL BEYOND PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

DIMENSIONS SHOWN ARE BASED ON THE ORIGINAL STRUCTURE PLANS.

PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO THE ENTIRE TOP OF THE NEW CONCRETE OVERLAY.

SEAL OVERLAY CONSTRUCTION JOINTS ACCORDING TO SECTION 502.3.13.1 OF THE STANDARD SPECIFICATIONS. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY OVERLAY DECKS".

A MINIMUM OF 1-INCH OF CONCRETE SHALL BE REMOVED FROM THE ENTIRE BRIDGE DECK UNDER THE BID ITEM "CLEANING DECKS".

THE AVERAGE OVERLAY THICKNESS IS BASED ON THE MINIMUM OVERLAY THICKNESS PLUS 1/2-INCH TO ACCOUNT FOR VARIATIONS IN THE DECK SURFACE.

THE REMOVAL OF THE TOP OF THE WINGS TO BE PAID FOR USING THE BRIDGE ITEM "REMOVING STRUCTURE (B-6-59)". FOR FULL DEPTH DECK REPAIRS THE BID ITEM "DEBRIS CONTAINMENT OVER WATERWAY (B-6-59)" IS TO BE USED.

PREPARATION DECKS TYPE 1, PREPARATION DECKS TYPE 2, AND FULL-DEPTH DECK REPAIR AREAS ARE BASED ON THE PLANS AND AS DETERMINED BY THE ENGINEER. DECK PREPARATION AND FULL-DEPTH DECK REPAIRS SHALL BE FILLED WITH "CONCRETE MASONRY OVERLAY DECKS".

ANY EXCAVATION NECESSARY TO COMPLETE THE OVERLAY AT THE ABUTMENTS OR WING TOP REPLACEMENT IS TO BE CONSIDERED INCIDENTAL TO THE BID ITEM "CONCRETE MASONRY BRIDGES".

PROFILE GRADE LINE SHALL BE DETERMINED IN THE FIELD BASED ON A MINIMUM OVERLAY THICKNESS OF 1 1/2" PLACED ABOVE THE DECK SURFACE AFTER SURFACE PREPARATION. EXPECTED AVERAGE OVERLAY THICKNESS IS 2" (OR AS GIVEN ON PLANS). IF EXPECTED AVERAGE OVERLAY THICKNESS IS EXCEEDED BY MORE THAN 1/2", CONTACT THE STRUCTURES DESIGN SECTION.

DESIGN DATA

LIVE LOAD:

DESIGN LOADING: HS-20

INVENTORY RATING: HS-20

OPERATING RATING: HS-33

WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 240 (KIPS)

TRAFFIC DATA

FEATURE ON:

ADT = 6,630 (2046)

R.D.S. = 55 MPH

MATERIAL PROPERTIES:

CONCRETE MASONRY:


CONCRETE MASONRY OVERLAY DECKS $f'_c = 4,000$ PSI

ALL OTHER $f'_c = 3,500$ PSI


BAR STEEL REINFORCEMENT

GRADE 60 $f_y = 60,000$ PSI

| | | | |
|--|------|--------------|-----|
| NO. | DATE | REVISION | BY |
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE B-6-59 | | | |
| DRAWN BY | CLP | PLANS CK'D | AEB |
| QUANTITIES AND NOTES | | SHEET 3 OF 8 | |
| SCALE = | | | |




ABUTMENT ELEVATIONS ARE FROM
SURVEY. TO BE VERIFIED IN FIELD.




(A17) ½" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF ½" FILLER WITH NON-STAINING GREY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD ½" SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.


| NO. | DATE | REVISION | BY |
|--|------|--------------|---------|
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE B-6-59 | | | |
| DRAWN BY CLP PLANS CK'D AEB | | | |
| EAST ABUTMENT WING 1 REPLACEMENT | | SHEET 4 OF 8 | SCALE = |




ELEVATION - WING 1




SECTION A - WING 1



SECTION B - WING 1



PLAN - WING 1



A501, A502

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

| BAR MARK | COAT | NO. REQ'D. | LENGTH | BENT | BAR SERIES | LOCATION |
|----------|------|------------|--------|------|------------|--------------------|
| A501 | X | 9 | 12'-9" | X | | WING 1 VERT. |
| A502 | X | 11 | 10'-1" | X | | WING 1 VERT. |
| A403 | X | 9 | 6'-2" | | | WING 1 HORIZ. E.F. |
| A404 | X | 12 | 13'-8" | | | WING 1 HORIZ. E.F. |
| A605 | X | 2 | 13'-8" | | | WING 1 HORIZ. E.F. |
| A506 | X | 11 | 4'-0" | | | WING 1 DOWELS B.F. |
| A607 | X | 1 | 6'-2" | | | WING 1 HORIZ. F.F. |
| A408 | X | 14 | 2'-0" | | | WING 1 DOWELS |
| | | | | | | |


BENDING DIMENSIONS ARE OUT TO OUT OF BARS

↑ ADHESIVE ANCHORS NO. 5 BAR


A19 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING
SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.

A17 $\frac{1}{2}$ " FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF $\frac{1}{2}$ " FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD $\frac{1}{8}$ " BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.

| | | | |
|--|------|--------------|-------------------|
| | | | |
| NO. | DATE | REVISION | BY |
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE B-6-59 | | | |
| EAST ABUTMENT WING 1 DETAILS | | DRAWN BY | PLANS CLP CK'D |
| | | SHEET 5 OF 8 | |
| SCALE: 1 | | | |




ABUTMENT ELEVATIONS ARE FROM SURVEY. TO BE VERIFIED IN FIELD.




A17 $\frac{1}{2}$ " FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF $\frac{3}{8}$ " FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD $\frac{1}{8}$ " BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GLITTER LINE AT INSIDE FACE

| | | | | |
|---|------|--------------|-------------|--------------|
| NO. | DATE | REVISION | BY | |
| STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION | | | | |
| STRUCTURE B-6-59 | | | | |
| WEST ABUTMENT WING 4 REPLACEMENT | | DRAWN BY | CLP CK'D | PLANS AEB |
| | | SHEET 6 OF 8 | | |
| | | | | SCALE = |


PLAN



ELEVATION - WING 4



SECTION B - WING 4



PLAN - WING 4

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE

| BAR MARK | COAT | NO. REQ'D. | LENGTH | BENT | BAR SERIES | LOCATION |
|----------|------|------------|--------|------|------------|--------------------|
| B501 | X | 9 | 13'-1" | X | | WING 4 VERT. |
| B502 | X | 9 | 10'-1" | X | | WING 4 VERT. |
| B403 | X | 9 | 6'-2" | | | WING 4 HORIZ. E.F. |
| B404 | X | 12 | 12'-2" | | | WING 4 HORIZ. E.F. |
| B605 | X | 2 | 12'-2" | | | WING 4 HORIZ. E.F. |
| B506 | X | 9 | 4'-0" | | | WING 4 DOWELS B.F. |
| B607 | X | 1 | 6'-2" | | | WING 4 HORIZ. F.F. |
| B408 | X | 13 | 2'-0" | | | WING 4 DOWELS |
| | | | | | | |

BENDING DIMENSIONS ARE OUT TO OUT OF BARS

ADHESIVE ANCHORS NO. 5 BAR

| | | |
|-----|------|----------|
| NO. | DATE | REVISION |
|-----|------|----------|

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

NE WATERPROOFING
T BACKFACE.

STRUCTURE B-6-59


5TH): SEAL ALL
S OF $\frac{1}{2}$ " FILLER WITH
NOIS JOINT SEALER

WEST ABUTMENT

WING 4 DETAILS

Page 1 of 1

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions
through innovation and exceptional service.

<http://www.dot.wisconsin.gov>