



Wisconsin Department of Transportation

February 18, 2026

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #11: 5889-00-73, WISC 2026222
T Primrose – T Springdale (CTH G)
Mt Vernon Creek Bridge B-13-0902
CTH G
Dane County

5889-00-75
T Primrose – T Springdale (CTH G)
W Br Sugar Rv Bridge B-13-0904
CTH G
Dane County

Letting of March 10, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5889-00-73/75

February 18, 2026

Special Provisions

5. Utilities.

*Replace entire subsection titled **TDS Telecom** under section titled 5889-00-73 with the following:*

TDS Telecom has two utility lines in the project vicinity. An underground fiber optic line runs parallel to CTH G southeast of the road centerline at approx. 32' offset RT south of Liberty Street, at approx. 34' offset RT between Liberty Street and the bridge, and at approx. 36' offset RT north of the bridge. This line is located at least 6' deep. An underground telephone line runs parallel to CTH G northwest of the road centerline at approx. 31' offset LT south of the bridge and at least 3' deep. The telephone line is approx. 28' offset LT, and at least 6' deep, north of the bridge. The telephone line then crosses CTH G north of Penn Street. Both lines will remain in place during construction. Contact TDS at least 3 days prior to guardrail installation at Liberty Street.

END OF ADDENDUM