



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

March 2, 2026

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #12: 6085-02-76**  
**Mazomanie – Sun Prairie**  
**Westmount Drive Intersection**  
**STH 19**  
**Dane County**

**6085-02-78**  
**Mazomanie – Sun Prairie**  
**Westmount Drive Intersection**  
**STH 19**  
**Dane County**

### Letting of March 10, 2026

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
204.0100	Removing Concrete Pavement	SY	0	4,816	4,816

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
92	Added miscellaneous quantity table for Removing Concrete Pavement.
251	Updated earthwork data sheet to correct values matching totals in the earthwork summary table.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**6085-02-76/78**

**March 2, 2026**

**Schedule of Items**

Attached, dated March 2, 2026, are the revised Schedule of Items Page 12.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 92, 251

END OF ADDENDUM



GRUBBING

STATION	STATION	LOCATION	STA	201.0205 GRUBBING	LF
202'NB+49	- 203'NB+49	RT/LT	1		
ITEM TOTALS					1

REMOVING SMALL PIPE CULVERTS

STATION	STATION	REMARKS	203.0100	EACH	
119'EB+76	- 119'EB+77	36" CPVC	1		
119'EB+77	- 119'EB+77	42" CPVC	1		
ITEM TOTAL					2

REMOVING STORM SEWER ITEMS

STATION	STATION	LOCATION	204.0210	204.0210	204.0210	204.0245.01	204.0245.02	
203'NB+72	- 203'NB+92	LT	1	1	26			
203'NB+81	- 203'NB+92	RT/LT	1	1	38			
203'NB+92	- 203'NB+92	LT	1	1	64			
ITEM TOTAL								52

REMOVING CURB & GUTTER

STATION - STATION	LOCATION	204.0150	LF	
STAGE 1				
205'NB+23 - 205'NB+30	LT	20		
205'NB+43 - 205'NB+44	RT	24		
STAGE 1 SUBTOTAL				44
STAGE 2				
207'NB+36 - 204'NB+83	RT	258		
207'NB+39 - 204'NB+62	LT	279		
STAGE 2 SUBTOTAL				537
STAGE 3				
205'NB+30 - 207'NB+65	LT	223		
205'NB+44 - 207'NB+65	RT	232		
STAGE 3 SUBTOTAL				455
ITEM TOTAL				1036

REMOVING CONCRETE PAVEMENT

STATION	LOCATION	204.0100	SY	
109'EB+10 - 123'EB+60		4816		
ITEM TOTAL				4816

TEMPORARY LANES SHIFT DURING CULVERT WORK

STATION	LOCATION	208.1500.S	EACH	
110'EB+06	RT	1		
119'EB+77	RT	1		
ITEM TOTAL				2

Addendum No. 01  
ID 6085-02-76  
Revised Sheet 92  
March 2, 2026

PROJECT NO: 6085-02-76

HWY: STH 19

COUNTY: DANE

MISCELLANEOUS QUANTITIES

SHEET 92

E

FILE NAME: H:\PROJECTS\608502\76\DATA\608502\92\SHEETS\030001-MGD.WG

LAYOUT NAME: 01

PLOT DATE: 2/24/2026 12:22 PM

PLOT BY: RACHEL BURHAM

PLOT SCALE: 1"=1'

WISDOT/CADDIS SHEET 42

Addendum No. 01  
 ID 6085-02-76  
 Revised Sheet 251  
 March 2, 2026

DIVISION 2 - 1 CL - WEST MOUNT DR - SB

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
203+61.61	20361.61	0.00	34.13	5.03	11.06	0	0	0	0	0	0
204+00.00	20400.00	38.39	25.40	3.77	35.61	42	6	33	42	41	-5
204+16.45	20416.45	16.45	21.27	1.77	37.77	14	2	22	56	69	-21
205+54.90	20554.91	0.00	31.97	6.97	15.73	0	0	0	56	69	-21
206+00.00	20600.00	45.09	37.99	9.40	11.84	58	14	23	114	98	-6
206+32.15	20632.15	32.15	73.60	8.63	0.00	66	11	7	180	106	41

DIVISION 3 - RD/BT-19-WM-CIRC

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)			
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
1+00.00	100.00	0.00	71.38	25.87	137.35	0	0	0	0	0	0
1+25.00	125.00	25.00	118.66	10.50	136.22	88	17	127	88	159	-88
1+50.00	150.00	25.00	121.22	8.03	147.25	111	9	131	199	323	-150
1+75.00	175.00	25.00	109.16	9.43	124.51	107	8	126	306	480	-208
2+00.00	200.00	25.00	123.14	24.30	117.48	108	16	112	414	620	-256
2+25.00	225.00	25.00	150.78	60.53	117.15	127	39	109	541	756	-304
2+50.00	250.00	25.00	130.97	38.89	114.45	130	46	107	671	890	-354
2+75.00	275.00	25.00	87.56	37.57	116.16	101	35	107	772	1024	-422
3+00.00	300.00	25.00	97.54	44.63	118.99	86	38	109	858	1160	-510
3+25.00	325.00	25.00	102.31	51.23	140.66	93	44	120	951	1310	-611
3+50.00	350.00	25.00	97.57	47.04	126.46	93	45	124	1044	1465	-718
3+75.00	375.00	25.00	85.44	22.17	132.43	85	32	120	1129	1615	-815
4+00.00	400.00	25.00	73.10	18.33	193.75	73	19	151	1202	1804	-950
4+25.00	425.00	25.00	61.74	24.37	136.87	62	20	153	1264	1995	-1099
4+32.99	432.99	7.99	71.39	25.87	137.35	20	7	41	1284	2046	-1137

NOTES:  
 1 - CUT  
 2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL  
 3 - FILL  
 4 - MASS ORDINATE  
 4 - MASS ORDINATE  
 4 - MASS ORDINATE  
 4 - MASS ORDINATE

CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL

THIS DOES NOT SHOW UP IN CROSS SECTIONS  
 DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME  
 IF MARSH OR EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) \* FILL FACTOR)]  
 IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - ((FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) \* FILL FACTOR)]  
 IF MARSH AND EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - EXPANDED ROCK) \* FILL FACTOR)]  
 IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - ((FILL - EXPANDED ROCK) \* FILL FACTOR)]



Proposal Schedule of Items

Proposal ID: 20260310012 Project(s): 6085-02-76, 6085-02-78

Federal ID(s): N/A, N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0330	SPV.0090 Special 03. Ductile Iron Water Main 12-Inch	282.000 LF	_____.	_____.
0332	204.0100 Removing Concrete Pavement	4,816.000 SY	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.

