



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

February 26, 2026

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #27: 6832-06-72, WISC 2026234**  
**Ogdensburg - Manawa**  
**Little Wolf River Bridge, B-68-0150**  
**CTH B**  
**Waupaca County**

### Letting of March 10, 2026

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
643.0420	Traffic Control Barricades Type III	DAY	1,666	560	2,226
643.0705	Traffic Control Warning Lights Type A	DAY	2,660	896	3,556
643.0900	Traffic Control Signs	DAY	11,788	4,256	16,044

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
450.4000	HMA Cold Weather Paving	TON	0	408	408
646.6464	Cold Weather Marking Epoxy 4-Inch	LF	0	1,781	1,781

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
21-22	Miscellaneous Quantities (updated traffic control items to account for additional working days and added HMA Cold Weather Paving and Cold Weather Marking due to additional working days)

**Other**

Revised the contract completion time from 50 working days to 70 working days (an increase of 20 working days).

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**6832-06-72**

**February 26, 2026**

**Special Provisions**

**3. Prosecution and Progress**

*Replace the paragraph one with the following:*

Begin work within 10 calendar days after the general engineer issues a written notice to do so. Do not start prior to July 7, 2026. Start work prior to July 21, 2026.

**Schedule of Items**

Attached, dated February 26, 2026, are the revised Schedule of Items Pages 4 and 5.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 21, 22

END OF ADDENDUM

GRUBBING

201 0205 GRUBBING CATEGORY	STATION	LOCATION	204-0165 LF
0010	13+00 - 14+00	LT/RT	110
	16+00 - 17+00	LT/RT	120
	17+00 - 18+00	LT/RT	110
TOTAL			460

REMOVING GUARDRAIL

205-0100 EXCAVATION COMMON CATEGORY	STATION	LOCATION	204-0165 LF
0010	13+69 - 14+79	LT	110
	13+69 - 14+90	RT	120
	15+95 - 17+14	LT	120
	16+05 - 17+12	RT	110
TOTAL			460

FINISHING ROADWAY

213-0100 PROJECT CATEGORY	PROJECT	213-0100 EACH
0010	6832-06-72	1
TOTALS		1,390

BASE AGGREGATE SUMMARY

305-0110 BASE AGGREGATE CATEGORY	STATION	LOCATION	TON
0010	12+51 - 14+62	LT/RT	720
	16+22 - 18+37	LT/RT	670
TOTALS			1,390

CATEGORY	DIVISION	FROM/TO STATION	LOCATION	205-0100 EXCAVATION COMMON		SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL (6)	UNEXPANDED FILL	EXPANDED FILL FACTOR 1.25 (6)	MASS ORDNATE +/- (7)	WASTE (8)	312.0110 SELECT CRUSHED MATERIAL	*624.0100 WATER (FOR DUST CONTROL)
				CUT (2)	EMB EXCAVATION (3)(4)								
0010	DIVISION 1	12+51.86/18+00.00	LT/RT	894	45	0	894	392	490	404	449	79	1.8
	DIVISION 1 SUBTOTAL			894	45	0	894	392	490	404	449	79	1.8
	GRAND TOTAL			894	45	0	894	392	490	404	449	79	1.8
TOTAL COMMON/EXC 939													

- NOTES:  
 (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EMB EXCAVATION COLUMNS. ITEM NUMBER 205-0100  
 (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT  
 (3) EMB EXCAVATION TO BE BACK FILLED WITH SELECT CRUSHED MATERIAL ITEM NUMBER 312.0110  
 (4) EMB CALCULATED AS 5 PERCENT OF CUT.  
 (5) AVAILABLE MATERIAL - CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL  
 (6) EXPANDED FILL = (UNEXPANDED FILL)\*EXPANDED FILL FACTOR=1.25  
 (7) MASS ORDNATE: MASS ORDNATE - CUT EXPANDED FILL  
 (8) WASTE = MASS ORDNATE + EMB EXCAVATION

\*ADDITIONAL QUANTITY LISTED ELSEWHERE

GUARDRAIL SUMMARY

CATEGORY	STATION	LOCATION	614.2610 MATERIAL TRANSITION	
			BEAM	LF
0010	13+62 - 14+55	RT	1	39.4
	13+62 - 14+55	LT	1	39.4
	16+29 - 17+22	RT	1	39.4
	16+29 - 17+22	LT	1	39.4
TOTALS			4	157.6

MAINTENANCE AND REPAIR OF PAVE ROADS

618-0100 EACH CATEGORY	PROJECT	1
0030	6832-06-72	1
TOTALS		619-1000 EACH

MOBILIZATION

619-1000 EACH CATEGORY	PROJECT	1
0010	6832-06-72	1
TOTALS		619-1000 EACH

NOTE: HMA PAVEMENT WEIGHT CALCULATIONS BASED ON 112 LBS/SYIN. TACK COAT APPLICATION RATE IS 0.05 GAL/SY.

ASPHALTIC ITEMS

CATEGORY	STATION	LOCATION	TON	REMARKS
460.6223	HMA PAVEMENT	3 MT 58-28 S	135	450.4000
460.6224	HMA PAVEMENT	4 MT 58-28 S	89	450.4000
450.0605	WEATHER PAVING	COAT	224	450.0605
			184	450.0605
TOTALS			408	408

EROSION CONTROL

CATEGORY	STATION	LOCATION	628-1504		628-1520		628-6005		628-7504		628-7555	
			SILT FENCE	TEMPORARY DITCH CHECKS	SILT FENCE	TEMPORARY DITCH CHECKS	TURBIDITY BARRIERS	TEMPORARY DITCH CHECKS	CLUMBERT PIPES	CLUMBERT PIPES		
0010	12+51 - 14+62	LT/RT	160	245	140	48	3	3	3	3	3	
	16+22 - 18+37	LT/RT	410	620	165	...	...	...	...	...	...	
	WASTE SITE	UNDISTRIBUTED	200	300	...	...	...	...	...	...	...	
	UNDISTRIBUTED	UNDISTRIBUTED	190	290	76	12	...	...	...	...	...	
TOTALS			960	1,455	381	60	60	3	3	3	3	

TRACKING PADS

628-1905 EACH CATEGORY	PROJECT	2
0010	6832-06-72	2
TOTALS		628-1905 EACH

MOBILIZATIONS EROSION CONTROL

628-1910 EACH CATEGORY	PROJECT	3
0010	6832-06-72	3
TOTALS		628-1910 EACH

PROJECT NO: 6832-06-72

HWY: CTH B

COUNTY: WAUPACA

MISCELLANEOUS QUANTITIES

SHEET: 21

WSPROTCADDSS SHEET 42

FINISHING ITEMS

625.0500	627.0200	628.2008	629.0205	630.0120	630.0300	630.0500
SAVED TOPSOIL	MULCHING	EROSION CONTROL	FERTILIZER	SEEDING	SPRINKLING	SEED
SY	SY	CLASS	TYPE A	NO. 20	PIT	WATER
SY	SY	SY	CWT	LB	LB	MGAL
0010	12-51 - 14+62	460	0.4	27	...	14
	16-22 - 18+37	700	0.6	24	...	20
	WASTE SITE	270	...	...	...	7
	UNDISTRIBUTED	70	2.90	13	2	10
TOTALS		340	1.450	64	9	50

FIELD OFFICE TYPE B	PROJECT	EACH
0010	6832-06-72	1

CONSTRUCTION STAKING

650.4500	650.5000	650.9920
SUBGRADE	BASE	SLOPE STAKES
LF	LF	LF
0010	12-51 - 14+62	210
	16-22 - 18+37	215
TOTALS	425	425

CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT)	PROJECT	EACH
0010	6832-06-72	1

CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE)

STRUCTURE	PROJECT	EACH
B-48-0150	1	

TRAFFIC CONTROL

PROJECT	EACH
6832-06-72	1

TRAFFIC CONTROL

643.0900	643.1050	643.0420	643.0705	643.0920
TRAFFIC CONTROL OPERATIONS	TRAFFIC CONTROL SIGNS	BARRICADES TYPE III	WARNING LIGHTS TYPE A	COVERING SIGNS
DURATION (DAYS)	NUMBER OF CYCLES	EACH	DAY	TYPE II
0010	105	15,960	2,100	3,360
	14	6	126	196
TOTALS	119	15,966	2,226	3,556

MARKING LINE ITEMS

MARKING LINE	LOCATION	LF
646.1020	646.464	1,781
646.1020	646.464	1,781
TOTAL		3,562

SAWING	STATION	LF
0010	12-51	32
	12-52 - 13+35	83
	18+00	27
TOTAL		142

MAINTAINING BIRD DETERRENT SYSTEM	STATION	EACH
0010	15+42	1

PROJECT NO: 6832-06-72

HWY: CTH B

COUNTY: WAUPACA

MISCELLANEOUS QUANTITIES

SHEET: 22

FILE NAME:

PLOT DATE:

PLOT BY:

PLOT SCALE: 1" = 1'



Proposal Schedule of Items

Proposal ID: 20260310027 Project(s): 6832-06-72

Federal ID(s): WISC 2026234

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0096	643.0420 Traffic Control Barricades Type III	2,226.000 DAY	_____.	_____.
0098	643.0705 Traffic Control Warning Lights Type A	3,556.000 DAY	_____.	_____.
0100	643.0900 Traffic Control Signs	16,044.000 DAY	_____.	_____.
0102	643.0920 Traffic Control Covering Signs Type II	6.000 EACH	_____.	_____.
0104	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.
0106	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0108	645.0111 Geotextile Type DF Schedule A	58.000 SY	_____.	_____.
0110	645.0120 Geotextile Type HR	512.000 SY	_____.	_____.
0112	646.1020 Marking Line Epoxy 4-Inch	1,781.000 LF	_____.	_____.
0114	650.4500 Construction Staking Subgrade	425.000 LF	_____.	_____.
0116	650.5000 Construction Staking Base	425.000 LF	_____.	_____.
0118	650.6501 Construction Staking Structure Layout (structure) 01. B-68-0150	1.000 EACH	_____.	_____.
0120	650.9911 Construction Staking Supplemental Control (project) 01. 6832-06-72	1.000 EACH	_____.	_____.
0122	650.9920 Construction Staking Slope Stakes	425.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20260310027 Project(s): 6832-06-72

Federal ID(s): WISC 2026234

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	690.0150 Sawing Asphalt	142.000 LF	_____	_____
0126	715.0502 Incentive Strength Concrete Structures	3,624.000 DOL	1.00000	3,624.00
0128	999.2005.S Maintaining Bird Deterrent System (station) 01. Station 15+50	1.000 EACH	_____	_____
0130	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0132	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0134	SPV.0195 Special 01. Infill Riprap B-68-150	71.000 TON	_____	_____
0136	450.4000 HMA Cold Weather Paving	408.000 TON	_____	_____
0138	646.6464 Cold Weather Marking Epoxy 4-Inch	1,781.000 LF	_____	_____
<b>Section: 0001</b>			<b>Total:</b>	_____
			<b>Total Bid:</b>	_____

