



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

March 18, 2026

NOTICE TO ALL CONTRACTORS:

Proposal #21: 6530-01-70
Princeton – Plainfield
White River Bridge to STH 21
STH 73
Waushara County

Letting of April 14, 2026

This is Addendum No. 01, which provides for the following:

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
52 – 61	Miscellaneous Quantities (advertised set is not legible)

A full size set of Miscellaneous Quantities Sheets can be found at the following location:

<https://wisdot.box.com/s/n2w94vj475b75hi56znbjf6gawkbeshk>

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

GRUBBING		
STATION - STATION	LOCATION	SY
CAT 0010		
W CTH YY	LT	409
12+89 - 13+52	RT	641
13+66 - 14+12		
E CTH YY	LT	815
20+28 - 22+55	RT	361
20+88 - 21+50		
ITEM TOTALS		2226

REMOVING SMALL PIPE CULVERTS				
STATION	CULVERT	LENGTH FT	203.0100 EACH	REMARKS
CAT 0010				
STH 73	COTTONVILLE DR	43	1	24" CMCP
426+58	69073007071	55	1	24" CMCP
478+94				
CTH YY	W CTH YY	45	1	24" CMCP
13+03	E CTH YY	66	1	24" CMCP
20+28				
CAT 0010 SUBTOTAL			4	
ITEM TOTAL			4	

REMOVING ASPHALTIC SURFACE				
STATION	LOCATION	SY	REMARKS	
CAT 0010				
111+58	LT	2	INLET REPAIR	
111+59	RT	2	INLET REPAIR	
118+06	LT	3	CURB RAMP	
118+06	RT	5	CURB RAMP	
118+61	LT	6	CURB RAMP	
118+69	LT	10	CURB RAMP	
121+25	LT	7	CURB RAMP	
121+28	RT	6	CURB RAMP	
123+07	LT	6	DRIVEWAY APRON	
123+07	RT	6	DRIVEWAY APRON	
124+82	RT	8	DRIVEWAY APRON	
139+64	LT	9	DRIVEWAY APRON	
143+24	LT	13	DRIVEWAY APRON	
147+03	LT	12	DRIVEWAY APRON	
154+01	RT	10	DRIVEWAY APRON	
154+69	RT	18	DRIVEWAY APRON	
156+43	RT	12	DRIVEWAY APRON	
157+84	RT	9	DRIVEWAY APRON	
160+61	LT	14	DRIVEWAY APRON	
161+04	RT	8	DRIVEWAY APRON	
162+13	RT	8	DRIVEWAY APRON	
164+99	RT	13	DRIVEWAY APRON	
168+00	RT	11	DRIVEWAY APRON	
168+02	RT	10	DRIVEWAY APRON	
174+21	RT	13	DRIVEWAY APRON	
177+98	LT	16	DRIVEWAY APRON	
181+65	LT	11	DRIVEWAY APRON	
183+36	RT	17	DRIVEWAY APRON	
184+23	LT	11	DRIVEWAY APRON	
192+30	RT	10	DRIVEWAY APRON	
194+45	RT	9	DRIVEWAY APRON	
203+88	LT	9	DRIVEWAY APRON	
203+97	RT	8	DRIVEWAY APRON	
207+02	RT	10	DRIVEWAY APRON	
210+21	RT	15	DRIVEWAY APRON	
216+21	RT	5	DRIVEWAY APRON	
216+52	RT	5	DRIVEWAY APRON	
238+20	LT	14	DRIVEWAY APRON	
238+45	RT	9	DRIVEWAY APRON	
247+59	RT	5	DRIVEWAY APRON	
255+01	RT	7	DRIVEWAY APRON	
260+93	RT	6	DRIVEWAY APRON	
263+17	LT	12	DRIVEWAY APRON	
273+03	RT	9	DRIVEWAY APRON	
278+22	RT	8	DRIVEWAY APRON	

REMOVING ASPHALTIC SURFACE CONT'D				
STATION	LOCATION	SY	REMARKS	
CAT 0010				
283+05	LT	14	DRIVEWAY APRON	
290+29	RT	51	DRIVEWAY APRON	
297+62	LT	14	DRIVEWAY APRON	
299+83	LT	14	DRIVEWAY APRON	
328+35	LT	12	DRIVEWAY APRON	
329+72	RT	9	DRIVEWAY APRON	
339+71	RT	17	DRIVEWAY APRON	
347+49	RT	6	DRIVEWAY APRON	
351+22	LT	4	DRIVEWAY APRON	
351+26	LT	13	DRIVEWAY APRON	
364+06	LT	8	DRIVEWAY APRON	
378+26	RT	13	DRIVEWAY APRON	
380+38	LT	11	DRIVEWAY APRON	
385+88	RT	9	DRIVEWAY APRON	
393+58	RT	10	DRIVEWAY APRON	
394+14	RT	14	DRIVEWAY APRON	
413+92	LT	16	DRIVEWAY APRON	
417+47	RT	9	DRIVEWAY APRON	
482+20 - 484+72	RT	99	PAVED SHOULDER	
ITEM TOTAL		770		

REMOVING ASPHALTIC SURFACE BUTT JOINTS				
STATION	LOCATION	SY	REMARKS	
CAT 0010				
111+34	BEGIN PROJECT	36		
118+37	E PARK ST	42		
118+38	W PARK ST	43		
121+54	W BLUFF ST	36		
121+55	E BLUFF ST	39		
124+75	DRIVEWAY RT	21		
125+82	DRIVEWAY LT	17		
126+43	DRIVEWAY RT	18		
126+43	DRIVEWAY LT	19		
130+41	DRIVEWAY LT	21		
132+62	DRIVEWAY LT	18		
135+96	DRIVEWAY RT	26		
138+42	DRIVEWAY LT	23		
140+36	DRIVEWAY RT	31		
141+54	DRIVEWAY RT	25		
144+44	DRIVEWAY RT	25		
147+48	DRIVEWAY RT	65		
151+10	CH/IN/CH/E	31		
152+86	DRIVEWAY RT	30		
154+68	DRIVEWAY LT	38		
206+98	DRIVEWAY LT	18		
215+96	DRIVEWAY LT	36		
224+99	BANNERMAN JUNCTION RD	24		
234+02	CZECH AVE	24		
234+20	DRIVEWAY LT	22		
234+90	DRIVEWAY LT	18		
247+40	CYPRESS RD	25		
268+57	DRIVEWAY LT	23		
269+99	DRIVEWAY LT	24		
270+26	E CREE DR	22		
378+28	DRIVEWAY LT	28		
386+42	DRIVEWAY LT	26		
391+19	DRIVEWAY LT	25		
395+04	DRIVEWAY RT	33		
402+85	COTTONVILLE LN	23		
403+12	DRIVEWAY RT	27		
426+57	COTTONVILLE DR	25		
428+45	CTH F	36		
451+24	CHICAGO POINT RD	26		
462+84	CHICAGO POINT RD	49		
482+20	END MILL & OVERLAY	40		
ITEM TOTAL		1189		

Addendum No. 01
ID 6530-01-70
Revised Sheet 52
March 18, 2026

REMOVING ASPHALTIC SURFACE MILLING			REMOVING CURB & GUTTER			REMOVING CONCRETE SIDEWALK		
STATION - STATION	LOCATION	REMARKS	STATION - STATION	LOCATION	REMARKS	STATION - STATION	LOCATION	REMARKS
CAT 0010								
111+44 - 121+95	5TH 73	4093	111+55 - 111+62	RT	7	118+04	RT	
121+95 - 122+95	5TH 73	378	111+55 - 111+62	LT	7	118+09	LT	
122+95 - 429+25	5TH 73	110277	117+99 - 118+14	RT	22	118+09	LT	
429+25 - 430+25	5TH 73	444	118+03 - 118+13	LT	14	118+60	RT	
430+25 - 482+40	5TH 73	20763	118+57 - 118+74	RT	23	118+71	LT	
482+40 - 486+27	5TH 73	474	118+64 - 118+81	LT	19	121+22	LT	
PARK ST	RT & LT	280	121+10 - 121+33	LT	28	121+27	RT	
BIJEE ST	RT & LT	288	121+12 - 121+33	RT	25			
N LUMT RD/CTH/CTH N	RT	405						
BANNERMAN JUNCTION RD	LT	102						
CZECH AVE	LT	95						
CYPRESS RD	RT	157						
CREE DR	RT & LT	85						
COTTONVILLE LN	LT	324						
COTTONVILLE DR	LT	79						
CTH N	LT	100						
CHICAGO POINT RD	RT	303						
CHICAGO POINT RD	RT	213						
CHICAGO POINT RD	RT	199						
ITEM TOTAL		139067	ITEM TOTAL		145	ITEM TOTAL		78

EARTHWORK												
DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION (1)	SALVAGED/UNUSABLE PAVEMENT MATERIAL (3)	AVAILABLE MATERIAL (4)	UNEXPANDED FILL	EXPANDED FILL (5)		MASS ORDINATE +/- (6)	WASTE	COMMENT	
							CUT (2)	FACTOR 1.25				
DIVISION 1												
CUVERT 69073007071	478+94	5TH 73	465	61	404	0	0	0	454	454		
DIVISION 1 SUBTOTAL			465	61	404	0	0	0	454	454		
DIVISION 2												
12+42.28/14+23.00	CTH YY	CTH YY	587	68	519	33	41	41	478	478		
20+06.61/23+75.00	CTH YY	CTH YY	1,041	145	896	45	56	56	840	840		
313+927.75/314+50.74	CTH YY	CTH YY	201	0	201	11	14	14	166	166		
DIVISION 2 SUBTOTAL			1,829	213	1,616	89	111	111	1,484	1,484		
GRAND TOTAL			2,294	274	2,020	89	111	111	1,938	1,938		
TOTAL COMMON EXC			2,294									

Addendum No. 01
 ID 6530-01-70
 Revised Sheet 53
 March 18, 2026

NOTES:
 (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
 (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
 (3) SALVAGED/UNUSABLE PAVEMENT MATERIAL
 (4) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
 (5) EXPANDED FILL FACTOR = 1.25
 (6) THE MASS ORDINATE +/- OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
 (7) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.

BORROW

STATION-STATION	LOCATION	REMARKS	208.0100 CY
CAT 0010			
113+91 - 115+41	LT	DITCH BERM	140
426+37 - 426+60	LT	CUVERT REMOVAL	8
ITEM TOTALS			148

BASE AGGREGATE DENSE

305.0110 305.0120
3/4-INCH 1 1/4-INCH

STATION-STATION	LOCATION	TON	TON	REMARKS
CAT 0010				
111+58	LT & RT	--	3	INLET REPAIR
118+09	LT	--	9	W PARK ST SW CURB RAMP
118+11	RT	--	14	E PARK ST SE CURB RAMP
118+60	RT	--	16	E PARK ST NE CURB RAMP
138+73	LT	--	19	W PARK ST NW CURB RAMP
138+73	RT	--	15	W PARK ST SW CURB RAMP
121+22	RT	--	12	E BLUEF ST CURB RAMP
121+95 - 482+20	LT & RT	4166	--	DRIVEWAYS
121+95 - 430+25	LT & RT	663	--	DRIVEWAYS
426+57	LT	--	12	COITTONVILLE DR
478+94	LT	--	372	CUVERT REPLACEMENT
482+20 - 486+27	LT	13	--	SHOULDER
CHYY				
12+42 - 14+04	W CHYY	29	589	
20+18 - 23+75	E CHYY	78	1456	
CAT 0010 SUBTOTAL			4949	2517
ITEM TOTALS			4949	2517

PREPARE FOUNDATION

STATION-STATION	LOCATION	211.010101 PREPARE FOUNDATION FOR ASPHALTIC PAVING (6530-01-70) EACH	211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS STA
CAT 0010			
111+34 - 482+20	5TH 73	1	--
482+20 - 484+72	RT	--	3
ITEM TOTALS			3

CONCRETE PAVEMENT ITEMS

STATION-STATION	LOCATION	416.0610 DRILLED TIE BARS EACH	416.0620 DRILLED DOWEL BARS EACH	416.1710 CONCRETE PAVEMENT REPAIR SY	416.1720 CONCRETE PAVEMENT REPLACEMENT SY
CAT 0010					
482+56	RT	--	16	8	--
482+98	LT	--	16	8	--
483+20	LT	--	16	8	--
483+48	LT	--	16	8	--
484+56	RT	--	16	8	--
485+02 - 485+24	RT	14	54	--	55
UNDISTRIBUTED		--	--	8	--
ITEM TOTAL			14	134	48

Addendum No. 01
ID 6530-01-70
Revised Sheet 54
March 18, 2026

PROJECT NO: 6530-01-70

HWY: 5TH 73

COUNTY: WAUSHARA

MISCELLANEOUS QUANTITIES

SHEET 54

E

FILE NAME: H:\PROJECTS\600016221\EGDATA\653001\05\SHETS\03001-MGLDWG

LAYOUT NAME: 03

PLOT DATE: 10/20/2025 4:31 PM

PLOT BY: BRAN GENSKOW

PLOT SCALE: 1" = 1'

WISDOT/CADDS SHEET 42

HMA PAVEMENT				ASPHALTIC SURFACE ITEMS			
STATION - STATION	LOCATION	455.0605 * TACK COAT GAL	460.5224 4 LT 58.28 S TON	465.0105 ASPHALTIC SURFACE TON	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES TON	REMARKS	
CAT 0010							
STH 73							
111+34 - 482+20	STH 73	9527	15243	0.5	--	INLET REPAIR	
482+20 - 485+67	STH 73 RT	11	24	0.5	--	INLET REPAIR	
482+20 - 486+27	STH 73 LT	30	47	2	--	CURB RAMP	
	PARK ST RT & LT	26	41	1	--	CURB RAMP	
	BLUFF ST RT & LT	25	41	2	--	CURB RAMP	
	N UMIT RD / CTHEY CTH N	30	49	3	--	CURB RAMP	
	CZECH LN	9	14	2	--	CURB RAMP	
	BANNERBERRY DIVISION RD	13	20	2	--	CURB RAMP	
	CYRESS RD	8	12	2	--	DRIVEWAY	
	CREEDR	26	41	2	--	DRIVEWAY	
	COTTONVILLE LN	7	11	2	--	DRIVEWAY	
	COTTONVILLE DR	9	15	2	--	DRIVEWAY	
	CTHF	19	31	2	--	DRIVEWAY	
	CHICAGO POINT RD	17	28	3	--	DRIVEWAY	
	CHICAGO POINT RD	17	28	3	--	DRIVEWAY	
	CHY Y						
12+41 - 14+04	W CTH Y	32	71	--	--	DRIVEWAY	
20+18 - 23+75	E CTH Y	80	178	--	--	DRIVEWAY	
CAT 0010 SUBTOTAL				9894	15907		
ITEM TOTALS				9894	15907		
* ADDITIONAL QUANTITIES SHOWN ELSEWHERE							
HMA COLD WEATHER PAVING							
CAT 0010				450.4000	TON		
111+34 - 486+27	STH 73		3025				
ITEM TOTALS				3025			

ASPHALTIC FLUMES				ASPHALTIC RUMBLE STRIPS			
STATION	LOCATION	465.0315 ASPHALTIC FLUMES SY	450.4000 TON	465.0520 ASPHALTIC RUMBLE STRIPS, SHOULDER LF	465.0560 ASPHALTIC RUMBLE STRIPS, CENTERLINE LF	REMARKS	
CAT 0010							
STH 73							
315+74	STH 73	10					
315+93	STH 73	10					
	E CTH Y	11					
	21+02						
ITEM TOTAL				31			

Addendum No. 01
ID 6530-01-70
Revised Sheet 55
March 18, 2026

MISCELLANEOUS QUANTITIES			
STATION - STATION	LOCATION	465.0520 ASPHALTIC RUMBLE STRIPS, SHOULDER LF	465.0560 ASPHALTIC RUMBLE STRIPS, CENTERLINE LF
CAT 0010			
STH 73			
157+07 - 174+71	STH 73	2895	1764
174+71 - 424+57	STH 73	--	22176
ITEM TOTAL			
		2895	23940

MONUMENTS		TOWN/RANGE		CORNER	VERIFY/RESET	REMARKS
STATION	OFFSET	TYPE				
PROJECT 6530-01-66						
CAT 0010						
124+73	1.0' RT	QUARTER CORNER	T17N R1E	5-8	1	
151+06	8.1' RT	QUARTER CORNER	T17N R1E	5	1	
181+13	1.0' LT	QUARTER CORNER	T17N R1E/ T18N R1E	32-5	1	
207+60	7.9' LT	QUARTER CORNER	T18N R1E	32	1	
234+08	19.3' LT	QUARTER CORNER	T18N R1E	32-29	1	
260+69	16.1' LT	QUARTER CORNER	T18N R1E	29	1	
ITEM TOTALS					6	

MONUMENTS		TOWN/RANGE		CORNER	VERIFY/RESET	REMARKS
STATION	OFFSET	TYPE				
PROJECT 6530-01-66						
CAT 0010						
124+73	1.0' RT	QUARTER CORNER	T17N R1E	5-8	1	
151+06	8.1' RT	QUARTER CORNER	T17N R1E	5	1	
181+13	1.0' LT	QUARTER CORNER	T17N R1E/ T18N R1E	32-5	1	
207+60	7.9' LT	QUARTER CORNER	T18N R1E	32	1	
234+08	19.3' LT	QUARTER CORNER	T18N R1E	32-29	1	
260+69	16.1' LT	QUARTER CORNER	T18N R1E	29	1	
ITEM TOTALS					6	

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2	6	--		
CAT 0010 SUBTOTAL		3153	3	79	66		
ITEM TOTALS		3153	3	79	66		

TOPSOIL, FERTILIZER, AND SEEDING		625.0100 TOPSOIL		630.0120 SEEDING MIXTURE		630.0500 WATER	
STATION- STATION	LOCATION	SY	CWT	NO. 20	LB	MGAL	MGAL
CAT 0010							
S1H 73	LT	211	0.2	7.0	6		
113+91 - 115+50	RT	14	0.1	0.4	1		
117+86 - 118+14	LT	7	0.1	0.2	1		
118+66 - 118+80	LT	7	0.1	0.2	1		
118+65 - 118+80	LT	7	0.1	0.2	1		
121+10 - 121+32	LT	6	0.1	0.2	1		
121+10 - 121+32	RT	10	0.1	0.3	1		
121+14 - 121+27	LT	201	0.0	0.0	0		
425+11 - 426+93	LT	178	0.2	4.8	4		
478+36 - 479+40	LT & RT						
W.CTH.YY							
1242-14+04	LT & RT	929	0.6	25.1	21		
E.CTH.YY							
20+16 - 23+75	LT & RT	1293	0.9	34.9	29		
UNDISTRIBUTED		287	0.2				

EROSION CONTROL ITEMS

STATION	LOCATION	LF	628.1504 SILT FENCE MAINTENANCE	LF	628.1520 SILT FENCE	SY	628.2004 EROSION MAT CLASS 1	SY	628.2008 EROSION MAT URBAN CLASS 1	TYPE B	628.7010 INLET PROTECTION	EACH	628.7555 CULVERT PIPE CHECKS	EACH	606.0100 RIPRAP LIGHT	CY	645.0130 GEOTEXTILE FABRIC TYPE R	SY	999.2105.5 MAINTAINING CLIMBING TURTLE EXCLUSION FENCE	LF
CAT 0010																				
113491	LT	195		195					257						5		186			
117486	RT							14			1									
117490	RT							7			1									
118458	RT							10												
118465	LT							7			1									
121+10	LT							6												
121+14	RT							10												
425+11	LT						201													
478+36	LT & RT							178				4								293
W.CTH.YY																				
12+42	LT & RT						931					4			8		24			
E.CTH.YY																				
20+16	LT & RT	160		160			1289					4			7		22			
UNDISTRIBUTED																				
		36		36			242		49											
CAT 0010 SUBTOTAL																				
		391		391			2663		538		3		12		20		232			293
ITEM TOTALS																				
		391		391			2663		538		3		12		20		232			293

Addendum No. 01
 ID 6530-01-70
 Revised Sheet 59
 March 18, 2026

STATION	OFFSET	LOCATION	MESSAGE	638.2602 REMOVING SIGNS TYPE II	EA	638.3000 REMOVING SMALL SIGN SUPPORTS	EA
CAT 0010							
476+80	25.8 LT	5TH 73	NO PASSING ZONE	1			1
CTH.YY							
13+85	32.3 LT	W.CTH.YY	CTH.YY	1			1
13+85	32.3 LT	W.CTH.YY	DOUBLE ARROW	1			1
13+93	25.3 RT	W.CTH.YY	5TH 73	1			1
13+93	25.3 RT	W.CTH.YY	DOUBLE ARROW	1			1
13+93	18.8 RT	W.CTH.YY	STOP	1			1
20+34	25.6 LT	E.CTH.YY	STOP	1			1
20+35	28.4 LT	E.CTH.YY	5TH 73	1			1
20+35	28.4 LT	E.CTH.YY	DOUBLE ARROW	1			1
20+37	52.5 RT	E.CTH.YY	CTH.YY	1			1
20+37	52.5 RT	E.CTH.YY	DOUBLE ARROW	1			1
20+45	44.0 LT	E.CTH.YY	CAMP SIGN	1			1
CAT 0010 SUBTOTAL				12			8
ITEM TOTAL				12			8

STATION	OFFSET	LOCATION	REMARKS	637.2210 SIGNS TYPE II	634.0616 POSTS WOOD
CAT 0010					
313+70	20.7 RT	5TH 73	CTH.YY; DOUBLE ARROW	7.5	1
316+41	21.1 LT	5TH 73	CTH.YY; DOUBLE ARROW	7.5	1
13+68	19.5 RT	W.CTH.YY	STOP	7.46	1
13+68	27.3 RT	W.CTH.YY	DOUBLE ARROW	7.5	1
20+23	19.2 LT	E.CTH.YY	STOP	7.46	1
20+37	46.5 LT	E.CTH.YY	STOP	7.46	1
21+68	27.9 LT	E.CTH.YY	5TH 73; DOUBLE ARROW	7.5	1
ITEM TOTAL				52.38	7

PAVEMENT MARKING

STATION - STATION	LOCATION	646.7420 CROSSWALK MARKING TRANSVERSE LINE 6-INCH	650.6000 PIPE CULVERT EACH	650.8000 RESURFACING REFERENCE LF	650.9000 CURB RAMP EACH	650.9500 SUPPLEMENTAL SLOPE SHAPES (650.01-70) EACH	650.9911.01 SUPPLEMENTAL SLOPE SHAPES (650.01-70) EACH	REMARKS
CAT 0010								
5TH 73								
118+16 - 118+62	LT	108						
118+16 - 118+55	RT	90						
118+69	R/LT	89		37493				
119+15 - 124+04	R/LT	53						
121+22	R/LT							
ITEM TOTALS		377						

REMOVE, SALVAGE, AND REINSTALL RIPRAP LIGHT

STATION - STATION	LOCATION	SPV.0035.01	*AVAILABLE RIPRAP CY
CAT 0010			
113+91 - 115+50	LT	50	85
ITEM TOTALS		50	

* FOR REFERENCE ONLY. EXCESS RIPRAP IS TO BE DISPOSED OF OFF-SITE.

REMOVING DISTRESSED PAVEMENT

STATION - STATION	SY	GAL	TON
CAT 0010			
UNDISTRIBUTED	2000	140	224
ITEM TOTALS		2000	224

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

CONSTRUCTION STAKING

STATION - STATION	LOCATION	650.5000 BASE LF	650.6000 PIPE CULVERT EACH	650.8000 RESURFACING REFERENCE LF	650.9000 CURB RAMP EACH	650.9500 SUPPLEMENTAL SLOPE SHAPES (650.01-70) EACH	650.9911.01 SUPPLEMENTAL SLOPE SHAPES (650.01-70) EACH	REMARKS
CAT 0010								
PROJECT 6530-01-70								
5TH 73								
111+34 - 486+27								
113+91 - 115+41				37493				
118+09								
118+41								
118+63								
118+70								
121+21								
121+22								
425+13 - 426+93								
478+39 - 479+54								
W.CTHYY								
12+42 - 14+04		162						
13+78			1					
E.CTHYY								
20+18 - 23+75		357						
20+45								
CAT 0010 SUBTOTAL		519	3	37493	6	1	1	964
ITEM TOTALS		519	3	37493	6	1	1	964

MISCELLANEOUS QUANTITIES

STATION - STATION	LOCATION	690.0150 ASPHALT LF	690.0250 CONCRETE LF	REMARKS
CAT 0010				
SAWING				
5TH 73				
111+55 - 111+62	LT	14	5	INLET
111+55 - 111+62	RT	14	5	INLET
118+03 - 118+13	LT	20	10	CURB RAMP
117+99 - 118+14	RT	29	10	CURB RAMP
118+57 - 118+74	RT	33	15	CURB RAMP
118+64 - 118+81	LT	32	15	CURB RAMP
124+10 - 121+33	LT	36	17	CURB RAMP
124+11 - 121+33	RT	33	10	CURB RAMP
426+41 - 426+78	COTTONVILLE DR			CULVERT
478+94	69073007071	123		
W.CTHYY				
12+42		22		
14+05		208		
E.CTHYY				
20+17		256		
23+75		23		
CAT 0010 SUBTOTAL		913	87	
ITEM TOTAL		913	87	

REMOVING DISTRESSED PAVEMENT

STATION - STATION	SY	GAL	TON
CAT 0010			
UNDISTRIBUTED	2000	140	224
ITEM TOTALS		2000	224

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

Addendum No. 01
ID 6530-01-70
Revised Sheet 61
March 18, 2026

