



Wisconsin Department of Transportation

June 18, 2026

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #09: 9030-07-72, WISC 2026396
Merrill – Rhinelander
STH 64 to Big Hay Meadow Creek
STH 17
Lincoln County

Letting of July 14, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

9030-07-72

June 17, 2026

Special Provisions

6. Utilities.

Replace entire article language with the following:

This contract comes under the provision of Administrative Rule Trans 220.

The utility work plan includes additional detailed information regarding the location of known discontinued, relocated, or removed utility facilities. These can be requested from the department during the bid preparation process, or from the project engineer after the contract has been awarded and executed.

Any utility facility locations listed in this article are approximate.

stp-107-065 (20240703)

Spectrum (Communication)

Spectrum has communication lines running along the east side of STH 17 between STH 64 and CTH G (south).

Spectrum proposes to install fiber optic cable in a 1.25" duct along STH 17 at a minimum 36" depth:

- 2' inside the east R/W line from Station 1+00 (STH 64) north to Station 52+30 (CTH G).
- 32' inside the east R/W line from Station 53+10 north to Station 64+00 where it narrows again.
- 2' inside the east R/W line from Station 64+00 north ending at a pole at Station 77+50
- 40' west of existing pavement/ 53' inside west R/W line from Station 109+20 to Station 114+10
- 2' inside the east R/W line from Station 119+00 (Norwegian Rd) north to Station 140+50 (north of Lacelle Rd), with 4 crossings.
- 40' west of existing pavement/ 45' inside west R/W line from Station 140+50 to Station 144+84

Spectrum fiber optic crossing STH 17 at 48" minimum depth from existing pavement surface:

- at Station 53+25 (the north side of CTH G).
- at Station 74+30.
- at Station 83+90.
- at Station 94+00 and short length along the west R/W line at Smith Road.
- at Station 100+60 and short length along the west R/W line by Barnes Creek Av.
- at Station 104+75.
- at Station 111+90.
- at Station 140+50.

This work has been completed.

Wisconsin Public Service Corporation (Electric)

Wisconsin Public Service has overhead electric lines running along the east side of STH 17 from the south limits (Station 19+31) to Station 138+75 and continuing underground along the west side from Station 138+75 to the north limits (Station 449+61).

Wisconsin Public Service will relocate approximately 1900' of underground facilities at the following locations:

- Station 299+00 to Station 303+00 - Relocate 1 PH & 3 PH UG facilities to approx. 61' Lt at minimum 30" depth, including the existing Junction box at approx. Station 301+00 Lt.
- Station 323+00 to STA 327+00 - Relocate 1 PH & 3 PH UG facilities to approx. 53' Lt. at minimum 30" depth.

- Station 391+00 to STA 399+00 - Relocate 1 PH & 3 PH UG facilities to approx. 52' Lt. at minimum 30" depth.
- Station 346+75 – Relocate (2) 1 PH UG facilities crossing STH 17 at minimum 54" depth.
- Station 348+75 – Relocate 1 PH UG facilities crossing STH 17 at minimum 54" depth.

This work is anticipated to start July 6, 2026 and take 21 working days.

The following utility owners have facilities within the project area; however, no adjustments are anticipated:

- **Frontier Communications of WI LLC (Communication)**
- **Nsight Teleservices (Communication)**
- **Wisconsin Public Service Corporation (Gas/Petroleum)**

END OF ADDENDUM

