



Wisconsin Department of Transportation

August 6, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #09: 1090-09-75, WISC 2026437
IH 43 Rock Freeway
STH 20 to STH 83
IH 043
Walworth County

1090-09-77, WISC 2026438
IH 43 Rock Freeway
Bowers Rd to STH 20
IH 043
Walworth County

Letting of August 11, 2026

This is Addendum No. 02, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
SPV.0165.403	Prestressed Girder Surface Repair, Item SPV.0165.403

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change	Proposal Total After Addendum
205.0100	Excavation Common	CY	495,399	19,303	514,702
460.5223	HMA Pavement 3 LT 58-28 S	TON	31,951	-4,027	27,924
460.5224	HMA Pavement 4 LT 58-28 S	TON	35,919	-4,027	31,892
465.0125	Asphaltic Surface Temporary	TON	30,094	-16,087	14,007
509.1500	Concrete Surface Repair	SF	1,434	-51	1,383

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0165.403	Prestressed Girder Surface Repair	SF	0	51	51

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
685	1090-09-75: Miscellaneous quantities revised to incorporate EBS Excavation into Excavation Common quantity per sheet note 4.
604	1090-09-77: Miscellaneous quantities revised earthwork quantities for IH-43 SB between station 684+00 and 693+00.
637	1090-09-77: Miscellaneous quantities revised for HMA Pavement.
933	1090-09-77: Structure B-64-0092 – Updated bid item
958	1090-09-77: Earthwork Data sheet revised earthwork quantities for IH-43 SB between station 684+00 and 693+00.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02
1090-09-75/1090-09-77
August 6, 2026

Special Provisions

125. Prestressed Girder Surface Repair, Item SPV.0165.403

A Description

This special provision describes removing deteriorated concrete from surfaces of precast prestressed concrete girders as designated by the engineer and replacing it with a polymer modified Portland cement mortar.

B Materials

Provide a polymer modified Portland cement mortar meeting the following requirements:

- Have a corrosion inhibitor additive.
- A workable mix capable of bonding and holding its own plastic weight, when mixed and placed according to manufacturer instructions, on vertical and overhead surfaces..
- A minimum compressive strength of 1,500 psi at 24 hours, 3,500 psi at 3 days, and 5,000 psi at 28 days; according to ASTM C 109.
- Have minimum bond strength of 2,000 psi at 28 days

Have a water-soluble chloride ion content of less than 0.40 lb/cu yd. The test shall be performed according to ASTM C 1218, and the mortar shall have an age of 28 to 42 days at the time of test. The ASTM C 1218 test shall be performed by an independent lab a minimum of once every two years, and the test results shall be provided to the department.

C Construction

Perform the work according to the requirements of standard spec 509.3.7 and as specified herein. Remove all deteriorated concrete to sound material. The repair depth shall be a minimum of 3/8 inches. Take necessary precautions while removing deteriorated concrete to preserve all existing reinforcing steel and prestressing strands. At locations where reinforcing steel is exposed due to deteriorated and/or spalled concrete, remove concrete to a minimum depth of ½ inch behind the steel. Do not remove concrete behind prestressing strands except of it is heavily deteriorated.

Abrasive blast clean concrete and exposed steel reinforcement and prestressing strands against which repair mortar will be placed.

Use chipping hammers for removing concrete that are a light-duty pneumatic or electric tool with a 15-pound class or less. Use blast cleaning equipment for concrete surface preparation of the abrasive type with equipment having oil traps.

Power wash using water pressure between 1,200 psi to 2,000 psi to remove all chlorides, dust and loose materials, and any bond-inhibiting materials from the prepared surface.

After power washing, coat the blast cleaned surfaces of steel reinforcement and prestressing strands with zinc rich paint.

Just prior to mortar placement, saturate the repair surface with water to a saturated surface-dry condition.

Mix and place the polymer modified Portland cement mortar according to the manufacturer's instructions. Place and finish mortar to the contours of the member, as originally constructed. Do not place the mortar when the air temperature is below 45° F and falling below 40° F. Do not place mortar when the surface temperature of the repair area is less than 40° F. Do not place mortar when the air temperature is greater than 90° F. Ensure mortar has a minimum temperature of 50° F and a maximum temperature of 90° F.

Apply cotton mats for curing the exposed layer of mortar within 10 minutes after finishing and begin wet curing immediately. Maintain curing for a minimum of 3 days. If temperatures below 45° F are forecast during the curing period, provide protection methods during the curing period.

Provide appropriate equipment for the engineer to inspect repaired areas. After curing but no sooner than 28 days after placement of the mortar, examine the repair in the presence of the engineer for conformance with original dimensions, cracks, and delaminations. Perform sounding for delaminations with a hammer or by other methods determined by the engineer. Remove and replace repaired areas of mortar as determined by the engineer for delaminations or surface cracks greater than 0.01 inches in width.

D Measurement

The department will measure Prestressed Girder Surface Repair by the square foot acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0165.403	Prestressed Girder Surface Repair	SF

Payment is full compensation for completing all work including saw cutting, removing concrete; abrasive blasting, preparing surfaces; furnishing, applying and curing the repair mortar; and cleanup.

Schedule of Items

Attached, dated August 6, 2026, are the revised Schedule of Items Pages 1 - 30.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

1190-09-75 Revised: 685.

1190-09-77 Revised: 604, 637, 933, and 958.

END OF ADDENDUM

EARTHWORK SUMMARY																
DIVISION	FROM/TO STATION	ALIGNMENT	CUT (1)	EBS EXCAVATION (2)	SALVAGED/ UNUSABLE PAVEMENT MATERIAL (3)	205.0100 EXCAVATION COMMON (4)	SPV.0035.001 REMOVING CONCRETE PAVEMENT MODIFIED CY	SPV.0035.002 REMOVING ASPHALTIC PAVEMENT MODIFIED CY	AVAILABLE MATERIAL (5)	EXPANDED EBS BACKFILL (11)		EXPANDED FILL (13)	MASS ORDINATE +/- (14)	WASTE (15)	BORROW CY	REMARKS
										FACTOR 1.00	FACTOR 1.00					
STAGE 1																
IH 43 NB AT STH 20 END PROTECTION	757+38.12/769+88.60	43-PRL	350	0	0	350	0	0	350	0	16	334	0	0		
IH 43 NB AT CNRR END PROTECTION	75+66.37/78+89.45	43-PRL	189	0	0	189	0	0	189	0	67	122	0	0		
SB EXIT RAMP TO STH 20 X-OVER	24+28.21/37+67.91	X-OVER 20SBEXIT	952	0	180	772	0	180	772	0	1,352	580	0	580		
SB ENTRANCE RAMP FROM STH 83 X-OVER	-8+34.72/15+38.18	X-OVER 83SBENTR	1,257	0	354	1,403	0	354	1,403	0	674	729	0	0		
DIVISION 1 SUBTOTAL			3,248	0	534	2,714	0	534	2,714	0	2,109	605	1,185	580		
STAGE 2 - PERMANENT CONSTRUCTION																
IH 43 SB	730+00.00/90+33.62	43SB-PGL	140,484	0	44,364	96,120	17,997	26,367	96,120	0	1,901	94,219	94,219	0		
STH 20 RAMP B	742+88.09/754+34.00	RMP-20-B	3,518	0	982	2,136	495	487	2,136	0	88	2,148	2,148	0		
STH 20 RAMP C	754+25.00/768+91.83	RMP-20-C	4,210	0	1,239	2,951	653	606	2,951	0	171	2,780	2,780	0		
STH 83 RAMP B	87+43.27/97+00.00	RMP-83-B	3,149	0	866	2,283	424	387	2,283	0	16	2,267	2,267	0		
STH 83 RAMP C	97+25.88/101+75.70	RMP-83-C	274	0	39	235	8	31	235	0	50	185	185	0		
STONE SCHOOL RD	15+86.37/24+50.45	ALL-STONESCHOOL	410	0	0	410	0	0	410	0	59	351	351	0		
DIVISION 2 PERMANENT SUBTOTAL			152,045	0	47,510	104,535	19,577	27,878	104,535	0	2,285	102,250	102,250	0		
STAGE 2 - TEMPORARY CONSTRUCTION																
IH 43 SB AT STH 20 END PROTECTION	752+25.33/75+471.60	43-PRL	79	0	0	79	0	0	79	0	5	74	74	0		
IH 43 SB AT CNRR END PROTECTION	71+48.07/74+03.03	43-PRL	86	0	0	86	0	0	86	0	0	86	86	0		
DIVISION 2 TEMPORARY SUBTOTAL			165	0	0	165	0	0	165	0	5	160	160	0		
STAGE 3 - PERMANENT CONSTRUCTION																
IH 43 NB	730+00.00/90+33.62	43NB-PGL	135,264	0	44,035	91,229	17,925	26,110	91,229	0	2,662	88,567	88,567	0		
STH 20 RAMP A	739+14.14/757+33.24	RMP-20-A	5,909	0	1,623	4,286	839	784	4,286	0	36	4,250	4,250	0		
STH 20 RAMP D	757+93.69/769+91.77	RMP-20-D	3,471	0	1,024	2,447	515	509	2,447	0	58	2,389	2,389	0		
STH 83 RAMP A	85+66.68/92+25.42	RMP-83-A	1,959	0	550	1,409	276	274	1,409	0	27	1,382	1,382	0		
MIRAMAR RD	17+00.00/24+40.65	ALL-MIRAMAR	334	0	0	334	0	0	334	0	52	282	282	0		
DIVISION 3 PERMANENT SUBTOTAL			146,937	0	47,232	99,705	19,555	27,677	99,705	0	2,835	96,870	96,870	0		
STAGE 3 - TEMPORARY CONSTRUCTION																
NB ENTRANCE RAMP FROM STH 20 X-OVER	44+675/21+32.22	X-OVER 20NBENTR	3,310	0	456	2,854	0	456	2,854	0	348	2,506	2,506	0		INCL REMOVAL OF SB EXIT RAMP X-OVER
SB ENTRANCE RAMP FROM STH 83 X-OVER REMOVAL	984+00.00/69+76.08	43NB-PGL	2,668	0	565	2,103	0	565	2,103	0	56	2,047	2,047	0		
DIVISION 3 TEMPORARY SUBTOTAL			5,978	0	1,021	4,957	0	1,021	4,957	0	404	4,553	4,553	0		
STAGE 4																
NB ENTRANCE RAMP FROM STH 20 X-OVER REMOVAL	774+65.13/790+00.00	43NB-PGL	1,554	0	326	1,228	0	326	1,228	0	23	1,205	1,205	0		CONSTRUCTED UNDER 1090-39-70
1090-39-70 TEMPORARY X-OVER REMOVAL	79+59.80/95+46.56	43SB-PGL	4,610	0	672	3,938	0	672	3,938	0	105	3,833	3,833	0		CONSTRUCTED UNDER 1090-39-70
NORTH TEMPORARY X-OVER REMOVAL	116+95.72/140+96.54	43-PRL	8,203	0	569	7,634	0	569	7,634	0	23	7,611	7,611	0		CONSTRUCTED UNDER 1090-39-70
DIVISION 4 SUBTOTAL			14,367	0	1,567	12,800	0	1,567	12,800	0	151	12,649	12,649	0		
UNDISTRIBUTED EBS EXCAVATION																
			0	15,000	0	0	0	0	0	15,000	0	0	0	0		
GRAND TOTAL			322,740	15,000	97,864	239,876	39,132	58,677	224,876	15,000	7,789	217,087	217,424	580		
* ADDITIONAL QUANTITIES SHOWN ELSEWHERE																
** EXPANDED EBS BACKFILL MEASURED BY THE CY. TO BE BACKFILLED WITH BREAKER RUN, MEASURED BY THE TON. 15,000 CY = 27,000 TON OF BREAKER RUN																
NOTES:																
(1) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.																
(2) EBS EXCAVATION TO BE BACKFILLED WITH BREAKER RUN.																
(3) SALVAGED/UNUSABLE PAVEMENT MATERIAL INCLUDES ASPHALTIC AND CONCRETE PAVEMENTS, CURB AND GUTTER NOT INCLUDED.																
(4) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS, SUBTRACTED BY THE SALVAGED/UNUSABLE PAVEMENT MATERIAL COLUMN. ITEM NUMBER 205.0100																
(5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL																
(11) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH BREAKER RUN MATERIAL. EBS BACKFILL FACTOR = 1.00. ITEM NUMBER 311.0110*																
(13) EXPANDED FILL FACTOR = 1.00																
(14) THE MASS ORDINATE +/- OR - CITY CALCULATED FOR THE DIVISION PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION																
(15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.																

Addendum No. 02

ID 1090-09-75

Revised Sheet 685

August 6, 2026

Addendum No. 02
ID 1090-09-75
Revised Sheet 685
August 6, 2026

DIVISION		FROM/TO STATION	CUT (1)	EBS EXCAVATION (2)	SALVAGED/UNUSABLE PAVEMENT MATERIAL (3)	205.0100 EXCAVATION COMMON (4) CY	SPV.0035.001 REMOVING CONCRETE PAVEMENT MODIFIED CY	SPV.0035.002 REMOVING ASPHALTIC SURFACE MODIFIED CY	AVAILABLE MATERIAL (5)	EXPANDED EBS BACKFILL FACTOR (11) 1.00	UNEXPANDED FILL	EXPANDED FILL FACTOR (13) 1.00	MASS ORDINATE +/- (14)	WASTE (15)
DIVISION 1 - STAGE 2														
IH-43 SB		488+39.20/605+00.00	605.40	0	17,847	45,100	7,944	10,921	13,100	0	336	336	12,770	-
IH-43 SB		606+59.27/693+00.00	42,640	0	18,343	24,297	7,990	10,662	24,297	0	1,193	1,193	23,068	-
IH-43 SB		693+00.00/729+16.59	3,610	0	5,299	9,435	2,396	3,465	9,435	0	606	606	8,829	-
BOWERS RD RAMP E		499+92.56/512+60.84	3,591	0	1,113	2,478	503	474	2,478	0	32	32	2,446	-
BOWERS RD RAMP H		514+40.38/533+85.24	5,745	0	1,709	4,036	842	799	4,036	0	4	4	4,032	-
BOWERS RD RAMP G		522+44.65/533+61.06	3,129	0	982	2,147	539	482	2,147	0	3	3	2,144	-
BOWERS RD RAMP F		500+59.76/519+84.11	5,106	0	1,689	3,417	942	858	3,417	0	99	99	3,318	-
STH 120 NW RAMP K		642+93.62/665+50.00	6,251	0	1,769	4,482	818	790	4,482	0	35	35	4,447	-
STH 120 NE RAMP L		666+00.00/682+20.97	2,740	0	1,400	1,340	689	633	1,340	0	605	605	735	-
BOWERS RD - SOUTH-SB		33+13.25/37+67.32	810	0	248	562	248	406	562	0	0	0	562	-
BOWERS RD - NORTH-SB		41+87.11/50+87.28	1,346	0	422	924	0	438	924	0	28	28	896	-
BOWERS RD - SOUTH - NB		32+40.86/38+15.45	889	0	305	584	0	308	584	0	4	4	580	-
BOWERS RD - NORTH - NB		42+35.24/47+62.54	967	0	261	655	0	407	655	0	2	2	653	-
DIVISION 1 SUBTOTAL			148,737	0	51,387	97,350	22,663	30,644	97,350	0	3,024	3,024	94,290	94,290
DIVISION 2 - STAGE 3														
IH-43 NB		489+98.18/601+00.00	52,963	0	18,010	34,953	7,795	10,906	34,953	0	336	336	34,617	-
IH-43 NB		603+05.59/693+00.00	37,917	0	13,816	24,101	5,652	8,371	24,101	0	582	582	23,519	-
IH-43 NB		693+00.00/730+16.76	17,501	0	4,981	12,520	2,217	3,490	12,489	0	630	630	11,890	-
STH 120 SW RAMP J		644+95.63/660+75.00	4,429	0	1,303	3,126	702	630	3,126	0	35	35	3,091	-
STH 120 SE RAMP M		660+75.00/677+59.31	4,529	0	1,471	3,058	655	629	3,058	0	55	55	3,003	-
DIVISION 2 SUBTOTAL			117,339	0	39,581	77,758	17,021	24,026	77,727	0	1,638	1,638	76,120	76,120
UNDISTRIBUTED EBS EXCAVATION														
			0	13,089	0	13,089	0	0	0	13,089	0	0	0	0
GRAND TOTAL			266,076	13,089	90,968	188,197	39,684	54,670	175,077	**	4,662	4,662	170,410	170,410
* ADDITIONAL QUANTITIES LISTED ELSEWHERE														
** EXPANDED EBS BACKFILL MEASURED BY THE CY. TO BE BACKFILLED WITH BREAKER RUN, MEASURED BY THE TON.														
13,089 CY = 23,561 TON OF BREAKER RUN														
NOTES:														
(1) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.														
(2) EBS EXCAVATION TO BE BACKFILLED WITH BREAKER RUN.														
(3) SALVAGED/UNUSABLE PAVEMENT MATERIAL INCLUDES ASPHALTIC AND CONCRETE PAVEMENTS, CURB AND GUTTER NOT INCLUDED.														
(4) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS, SUBTRACTED BY THE SALVAGED/UNUSABLE PAVEMENT MATERIAL COLUMN. ITEM NUMBER 205.0100														
(5) AVAILABLE MATERIAL - CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL														
(11) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH BREAKER RUN. EBS BACKFILL FACTOR = 1.00. ITEM NUMBER 311.0110														
(13) EXPANDED FILL FACTOR = 1.00														
(14) THE MASS ORDINATE +/- OR -QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.														
(15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.														

Addendum No. 02
ID 1090-09-77
Revised Sheet 604
August 6, 2026

ALL ITEMS ARE CATEGORY 1000 UNLESS OTHERWISE SPECIFIED.

PROJECT NO: 1090-09-77

HWY: IH 43

COUNTY: WALWORTH

MISCELLANEOUS QUANTITIES

SHEET 604

E

FILE NAME : C:\OneDrive\ASCOM\0710428-West Zinda Dr Bridge, Stevens Point - General\900_CAD_GBS\910_CAD\93841303\SheetPlan\032021_mcp.dgn

PLOT DATE : 8/23/2026 1:49 PM

PLOT BY :

PLOT NAME : 032021.mn

PLOT SCALE : 1.000000:1.000000

WISDOT / CADOS SHEET 42

143 SB - PGL

STATION	REAL STATION	DISTANCE	AREA (SF)				INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)	
			REMOVING CONCRETE PAVEMENT MODIFIED	REMOVING ASHPALTIC SURFACE MODIFIED	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL 1.00	MASS ORDINATE
669+00.00	66900.00	23.91	131.35	33.00	58.33	39.23	115	52	26	31809	521	18260
669+01.07	66901.07	1.07	131.52	33.00	58.33	39.99	5	2	2	31814	523	18261
670+00.00	67000.00	98.93	118.15	33.00	58.33	6.95	457	214	86	32271	609	18418
671+00.00	67100.00	100	118.52	33.00	58.33	4.11	438	216	20	32709	629	18620
672+00.00	67200.00	100	118.39	33.00	58.33	3.06	439	216	13	33148	642	18830
673+00.00	67300.00	100	123.14	33.00	58.33	4.25	447	216	14	33595	656	19047
674+00.00	67400.00	100	121.08	33.00	58.33	2.88	452	216	13	34047	669	19270
675+00.00	67500.00	100	119.45	33.00	58.33	5.92	445	216	16	34492	685	19483
676+00.00	67600.00	100	120.13	33.00	58.33	3.58	444	216	18	34936	703	19693
677+00.00	67700.00	100	119.69	33.00	58.33	3.76	444	216	14	35380	717	19907
678+00.00	67800.00	100	118.48	33.00	58.33	6.30	441	216	19	35821	736	20113
679+00.00	67900.00	100	119.09	33.00	58.33	7.98	440	216	26	36261	762	20311
680+00.00	68000.00	100	138.01	33.00	58.33	0.84	476	216	16	36737	778	20555
681+00.00	68100.00	100	116.86	32.44	56.44	0.12	472	213	2	37209	780	20812
682+00.00	68200.00	100	111.72	28.79	52.79	0.05	423	202	0	37632	780	21033
683+00.00	68300.00	100	134.31	38.17	64.17	14.21	456	255	2	38088	801	21253
684+00.00	68400.00	100	130.28	38.17	72.17	10.61	490	271	40	38578	841	21412
685+00.00	68500.00	100	123.50	36.60	68.60	12.84	470	261	43	39048	884	21578
686+00.00	68600.00	100	127.37	31.33	67.42	9.00	465	252	40	39513	924	21751
687+00.00	68700.00	100	122.15	35.04	65.04	7.90	462	245	31	39975	955	21937
688+00.00	68800.00	100	120.87	33.74	62.07	7.36	450	235	28	40425	983	22124
689+00.00	68900.00	100	124.68	32.70	59.70	10.32	455	226	33	40880	1016	22320
690+00.00	69000.00	100	121.63	31.92	57.92	13.05	456	218	43	41336	1059	22515
691+00.00	69100.00	100	114.65	29.83	55.17	12.79	428	209	48	41774	1107	22696
692+00.00	69200.00	100	116.43	29.83	55.17	11.90	428	204	46	42202	1153	22874
693+00.00	69300.00	100	120.13	29.83	55.17	9.69	438	204	40	42640	1193	23068

Addendum No. 02
ID 1090-09-77
Revised Sheet 958
August 6, 2026

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME



Proposal Schedule of Items

Page 1 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	29.000 STA	_____.	_____.
0004	201.0205 Grubbing	29.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	36.000 EACH	_____.	_____.
0008	203.0211.S Abatement of Asbestos Containing Material (structure) 001. B-64-0092	1.000 EACH	_____.	_____.
0010	203.0211.S Abatement of Asbestos Containing Material (structure) 002. B-64-0093	1.000 EACH	_____.	_____.
0012	203.0211.S Abatement of Asbestos Containing Material (structure) 003. B-64-0094	1.000 EACH	_____.	_____.
0014	203.0220 Removing Structure (structure) 001. B-64-89	1.000 EACH	_____.	_____.
0016	203.0220 Removing Structure (structure) 002. B-67-129	1.000 EACH	_____.	_____.
0018	203.0220 Removing Structure (structure) 003. B-64-0094	1.000 EACH	_____.	_____.
0020	204.0100 Removing Concrete Pavement	1,642.000 SY	_____.	_____.
0022	204.0110 Removing Asphaltic Surface	3,502.000 SY	_____.	_____.
0024	204.0115 Removing Asphaltic Surface Butt Joints	10.000 SY	_____.	_____.
0026	204.0120 Removing Asphaltic Surface Milling	36,039.000 SY	_____.	_____.
0028	204.0150 Removing Curb & Gutter	3,790.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.0155 Removing Concrete Sidewalk	260.000 SY	_____.	_____.
0032	204.0165 Removing Guardrail	8,079.000 LF	_____.	_____.
0034	204.0170 Removing Fence	448.000 LF	_____.	_____.
0036	204.0180 Removing Delineators and Markers	525.000 EACH	_____.	_____.
0038	204.0190 Removing Surface Drains	9.000 EACH	_____.	_____.
0040	204.0210 Removing Manholes	1.000 EACH	_____.	_____.
0042	204.0215 Removing Catch Basins	9.000 EACH	_____.	_____.
0044	204.0220 Removing Inlets	31.000 EACH	_____.	_____.
0046	204.0245 Removing Storm Sewer (size) 801. 12-inch	1,722.000 LF	_____.	_____.
0048	204.0245 Removing Storm Sewer (size) 802. 18-inch	4,029.000 LF	_____.	_____.
0050	204.0245 Removing Storm Sewer (size) 804. 30-inch	243.000 LF	_____.	_____.
0052	204.0245 Removing Storm Sewer (size) 805. 36-inch	503.000 LF	_____.	_____.
0054	204.0280 Sealing Pipes	2.000 EACH	_____.	_____.
0056	204.9060.S Removing (item description) 001. Pavement Terminal Anchors	16.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0058	204.9060.S Removing (item description) 002. Crash Cushions Temporary Left in Place	2.000 EACH	_____.	_____.
0060	204.9060.S Removing (item description) 301. Traffic Signals (STH 83 at IH 43 NB Ramps)	1.000 EACH	_____.	_____.
0062	204.9060.S Removing (item description) 302. Traffic Signals (STH 83 at IH 43 SB Ramps)	1.000 EACH	_____.	_____.
0064	204.9060.S Removing (item description) 303. Traffic Signals (STH 83 at Bay View Road)	1.000 EACH	_____.	_____.
0066	204.9060.S Removing (item description) 304. Loop Detector Wire & Lead-In Cable (STH 83 at IH 43 NB Ramps)	1.000 EACH	_____.	_____.
0068	204.9060.S Removing (item description) 305. Loop Detector Wire & Lead-In Cable (STH 83 at IH 43 SB Ramps)	1.000 EACH	_____.	_____.
0070	204.9060.S Removing (item description) 306. Loop Detector Wire & Lead-In Cable (STH 83 at Bay View Road)	1.000 EACH	_____.	_____.
0072	204.9060.S Removing (item description) 801. Apron Endwalls for Underdrain Reinforced Concrete	434.000 EACH	_____.	_____.
0074	204.9060.S Removing (item description) 802. Apron Endwalls	68.000 EACH	_____.	_____.
0076	204.9090.S Removing (item description) 001. Concrete Barrier Temporary Precast Left in Place	812.000 LF	_____.	_____.
0078	204.9090.S Removing (item description) 801. Underdrain	140,356.000 LF	_____.	_____.
0080	205.0100 Excavation Common	514,702.000 CY	_____.	_____.



Proposal Schedule of Items

Page 4 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0082	205.3000.S Temporary Emergency Pullouts	16.000 EACH	_____.	_____.
0084	206.1001 Excavation for Structures Bridges (structure) 001. B-64-89	1.000 EACH	_____.	_____.
0086	208.0100 Borrow	16,199.000 CY	_____.	_____.
0088	209.1100 Backfill Granular Grade 1	705.000 CY	_____.	_____.
0090	210.1500 Backfill Structure Type A	85.000 TON	_____.	_____.
0092	211.0101 Prepare Foundation for Asphaltic Paving (project) 001. 1090-09-75	1.000 EACH	_____.	_____.
0094	213.0100 Finishing Roadway (project) 001. 1090-09-75	1.000 EACH	_____.	_____.
0096	213.0100 Finishing Roadway (project) 002. 1090-09-77	1.000 EACH	_____.	_____.
0098	305.0110 Base Aggregate Dense 3/4-Inch	35,421.000 TON	_____.	_____.
0100	305.0120 Base Aggregate Dense 1 1/4-Inch	415,987.000 TON	_____.	_____.
0102	310.0110 Base Aggregate Open-Graded	284.000 TON	_____.	_____.
0104	311.0110 Breaker Run	467,896.000 TON	_____.	_____.
0106	415.0085 Concrete Pavement 8 1/2-Inch	807.000 SY	_____.	_____.
0108	415.0090 Concrete Pavement 9-Inch	1,893.000 SY	_____.	_____.
0110	415.0410 Concrete Pavement Approach Slab	499.000 SY	_____.	_____.



Proposal Schedule of Items

Page 5 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0112	415.6000.S Rout and Seal	264,695.000 LF	_____.	_____.
0114	416.0610 Drilled Tie Bars	1,077.000 EACH	_____.	_____.
0116	416.0620 Drilled Dowel Bars	1,275.000 EACH	_____.	_____.
0118	416.1710 Concrete Pavement Repair	59.000 SY	_____.	_____.
0120	416.1720 Concrete Pavement Replacement	1,214.000 SY	_____.	_____.
0122	416.1725 Concrete Pavement Replacement SHES	398.000 SY	_____.	_____.
0124	450.4000 HMA Cold Weather Paving	7,300.000 TON	_____.	_____.
0126	455.0605 Tack Coat	20,155.000 GAL	_____.	_____.
0128	460.2000 Incentive Density HMA Pavement	43,440.000 DOL	1.00000	43,440.00
0130	460.5223 HMA Pavement 3 LT 58-28 S	27,924.000 TON	_____.	_____.
0132	460.5224 HMA Pavement 4 LT 58-28 S	31,892.000 TON	_____.	_____.
0134	465.0105 Asphaltic Surface	213.000 TON	_____.	_____.
0136	465.0110 Asphaltic Surface Patching	1,412.000 TON	_____.	_____.
0138	465.0125 Asphaltic Surface Temporary	14,007.000 TON	_____.	_____.
0140	465.0315 Asphaltic Flumes	36.000 SY	_____.	_____.
0142	465.0510 Asphaltic Rumble Strips, Shoulder Divided Roadway	118,794.000 LF	_____.	_____.



Proposal Schedule of Items

Page 6 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0144	495.1000.S Cold Patch	100.000 TON	_____.	_____.
0146	502.0100 Concrete Masonry Bridges	1,289.000 CY	_____.	_____.
0148	502.0180.S Bridge Deck Crack Sealing	45.000 LF	_____.	_____.
0150	502.3101 Expansion Device	477.000 LF	_____.	_____.
0152	502.3200 Protective Surface Treatment	7,008.000 SY	_____.	_____.
0154	502.3205 Pigmented Surface Sealer Reseal	1,998.000 SY	_____.	_____.
0156	502.3210 Pigmented Surface Sealer	660.000 SY	_____.	_____.
0158	502.3215 Protective Surface Treatment Reseal	26.000 SY	_____.	_____.
0162	502.4108 Adhesive Anchors 1-Inch	52.000 EACH	_____.	_____.
0164	502.4204 Adhesive Anchors No. 4 Bar	142.000 EACH	_____.	_____.
0166	502.4205 Adhesive Anchors No. 5 Bar	710.000 EACH	_____.	_____.
0168	505.0600 Bar Steel Reinforcement HS Coated Structures	299,150.000 LB	_____.	_____.
0170	506.2610 Bearing Pads Elastomeric Laminated	34.000 EACH	_____.	_____.
0172	506.6000 Bearing Assemblies Expansion (structure) 001. B-67-129	22.000 EACH	_____.	_____.
0174	506.7050.S Removing Bearings (structure) 001. B-67-129	22.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 7 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0176	506.7050.S Removing Bearings (structure) 002. B-67-130	8.000 EACH	_____.	_____.
0178	506.7050.S Removing Bearings (structure) 003. B-64-0092	14.000 EACH	_____.	_____.
0180	506.7050.S Removing Bearings (structure) 004. B-64-0093	12.000 EACH	_____.	_____.
0182	509.0301 Preparation Decks Type 1	226.000 SY	_____.	_____.
0184	509.0302 Preparation Decks Type 2	92.000 SY	_____.	_____.
0186	509.0310.S Sawing Pavement Deck Preparation Areas	230.000 LF	_____.	_____.
0188	509.0500 Cleaning Decks	3,053.000 SY	_____.	_____.
0190	509.1000 Joint Repair	102.000 SY	_____.	_____.
0192	509.1200 Curb Repair	18.000 LF	_____.	_____.
0194	509.1500 Concrete Surface Repair	1,383.000 SF	_____.	_____.
0196	509.2000 Full-Depth Deck Repair	2.000 SY	_____.	_____.
0198	509.2100.S Concrete Masonry Deck Repair	24.000 CY	_____.	_____.
0200	509.2500 Concrete Masonry Overlay Decks	312.000 CY	_____.	_____.
0202	509.5100.S Polymer Overlay	1,014.000 SY	_____.	_____.
0204	509.9010.S Removing Asphaltic Concrete Deck Overlay (structure) 001. B-64-86	1,596.000 SY	_____.	_____.



Proposal Schedule of Items

Page 8 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0206	509.9010.S Removing Asphaltic Concrete Deck Overlay (structure) 002. B-64-87	1,389.000 SY	_____.	_____.
0208	511.1100 Temporary Shoring	100.000 SF	_____.	_____.
0210	513.7011 Railing Steel Type C2	571.000 LF	_____.	_____.
0212	513.9006.S Removing and Resetting Tubular Railing (structure) 001. B-64-88	3.000 EACH	_____.	_____.
0214	513.9006.S Removing and Resetting Tubular Railing (structure) 002. B-67-130	3.000 EACH	_____.	_____.
0216	516.0500 Rubberized Membrane Waterproofing	14.000 SY	_____.	_____.
0218	517.0901.S Preparation and Coating of Top Flanges (structure) 001. B-64-86	1.000 EACH	_____.	_____.
0220	517.0901.S Preparation and Coating of Top Flanges (structure) 002. B-64-87	1.000 EACH	_____.	_____.
0222	517.0901.S Preparation and Coating of Top Flanges (structure) 003. B-64-89	1.000 EACH	_____.	_____.
0224	517.0901.S Preparation and Coating of Top Flanges (structure) 004. B-64-0094	1.000 EACH	_____.	_____.
0226	520.1012 Apron Endwalls for Culvert Pipe 12-Inch	2.000 EACH	_____.	_____.
0228	520.1015 Apron Endwalls for Culvert Pipe 15-Inch	2.000 EACH	_____.	_____.
0230	520.1018 Apron Endwalls for Culvert Pipe 18-Inch	20.000 EACH	_____.	_____.
0232	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 9 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0234	520.1036 Apron Endwalls for Culvert Pipe 36-Inch	2.000 EACH	_____.	_____.
0236	520.1072 Apron Endwalls for Culvert Pipe 72-Inch	1.000 EACH	_____.	_____.
0238	520.2012 Culvert Pipe Temporary 12-Inch	164.000 LF	_____.	_____.
0240	520.2015 Culvert Pipe Temporary 15-Inch	66.000 LF	_____.	_____.
0242	520.2018 Culvert Pipe Temporary 18-Inch	1,157.000 LF	_____.	_____.
0244	520.2024 Culvert Pipe Temporary 24-Inch	44.000 LF	_____.	_____.
0246	520.2036 Culvert Pipe Temporary 36-Inch	61.000 LF	_____.	_____.
0248	520.2072 Culvert Pipe Temporary 72-Inch	28.000 LF	_____.	_____.
0250	520.8000 Concrete Collars for Pipe	35.000 EACH	_____.	_____.
0252	520.8700 Cleaning Culvert Pipes	54.000 EACH	_____.	_____.
0254	521.1024 Apron Endwalls for Culvert Pipe Steel 24-Inch	2.000 EACH	_____.	_____.
0256	521.3124 Culvert Pipe Corrugated Steel 24-Inch	44.000 LF	_____.	_____.
0258	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	283.000 LF	_____.	_____.
0260	522.0130 Culvert Pipe Reinforced Concrete Class III 30-Inch	80.000 LF	_____.	_____.
0262	522.0136 Culvert Pipe Reinforced Concrete Class III 36-Inch	32.000 LF	_____.	_____.



Proposal Schedule of Items

Page 10 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0264	522.0142 Culvert Pipe Reinforced Concrete Class III 42-Inch	222.000 LF	_____.	_____.
0266	522.0148 Culvert Pipe Reinforced Concrete Class III 48-Inch	16.000 LF	_____.	_____.
0268	522.0160 Culvert Pipe Reinforced Concrete Class III 60-Inch	48.000 LF	_____.	_____.
0270	522.0166 Culvert Pipe Reinforced Concrete Class III 66-Inch	32.000 LF	_____.	_____.
0272	522.0172 Culvert Pipe Reinforced Concrete Class III 72-Inch	32.000 LF	_____.	_____.
0274	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	640.000 LF	_____.	_____.
0276	522.0430 Culvert Pipe Reinforced Concrete Class IV 30-Inch	80.000 LF	_____.	_____.
0278	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	13.000 EACH	_____.	_____.
0280	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	34.000 EACH	_____.	_____.
0282	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	14.000 EACH	_____.	_____.
0284	522.1036 Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	5.000 EACH	_____.	_____.
0286	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	8.000 EACH	_____.	_____.
0288	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 11 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0290	522.1060 Apron Endwalls for Culvert Pipe Reinforced Concrete 60-Inch	3.000 EACH	_____.	_____.
0292	522.1066 Apron Endwalls for Culvert Pipe Reinforced Concrete 66-Inch	2.000 EACH	_____.	_____.
0294	531.1100 Concrete Masonry Ancillary Structures Type NS	52.200 CY	_____.	_____.
0296	531.1140 Steel Reinforcement HS Ancillary Structures Type NS	7,225.000 LB	_____.	_____.
0298	531.2024 Drilling Shaft 24-Inch	437.000 LF	_____.	_____.
0300	531.2036 Drilling Shaft 36-Inch	30.000 LF	_____.	_____.
0302	531.4050 Foundation Camera Pole 50-FT	3.000 EACH	_____.	_____.
0304	601.0409 Concrete Curb & Gutter 30-Inch Type A	1,285.000 LF	_____.	_____.
0306	601.0411 Concrete Curb & Gutter 30-Inch Type D	2,272.000 LF	_____.	_____.
0308	601.0413 Concrete Curb & Gutter 6-Inch Sloped 30-Inch Type G	231.000 LF	_____.	_____.
0310	601.0555 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type A	319.000 LF	_____.	_____.
0312	601.0576 Concrete Curb & Gutter 4-Inch Sloped 30-Inch Type J	116.000 LF	_____.	_____.
0314	601.0588 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	943.000 LF	_____.	_____.
0316	601.0590 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	229.000 LF	_____.	_____.



Proposal Schedule of Items

Page 12 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0318	601.0600 Concrete Curb Pedestrian	23.000 LF	_____.	_____.
0320	602.0410 Concrete Sidewalk 5-Inch	3,550.000 SF	_____.	_____.
0322	602.0505 Curb Ramp Detectable Warning Field Yellow	80.000 SF	_____.	_____.
0324	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	64.000 SF	_____.	_____.
0326	602.2400 Concrete Safety Islands	1,690.000 SF	_____.	_____.
0328	602.3010 Concrete Surface Drains	47.000 CY	_____.	_____.
0330	602.3210 Concrete Rumble Strips, Shoulder Divided Roadway	102,175.000 LF	_____.	_____.
0332	603.8000 Concrete Barrier Temporary Precast Delivered	112,762.000 LF	_____.	_____.
0334	603.8125 Concrete Barrier Temporary Precast Installed	113,100.000 LF	_____.	_____.
0336	603.8500 Anchoring Concrete Barrier Temporary Precast	2,050.000 LF	_____.	_____.
0338	604.9010.S Slope Paving Repair Crushed Aggregate	218.000 CY	_____.	_____.
0340	604.9015.S Reseal Crushed Aggregate Slope Paving	5,095.000 SY	_____.	_____.
0342	606.0100 Riprap Light	2.000 CY	_____.	_____.
0344	606.0200 Riprap Medium	638.000 CY	_____.	_____.



Proposal Schedule of Items

Page 13 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0346	606.0300 Riprap Heavy	36.000 CY	_____.	_____.
0348	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	567.000 LF	_____.	_____.
0350	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	1,256.000 LF	_____.	_____.
0352	608.0330 Storm Sewer Pipe Reinforced Concrete Class III 30-Inch	254.000 LF	_____.	_____.
0354	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	224.000 LF	_____.	_____.
0356	608.0348 Storm Sewer Pipe Reinforced Concrete Class III 48-Inch	235.000 LF	_____.	_____.
0358	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	98.000 LF	_____.	_____.
0360	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	340.000 LF	_____.	_____.
0362	608.0430 Storm Sewer Pipe Reinforced Concrete Class IV 30-Inch	16.000 LF	_____.	_____.
0364	608.0436 Storm Sewer Pipe Reinforced Concrete Class IV 36-Inch	274.000 LF	_____.	_____.
0366	608.0518 Storm Sewer Pipe Reinforced Concrete Class V 18-Inch	797.000 LF	_____.	_____.
0368	611.0430 Reconstructing Inlets	3.000 EACH	_____.	_____.
0370	611.0530 Manhole Covers Type J	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 14 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0372	611.0612 Inlet Covers Type C	4.000 EACH	_____.	_____.
0374	611.0642 Inlet Covers Type MS	26.000 EACH	_____.	_____.
0376	611.2003 Manholes 3-FT Diameter	3.000 EACH	_____.	_____.
0378	611.3003 Inlets 3-FT Diameter	2.000 EACH	_____.	_____.
0380	611.3902 Inlets Median 2 Grate	13.000 EACH	_____.	_____.
0382	611.8115 Adjusting Inlet Covers	3.000 EACH	_____.	_____.
0384	611.8120.S Cover Plates Temporary	1.000 EACH	_____.	_____.
0386	612.0106 Pipe Underdrain 6-Inch	4,250.000 LF	_____.	_____.
0388	612.0206 Pipe Underdrain Unperforated 6-Inch	540.000 LF	_____.	_____.
0390	612.0806 Apron Endwalls for Underdrain Reinforced Concrete 6-Inch	17.000 EACH	_____.	_____.
0392	614.0150 Anchor Assemblies for Steel Plate Beam Guard	14.000 EACH	_____.	_____.
0394	614.0200 Steel Thrie Beam Structure Approach	21.000 LF	_____.	_____.
0396	614.0220 Steel Thrie Beam Bullnose Terminal	6.000 EACH	_____.	_____.
0398	614.0230 Steel Thrie Beam	450.000 LF	_____.	_____.
0400	614.0345 Steel Plate Beam Guard Short Radius	25.000 LF	_____.	_____.



Proposal Schedule of Items

Page 15 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0402	614.0390 Steel Plate Beam Guard Short Radius Terminal	1.000 EACH	_____.	_____.
0404	614.0397 Guardrail Mow Strip Emulsified Asphalt	3,438.000 SY	_____.	_____.
0406	614.0905 Crash Cushions Temporary	3.000 EACH	_____.	_____.
0408	614.1000 MGS Guardrail Temporary	302.000 LF	_____.	_____.
0410	614.1100 MGS Guardrail Temporary Thrie Beam Transition	320.000 LF	_____.	_____.
0412	614.1200 MGS Guardrail Temporary Terminal EAT	8.000 EACH	_____.	_____.
0414	614.2300 MGS Guardrail 3	4,367.000 LF	_____.	_____.
0416	614.2500 MGS Thrie Beam Transition	1,080.000 LF	_____.	_____.
0418	614.2610 MGS Guardrail Terminal EAT	27.000 EACH	_____.	_____.
0420	614.2620 MGS Guardrail Terminal Type 2	2.000 EACH	_____.	_____.
0422	616.0100 Fence Woven Wire (height) 001. 4-FT	448.000 LF	_____.	_____.
0424	618.0100 Maintenance and Repair of Haul Roads (project) 001. 1090-09-75	1.000 EACH	_____.	_____.
0426	618.0100 Maintenance and Repair of Haul Roads (project) 002. 1090-09-77	1.000 EACH	_____.	_____.
0428	619.1000 Mobilization	1.000 EACH	_____.	_____.
0430	620.0300 Concrete Median Sloped Nose	263.000 SF	_____.	_____.



Proposal Schedule of Items

Page 16 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0432	623.0200 Dust Control Surface Treatment	565,387.000 SY	_____.	_____.
0434	624.0100 Water	10,713.000 MGAL	_____.	_____.
0436	625.0500 Salvaged Topsoil	504,012.000 SY	_____.	_____.
0438	627.0200 Mulching	5,000.000 SY	_____.	_____.
0440	628.1504 Silt Fence	76,498.000 LF	_____.	_____.
0442	628.1520 Silt Fence Maintenance	76,498.000 LF	_____.	_____.
0444	628.1530.S Silt Fence Heavy Duty	3,500.000 LF	_____.	_____.
0446	628.1535.S Silt Fence Heavy Duty Maintenance	3,500.000 LF	_____.	_____.
0448	628.1905 Mobilizations Erosion Control	14.000 EACH	_____.	_____.
0450	628.1910 Mobilizations Emergency Erosion Control	20.000 EACH	_____.	_____.
0452	628.2004 Erosion Mat Class I Type B	482,242.000 SY	_____.	_____.
0454	628.2008 Erosion Mat Urban Class I Type B	21,315.000 SY	_____.	_____.
0456	628.2027 Erosion Mat Class II Type C	300.000 SY	_____.	_____.
0458	628.7005 Inlet Protection Type A	32.000 EACH	_____.	_____.
0460	628.7010 Inlet Protection Type B	51.000 EACH	_____.	_____.
0462	628.7015 Inlet Protection Type C	17.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 17 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	628.7020 Inlet Protection Type D	27.000 EACH	_____.	_____.
0466	628.7504 Temporary Ditch Checks	9,595.000 LF	_____.	_____.
0468	628.7555 Culvert Pipe Checks	128.000 EACH	_____.	_____.
0470	628.7560 Tracking Pads	84.000 EACH	_____.	_____.
0472	628.7570 Rock Bags	138.000 EACH	_____.	_____.
0474	629.0210 Fertilizer Type B	864.590 CWT	_____.	_____.
0476	630.0110 Seeding Mixture No. 10	145.000 LB	_____.	_____.
0478	630.0130 Seeding Mixture No. 30	21,714.000 LB	_____.	_____.
0480	630.0160 Seeding Mixture No. 60	283.000 LB	_____.	_____.
0482	630.0200 Seeding Temporary	13,665.000 LB	_____.	_____.
0484	630.0500 Seed Water	10,444.000 MGAL	_____.	_____.
0486	633.0100 Delineator Posts Steel	572.000 EACH	_____.	_____.
0488	633.0500 Delineator Reflectors	713.000 EACH	_____.	_____.
0490	633.1100 Delineators Temporary	532.000 EACH	_____.	_____.
0492	633.5200 Markers Culvert End	157.000 EACH	_____.	_____.
0494	634.0618 Posts Wood 4x6-Inch x 18-FT	224.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 18 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0496	634.0622 Posts Wood 4x6-Inch x 22-FT	181.000 EACH	_____.	_____.
0498	635.0200 Sign Supports Structural Steel HS	27,750.000 LB	_____.	_____.
0500	637.1220 Signs Type I Reflective SH	3,496.000 SF	_____.	_____.
0502	637.2210 Signs Type II Reflective H	3,359.990 SF	_____.	_____.
0504	637.2215 Signs Type II Reflective H Folding	147.000 SF	_____.	_____.
0506	637.2230 Signs Type II Reflective F	555.250 SF	_____.	_____.
0508	638.2101 Moving Signs Type I	2.000 EACH	_____.	_____.
0510	638.2102 Moving Signs Type II	6.000 EACH	_____.	_____.
0512	638.2601 Removing Signs Type I	22.000 EACH	_____.	_____.
0514	638.2602 Removing Signs Type II	256.000 EACH	_____.	_____.
0516	638.3000 Removing Small Sign Supports	305.000 EACH	_____.	_____.
0518	638.3100 Removing Structural Steel Sign Supports	46.000 EACH	_____.	_____.
0520	643.0300 Traffic Control Drums	766,032.000 DAY	_____.	_____.
0522	643.0370.S Digital Speed Reduction System (DSRS)	350.000 DAY	_____.	_____.
0524	643.0420 Traffic Control Barricades Type III	67,682.000 DAY	_____.	_____.
0526	643.0500 Traffic Control Flexible Tubular Marker Posts	196.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 19 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0528	643.0600 Traffic Control Flexible Tubular Marker Bases	196.000 EACH	_____.	_____.
0530	643.0705 Traffic Control Warning Lights Type A	96,220.000 DAY	_____.	_____.
0532	643.0715 Traffic Control Warning Lights Type C	148,370.000 DAY	_____.	_____.
0534	643.0810 Traffic Control Connected Arrow Boards	1,322.000 DAY	_____.	_____.
0536	643.0900 Traffic Control Signs	174,653.000 DAY	_____.	_____.
0538	643.0910 Traffic Control Covering Signs Type I	33.000 EACH	_____.	_____.
0540	643.0920 Traffic Control Covering Signs Type II	123.000 EACH	_____.	_____.
0542	643.1000 Traffic Control Signs Fixed Message	1,333.000 SF	_____.	_____.
0544	643.1050 Traffic Control Signs PCMS	619.000 DAY	_____.	_____.
0546	643.1070 Traffic Control Cones 42-Inch	10,138.000 DAY	_____.	_____.
0548	643.1100.S Dynamic Lane Merge System	50.000 DAY	_____.	_____.
0550	643.1200.S Portable Automated Real-Time Traffic Queue Warning System	50.000 DAY	_____.	_____.
0552	643.1205.S Basic Traffic Queue Warning System	706.000 DAY	_____.	_____.
0554	643.1220 Traffic Control Connected Work Zone Start and End Location Markers	2,043.000 DAY	_____.	_____.
0556	643.3170 Temporary Marking Line Epoxy 6-Inch	826,603.000 LF	_____.	_____.



Proposal Schedule of Items

Page 20 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0558	643.3180 Temporary Marking Line Removable Tape 6-Inch	50,657.000 LF	_____.	_____.
0560	643.3270 Temporary Marking Line Epoxy 10-Inch	10,956.000 LF	_____.	_____.
0562	643.3280 Temporary Marking Line Removable Tape 10-Inch	2,519.000 LF	_____.	_____.
0564	643.3760 Temporary Marking Raised Pavement Marker Type I	924.000 EACH	_____.	_____.
0566	643.3820 Temporary Marking Stop Line Epoxy 18-Inch	30.000 LF	_____.	_____.
0568	643.4100 Traffic Control Interim Lane Closure	21.000 EACH	_____.	_____.
0570	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0572	644.1410 Temporary Pedestrian Surface Asphalt	190.000 SF	_____.	_____.
0574	644.1440 Temporary Pedestrian Surface Matting	192.000 SF	_____.	_____.
0576	644.1601 Temporary Pedestrian Curb Ramp	222.000 DAY	_____.	_____.
0578	644.1810 Temporary Pedestrian Barricade	2,239.000 LF	_____.	_____.
0580	645.0111 Geotextile Type DF Schedule A	3,029.000 SY	_____.	_____.
0582	645.0120 Geotextile Type HR	1,335.000 SY	_____.	_____.
0584	645.0220 Geogrid Type SR	688,213.000 SY	_____.	_____.
0586	646.1020 Marking Line Epoxy 4-Inch	12,664.000 LF	_____.	_____.



Proposal Schedule of Items

Page 21 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0588	646.2020 Marking Line Epoxy 6-Inch	4,752.000 LF	_____.	_____.
0590	646.2025 Marking Line Grooved Black Epoxy 6-Inch	33,290.000 LF	_____.	_____.
0592	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	319,045.000 LF	_____.	_____.
0594	646.3020 Marking Line Epoxy 8-Inch	1,039.000 LF	_____.	_____.
0596	646.4020 Marking Line Epoxy 10-Inch	2,006.000 LF	_____.	_____.
0598	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	16,746.000 LF	_____.	_____.
0600	646.5020 Marking Arrow Epoxy	56.000 EACH	_____.	_____.
0602	646.5120 Marking Word Epoxy	20.000 EACH	_____.	_____.
0604	646.5420 Marking Aerial Enforcement Bar Epoxy	20.000 EACH	_____.	_____.
0606	646.5520 Marking Outfall Epoxy	17.000 EACH	_____.	_____.
0608	646.6120 Marking Stop Line Epoxy 18-Inch	581.000 LF	_____.	_____.
0610	646.6220 Marking Yield Line Epoxy 18-Inch	46.000 EACH	_____.	_____.
0612	646.7120 Marking Diagonal Epoxy 12-Inch	41.000 LF	_____.	_____.
0614	646.7220 Marking Chevron Epoxy 24-Inch	960.000 LF	_____.	_____.
0616	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	621.000 LF	_____.	_____.



Proposal Schedule of Items

Page 22 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0618	646.8020 Marking Corrugated Median Epoxy	278.000 SF	_____.	_____.
0620	646.8120 Marking Curb Epoxy	75.000 LF	_____.	_____.
0622	646.8220 Marking Island Nose Epoxy	7.000 EACH	_____.	_____.
0624	646.9000 Marking Removal Line 4-Inch	37,047.000 LF	_____.	_____.
0626	646.9002 Marking Removal Line 6-Inch	3,621.000 LF	_____.	_____.
0628	646.9100 Marking Removal Line 8-Inch	1,444.000 LF	_____.	_____.
0630	646.9150 Marking Removal Line Grooved Permanent Tape 8-Inch	329.000 LF	_____.	_____.
0632	652.0125 Conduit Rigid Metallic 2-Inch	50.000 LF	_____.	_____.
0634	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	4,188.000 LF	_____.	_____.
0636	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	1,679.000 LF	_____.	_____.
0638	652.0605 Conduit Special 2-Inch	56.000 LF	_____.	_____.
0640	652.0615 Conduit Special 3-Inch	2,573.000 LF	_____.	_____.
0642	652.0700.S Install Conduit into Existing Item	1.000 EACH	_____.	_____.
0644	652.0800 Conduit Loop Detector	5,372.000 LF	_____.	_____.
0646	653.0135 Pull Boxes Steel 24x36-Inch	24.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 23 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0648	653.0140 Pull Boxes Steel 24x42-Inch	43.000 EACH	_____.	_____.
0650	653.0905 Removing Pull Boxes	59.000 EACH	_____.	_____.
0652	654.0101 Concrete Bases Type 1	1.000 EACH	_____.	_____.
0654	654.0217 Concrete Control Cabinet Bases Type 9 Special	2.000 EACH	_____.	_____.
0656	655.0230 Cable Traffic Signal 5-14 AWG	5,779.000 LF	_____.	_____.
0658	655.0240 Cable Traffic Signal 7-14 AWG	1,881.000 LF	_____.	_____.
0660	655.0260 Cable Traffic Signal 12-14 AWG	1,271.000 LF	_____.	_____.
0662	655.0515 Electrical Wire Traffic Signals 10 AWG	43,545.000 LF	_____.	_____.
0664	655.0525 Electrical Wire Traffic Signals 6 AWG	330.000 LF	_____.	_____.
0666	655.0615 Electrical Wire Lighting 10 AWG	25,580.000 LF	_____.	_____.
0668	655.0625 Electrical Wire Lighting 6 AWG	540.000 LF	_____.	_____.
0670	655.0700 Loop Detector Lead In Cable	22,037.000 LF	_____.	_____.
0672	655.0800 Loop Detector Wire	19,378.000 LF	_____.	_____.
0674	655.0900 Traffic Signal EVP Detector Cable	3,376.000 LF	_____.	_____.
0676	656.0201 Electrical Service Meter Breaker Pedestal (location) 201. MB-CCTV-64-0249	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 24 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0678	656.0201 Electrical Service Meter Breaker Pedestal (location) 202. MB-CCTV-64-0252	1.000 EACH	_____.	_____.
0680	656.0201 Electrical Service Meter Breaker Pedestal (location) 203. MB-CCTV-64-0253	1.000 EACH	_____.	_____.
0682	656.0501 Electrical Service Breaker Disconnect Box (location) 201. CCTV640249	1.000 EACH	_____.	_____.
0684	656.0501 Electrical Service Breaker Disconnect Box (location) 202. CCTV640252	1.000 EACH	_____.	_____.
0686	656.0501 Electrical Service Breaker Disconnect Box (location) 203. CCTV640253	1.000 EACH	_____.	_____.
0688	658.0173 Traffic Signal Face 3S 12-Inch	1.000 EACH	_____.	_____.
0690	658.0416 Pedestrian Signal Face 16-Inch	1.000 EACH	_____.	_____.
0692	658.5070 Signal Mounting Hardware (location) 301. STH 83 & IH 43 NB Ramps	1.000 EACH	_____.	_____.
0694	658.5070 Signal Mounting Hardware (location) 302. STH 83 & IH 43 SB Ramps	1.000 EACH	_____.	_____.
0696	661.0201 Temporary Traffic Signals for Intersections (location) 301. STH 83 & IH 43 NB Ramps	1.000 EACH	_____.	_____.
0698	661.0201 Temporary Traffic Signals for Intersections (location) 302. STH 83 & IH 43 SB Ramps	1.000 EACH	_____.	_____.
0700	661.0201 Temporary Traffic Signals for Intersections (location) 303. STH 83 & Bay View Road	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 25 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0702	670.0101 Field System Integrator	2.000 EACH	_____.	_____.
0704	670.0201 ITS Documentation	2.000 EACH	_____.	_____.
0706	671.0122 Conduit HDPE 2-Duct 2-Inch	715.000 LF	_____.	_____.
0708	671.0132 Conduit HDPE 3-Duct 2-Inch	44,605.000 LF	_____.	_____.
0710	671.0232 Conduit HDPE Directional Bore 3-Duct 2-Inch	7,895.000 LF	_____.	_____.
0712	671.0300 Fiber Optic Cable Marker	70.000 EACH	_____.	_____.
0714	673.0105 Communication Vault Type 1	38.000 EACH	_____.	_____.
0716	673.0200 Tracer Wire Marker Posts	6.000 EACH	_____.	_____.
0718	673.1225.S Install Pole Mounted Cabinet	3.000 EACH	_____.	_____.
0720	677.0150 Install Camera Pole 50-FT	3.000 EACH	_____.	_____.
0722	677.0200 Install Camera Assembly	3.000 EACH	_____.	_____.
0724	678.0006 Install Fiber Optic Cable Outdoor Plant 6-CT	1,495.000 LF	_____.	_____.
0726	678.0072 Install Fiber Optic Cable Outdoor Plant 72-CT	55,440.000 LF	_____.	_____.
0728	678.0200 Fiber Optic Splice Enclosure	5.000 EACH	_____.	_____.
0730	678.0300 Fiber Optic Splice	368.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 26 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0732	678.0400 Fiber Optic Termination	12.000 EACH	_____.	_____.
0734	678.0501 Communication System Testing	2.000 EACH	_____.	_____.
0736	678.0600 Install Ethernet Switches	3.000 EACH	_____.	_____.
0738	690.0150 Sawing Asphalt	48,664.000 LF	_____.	_____.
0740	690.0250 Sawing Concrete	4,631.000 LF	_____.	_____.
0742	715.0502 Incentive Strength Concrete Structures	7,858.000 DOL	1.00000	7,858.00
0744	715.0715 Incentive Flexural Strength Concrete Pavement	113,446.000 DOL	1.00000	113,446.00
0746	740.0440 Incentive IRI Ride	79,541.000 DOL	1.00000	79,541.00
0748	801.0117 Railroad Flagging Reimbursement	22,500.000 DOL	1.00000	22,500.00
0750	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	14,000.000 HRS	5.00000	70,000.00
0752	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	27,000.000 HRS	5.00000	135,000.00
0754	SPV.0035 Special 001. Removing Concrete Pavement Modified	78,816.000 CY	_____.	_____.
0756	SPV.0035 Special 002. Removing Asphaltic Surface Modified	117,152.000 CY	_____.	_____.
0758	SPV.0060 Special 001. Baseline CPM Progress Schedule	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 27 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0760	SPV.0060 Special 002. Monthly CPM Progress Schedule Updates	41.000 EACH	_____.	_____.
0762	SPV.0060 Special 003. Survey Project 1090-09-75	1.000 EACH	_____.	_____.
0764	SPV.0060 Special 004. Survey Project 1090-09-77	1.000 EACH	_____.	_____.
0766	SPV.0060 Special 005. Exposing Existing Infrastructure Paved Area	16.000 EACH	_____.	_____.
0768	SPV.0060 Special 006. Exposing Existing Infrastructure Unpaved Area	16.000 EACH	_____.	_____.
0770	SPV.0060 Special 007. Drilled High Performance Dowel Bars	325.000 EACH	_____.	_____.
0772	SPV.0060 Special 008. Mobilizations Emergency Pavement Repair	10.000 EACH	_____.	_____.
0774	SPV.0060 Special 009. Traffic Control Close-Open Freeway Ramp	14.000 EACH	_____.	_____.
0776	SPV.0060 Special 010. Traffic Control Full Freeway Closure	18.000 EACH	_____.	_____.
0778	SPV.0060 Special 011. Traffic Control Local Road Lane Closure	20.000 EACH	_____.	_____.
0780	SPV.0060 Special 012. Emergency Response To Traffic Incident Involving Concrete Barrier Temporary	12.000 EACH	_____.	_____.
0782	SPV.0060 Special 013. Emergency Response To Traffic Incident Involving Temporary Crash Cushion	8.000 EACH	_____.	_____.
0784	SPV.0060 Special 014. Temporary Concrete Barrier Gate, 24-FT	19.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 28 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0786	SPV.0060 Special 201. Ground Rod	3.000 EACH	_____.	_____.
0788	SPV.0060 Special 202. Enter Existing Splice Enclosure	1.000 EACH	_____.	_____.
0790	SPV.0060 Special 301. Trnspt & Install State Furn Traffic Control Cabinet STH 83 & IH 43 NB Ramp	1.000 EACH	_____.	_____.
0792	SPV.0060 Special 302. Trnspt & Install State Furn Traffic Control Cabinet STH 83 & IH 43 SB Ramp	1.000 EACH	_____.	_____.
0794	SPV.0060 Special 401. Replace Diaphragm Bolt	2.000 EACH	_____.	_____.
0796	SPV.0060 Special 402. Parapet Repair	6.000 EACH	_____.	_____.
0798	SPV.0060 Special 403. Strapping B-64-89	2.000 EACH	_____.	_____.
0800	SPV.0060 Special 404. Strapping B-64-113	3.000 EACH	_____.	_____.
0802	SPV.0060 Special 405. Cleaning and Sealing Concrete Girder Repair	11.000 EACH	_____.	_____.
0804	SPV.0060 Special 801. Connect to Existing Inlet	1.000 EACH	_____.	_____.
0806	SPV.0075 Special 001. Pavement Cleanup Project 1090-09-75	300.000 HRS	_____.	_____.
0808	SPV.0075 Special 002. Pavement Cleanup Project 1090-09-77	300.000 HRS	_____.	_____.
0810	SPV.0075 Special 003. Animal Carcass and Debris Removal	124.000 HRS	_____.	_____.



Proposal Schedule of Items

Page 29 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0812	SPV.0085 Special 001. Sealing Cracks and Joints with Hot-Applied Sealant	247.250 LB	_____.	_____.
0814	SPV.0090 Special 001. Marking Epoxy 6-Inch Black Non-Grooved	439.000 LF	_____.	_____.
0816	SPV.0090 Special 002. Glare Screens Temporary	112,762.000 LF	_____.	_____.
0818	SPV.0090 Special 003. Re-Lap Guardrail	2,820.000 LF	_____.	_____.
0820	SPV.0135 Special 001. Field Facilities Office Space	30.000 MON	_____.	_____.
0822	SPV.0165 Special 001. Anchored Median Curb	270.000 SF	_____.	_____.
0824	SPV.0165 Special 401. Removing Loose Concrete	214.000 SF	_____.	_____.
0826	SPV.0165 Special 402. Fiber Wrap Reinforcing Non-Structural	261.000 SF	_____.	_____.
0828	SPV.0180 Special 001. Excavation of Phragmites Contaminated Soil	7,875.000 SY	_____.	_____.
0830	SPV.0180 Special 002. Herbicide Application	7,875.000 SY	_____.	_____.
0832	SPV.0180 Special 003. HPC Pavement 8 1/2-Inch	37,146.000 SY	_____.	_____.
0834	SPV.0180 Special 004. HPC Pavement 10-Inch	338,373.000 SY	_____.	_____.
0836	SPV.0180 Special 401. Methacrylate Flood Seal	5,057.000 SY	_____.	_____.
0838	SPV.0180 Special 402. Abutment Seat Cleaning and Sealing	34.000 SY	_____.	_____.



Proposal Schedule of Items

Page 30 of 30

Proposal ID: 20260811009 Project(s): 1090-09-75, 1090-09-77

Federal ID(s): WISC 2026437, WISC 2026438

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0840	SPV.0195 Special 001. HMA Longitudinal Joint Repair	367.000 TON	_____.	_____.
0842	502.4112 Adhesive Anchors 1 1/2-Inch	44.000 EACH	_____.	_____.
0844	SPV.0165 Special 403. Prestressed Girder Surface Repair	51.000 SF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

